

Nonlinear magneto-optical response to light carrying orbital angular momentum

Thomas Bose^{1,‡} and Jamal Berakdar²

¹ Theory Department, Max Planck Institute of Microstructure Physics, D-06120 Halle, Germany

² Institute of Physics, Martin-Luther-University, D-06120 Halle, Germany

Abstract. We predict a non-thermal magneto-optical effect for magnetic insulators subject to intense light carrying orbital angular momentum (OAM). Using a classical approach to second harmonic generation in non-linear media with specific symmetry properties we predict a significant nonlinear contribution to the local magnetic field triggered by light with OAM. The resulting magnetic field originates from the displacement of electrons driven by the electrical field (with amplitude E_0) of the spatially inhomogeneous optical pulse, modeled here as a Laguerre-Gaussian beam carrying OAM. In particular, the symmetry properties of the irradiated magnet allow for magnetic field responses which are second-order ($\sim E_0^2$) and fourth-order ($\sim E_0^4$) in electric-field strength and have opposite signs. For sufficiently high laser intensities, terms $\sim E_0^4$ dominate and generate magnetic field strengths which can be as large as several Tesla. Moreover, changing the OAM of the laser beam is shown to determine the direction of the total light-induced magnetic field, which is further utilized to study theoretically the non-thermal magnetization dynamics.

PACS numbers: 78.20.Ls; 42.65.Ky; 75.78.-n; 75.70.-i

[‡] Present address: Department of Physics, University of York, Heslington, York YO10 5DD, UK.

1. Introduction

The design and fabrication of ever smaller and faster magnetic devices for data storage, sensorics and information processing entail the development of efficient tools to control the dynamic behavior of the magnetization. In particular, femtosecond laser-induced magnetic excitations, originating in thermal and nonthermal effects, offer the possibility to study magnetic systems on time scales down to (10 – 100 fs) [1, 2]. Thermal effects describe the energy transfer from a laser to the medium which is usually thought to consist of three reservoirs - phonons, electrons and spins [3, 4, 5, 6, 7, 8, 9], for a recent review see [2]. Beside those thermal effects, nonthermal effects can influence magnetization dynamics as well, e.g. the impulsive stimulated Raman scattering [10] which was experimentally observed [11] and theoretically described in the context of coherent magnon generation [12]. Furthermore, the inverse Faraday effect (IFE) [13, 14, 15, 16] is another intriguing nonthermal phenomenon that refers to a build-up of a static magnetization or an effective magnetic field in response to circularly polarized light. On a microscopic level IFE relies heavily on the sample symmetry and/or spin-orbital coupling (SOC). Several experimental [17, 18, 19, 20, 21, 22] as well as theoretical [23, 24, 25, 26, 27, 28, 29] studies were performed during the recent past to obtain new insight into opto-magnetic effects related to the IFE. A microscopic description of the IFE often involves a Raman scattering process [10, 17, 28]. However, models were put forward to understand IFE within the framework of classical single electron currents [23, 24, 26]. Despite the progress on opto-magnetic effects the role of higher order nonlinear processes has not yet been addressed. The aforementioned studies consider effects characterized by a quadratic dependence of the optically generated magnetic field $B_{\text{ind}}^{(1)}$ on the electric field of the light pulse E_0 , i.e. $B_{\text{ind}}^{(1)} \propto E_0^2$. It is one goal of the present paper to emphasize the role of higher order effects in opto-magnetic phenomena, that is $B_{\text{ind}}^{(2)} \propto E_0^4$.

In addition to the usage of laser beams to control the irradiated magnetic material the beam itself can be modified to achieve a new form of magnetic sensing. E.g. one can engineer the time structure of the pulses such that orbital current is created [30, 31, 32, 33, 34]. The associated Oersted field can then be utilized for steering magnetic dynamics in the sample. The other possibility is to shape appropriately the light pulses spatial structure, for instance by using optical vortices, i.e. laser beams designed as to carry transferrable orbital angular momentum (OAM) in addition to the light polarization (associated with the photon spin) [35, 36, 37].

We note here that vortex beams of matter offer another promising opportunity for material research. The generation of electron vortex beams was suggested theoretically in [38] and recently demonstrated experimentally by utilizing spiral phase plates [39] and nanofabricated diffraction holograms [40] achieving vortex beams with high OAM numbers ($|l| = 100$) [41]. These works imply that electron vortices could lead to novel concepts in electron microscopy providing additional information about structure and properties of samples by analyzing the OAM-dependent signal. Currently, experimental

methods for the generation and modification of electron beams carrying OAM are under intense research [42, 43, 44] and electron vortex beams have even been produced down to atomic resolution [45]. Likewise, the theoretical understanding of electron vortices was put forward by investigating relativistic and nonparaxial corrections to the scalar electron beams [46] and by studying the transfer of OAM from an electron vortex to atomic electrons [47, 48].

In this present work we will investigate the effect of optical vortices, the theory however is straightforwardly extendable to the action of electron vortex beams, which have some similar as well as different characteristics compared to optical beams, as discussed in [38] (the advantage of optical beams lies in their precise temporal and frequency control while electron vortex beams are superior when it comes to spatial resolution).

Considering optical vortex beams it was predicted, based on a quantum mechanical theory, that an OAM transfer for laser beams interacting with molecules will not occur between the light and the internal electronic-type motion in the electric dipole approximation, but can take place in the quadrupole interaction [49]. Later on, this was experimentally verified in chiral matter [50, 51]. In the present paper, we are particularly interested in the higher-order effect of the electronic motion of the irradiated magnet induced by laser light carrying OAM within a classical theory.

The core of our model is based on the classical anharmonic oscillator

$$m_e \frac{d^2}{dt^2} x_\alpha(t) + 2\tilde{\gamma} \frac{d}{dt} x_\alpha(t) + \frac{d}{dx_\alpha} V(\mathbf{x}) = F_\alpha(\mathbf{x}, t), \quad (1)$$

with mass m_e , damping constant $\tilde{\gamma}$ and the potential $V(\mathbf{x})$ containing harmonic and anharmonic parts, which is driven by the external force $\mathbf{F}(\mathbf{x}, t)$. This force results from the electrical field of the optical pulse and leads to a time-dependent displacement $\mathbf{x}(t)$ (with components x_α) of the electron which entails two effects. On the one hand, an electric polarization is induced in the material and, on the other hand, microscopic electron currents are generated which are responsible for the build-up of a magnetic field. A theory based on Eq. (1) with a harmonic potential $V(\mathbf{x}) \propto \mathbf{x}^2$ describing the latter process was presented in [26] where the inverse Faraday effect was mimicked by assuming a linear dependence between the electron displacement and the external electric field (note, however, that in these works the sample symmetry effects were not considered, cf. in contrast the potential Eq. (5) used in this work). Further effects are expected upon including non-linear response, e.g., second-harmonic generation (SHG). Thus, the electron motion is in general not only affected by the fundamental frequency Ω of the external field but also by the SHG frequency 2Ω . This nonlinear effect is allowed in all media lacking a center of inversion symmetry [10, 52]. In the present study we consider thin magnetic garnet films which, although centrosymmetric in their bulk form, can be used for SHG due to the loss of inversion symmetry at the surface and/or the presence of a nonzero magnetization [53, 54, 55, 56, 57, 58].

We consider circularly polarized laser pulses which are spatially inhomogeneous, and additionally, carry OAM. More explicitly, we employ cylindrically symmetric Laguerre-




Figure 1. (Color online) Schematic of the system. \mathbf{M} is the magnetization of the sample, e^- indicates the single-electron current, $\boldsymbol{\mu}$ designates the magnetic moment of the current loop and σ^\pm is the polarization of the circularly polarized light pulse, (right-handed: +, left-handed: -). Further description is given in the text.

Gaussian beams [35] which are able to produce local orbital currents (e.g., [59] and references therein) and hence orbital local magnetic fields that can be utilized for initiating locally spin dynamics in the sample. The influence of light with OAM on the spin-degrees of freedom in a condensed matter system was discussed in [60], here this aspect is not considered in our classical treatment. The time structure of these magnetic field pulses is related mainly to the laser pulse duration. As shown below, substantial intensities are needed. Hence, short pulses should be used to minimize radiation damage.

The paper is organized as follows: In Sec. 2 we introduce the theoretical model emphasizing the role of the geometry and crystallographic and magnetization-induced symmetry under consideration. Further, we explain the procedure applied to calculate the time-dependent light-induced magnetic field. This induced magnetic field is then used to model magnetization dynamics. After the detailed description of the model parameters we present and discuss our results in Sec. 3. Finally, the results are summarized and the corresponding conclusion is given in Sec. 4.

2. Theory

We investigate the physical situation sketched in Fig. 1. An optical pulse is applied to a magnetic sample with magnetization \mathbf{M} in \hat{e}_Y -direction. As a consequence of the circularly polarized light microscopic electronic currents will be generated. Moving on a closed curve the electron current generates a magnetic moment $\boldsymbol{\mu}$. The absolute value of the magnetic moment is given by the area enclosed by the current loop Λ multiplied by the strength of the single-electron current j_e , i.e. $|\boldsymbol{\mu}| = j_e \Lambda$. Due to the inhomogeneity of the laser pulse the absolute value of the magnetic moment differs spatially.




Figure 2. (Color online) Coordinate systems considered. The spatial inhomogeneous laser pulse produces an intensity profile in the \hat{e}_X - \hat{e}_Y -plane. Here, only the region of highest intensity is shown. The electron is initially located at the origin of the x-y-frame at position (r, ϕ) according to the center of the light beam. Due to the electrical field of the laser pulse the electron starts to move.

We are interested in the two-dimensional motion of the electrons in the film plane (e_z is along the film normal). For that purpose we refer to different coordinate systems as shown in Fig. 2. The laser pulse impinges on the surface of the magnetic film and generates an intensity profile which varies in the \hat{e}_X - \hat{e}_Y -plane. The origin of the \hat{e}_X - \hat{e}_Y -coordinate system coincides with the center of the light beam. We will operate in cylindrical coordinates with e_z coinciding with the light propagation direction ((r, ϕ) indicate the planar spatial position), and assume the electron initial velocity distribution (given by the Compton profile) to be subsidiary with the respect to the intense laser induced velocities. Applying the laser pulse the electrical field of the optical pulse couples to the electronic charge which leads to a displacement of the electron. This motion of the electron is described in the x-y (displacement) frame. Comparing the typical length scale of the laser pulse ($\lambda_L \sim \mu\text{m}$) with that of the induced electron displacement ($\lambda_D \lesssim \text{nm}$) it follows that $\lambda_D \ll \lambda_L$. Therefore when treating the charge dynamics, the spatial variation of the electrical field of the laser pulse in the x-y-frame (i.e., in the *displacement frame*) may be neglected.

The laser light is described by a circularly polarized Laguerre-Gaussian beam propagating in Z-direction. Using cylindrical coordinates $r = \sqrt{X^2 + Y^2}$, $\phi = \arctan[Y/X]$ and $Z = Z$ the corresponding electrical field distribution is given by

$$\begin{aligned} \mathbf{E}(r, \phi, Z; t) &= \mathbf{E}_0(r, \phi, Z) \exp[-i\tilde{\Omega}t] + \text{c.c.}, \\ \mathbf{E}_0(r, \phi, Z) &= 2\hat{e}_\sigma E_0 \mathcal{F}_l^p(r, \phi) \exp[iq_Z Z], \\ \tilde{\Omega} &= \Omega - \frac{i}{\tau_p}, \end{aligned} \tag{2}$$

with the fundamental frequency Ω and the field pulse duration τ_p . E_0 is the amplitude of the electrical field, q_Z is the wave vector along the Z-axis, $\hat{e}_\sigma = \frac{1}{2}(\hat{\mathbf{e}}_X + i\sigma\hat{\mathbf{e}}_Y)$ is the vector of the light polarization (related to the photon spin) with $\sigma = \pm 1$ standing for right-handed (+1), or left-handed (-1) helicity; and c.c. stands for the complex conjugate of the first term. The function \mathcal{F}_l^p describes the spatial structure of the light beam and has the form

$$\mathcal{F}_l^p(r, \phi) = \frac{1}{N_l} \mathcal{L}_p^{|l|} \left(\frac{2r^2}{w_0^2} \right) \exp \left[\frac{-r^2}{w_0^2} \right] \left(\frac{\sqrt{2}r}{w_0} \right)^{|l|} \exp[i l \phi], \quad (3)$$

with the associated Laguerre polynomial $\mathcal{L}_p^{|l|}$. The parameter $l \in \mathbb{Z}$ is the topological charge of the optical vortex and can be considered as the amount of OAM transferred to the charge when interacting with the laser beam. We note that in case of $l \neq 0$, Eq. (3) describes an optical vortex with topological charge l . For later purposes we introduce the absolute value of the OAM number as $L = |l|$. Further parameters are the number of radial nodes p , the waist of the beam w_0 and the normalization constant N_l which depends on l . The latter is introduced to ensure that the laser power transferred to the medium is independent of the OAM represented by l .

2.1. Electron displacement

Due to the presence of anharmonicity we expand the electron displacement coordinates $x_\alpha = x, y$ according to

$$x_\alpha = \epsilon x_\alpha^{(1)} + \epsilon^2 x_\alpha^{(2)} + \epsilon^3 x_\alpha^{(3)} + \dots, \quad (4)$$

with the small perturbation parameter ϵ (which will be set equal to one later). It is our aim to analyze the effect of second harmonics and, therefore, we calculate the solution up to the order ϵ^2 . The new aspect in this work is that we consider the potential to consist of harmonic and anharmonic contributions, V_h and V_{anh} , and has the form

$$V(\mathbf{x}) = V_h(\mathbf{x}) + V_{anh}(\mathbf{x}) = \frac{m_e}{2} \omega_{0\alpha}^2 x_\alpha^2 + \frac{m_e a}{3} \Gamma_{\alpha\beta\gamma} x_\alpha x_\beta x_\gamma, \quad (5)$$

where sums over repeated indices is implicitly assumed. The eigenfrequencies are given by $\omega_{0\alpha}$ and the anharmonic constant a . $\Gamma_{\alpha\beta\gamma}$ is the higher order coupling tensor. The potential in Eq. (5) is an appropriate choice for noncentrosymmetric media [52].

The evolution equation (1) for the first-order displacement $\propto \epsilon$ which is driven by the external electric field given in Eqs. (2) and (3) is cast as

$$\frac{d^2}{dt^2} x_\alpha^{(1)} + 2\gamma \frac{d}{dt} x_\alpha^{(1)} + \omega_{0\alpha}^2 x_\alpha^{(1)} = -\frac{e}{m_e} E_\alpha(r, \phi, t), \quad (6)$$

where we have substituted $\tilde{\gamma}/m_e = \gamma$.

We are interested in the solution of Eq. (6) which follows the electrical field of the optical pulse, that is we neglect the fast decaying transient solutions. Assuming

$\omega_{0x}^2 = \omega_{0y}^2 = \omega_0^2$ and $Z = 0$, the displacement of the electron in the x-y-frame becomes

$$\begin{aligned} x^{(1)}(t) &= -\frac{e E_0}{m_e} F_l^p(r, \phi) \frac{\exp[-i\tilde{\Omega}t]}{\psi(\tilde{\Omega})}, \\ x_{\text{tot}}^{(1)}(t) &= x^{(1)}(t) + x^{(1)*}(t), \\ y_{\text{tot}}^{(1)}(t) &= y^{(1)}(t) + y^{(1)*}(t) = \sigma i (x^{(1)}(t) - x^{(1)*}(t)), \end{aligned} \quad (7)$$

which is the particular solution of Eq. (6). We note that the expression for the total displacement $(x_{\text{tot}}^{(1)}, y_{\text{tot}}^{(1)})$ in Eq. (7) yields real quantities. The function $\psi(\tilde{\Omega})$ reads

$$\psi(\tilde{\Omega}) = \omega_0^2 - \tilde{\Omega}^2 - 2i\gamma\tilde{\Omega}, \quad (8)$$

with $\tilde{\Omega}$ given in Eq. (2).

The equation of motion of the second-order electron displacements is

$$\begin{aligned} \frac{d^2}{dt^2} x_\mu^{(2)} + 2\gamma \frac{d}{dt} x_\mu^{(2)} + \omega_0^2 x_\mu^{(2)} &= -\frac{1}{m_e} \frac{dV_{\text{anh}}(\mathbf{x})}{dx_\mu}, \\ \frac{dV_{\text{anh}}(\mathbf{x})}{dx_\mu} &= \frac{m_e a}{3} \Gamma_{\alpha\beta\gamma\delta} (x_\beta x_\gamma M_\delta \delta_{\alpha\mu} + x_\alpha x_\gamma M_\delta \delta_{\beta\mu} + x_\alpha x_\beta M_\delta \delta_{\gamma\mu}), \end{aligned} \quad (9)$$

with the Kronecker delta symbol $\delta_{\rho\nu}$. The anharmonic potential V_{anh} is given in Eq. (5). An important statement of Eq. (9) is that the actual symmetry properties of the material do matter. To obtain an explicit solution the nonzero components of the coupling tensor $\Gamma_{\alpha\beta\gamma}$ have to be determined first. $\Gamma_{\alpha\beta\gamma}$ is related to the second-order susceptibility $\chi_{\alpha\beta\gamma}$ via the expression

$$\mathcal{P}_\alpha^{(2)} = \epsilon_0 \chi_{\alpha\beta\gamma} E_\beta E_\gamma = e N_e x_\alpha^{(2)} \quad (10)$$

for the components of the second-order nonlinear electric polarization $\mathcal{P}_\alpha^{(2)}$. Here $x_\alpha^{(2)}$ are the components $(x^{(2)}, y^{(2)})$ of the second-order displacement, and ϵ_0 and N_e are the permittivity of free space and the number of oscillators per unit volume. Therefore, the symmetry properties of the susceptibility $\chi_{\alpha\beta\gamma}$ can be transferred to the coupling tensor $\Gamma_{\alpha\beta\gamma}$. For thin magnetic garnet films, which were shown to be of great importance for the investigation of nonthermal effects [61, 18], the second-order susceptibility comprises two terms, a crystallographic contribution $\chi_{\alpha\beta\gamma}^{\text{cr}}$ and a magnetic contribution $\chi_{\alpha\beta\gamma\delta}^{\text{m}} M_\delta$ [55], where M_δ are the components of the magnetization in the sample frame. For the geometry depicted in Fig. 1 we assume (001)-oriented films. Thus, the corresponding point group symmetry is $4mm$ ($C_{4\nu}$) and the crystallographic contribution vanishes for normal incidence of the optical pulse [55, 57]. Hence, the SHG is purely magnetization induced and the nonvanishing components of $\chi_{\alpha\beta\gamma\delta}^{\text{m}}$ are $\chi_{xxxy}^{\text{m}} = -\chi_{yyyx}^{\text{m}}$, $\chi_{xxyx}^{\text{m}} = \chi_{xyxx}^{\text{m}} = -\chi_{yyxy}^{\text{m}} = -\chi_{yxyy}^{\text{m}}$, and $\chi_{yxxx}^{\text{m}} = -\chi_{xyyy}^{\text{m}}$, see [57]. Assuming the same symmetry for the coupling tensor $\Gamma_{\alpha\beta\gamma} = \Gamma_{\alpha\beta\gamma\delta}^{\text{m}} M_\delta$, its nonvanishing components are

$$\begin{aligned} \Sigma_1 &= \Gamma_{xxxy}^{\text{m}} = -\Gamma_{yyyx}^{\text{m}}, \\ \Sigma_2 &= \Gamma_{xxyx}^{\text{m}} = \Gamma_{xyxx}^{\text{m}} = -\Gamma_{yxyy}^{\text{m}} = -\Gamma_{yyxy}^{\text{m}}, \\ \Sigma_3 &= \Gamma_{yxxx}^{\text{m}} = -\Gamma_{xyyy}^{\text{m}}. \end{aligned} \quad (11)$$

For a magnetic garnet film with magnetization in y-direction, i.e. $\mathbf{M} = M_s \hat{\mathbf{e}}_Y = M_s \mathbf{y}$, after some algebra we find the evolution equation for the second order displacement $\propto \epsilon^2$ which has the form

$$\begin{aligned} \frac{d^2}{dt^2} x^{(2)} + 2\gamma \frac{d}{dt} x^{(2)} + \omega_0^2 x^{(2)} &= -a M_s \left[(3\Sigma_1 + (2\Sigma_2 + \Sigma_3)) (x^{(1)^2} + x^{(1)*^2}) \right. \\ &\quad \left. + 2(3\Sigma_1 - (2\Sigma_2 + \Sigma_3)) x^{(1)} x^{(1)*} \right] \\ \frac{d^2}{dt^2} y^{(2)} + 2\gamma \frac{d}{dt} y^{(2)} + \omega_0^2 y^{(2)} &= \sigma i 2 a M_s (2\Sigma_2 + \Sigma_3) (x^{(1)^2} - x^{(1)*^2}) . \end{aligned} \quad (12)$$

The expression for $x^{(1)}$ is given in Eq. (7). Thus, the particular solution of Eq. (12) can be expressed as

$$\begin{aligned} x_{\text{tot}}^{(2)}(t) &= x^{(2)}(+2\Omega, +\Omega, +\Omega; t) + x^{(2)}(-2\Omega, -\Omega, -\Omega; t) + x^{(2)}(0, +\Omega, -\Omega; t) , \\ y_{\text{tot}}^{(2)}(t) &= y^{(2)}(+2\Omega, +\Omega, +\Omega; t) + y^{(2)}(-2\Omega, -\Omega, -\Omega; t) \end{aligned} \quad (13)$$

where the $\pm 2\Omega$ terms represent the second harmonics and the last term in the expression for $x_{\text{tot}}^{(2)}(t)$ is usually referred to as optical rectification [62, 10, 52]. Therefore, a dc-shift of the electron is only observed in the x-direction which is a direct consequence of the underlying, magnetization-induced, symmetry.

2.2. Optically-generated magnetic field

Solving the evolution equations for the first-order and second-order displacement of the electrons derived in the preceding section enables the calculation of the optically-generated magnetic field. Illuminating the magnetic film with circularly polarized light forces the electron to move on a loop which is closed for laser pulses of infinite length. For a finite pulse width τ_p the electron trajectory can be approximated by a closed loop in case $\tau_p^{-1} \ll \Omega$. This condition is approximately fulfilled in our model. Calculating the trajectory of the single-electron allows to determine the magnetic moment associated with this displacement. The total optically-induced magnetic field is obtained by summing over all contributing electron orbits. The magnetic moment μ of a closed current loop of a single-electron is given by $j_e \Lambda(r, \phi; t)$, where j_e is the single-electron current and $\Lambda(r, \phi; t)$ is the time dependent area enclosed by the current loop in the coordinate system of the light beam. Separating first-order and second-order displacements the total light-induced magnetic moment is then given by

$$\begin{aligned} \boldsymbol{\mu}^{\text{tot}}(r, \phi; t) &= \boldsymbol{\mu}^{(1)}(r, \phi; t) + \boldsymbol{\mu}^{(2)}(r, \phi; t) , \\ \mu^{(1)}(r, \phi; t) &= \frac{e\Omega}{2\pi} \Lambda^{(1)}(r, \phi; t) , \\ \mu^{(2)}(r, \phi; t) &= \frac{e\Omega}{\pi} \Lambda^{(2)}(r, \phi; t) . \end{aligned} \quad (14)$$

Here, we introduced the areas $\Lambda^{(1)}$ and $\Lambda^{(2)}$ enclosed by the first-order and second-order electronic displacements. Right-handed (left-handed) circularly polarized beam creates a light-induced magnetic moment $\boldsymbol{\mu}^{(1)}$ in $+Z$ ($-Z$)-direction. The direction of the second-order magnetic moment $\boldsymbol{\mu}^{(2)}$ strongly depends on the coupling tensor $\Gamma_{\alpha\beta\gamma}$

introduced in Eq. (11). The total light induced magnetic field in Z-direction can then be calculated from

$$\mathbf{B}_{\text{ind}}(t) = N_e \mu_0 \frac{1}{\Lambda_0} \int_0^{R_0} \boldsymbol{\mu}^{\text{tot}}(r, \phi; t) r dr d\phi, \quad (15)$$

where N_e and μ_0 are the electron number density and the magnetic permeability. $\Lambda_0 = \pi R_0^2$ is the reference area over which the laser pulse influences the magnetic structure of the film.

The details of the procedure are as follows: First, we solved the equations of motion of the first-order and second-order single-electron displacements, Eqs. (6) and (12), for variable distance r between the electron and the center of the light-beam, i.e. the origin of the \hat{e}_X - \hat{e}_Y -coordinate system. The radial distance was varied in the range $0 \leq r \leq 5 \mu\text{m}$ with a resolution of $\Delta r = 2.5 \text{ nm}$. For each r the time-dependent single-electron displacement was determined. The peak field of the laser pulse sets in at $t = 0$ and diminishes exponentially within the time τ_p (cf. Eq.(2)). A waiting time of one cycle period $2\pi/\Omega \simeq 2.7 \text{ fs}$ until the transient solutions decreased significantly was taken into account. After the second full cycle of the electron, i.e. after 5.4 fs , the value of the light-induced magnetic field was calculated by computing the area enclosed by the electron trajectory. We point out that the elliptic motion of the electron according to the second-order displacement was already performed twice due to the motion with frequency 2Ω . In the same manner the magnetic moment of the single-electron was calculated each time the electron completes a full circle. In total, 29 values of the time-dependent magnetic moments according to Eq. (14) were computed; the last value corresponding to the time 81 fs after the laser pulse was applied. Finally, the average total magnetic moment and the total optically-induced magnetic field were calculated according to Eq. (15).

2.3. Magnetization dynamics

The light-induced magnetic field in Eq. (15) is used to excite magnetization dynamics described by the Landau-Lifshitz-Gilbert equation [63, 64]

$$\frac{\partial \mathbf{m}}{\partial t} = -\frac{\gamma_e}{1 + \alpha^2} (\mathbf{m} \times \mathbf{B}_{\text{eff}} + \alpha \mathbf{m} \times [\mathbf{m} \times \mathbf{B}_{\text{eff}}]), \quad (16)$$

with the damping parameter α , the absolute value of the gyromagnetic ratio for electrons γ_e and the effective magnetic field \mathbf{B}_{eff} . The magnetization vector \mathbf{m} is a unit vector according to $\mathbf{m} = \mathbf{M}/M_s$, where M_s is the saturation magnetization. In general, the effective field consists of different contributions, such as static magnetic fields, demagnetization fields, anisotropy fields and exchange fields. However, in the present study we consider the case when the static magnetic field \mathbf{B}_0 is supplemented by the light induced magnetic field $\mathbf{B}_{\text{ind}}(t)$, i.e.

$$\mathbf{B}_{\text{eff}}(t) = \mathbf{B}_0 + \mathbf{B}_{\text{ind}}(t). \quad (17)$$

Utilizing this effective magnetic field we solved Eq. (16) numerically.

2.4. Model parameters

Nonlinear magneto-optical phenomena in magnetic garnet films involving second harmonics generation, which are not related to optically-induced magnetic fields, were studied experimentally in [53, 54, 55, 56, 57, 58]. Regarding intensities, in [57] the authors report an average power density of approximately 10^3 W/cm^2 . Whereas, in [18], where the nonthermal optical control of the magnetization in magnetic garnet films was studied, a laser peak power density of about 10^{11} W/cm^2 was applied by 100 fs laser pulses. In the present theoretical study both aforementioned values do not lead to the generation of significant second-order effects, i.e. the build-up of a magnetic field induced by the second order electron displacement, which is comparable to the effects of first order. To observe first-order and second-order effects ranging in similar orders of magnitude we have chosen peak intensities between $2 \cdot 10^{14} - 2 \cdot 10^{16} \text{ W/cm}^2$. Taking into account a reference radius of $R_0 = 5 \mu\text{m}$ and a pulse duration of $\tau_p = 10 \text{ fs}$, as applied in the present model, pump pulse energies of $1.6 \mu\text{J}$ up to $160 \mu\text{J}$ are required. The above mentioned intensities are achieved by varying the electrical field strength in the interval $1.85 \cdot 10^8 \text{ V/cm} \leq E_0 \leq 1.85 \cdot 10^9 \text{ V/cm}$. In particular, we will make use of the reference intensity $I_0 = 2 \cdot 10^{14} \text{ W/cm}^2$ calculated at $t = 0$ for the electrical field strength of $1.85 \cdot 10^8 \text{ V/cm}$. The range of the absolute values of the topological charge (OAM) was chosen to be $0 \leq L = |l| \leq 6$.

The spatial distribution of the intensities for different values of L is shown in Fig. 3 (for simplicity we set the radial node to be $n = 0$). Varying the OAM number the spatial profile of the laser beam changes, in particular the radial distance where the peak intensity is located is shifted. The remaining model parameters have been chosen as follows: The damping constant is set to $\gamma = 10^{15} \text{ s}^{-1}$, the eigenfrequency takes $\omega_0 = 4.650 \cdot 10^{15} \text{ s}^{-1}$ (corresponding to $\hbar\omega_0 = 3.06 \text{ eV}$) and the external frequency is $\Omega = 2.325 \cdot 10^{15} \text{ s}^{-1}$ (corresponding to $\hbar\omega_0 = 1.53 \text{ eV}$). The eigenfrequency represents the energy gap leading to transparency of the magnetic garnet film for the fundamental beam [18]. Furthermore, the frequencies are chosen such that $\omega_0 = 2\Omega$. Following [52] the anharmonic parameter can be estimated from $a = \omega_0^2/d$, where d is the lattice constant. Here, the lattice constant is $d = 1.25 \text{ nm}$ as to simulate yttrium iron garnet. Further, right-handed circularly polarized light ($\sigma = +1$) has been considered and the number of radial nodes and the beam waist have been set to $n = 0$ and $w_0 = 2 \mu\text{m}$, respectively. The quantitative values of the elements of the coupling tensor $\Gamma_{\alpha\beta\gamma}$ have been chosen based on the values for the susceptibility $\chi_{\alpha\beta\gamma}$ experimentally determined and reported in [58]. Although, the exact numerical values with corresponding units could not be deduced from [58], we adopted the relations between the different tensor components mentioned in this article. In the present model the tensor components Σ_α always occur in product with the saturation magnetization M_s . We have chosen $\Sigma_1 M_s = -0.02$, $\Sigma_2 M_s = 0.2$ and $\Sigma_3 M_s = 0.1$. To model magnetization dynamics we made use of the Gilbert damping parameter $\alpha = 10^{-4}$.




Figure 3. (Color online) Intensities I/I_0 for different absolute values of the OAM number $L = |l|$ in the \hat{e}_X - \hat{e}_Y -plane. The reference intensity is $I_0 = 2 \cdot 10^{14} \text{ W/cm}^2$.

3. Results and Discussion

The investigated laser beam possesses a specific light polarization σ associated with the spin degrees of freedom of the photons, and an orbital angular momentum l , the effect of the latter is the prime focus of our study. The results presented in the following were all obtained using right-handed circularly polarized light, i.e. $\sigma = +1$. Important differences to the case of left-handed circularly polarized light ($\sigma = -1$) will be pointed out. Furthermore, in what follows we will present our results in terms of the absolute value of the OAM-number introduced previously as $L = |l|$.

Typical trajectories of the first-order and second-order electron loops are shown in Fig. 4, where, for the sake of clarity, we assumed an infinite pulse length for the illustrations. However, all subsequent graphics are created taking into account the finite pulse width $\tau_p = 10 \text{ fs}$. The first-order loop (dashed red line) is described by a circular motion whereas the second-order displacement (solid blue line) follows an ellipse. The elliptic motion arises from the presence and the direction of the magnetization. The direction of rotation is determined by the helicity σ of the light pulse. Here we assumed $\sigma = +1$. Deviations from the circular and elliptic motions result from the transient solutions. These solutions affect the motion of the electron significantly only during the first cycle (orbital period $\simeq 2.7 \text{ fs}$). As a consequence of the symmetry the directions of rotation of the first-order and second-order loops are opposite. The first-order loop




Figure 4. (Color online) Single electron current loops depending on the OAM number l for $I = 2 \cdot 10^{16} \text{ W/cm}^2$ at $t = 0$. The first-order solution is shown as dashed (red) line and the second-order solution is shown as solid (blue) line. Right-handed circularly polarized light ($\sigma = +1$) is considered. Each trajectory corresponds to the electron displacement at the position of maximum laser intensity which differs depending on l .

rotates anti-clockwise and the second-order motion is a clockwise rotation. Therefore, for the case considered here (magnetic garnet films, $4mm$ -symmetry) second-order effects will lead to a weakening of the first-order generated magnetic field because the direction of rotation determines the sign of the light-induced magnetic field. This may not be the general case. Depending on the material properties and on the experimental setup an enhancement of the first-order generated magnetic field by second-order effects might be observed as well. Further, the aforementioned dc-shift of the single-electron current loop in x -direction is another nonlinear effect and shown in Fig. 4. The direction of this dc-shift depends on the direction of the in-plane magnetization but does not alter the oscillatory motion of the electron. Hence, the magnitude of the light-induced magnetic field will not be influenced by optical rectification. Note that the sign of the OAM number l does not influence the direction of rotation of the electron but determines the phase $\propto \exp[i\phi l]$ depending on the position (r, ϕ) at which the electron resides in the frame of the light beam before the light pulse is applied. The electronic




Figure 5. (Color online) L -dependence of the ratio between second-order and first-order light-induced magnetic fields for different intensities (calculated at $t = 0$). The index *max* refers to the maximum value which is taken at $t = 5.4$ fs the time at which the first value of the light-induced magnetic field is calculated (see text for further explanation). Right-handed circularly polarized light is applied ($\sigma = +1$).

displacement depicted in Fig. 4 refers to a peak intensity (at $t = 0$) of $2 \cdot 10^{16} \text{ W/cm}^2$. For lower intensities the effect shown and discussed above occurs as well but the second-order contribution to the total electron displacement is much lower than the first-order contribution. As the first- and second-order generated magnetic fields are proportional to the square of first- and second-order electronic displacements, respectively, the ratio $|B_{\text{ind}}^{(2)}/B_{\text{ind}}^{(1)}|$ should decrease for decreasing intensities. This effect is shown in Fig. 5 for different values of L . Further, it can clearly be seen that the ratio shown in Fig. 5 is independent of L if the intensity goes to zero.

The total optically-generated magnetic field $B_{\text{ind}}^{(1)} + B_{\text{ind}}^{(2)}$ is drawn in Fig. 6 for different intensities and L -values. The markers represent the data points calculated after each full cycle the electrons finalize and the solid lines correspond to a fit of the superposition of two exponential functions (referring to $B_{\text{ind}}^{(1)}$ and $B_{\text{ind}}^{(2)}$) to the data points. Obviously, the values of the total magnetic field are always positive in Figs. 6 (a) and 6 (b). Whereas, at sufficient high intensities the total magnetic field can undergo a sign change as shown in Fig. 6 (c). Also note the different orders of magnitude in Figs. 6 (a) - 6 (c). Again it can be observed that the influence of L on the shape of the total magnetic field enhances as the intensity increases. For a quantitative comparison we refer to table 1. In addition, from a fitting of the curves in Fig. 6 we deduce the decay time $\tau^{(1)} = 5.05$ fs referring to $B_{\text{ind}}^{(1)}(t)$ and the decay time $\tau^{(2)} = 2.59$ fs referring to $B_{\text{ind}}^{(2)}(t)$. Taking into account that the exponential decay time of the external field pulse $E(t)$ is assumed to be $\tau_p = 10$ fs and that the first-order magnetic field $B_{\text{ind}}^{(1)}(t) \propto E^2(t)$ and the second-order magnetic field $B_{\text{ind}}^{(2)}(t) \propto E^4(t)$, these values are close to $\tau_p/2$ and $\tau_p/4$ which can be expected theoretically.

To further underline that a change in the optically-generated magnetic field induced




Figure 6. (Color online) Time dependence of the total light-induced magnetic field for different intensities and absolute values of the OAM number $L = |l|$. The dashed vertical line at $t = 5.4$ fs corresponds to two orbital periods as described in section 2.2. The reference intensity is $I_0 = 2 \cdot 10^{14}$ W/cm². Right-handed circularly polarized light is applied ($\sigma = +1$).

Table 1. Listing of the maximum values of the superposition of first- and second-order optically-generated magnetic fields. These values are calculated at 5.4 fs after the application of the laser pulse. Values are given in 10^{-3} Tesla. The value of the reference intensity is $I_0 = 2 \cdot 10^{14}$ W/cm². $L = |l|$ is the absolute value of the OAM number.

	$L = 0$	$L = 1$	$L = 2$	$L = 3$	$L = 4$	$L = 5$	$L = 6$
$I/I_0 = 1$	12	12	12	12	12	12	12
$I/I_0 = 10$	86	106	111	113	116	115	116
$I/I_0 = 100$	-2752	-748	-248	-1	148	240	289

by varying the OAM in terms of the number L is clearly a second-order effect, we present Fig. 7 where the time dependencies of the optically-generated first-order and second-order magnetic fields, $B_{\text{ind}}^{(1)}$ and $B_{\text{ind}}^{(2)}$, are depicted for different L . As is visible $B_{\text{ind}}^{(1)}(t)$ does not depend on $L = |l|$ whereas the magnitude and the sign of $B_{\text{ind}}^{(2)}(t)$ are significantly influenced by changing L .

Additionally, we point out that in the event the laser beam is left-handed circularly

polarized ($\sigma = -1$) both the first-order and the second-order generated magnetic fields will change sign. Consequently, the total optically-induced magnetic field will also undergo a sign change (not shown).

In the present model the second harmonics generation is solely due to the presence of a magnetization. Vice versa the second harmonics will produce the light-induced magnetic field $B_{\text{ind}}^{(2)}$ which influences the magnetic structure. To investigate the effect of the total light-induced magnetic field on the magnetic system we solved the Landau-Lifshitz-Gilbert in Eq. (16) numerically taking into account the effective magnetic field in Eqs. (15) and (17). A static magnetic field $\mathbf{B}_0 = B_0 \hat{\mathbf{e}}_Y$ with $B_0 = 250 \text{ mT}$ was applied. Whereas, the light-induced magnetic fields point into the $\pm Z$ -direction. The corresponding results are shown in Fig. 8 for different intensities. Obviously, the light pulses induce magnetization dynamics in terms of small-angle magnetic excitations. The precession amplitude can be varied by changing the intensity of the laser pulse. Regarding this, a variation of two orders of magnitude of the precession amplitudes is observed for $1 \leq I/I_0 \leq 100$, with $2 \cdot 10^{14} \text{ W/cm}^2$. For $I/I_0 = 100$ the total light-induced magnetic field is negative which is indicated by the excitation of the out-of-plane component of the magnetization m_z . As can be seen in Fig. 8 the oscillations of m_z start into the opposite direction compared with the cases $I/I_0 = 1$ and $I/I_0 = 10$.

Viewing the theoretical results from an experimental side [61, 18], the observed precession amplitudes are not in the experimentally determined order of magnitude. On the one hand, this discrepancy originates from the pulse width $\tau_p = 10 \text{ fs}$ of the single pulse, as applied in the present model. Because of the different time scales of the optical pulse and the precessional dynamics of the magnetization, the short presence of the light-induced magnetic field leads to small amplitudes of the precessing magnetization




Figure 7. (Color online) Comparison of the time dependence of first- and second-order light-induced magnetic fields for different absolute values of the OAM number $L = |l|$ and $I = 2 \cdot 10^{16} \text{ W/cm}^2$. The dashed vertical line at $t = 5.4 \text{ fs}$ corresponds to two orbital periods as described in section 2.2. Right-handed circularly polarized light is applied ($\sigma = +1$).

in the numerical modeling. For pulses which live longer, e.g. considering a pulse width $\tau_p = 100$ fs or a sequence of pulses the precession amplitude would increase. On the other hand, due to computational reasons we assumed a beam waist of $w_0 = 2 \mu\text{m}$. Experimentally a typical value for the beam waist is approximately $100 - 200 \mu\text{m}$. However, as shown theoretically [65], it is possible to exploit self-focussing effects to decrease the waist (and increase the intensity) quite significantly. A larger illuminated area may increase the magnitude of the magnetic field generated by the laser light as well. Fig. 9 shows the predictions for the magnetization dynamics when applying a sequence of 30 identical pulses with pulse width $\tau_p = 10$ fs and a time delay between two subsequent pulses of $\Delta t = 50$ fs assuming a peak intensity of $I = 2 \cdot 10^{16} \text{ W/cm}^2$ at $t = 0$. The $L = 0$ subfigure in Fig. 9 should be compared with the $I/I_0 = 100$ subfigure in Fig. 8. As can be seen, the changes described above lead to a gain of one order of magnitude with regard to the precessional amplitude. It is moreover obvious that the parameter L expressing the OAM of the laser beam determines the sign of the light-induced magnetic field as well as its magnitude. The sign change is indicated by the excitation of the magnetization to the opposite direction in the $L = 0$ case compared to the $L > 0$ cases. We will discuss below that this is a more subtle issue than obvious at first glance. Additionally, going from $L = 0$ to $L = 1$ the absolute value of the magnetization amplitude decreases and increases when further increasing $L > 1$. This behavior can be explained by looking at the curves plotted in Fig. 5 and the values given in table 1. Considering the $L = 0$ case a large negative magnetic field is observed after the first full cycle of the electron motion at $t = 5.4$ fs, see table 1, followed by two smaller values after the second loop (at $t = 8.1$ fs) and the third loop (at $t = 10.8$ fs). All subsequent values calculated at increments of $\Delta t = 2.7$ fs are positive but smaller




Figure 8. Numerical solution of the Landau-Lifshitz-Gilbert equation for different intensities and $L = 0$. The reference intensity $I_0 = 2 \cdot 10^{14} \text{ W/cm}^2$ as well as $I = I(E_0, t = 0)$ which is varied by varying the electrical field strength E_0 are taken at $t = 0$. The applied effective magnetic field is given in Eqs. (15) and (17).




Figure 9. Numerical solution of the Landau-Lifshitz-Gilbert equation for a sequence of 30 pulses with peak intensity $I = 2 \cdot 10^{16} \text{ W/cm}^2$ at $t = 0$.

in magnitude. However, the total magnetic field exhibits negative values for $L = 1, 2, 3$ as well, but, in contrast to the $L = 0$ behavior, this cannot be monitored by observing the magnetization dynamics on the picosecond-timescale as shown in the corresponding simulations in Fig. 9. For the $L = 1, 2, 3$ cases the optically-induced magnetic field becomes positive for all subsequent cyclic motions of the electrons. This circumstance cancels the negative field corresponding to $t = 5.4 \text{ fs}$ as the second-order magnetic field decays twice as fast as the first-order magnetic field, i.e. $\tau^{(2)} \approx \tau^{(1)}/2$. The occurrence that the $L = 1$ case offers the smallest amplitude of the magnetization of all shown examples in Fig. 9 arises from those cancellation effects during the first few time steps. For a comparison of the first- and second-order magnetic fields at $t = 5.4 \text{ fs}$ for different L we again refer to Fig. 5 (cf. also the behavior of the total magnetic field shown in Fig. 6 (c)).

We infer from these simulations that the light beams with OAM may in principle generate fs magnetic field pulses that can be used to coherently control the magnetization in the manner suggested in Ref.[66, 67, 68], where it was also shown that on this time scale the control scheme is robust to thermal fluctuations.

Finally, we briefly address the influence of the in-plane orientation of the magnetization. Rotating the magnetization by an angle ϕ_{rot} away from the $\hat{e}_Y = y$ -direction would change the equation of motion of the second-order displacement in Eq. (12) because of the contribution of the tensor components $\Gamma_{\alpha\beta\gamma x}$ in Eqs. (11) and

(12) which would vanish for $\phi_{\text{rot}} = 0$, that is $\mathbf{M} = M_s \hat{\mathbf{e}}_Y = M_s \mathbf{y}$ and $M_x = 0$. For a finite angle of rotation the magnetization components $M_x = M_s \cos \phi_{\text{rot}}$ and $M_y = M_s \sin \phi_{\text{rot}}$ should be considered instead. This would result in a dc-shift of the single-electron current loop either in x-direction or in y-direction or in both, depending on the rotation angle. In contrast, if $\phi_{\text{rot}} = 0$ as applied in the present study, a dc-shift is only observed in x-direction. Although the detailed dependence of the second-order displacement and the magnetic excitations on the rotation angle ϕ_{rot} is an interesting aspect, this is beyond the scope of the present paper.

4. Conclusion

Nonthermal opto-magnetic effects are intriguing phenomena in condensed matter physics that, on the one hand, bear high potential for promising magnetic devices and applications and pose interesting questions for theory. In the present study we worked out the role of nonlinear effects which are not negligible for intensities in the range of $2 \cdot 10^{14} - 2 \cdot 10^{16} \text{ W/cm}^2$. Utilizing a classical treatment of the laser-driven carrier in a given symmetry environment, it is possible to separate the electron motion into a first-order displacement that is directly proportional to the electrical field of the optical pulse and a second-order displacement that depends on the square of the electrical field. Considering magnetic insulators with a certain symmetry configuration we found that both the first-order and the second-order electron displacement create current loops that generate the light-induced magnetic fields $B_{\text{ind}}^{(1)}$ and $B_{\text{ind}}^{(2)}$. As the direction of rotation of the first-order electron displacement always opposes that of the second-order displacement, the light-induced fields $B_{\text{ind}}^{(1)}$ and $B_{\text{ind}}^{(2)}$ also carry opposite signs. Applying Laguerre-Gaussian laser beams which carry orbital angular momentum characterized by the number l , we showed that the optically-generated magnetic field can be controlled by a variation of $L = |l|$. Thus, in the classical model presented in this paper the light-induced magnetic field depends on the absolute value of the OAM number but is independent of its sign. Hence, the sign of the total magnetic field can be positive or negative and the strength of the light-induced magnetic field can reach several Tesla. In the present study we investigated nonlinear effects for $0 \leq L \leq 6$. Increasing the illuminated area, larger values of L can be studied as well.

Finally, we note that the here reported effect based on the generation of first-order and second-order magnetic fields with opposite signs may change for other crystallographic and/or magnetization induced symmetries. We assume that an enhancement of the first-order magnetic field by the second-order field may occur also in systems with different symmetries. However, nonlinear opto-magnetic effects as investigated in the present paper still need to be verified experimentally.

To verify the predicted phenomena we suggest an optical pump-probe experiment similar to that described in [2] for studying the magnetization dynamics. A high-intensity circularly polarized laser pulse that carries OAM could be used to excite magnetization dynamics which could then be measured by probing the motion of the magnetization

vector with linearly polarized light pulses of much lower intensity. From determining the excitation angle the light-induced magnetic field could be derived. In particular, the variation of the intensity and OAM of the pump pulse should lead to a point where first-order and second-order light induced fields, which have opposite signs, are almost equal in magnitude. If this compensation point is reached the amplitude of the magnetic excitations should be reduced significantly, compare Fig. 9. Therefore, by probing the magnetic changes those intensities and OAM-numbers could be derived.

We hope our investigations will stimulate further studies related to optical as well as electron vortex beams. In particular, it was shown recently within a quantum mechanical theory [47] that electron vortex beams are able to exchange orbital angular momentum with the electrons of the irradiated atom in the dipole as well as quadrupole transitions. Further, the transitions were shown to be independent of the sign of the OAM number which coincides with our results for optical vortex beams interacting with magnetic matter. This similarity is not surprising as in the optical limit charge particle scattering at small momentum transfer amounts to the interaction with photons.

5. Acknowledgments

We benefited from valuable discussions with S Trimper, L Chotorlishvili and R W Chantrell.

References

- [1] J. Stöhr and H. C. Siegmann. *Magnetism - From Fundamentals to Nanoscale Dynamics*. Springer, Berlin, 2006.
- [2] A. Kirilyuk, A.V. Kimel, and T. Rasing. Ultrafast optical manipulation of magnetic order. *Rev. Mod. Phys.*, 82:2731–2784, 2010.
- [3] E. Beauprepaire, J.-C. Merle, A. Daunois, and J.-Y. Bigot. Ultrafast spin dynamics in ferromagnetic nickel. *Phys. Rev. Lett.*, 76:4250, 1996.
- [4] N. Kazantseva, U. Nowak, R. W. Chantrell, J. Hohlfeld, and A. Rebei. Slow recovery of the magnetisation after a sub-picosecond heat pulse. *EPL*, 81:27004, 2008.
- [5] B. Koopmans, M. van Kampen, J. T. Kohlhepp, and W. J. M. de Jonge. Ultrafast magneto-optics in nickel: Magnetism or optics? *Phys. Rev. Lett.*, 85:844–847, 2000.
- [6] K. Vahaplar, A. M. Kalashnikova, A. V. Kimel, D. Hinzke, U. Nowak, R. Chantrell, A. Tsukamoto, A. Itoh, A. Kirilyuk, and Th. Rasing. Ultrafast path for optical magnetization reversal via a strongly nonequilibrium state. *Phys. Rev. Lett.*, 103:117201, 2009.
- [7] I. Radu, K. Vahaplar, C. Stamm, T. Kachel, N. Pontius, H. A. Durr, T. A. Ostler, J. Barker, R. F. L. Evans, R. W. Chantrell, A. Tsukamoto, A. Itoh, A. Kirilyuk, Th. Rasing, and A. V. Kimel. Transient ferromagnetic-like state mediating ultrafast reversal of antiferromagnetically coupled spins. *Nature*, 472:205, 2011.
- [8] T.A. Ostler, J. Barker, R.F.L. Evans, R.W. Chantrell, U. Atxitia, O. Chubykalo-Fesenko, S. El Moussaoui, L. Le Guyader, E. Mengotti, L.J. Heyderman, F. Nolting, A. Tsukamoto, A. Itoh, D. Afanasiev, B.A. Ivanov, A.M. Kalashnikova, K. Vahaplar, J. Mentink, A. Kirilyuk, Th. Rasing, and A.V. Kimel. Ultrafast heating as a sufficient stimulus for magnetization reversal in a ferrimagnet. *Nat. Commun.*, 3:666, 2012.
- [9] K. Vahaplar, A. M. Kalashnikova, A. V. Kimel, S. Gerlach, D. Hinzke, U. Nowak, R. Chantrell, A. Tsukamoto, A. Itoh, A. Kirilyuk, and Th. Rasing. All-optical magnetization reversal by

- circularly polarized laser pulses: Experiment and multiscale modeling. *Phys. Rev. B*, 85:104402, 2012.
- [10] Y. R. Shen. *The Principles of Nonlinear Optics*. John Wiley & Sons, 1984.
 - [11] A. M. Kalashnikova, A. V. Kimel, R. V. Pisarev, V. N. Gridnev, A. Kirilyuk, and Th. Rasing. Impulsive generation of coherent magnons by linearly polarized light in the easy-plane antiferromagnet FeBO_3 . *Phys. Rev. Lett.*, 99:167205, 2007.
 - [12] V. N. Gridnev. Phenomenological theory for coherent magnon generation through impulsive stimulated Raman scattering. *Phys. Rev. B*, 77:094426, 2008.
 - [13] L. P. Pitaevskii. Electric forces in a transparent dispersive medium. *Sov. Phys. JETP*, 12:1008–1013, 1961.
 - [14] J. P. van der Ziel, P. S. Pershan, and L. D. Malmstrom. Optically-induced magnetization resulting from the inverse faraday effect. *Phys. Rev. Lett.*, 15:190–193, 1965.
 - [15] P. S. Pershan, J. P. van der Ziel, and L. D. Malmstrom. Theoretical discussion of the inverse Faraday effect, Raman scattering, and related phenomena. *Phys. Rev.*, 143:574–583, 1966.
 - [16] L. D. Landau, E.M. Lifshitz, and L.P. Pitaevskii. *Electrodynamics of continuous media*. Pergamon Press, Oxford, 1989.
 - [17] A. V. Kimel, A. Kirilyuk, P. A. Usachev, R. V. Pisarev, A. M. Balbashov, and Th. Rasing. Ultrafast non-thermal control of magnetization by instantaneous photomagnetic pulses. *Nature*, 435(7042):655–657, June 2005.
 - [18] Fredrik Hansteen, Alexey Kimel, Andrei Kirilyuk, and Theo Rasing. Nonthermal ultrafast optical control of the magnetization in garnet films. *Phys. Rev. B*, 73:014421, 2006.
 - [19] Daniel Steil, Sabine Alebrand, Alexander Hassdenteufel, Mirko Cinchetti, and Martin Aeschlimann. All-optical magnetization recording by tailoring optical excitation parameters. *Phys. Rev. B*, 84:224408, 2011.
 - [20] T. Makino, F. Liu, T. Yamasaki, Y. Kozuka, K. Ueno, A. Tsukazaki, T. Fukumura, Y. Kong, and M. Kawasaki. Ultrafast optical control of magnetization in euo thin films. *Phys. Rev. B*, 86:064403, 2012.
 - [21] R. V. Mikhaylovskiy, E. Hendry, and V. V. Kruglyak. Ultrafast inverse faraday effect in a paramagnetic terbium gallium garnet crystal. *Phys. Rev. B*, 86:100405, 2012.
 - [22] M. I. Bakunov, R. V. Mikhaylovskiy, and S. B. Bodrov. Probing ultrafast optomagnetism by terahertz cherenkov radiation. *Phys. Rev. B*, 86:134405, 2012.
 - [23] R. Hertel. Theory of the inverse Faraday effect in metals. *J. Mag. Mag. Mat.*, 303:L1 – L4, 2006.
 - [24] Hui-Liang Zhang, Yan-Zhong Wang, and Xiang-Jun Chen. A simple explanation for the inverse Faraday effect in metals. *J. Mag. Mag. Mat.*, 321(24):L73 – L74, 2009.
 - [25] S. R. Woodford. Conservation of angular momentum and the inverse Faraday effect. *Phys. Rev. B*, 79:212412, 2009.
 - [26] T. Yoshino. Simple theory of the inverse Faraday effect with relationship to optical constants n and k . *J. Mag. Mag. Mat.*, 323:2531–2532, 2011.
 - [27] Katsuhisa Taguchi and Gen Tatara. Theory of inverse Faraday effect in a disordered metal in the terahertz regime. *Phys. Rev. B*, 84:174433, 2011.
 - [28] D. Popova, A. Bringer, and S. Blügel. Theoretical investigation of the inverse Faraday effect via a stimulated Raman scattering process. *Phys. Rev. B*, 85:094419, 2012.
 - [29] Katsuhisa Taguchi, Jun-ichiro Ohe, and Gen Tatara. Ultrafast magnetic vortex core switching driven by the topological inverse faraday effect. *Phys. Rev. Lett.*, 109:127204, Sep 2012.
 - [30] Z.-G. Zhu, C.-L. Jia, and J. Berakdar. Proposal for fast optical control of spin dynamics in a quantum wire. *Phys. Rev. B*, 82:235304, 2010.
 - [31] A. Matos-Abiague and J. Berakdar. Photoinduced charge currents in mesoscopic rings. *Phys. Rev. Lett.*, 94:166801, 2005.
 - [32] A. Matos-Abiague and J. Berakdar. Ultrafast build-up of polarization in mesoscopic rings. *Europhys. Lett.*, 69(2):277, 2005.
 - [33] A. S. Moskalenko and J. Berakdar. Light-induced valley currents and magnetization in graphene

- rings. *Phys. Rev. B*, 80:193407, 2009.
- [34] A. S. Moskalenko, A. Matos-Abiague, and J. Berakdar. Revivals, collapses, and magnetic-pulse generation in quantum rings. *Phys. Rev. B*, 74:161303, 2006.
 - [35] L. Allen, M. W. Beijersbergen, R. J. C. Spreeuw, and J. P. Woerdman. Orbital angular momentum of light and the transformation of laguerre-gaussian laser modes. *Phys. Rev. A*, 45:8185–8189, 1992.
 - [36] L. Allen, M.J. Padgett, and M. Babiker. The orbital angular momentum of light. *Prog. Opt.*, 39:291 – 372, 1999.
 - [37] Gabriel Molina-Terriza, Juan P. Torres, and Lluís Torner. Twisted photons. *Nat. Phys.*, 3(5):305–310, 2007.
 - [38] Konstantin Yu. Bliokh, Yury P. Bliokh, Sergey Savel’ev, and Franco Nori. Semiclassical dynamics of electron wave packet states with phase vortices. *Phys. Rev. Lett.*, 99:190404, 2007.
 - [39] Masaya Uchida and Akira Tonomura. Generation of electron beams carrying orbital angular momentum. *Nature*, 464(7289):737–739, 2010.
 - [40] J. Verbeeck, H. Tian, and P. Schattschneider. Production and application of electron vortex beams. *Nature*, 467(7313):301–304, 2010.
 - [41] Benjamin J. McMorran, Amit Agrawal, Ian M. Anderson, Andrew A. Herzing, Henri J. Lezec, Jabez J. McClelland, and John Unguris. Electron vortex beams with high quanta of orbital angular momentum. *Science*, 331(6014):192–195, 2011.
 - [42] Ebrahim Karimi, Lorenzo Marrucci, Vincenzo Grillo, and Enrico Santamato. Spin-to-orbital angular momentum conversion and spin-polarization filtering in electron beams. *Phys. Rev. Lett.*, 108:044801, Jan 2012.
 - [43] P. Schattschneider, M. Stöger-Pollach, and J. Verbeeck. Novel vortex generator and mode converter for electron beams. *Phys. Rev. Lett.*, 109:084801, Aug 2012.
 - [44] L. Clark, A. Béch , G. Guzzinati, A. Lubk, M. Mazilu, R. Van Boxem, and J. Verbeeck. Exploiting lens aberrations to create electron-vortex beams. *Phys. Rev. Lett.*, 111:064801, Aug 2013.
 - [45] J. Verbeeck, P. Schattschneider, S. Lazar, M. St ger-Pollach, S. L ffler, A. Steiger-Thirsfeld, and G. Van Tendeloo. Atomic scale electron vortices for nanoresearch. *Appl. Phys. Lett.*, 99(20):203109, 2011.
 - [46] Konstantin Y. Bliokh, Mark R. Dennis, and Franco Nori. Relativistic electron vortex beams: Angular momentum and spin-orbit interaction. *Phys. Rev. Lett.*, 107:174802, Oct 2011.
 - [47] Sophia Lloyd, Mohamed Babiker, and Jun Yuan. Quantized orbital angular momentum transfer and magnetic dichroism in the interaction of electron vortices with matter. *Phys. Rev. Lett.*, 108:074802, 2012.
 - [48] J. Yuan, S. M. Lloyd, and M. Babiker. Chiral-specific electron-vortex-beam spectroscopy. *Phys. Rev. A*, 88:031801, Sep 2013.
 - [49] M. Babiker, C. R. Bennett, D. L. Andrews, and L. C. D vila Romero. Orbital angular momentum exchange in the interaction of twisted light with molecules. *Phys. Rev. Lett.*, 89:143601, 2002.
 - [50] F. Araoka, T. Verbiest, K. Clays, and A. Persoons. Interactions of twisted light with chiral molecules: An experimental investigation. *Phys. Rev. A*, 71:055401, 2005.
 - [51] W. L ffler, D. J. Broer, and J. P. Woerdman. Circular dichroism of cholesteric polymers and the orbital angular momentum of light. *Phys. Rev. A*, 83:065801, 2011.
 - [52] R. W. Boyd. *Nonlinear Optics*. Elsevier, 2008.
 - [53] Ru-Pin Pan, H. D. Wei, and Y. R. Shen. Optical second-harmonic generation from magnetized surfaces. *Phys. Rev. B*, 39:1229–1234, 1989.
 - [54] R. V. Pisarev, B. B. Krichevstov, V. N. Gridnev, V. P. Klin, D. Fr hlich, and Ch. Pahlke-Lerch. Optical second-harmonic generation in magnetic garnet thin films. *J Phys. Cond Mat.*, 5:8621–8628, 1993.
 - [55] V. V. Pavlov, R. V. Pisarev, A. Kirilyuk, and Th. Rasing. Observation of a transversal nonlinear magneto-optical effect in thin magnetic garnet films. *Phys. Rev. Lett.*, 78:2004–2007, 1997.
 - [56] A. Kirilyuk, V. V. Pavlov, R. V. Pisarev, and Th. Rasing. Asymmetry of second harmonic

- generation in magnetic thin films under circular optical excitation. *Phys. Rev. B*, 61:R3796–R3799, 2000.
- [57] V. N. Gridnev, V. V. Pavlov, R. V. Pisarev, A. Kirilyuk, and Th. Rasing. Second harmonic generation in anisotropic magnetic films. *Phys. Rev. B*, 63:184407, 2001.
 - [58] Fredrik Hansteen, Ola Hunderi, Tom Henning Johansen, Andrei Kirilyuk, and Theo Rasing. Selective surface/interface characterization of thin garnet films by magnetization-induced second-harmonic generation. *Phys. Rev. B*, 70:094408, 2004.
 - [59] K. Köksal and J. Berakdar. Charge-current generation in atomic systems induced by optical vortices. *Phys. Rev. A*, 86:063812, 2012.
 - [60] G. F. Quinteiro, P. I. Tamborenea, and J. Berakdar. Orbital and spin dynamics of intraband electrons in quantum rings driven by twisted light. *Opt. Express*, 19(27):26733–26741, 2011.
 - [61] Fredrik Hansteen, Alexey Kimel, Andrei Kirilyuk, and Theo Rasing. Femtosecond photomagnetic switching of spins in ferrimagnetic garnet films. *Phys. Rev. Lett.*, 95:047402, 2005.
 - [62] M. Bass, P. A. Franken, J. F. Ward, and G. Weinreich. Optical rectification. *Phys. Rev. Lett.*, 9:446–448, 1962.
 - [63] L. Landau and E. Lifshitz. On the theory of the dispersion of magnetic permeability in ferromagnetic bodies. *Zeitschr. d. Sowj.*, 8:153, 1935.
 - [64] T. L. Gilbert. A phenomenological theory of damping in ferromagnetic materials. *IEEE Trans. Magn.*, 40:3443, 2004.
 - [65] Anita Thakur and Jamal Berakdar. Self-focusing and defocusing of twisted light in non-linear media. *Opt. Express*, 18(26):27691–27696, 2010.
 - [66] A. Sukhov and J. Berakdar. Local control of ultrafast dynamics of magnetic nanoparticles. *Phys. Rev. Lett.*, 102:057204, 2009.
 - [67] A. Sukhov and J. Berakdar. Steering magnetization dynamics of nanoparticles with ultrashort pulses. *Phys. Rev. B*, 79:134433, 2009.
 - [68] A. Sukhov and J. Berakdar. Influence offield orientation on the magnetization dynamics of nanoparticles. *Appl. Phys. A*, 98(4):837–842, 2010.