

Reverse Fingerprinting

Christian A. Gorke
University of Mannheim
Mannheim, Germany
mail@christiangorke.de

Frederik Armknecht
University of Mannheim
Mannheim, Germany
armknecht@uni-mannheim.de

Abstract—Software connected to the Internet is an attractive target for attackers: as soon as a security flaw is known, services may be taken under attack. In contrast, software developers release updates to add further features and fix flaws in order to increase its security. Consequently, a user of the software wants to have the latest secure version running. However, if the software is provided as a service, e.g., as part of the cloud, the user relies on the service provider (SP) to perform such updates. But when asking for the software version, the user has to trust the output of SP or his software. Latter may be malformed, since updating software costs time and money, i.e., in comparison to changing a (false) version string.

The question rises how a client of a software service can provably determine the real software version of the running service at the SP, also known as Remote Software Identification (RSI). While existing tools provide an answer, they can be tricked by the service to output any forged string because they rely on the information handed directly by the SP. We solve the problem of RSI by introducing Reverse Fingerprinting (RFP), a novel challenge-response scheme which employs the evaluation of inherit functions of software versions depending on certain inputs. That is, RFP does not rely on version number APIs but employs a database consisting of function inputs and according outputs and combines them with a strategy and a randomness source to provably determine the version number. We also provide a theoretical framework for RSI and RFP, and describe how to create databases and strategies. Additionally, RFP can be securely outsourced to a third party, called the auditor, to take away the burden of the user while respecting liability. We also provide an implementation and API to perform RFP in practice, showing that most of the providers have installed the latest versions.

Index Terms—Fingerprinting, Software Versioning, Remote Software Identification, Cloud Security

I. INTRODUCTION

Computers are present in various forms in our everyday life, for example desktop PCs, laptops, servers, smartphones, watches, TVs, routers, surveillance cameras, or even cars. A computer can be seen as a system that consists of storage, computational power, and interfaces to send and receive messages. Due to smart homes, smart grids, and the Internet of things, the amount of connected devices and computers will rise even more in the years to come.

At the end, most computers rely on software to perform nearly any task which also enables them to communicate with each other, especially over a network like the Internet. Therefore, from a connection point of view, any computer on the Internet is somehow connected to any other computer on the Internet. This allows for attacks from around the world,

resulting in security exploits such as data breaches, denial of service attacks, and credential phishing. In most cases, security faults exists due to insecure software, allowing attackers to perform actions they would not be able to do otherwise. Services and applications which run on the (public) cloud have negligible downtime and hence are prone to attacks. For example, authenticating to a service, reading and writing data, or performing computations and spreading to other systems. One reason for this situation is that the software employed today is very complex, reaching up to millions of lines of code for a single program. Hence, software is difficult to manage and verify at scale regarding their security. On the other hand, software developers often provide updates and patches to enhance and further secure their products. These should be installed as soon as possible to prevent attacks, especially on systems connected to the Internet. Unfortunately, there is also software running which is not maintained anymore and the only option for a user to be secure may be to switch to another software.

Since the advent of cloud computing, software is offered by cloud providers as a service (CSP, cloud service provider), for example Software at a Service (SaaS) or Platform as a Service (PaaS). In those cases, the user does not administrate the software and relies on the provider to install updates.

Due to the advancements in browser technology, web services and applications have become a central part of computer usage and hence an attractive target for hackers, since they often are publicly accessible. Services running on the Internet or a cloud cover a range of applications, for example the popular content management system (CMS) Wordpress [1], the most used programming language on the web, PHP [2] (about 79% of all web pages [3]), databases like MySQL [4], or services used by the system such as SMTP [5]. To offer a fair usage, these services have to be available over the Internet all the time at any place. This, however, attracts attackers while continuously new security flaws are discovered. For example, the CVE database contains over 6000 vulnerabilities for PHP alone [6]. Besides flaws, new versions with vastly improved security features are released that should be used over old versions. Additionally, some versions like PHP 5 and 7.0 will be no longer supported and should be updated as soon as possible [7]. Distributed public services also must be updated to fix security flaws, such as Bitcoin to prevent direct financial loss [8].

In conclusion, updating software is a foundation of todays

security and part of the Internet in general. Due to the service oriented structure of the cloud updating becomes the task of the service provider, who, in turn, wants to minimize costs and avoid configuration and dependency changes. If the provider is careless, there will be time windows for attacks. To cover this problem, CSPs blank out the version information on the service, i.e., employing security by obfuscation. But this makes it also difficult for the honest customer who may wonder if the most recent software version is running on the service, e.g., to run own applications on top. Of course, the customer can query the provider or the software itself for the version information, but both may answer whatever the provider wants the customer to believe. This is crucial since the customer thinks she gets the version number, while in reality she may be receiving an arbitrary string. Obviously, such a CSP may violate the mutual agreed Service Level Agreements (SLA), but customer may need some time to detect this behavior.

Ultimately, it comes down to the following question: *How can a customer of a remote software reliably and efficiently prove that the service provider is behaving correctly, i.e., runs software in the correct version?* In other words, the customer's goal is to identify the running software, i.e., determine its version number. Various methods cope with the problem of finding and detecting insecure software, mainly vulnerability scanner (e.g., Nessus [9]) and penetration tests. The first are looking for known security flaws (e.g., CVE) but require certain access roles or structural execution, such as execution on the CSPs machine by the CSP. The latter search for exploits like insufficient parsing of input values. While this can be performed by external parties, default interfaces are used to determine the version number of a software (e.g., by Metasploit [10] or Burp Suite [11]). In fact, existing solutions do not provide a sufficient level of security and can easily be fooled by a malicious service provider (see Section II-D).

In this paper, we will present the Reverse Fingerprinting (RFP) scheme as an answer to the postulated question. RFP does not rely on versioning interfaces or the support of the CSP to determine the software version number. Overall, we give the following contributions:

Formalization of Software and Versioning

We formalize software in general as finite state machines (FSM), where each software is represented by a unique FSM with a version number as label. This allows us to include software development properties, such as co-existent version numbers, i.e., branching, and deprecated software, which otherwise makes differentiating between any software version challenging.

Fingerprinting Techniques and Classification

We analyze existing software fingerprinting techniques and group them into classes. We further show that each existing fingerprinting technique lacks security properties to guarantee determination of the software version number. As a solution, we introduce three novel secure fingerprinting techniques.

Remote Software Identification (RSI)

We give a formal framework for RSI including system model, attacker model, and protocol.

Reverse Fingerprinting (RFP)

As the main contribution of this paper, we present Reverse Fingerprinting, a novel scheme that can be employed as a building block for RSI. It enables auditing of the provider, provably yielding the actual installed software version. RFP leverages a challenge-response protocol that relies on intrinsic functions of each individual software version to distinguish between them. A specifically created database holds all tests, which are applied using various strategies resulting in a sequence of tests. Furthermore, RFP randomizes challenges, verifies time constraints of responses, and is applicable over multiple interfaces and software types. We also present extensions of RFP, such as including an auditor to take away computational and storage burden of the customer.

Formal Security Analysis

To the best of our knowledge, we are the first providing a security analysis of fingerprinting techniques and an RSI scheme, i.e., RFP. We show that RFP is secure against CSP response caching and precomputation, proxy-forwarding of challenges, and erroneous halts, while determining reliably the remote software version.

Implementation and Real-World-Applicability

We provide insights in how to build a database for RFP and give examples for strategies, which describe the order to perform software version dependent tests. Additionally, we apply RFP to real-world applications and show that RFP increases the security overall.

II. REAL-WORLD SITUATION

We will now define software versioning, fingerprinting, and software identification as foundation for following sections. Furthermore, we summarize state of the art fingerprinting techniques and demonstrate their shortcomings with a practical attack.

A. Software Versioning

For now, let software be an algorithm or a machine which is in some state, receives inputs, performs processing, changes to other states, and yields an output. We give a formal definition of software in Section III. When a software reaches a certain state, it gets assigned a unique label.

Definition 1 (Software Version and Software Family): A *software version* is a label, e.g., a text string or a number, assigned by the software developer that uniquely identifies a certain state of a software. Each software belongs to a set of softwares, called a *software family*, where each member of the set has the same software version ancestor.

A software version label may consist of both a name in and a number, e.g. Windows Vista for Windows 6.0 Build 6000. However, most modern software sticks to semantic versioning

[12] for releases. Briefly, a version number is formatted as `Major.Minor.Patch`, where `Major`, `Minor`, and `Patch` are numbers. `Major` is increased when incompatible API changes are made, `Minor` when backwards-compatible functionalities are added, and `Patch` when backwards-compatible bugs are fixed. At the end, we are interested in the version number, not the label.

Let $v := (v_{(0)}, v_{(1)}, v_{(2)})$ be a software version, where $v_{(0)}, v_{(1)}, v_{(2)}$ are elements from a totally ordered set, e.g., $\mathbb{N}_0$, represented by `Major`, `Minor`, and `Patch`. Let $\mathcal{V}$ be the set of all software versions belonging to the same software family. For $v, v' \in \mathcal{V}$ it holds

$$v < v' \iff \begin{aligned} & (v_{(0)} < v'_{(0)}) \quad \text{or} \\ & (v_{(0)} = v'_{(0)} \wedge v_{(1)} < v'_{(1)}) \quad \text{or} \\ & (v_{(0)} = v'_{(0)} \wedge v_{(1)} = v'_{(1)} \wedge v_{(2)} < v'_{(2)}), \end{aligned}$$

otherwise we have $v \geq v'$. Note that we can map any software version format to the given structure.

B. Fingerprinting

The identity of an entity, e.g., a person or an object, can be represented by a unique (digital) *fingerprint* of the entity itself. If the identity is not given, a certain amount of information about the entity is required in order to still build such a fingerprint. *Fingerprinting* refers to reliably determining the fingerprint of an entity.

For example, the identity of a user is combined with gathering properties of unique characteristics in order to track the user across multiple websites and devices, in fact relying on browser configurations and behavior of the user to build the fingerprint [13]–[15]. Another example are hash values computed over files – also known as “checksums”. While fingerprinting a user yields the identity of the user, fingerprinting a software results in the software identity, i.e., the software version.

C. Auditing and Software Identification

An enormous variety of different software is used everyday nearly in every part of our life. For example, software is employed on the Internet, the cloud, computers, smartphones, Internet of things, networks, storage, automation, industry, etc. On top, for each use case often multiple software solutions exist, e.g., MySQL [4] or PostgreSQL [16] for a relational database. For nearly each software, new versions are being released continuously, containing new features and fixing security flaws of previous versions.

Since security flaws are discovered and published every day, updating the operating software is crucial to have the latest security updates installed. Hackers and automated attacks regularly exploit outdated software vulnerabilities resulting in data breaches, data loss, or functional disability, to name a few. Furthermore, a software may depend on other software with a certain software versions, implicitly relying on a correct determination of the version number in order to work properly.

Consequently, checking whether the latest software version is running or not is a standard task in almost all auditing processes. Auditing refers to performing a check on the software and to convince the verifying party, e.g., the customer, that the software provider is compliant to some kind of service level agreement (SLA), i.e., providing a software in a certain version. In other words, auditing yields the correct software version of the running software, where correct refers to the most recent version or the version they agreed on in the SLA. Hence, we need to perform fingerprinting of the software to perform this kind of audit, since this will result in the software version. The process of software fingerprinting gives a solution to *Remote Software Identification* (RSI).

D. Shortcomings of State of the Art Solutions

In order to solve the problem of RSI, many different solutions have already been developed and implemented. A description of different implementations and an overview of related work can be found in Section VII. As mentioned before, fingerprinting can be achieved in many different ways, we call a method to obtain a fingerprint a *fingerprint technique*. For software, a fingerprint technique aims to determine the software version of the currently running software. This is usually achieved by sending a request to the running software and evaluating its response to finally output the software version.

To the best of our knowledge, state of the art solutions employ one or more fingerprint techniques out of four different general types of fingerprinting techniques, denoted as class. We now will assign all existing fingerprinting techniques to one of the four classes and elaborate class specific properties. Each fingerprinting technique is described in detail in Appendix A, the according subsection is given in parentheses below.

Class 1: Version Label-Depending Techniques

This class of fingerprinting techniques asks the audited software to yield a static output containing its version label, usually in form of a string, e.g., the footer of a website. The determined software version is the returned label.

Fingerprinting techniques: Version Claim (A1), Version API (A2), Version Specific Features (A3), Sub-Software (A4), and Error Code (A5).

Class 2: Output Function-Depending Techniques

This class of fingerprinting techniques asks the audited software to output certain static values, e.g., one or more files characteristic for a certain version number. Next, these values are evaluated, for example matched by regular expressions or used as input into a hash function (file checksum). At the end, the result is compared to already known values computed beforehand which yields the determined software version.

Fingerprinting techniques: File Structure/Content (B1), File Hash Digest (B2), Sub-Software (A4), and Error Code (A5).

Class 3: Transition Function-Depending Techniques

This class of fingerprinting techniques requires the audited software to perform certain functions that are available only for certain software versions in a static order. Then, multiple requests are employed to deduce a range of software versions.

Fingerprinting technique: Static Function Output (C1).

Class 4: Security Flaw-Depending Techniques

In this class, security flaws of certain software versions are exploited in order to determine the version number. Note that if a security flaw leads to a halt of the software, e.g., crash or deadlock, no further tests can be performed.

Fingerprinting technique: Security Exploit (D1).

Let us briefly discuss the security of these four classes in regard of reliably determining the software version. A full security analysis of all four classes is given in Appendix D1. The first class is forwarding a value being output by the software without any further check, that is the verifier believes everything the software replies. The second class is similar to the first one, with the difference that the output of the software is transformed in some form, e.g., by applying filters. While both classes claim to be software version-dependent, the third class requires not only static values from the software, but also some form of behavior. However, note that this behavior may be precomputed by a malicious software or may be easily¹ malformed, too. Finally, the fourth class is not a reliable choice for fingerprinting, because exploiting a security flaw that is not yet fixed in the installed software version (which may be the case for all but the newest) will (maybe unintentionally) crash the software. Hence, the verifier gains not much information about the actual software version (maybe except that it is not the newest one). To the best of our knowledge, class 3 is only done by one implementation [17], and class 4 is only used by malicious users to attack software.

At the end, no class is fulfilling the goal of RSI if the software or the party running the software is malicious. The reasons are mainly that these techniques are either relying on static values chosen by the provider, i.e., values that do not depend on the randomness of the verifier, or the reply can be precomputed or faked easily.

E. Practical Attack on Fingerprinting Techniques

We will now give an example on how to trick RSI implementations that employ a Class 1 fingerprinting technique, such as Version Claim. As described above and shown in Appendix D1, a Class 1 fingerprint technique is not secure since it relies on fixed strings chosen by the provider.

Let us assume the software provider runs a software that is used by a customer who is going to audit the software. In this example, the software employed is PHP [2] in version 7.1.1 running on the operating system Ubuntu [18] in version

¹For example, an easy to fake function may return a certain configuration value introduced with a given software version.




Fig. 1. The version scanner WhatRuns determines the version number of the PHP engine processing an HTML page. The scanner outputs PHP 20.9.85 (red bordered value) and does not detect the additional Patch information (-car), while in fact PHP 7.1.1 is running. As a side note, version scanners are also tricked by the changed version number of Apache (also 20.9.85).

16.04.3. We have chosen the programming language PHP, since about 79% of all websites are processed by PHP [3]. Next, the provider runs the bash script in Listing 3 (cf. Appendix I) to manipulate the version number of PHP to the value 20.9.85-car, adding even extra version info to Patch. Then, the PHP functions `phpinfo()` and `phpversion()` as well as any related function with the goal to output the software version, will return 20.9.85-car.

At the time of writing, PHP 7 is the highest available major software version of PHP, so the fake is quite obvious. However, as a result every implementation of RSI that relies on static information will yield the faked value instead the real one. As expected, this behavior can be seen by using, for example, the version scanner WhatRuns [19] and visiting an example HTML page containing nothing else than 'Hello World!', see Figure 1. This demonstrates the contradiction of the current state of the art techniques and the goal they try to achieve: reliably determining the actual software version.

III. REMOTE SOFTWARE IDENTIFICATION

In this section, we describe the formal framework for Remote Software Identification (RSI). All communication is done over an authenticated and encrypted channel, e.g., by employing TLS.

A. System Model

We assume that a verifier has remote access to some software hosted by a service provider and wants to determine whether the correct software is running. Due to the fact that access is remote, the only channel of information available is to observe the input-output-behavior of the hosted software. To this end, we model software as a finite state machine with outputs:

Definition 2 (FSM with Outputs): A finite state machine M with outputs (FSM for short) is defined by a six-tuple

$$(\mathcal{Z}, z_0, \Sigma, \Gamma, \delta, \omega)$$

where

- $\mathcal{Z}$ is the set of states with $z_0 \in \mathcal{Z}$ being the start state,
- Σ denotes the (finite) input alphabet,
- Γ denotes the (finite) output alphabet,

- $\delta: \mathcal{Z} \times \Sigma \rightarrow \mathcal{Z}$ is the state transition function, and
- $\omega: \mathcal{Z} \times \Sigma \rightarrow \Gamma$ is the output function.

At the beginning, the FSM M is initialized to state z_0 . Then, the verifier can send input $\sigma \in \Sigma$ to M and receives output $\gamma \in \Gamma$. More formally, assume that M is in some state z and that the user sends an input σ . Then, M produces an output $\gamma = \omega(z, \sigma)$ and updates its state to $\delta(z, \sigma)$.

We extend the notation of the output function as follows to reflect sequences. Given a state $z \in \mathcal{Z}$ and a sequence $\vec{\sigma} = (\sigma_1, \dots, \sigma_n) \in \Sigma^n$, we define

$$\omega(z, \vec{\sigma}) = \vec{\gamma} = (\gamma_1, \dots, \gamma_n)$$

where there exists a sequence of states $z_1, \dots, z_n$ such that $z_1 = z$, $z_{i+1} = \delta(z_i, \sigma_i)$ for $i = 1, \dots, n-1$, and $\gamma_j = \omega(z_j, \sigma_j)$ for $j = 1, \dots, n$. Moreover, we will usually omit the state if we refer to the start state z_0 , that is

$$\omega(\vec{\sigma}) := \omega(z_0, \vec{\sigma}).$$

Sometimes, we need to distinguish between the output functions of different FSMs. In such a case, we will write ω_M instead of ω to make clear that we talk about the output function of a certain FSM M .

Recall that the only information a verifier gets about a FSM is its input-output-behavior. Consequently, we define equivalence of FSMs according to the observable outputs.

Definition 3 (Equivalence of FSMs): Consider two FSMs M and M' , both defined over the same input alphabet Σ and output alphabet Γ . Let $\vec{\sigma} \in \Sigma^*$. We say that M and M' are *equivalent with respect to $\vec{\sigma}$* (expressed by $M \equiv_{\vec{\sigma}} M'$) if $\omega_M(\vec{\sigma}) = \omega_{M'}(\vec{\sigma})$. Analogously, we define for a set $E \subseteq \Sigma^*$ that

$$M \equiv_E M' \iff M \equiv_{\vec{\sigma}} M' \forall \vec{\sigma} \in E.$$

Finally, two FSMs are equivalent, i.e., $M \equiv M'$, if $M \equiv_{\Sigma^*} M'$.

B. Attacker Model

The audited software is operated by the prover P, i.e., software provider, according to some previously agreed on SLA with the customer or verifier. In general, he wants to always let the latest software version. However, this implies installing updates, software, or new configurations which results in system changes that can impact the rest of the system platform and creates a financial burden for the prover. For example, software dependencies may change, configurations will be altered, and functionalities will be added and removed as well. Therefore, the prover is motivated to act economically driven, that is, to reduce the number of system changes. Hence, the rational attacker model applies to the prover. In other words, he may alter the running software to fake a certain software version. For example, by employing *security by obscurity*, the prover might use version blinding, i.e., hide or forge the software's version. Also, the prover could simulate some functions to convince the verifier that another software version is running.

The second party, the verifier V, wants to identify the software operated by the prover and represents a trusted party. When detecting misbehavior by the prover according to the SLA, i.e., a not secure software version, she might for example take legal actions. Observe that learning which software is being run also allows to perform tailored attacks on the service. However, we only focus on determining the identity of the software, the actions performed with this knowledge are out of scope of this work.

C. Remote Software Identification

RSI is defined with respect to a set $\mathcal{M}$ of pairwise non-equivalent FSMs and a target FSM M_{trg} together with two parties: a prover P and a verifier V. Both parties know the specifications of the FSMs contained in $\mathcal{M}$. The prover P is providing to V remote access to a challenge FSM M_{chl} and V has to decide (essentially) if $M_{\text{chl}} = M_{\text{trg}}$. We are going to make this more precise now.

RSI is divided into two phases: a setup phase and a verification phase. We assume that prior to these phases, a set $\mathcal{M}$ of pairwise distinct FSMs and a target FSM $M_{\text{trg}} \in \mathcal{M}$ have been agreed upon.

In the setup phase, P selects a source FSM $M_{\text{src}} \in \mathcal{M}$ and produces a challenge FSM $M_{\text{chl}} := \text{Produce}(M^*) \in \mathcal{M}$ from some FSM $M^* \in \mathcal{M}$. Note that M_{chl} might not be an element of the same software family as M_{src} and M^* anymore, since Produce might produce a FSM that is a new combination of distinct FSMs of the same software family. In the simplest case, it holds that $M_{\text{chl}} = M_{\text{src}}$, but we will also discuss the case that M_{chl} may be a modification of M_{src} , i.e., $M_{\text{chl}} \neq M_{\text{src}}$.

In the verification phase, V interacts with M_{chl} (which is run by P) as described above. That is, V can send inputs $\vec{\sigma}$ to M_{chl} and receives the corresponding outputs $\vec{\gamma}$. We assume furthermore that V can reset M_{chl} , that is to set its state back to z_0 . Eventually, V outputs a decision $\delta \in \{\text{true}, \text{false}\}$ whether it interacts with the correct FSM or not, i.e., if it holds $M_{\text{src}} = M_{\text{trg}}$.

Definition 4 (RSI Protocol, Correctness, and Soundness): Given the set of pairwise distinct FSMs $\mathcal{M}$ and a target FSM $M_{\text{trg}} \in \mathcal{M}$, we define the RSI protocol Π_{RSI} as

$$\Pi_{\text{RSI}}: [V: \vec{\sigma}; P: M_{\text{chl}}, M_{\text{src}}] \longrightarrow [V: \delta; P: \perp],$$

where the verifier V sends the input sequence $\vec{\sigma}$ to the FSM M_{chl} that is controlled by the prover P, as is the FSM M_{src} . At the end, V will output a decision $\delta \in \{\text{true}, \text{false}\}$ which is only true if $M_{\text{src}} = M_{\text{trg}}$. The prover's output is empty ($\perp$). We say V is Π_{RSI} -correct if it holds

$$\Pr[\delta = \text{true} \mid M_{\text{src}} = M_{\text{trg}}] = 1$$

and V is called $\Pi_{\text{RSI}}\text{-}\varepsilon_0$ -sound if it holds

$$\Pr[\delta = \text{true} \mid M_{\text{src}} \neq M_{\text{trg}}] \leq \varepsilon_0,$$

where ε_0 depends on the security parameter λ .

We discuss now the different existing possibilities for enabling an RSI scheme. To this end, we will first focus on

the case that $M_{\text{chl}} = M_{\text{src}}$. That is V is given remote access to an FSM $M_{\text{chl}} \in \mathcal{M}$ and has to decide based on selected inputs $\vec{\sigma}$ and corresponding outputs $\vec{\gamma}$ whether $M_{\text{chl}} = M_{\text{trg}}$. Obviously, the only possible approach for the verifier is to use inputs such that the outputs differ between the different FSMs in order to come to a decision. This gives rise to the following notion.

Definition 5 (Distinguishing Sequence): Let $\mathcal{M}$ be a set of FSMs, all being defined over the same input alphabet Σ and output alphabet Γ , and of size at least two. We call a sequence $\vec{\sigma} \in \Sigma^*$ a *distinguishing sequence* with respect to $\mathcal{M}$ if there exist $M, M' \in \mathcal{M}$ such that $\omega_M(\vec{\sigma}) \neq \omega_{M'}(\vec{\sigma})$. Moreover, we define by $\text{DS}(\mathcal{M}) \subseteq \Sigma^*$ the set of all distinguishing sequences. We say that a sequence $\vec{\sigma} \in \Sigma^*$ is *non-distinguishing* if $\vec{\sigma} \notin \text{DS}(\mathcal{M})$.

The motivation behind distinguishing sequences is that they are the only means for a verifier to solve the RSI problem, i.e., determining if $M_{\text{src}} = M_{\text{trg}}$. In other words, we can restrict to verifiers that only use distinguishing sequences as inputs.

Theorem 1: Consider an RSI instance given by a set $\mathcal{M}$ of pairwise distinct FSMs and a target FSM $M_{\text{trg}} \in \mathcal{M}$. Let V be a verifier for the RSI problem which is Π_{RSI} -correct and $\Pi_{\text{RSI}-\varepsilon_0}$ -sound. Then there exists a verifier V' that is likewise Π_{RSI} -correct and $\Pi_{\text{RSI}-\varepsilon_0}$ -sound and works analogously to V with the only exception that it omits all non-distinguishing sequences used by V.

Proof: We show the claim by specifying V'. Recall that V' knows the specifications of the FSMs contained in $\mathcal{M}$. One consequence is that V' can decide for a given input sequence $\vec{\sigma}$ whether it is a distinguishing sequence or not. This algorithm uses V and simulates all inputs and outputs for V as follows. When V uses as input a distinguishing sequence $\vec{\sigma} \in \text{DS}(\mathcal{M})$, the algorithm V' forwards this input to M_{chl} and the received output back to V. Whenever V uses a non-distinguishing sequence as input, V' computes the corresponding output on its own using the known specifications of the FSMs and returns the result to V. Eventually, when V outputs `true` or `false`, then V' outputs the same value. Obviously, V' perfectly simulates Π_{RSI} for V and hence “inherits” the same correctness and soundness properties. ■

Theorem 1 shows that the task of solving the RSI problem boils down to two procedures for the verifier:

- Design: Find and construct distinguishing sequences for appropriate sub-sets of $\mathcal{M}$;
- Strategy: Decide on a strategy on how to successively sort out candidates for M_{src} (from M_{chl}).

Note that current auditing processes for identifying the software version follow this principle. Asking the software for its version number can be interpreted as making a distinguishing input. However, as pointed out in Section II-E it is easy for a malicious provider to tamper with the software, e.g., to fake the response to the software version request. In the next section, we explain a novel approach for realizing RSI even in the context of more powerful adversaries.

IV. REVERSE FINGERPRINTING

We will first motivate Reverse Fingerprinting (RFP), explain its basic idea, then define the RFP scheme RFP with all including protocols and procedures as well as incorporating software development specific properties, and finally give a security analysis to show that RFP solves the RSI-problem.

Recall that according to the definition of RSI, the provider as prover P grants the verifier V access to $M_{\text{chl}} = \text{Produce}(M_{\text{src}})$. That is, a provider may modify M_{src} in this process to produce M_{chl} , especially it holds then $M_{\text{chl}} \neq M_{\text{src}}$. For example, installing additional software that checks for certain inputs, e.g., that asks for the version number, and returns a forged value. Within the framework explained in the previous section, this would mean that certain input sequences do not yield a distinguishing sequence anymore. As we have shown, it is mandatory for any verification algorithm to design distinguishing sequences. Thus, whether RSI is still possible or not strongly depends on (i) how P can affect the sets of distinguishing sequences and (ii) to what extent one can still design distinguishing sequences.

To illustrate this, let us consider the following example. Let $\mathcal{M} = \{M_0, M_1\}$ be a pair of distinct FSMs over the same input and output alphabets and let $M_{\text{trg}} = M_0$. Assume that P picks as source $M_{\text{src}} = M_1$ but that $M_0 = M_{\text{chl}} = \text{Produce}(M_1)$ holds. That is, P applies a total conversion to M_1 and transforms it into M_0 . Obviously, now it becomes impossible to distinguish between the cases $M_{\text{src}} = M_0$ and $M_{\text{src}} = M_1$. Thus, RSI is only possible if P applies “modest” changes at most to the FSM. This malicious actions bring us to RFP.

A. Basic Idea

We have designed RFP for exactly such cases, where $M_{\text{chl}} \neq M_{\text{src}}$. More precisely, it is based on the observation that extensive modifications of a software would contradict the economic incentives of P. For instance, the total conversion of one FSM into another explained above would not be meaningful as it would be more simple and also cheaper to install M_0 right from the start. The idea of RFP is that without extensive modifications, a software keeps its *intrinsic* functionalities and behavior.

The goal of RFP is to identify the remotely running software (FSM M_{src}), that is to determine its software version by communicating over basic interfaces (FSM M_{chl}).² The result can then be compared to a target software version (FSM M_{trg}) in order to determine if the prearranged software version is running. Hence, RFP is a building block to realize Π_{RSI} and is a new approach to solve the RSI problem. Reverse Fingerprinting incorporates the following features:

- RFP performs multiple times a challenge-response protocol to successively decrease the verifier’s insecurity of the audited software’s version number;

²Please note that the software provider might use RFP to audit himself. This allows him to prove his claims and, e.g., allows for certifications.

- for a challenge, RFP uses input σ to leverage the functionality of *intrinsic* processes of the audited software which are hard to simulate;
- for a response, RFP expects a certain output γ of the audited software within a certain time frame depending on σ and the therein included randomness ϕ ;
- RFP incorporates software versioning hierarchies and software development properties to eliminate false positives;
- at the end, RFP evaluates all tuples of challenges and responses to determine a software version candidate set C ;
- in comparison to state of the art, RFP is secure against caching, pre-computation, proxy-forwarding, and erroneous halts, of course in addition to determining the software version of M_{src} .

B. Reverse Fingerprinting Scheme

First, we will formalize the capabilities of P for the algorithm Produce, that is, simulating behavior of a FSM which is different from M_{src} , i.e., $M_{\text{chl}} \neq M_{\text{src}}$.

Definition 6 (Simulation-Hard Functions): Let $M \in \mathcal{M}$ be a FSM over the input alphabet Σ and output alphabet Γ . We call the union of all state transition functions δ and output functions ω the *set of functions* F of M and denote this by

$$F: \mathcal{Z} \times \Sigma \rightarrow \mathcal{Z} \cup \Gamma,$$

where $\mathcal{Z}$ is the set of states. By F_M we denote the function set of the FSM M . Let $M' = \text{Produce}(M) \in \mathcal{M}$ be a FSM with $F_{M'} \neq F_M$ that is also run by P. We say that P can perform Produce if it matches his economically incentives, that is installing the real target or newer software version will cost at most the same time and/or money for P as implementing or simulating its functions via Produce. Therefore, $F_{M'}$ contains a set of *simulation-hard functions* in respect to P that can not be constructed via Produce, but can only be the identical functions of M . We denote the set of simulation-hard functions by $F_{M'}^* \subset F_{M'}$, or if the FSM is given in the context by

$$F^* \subset F.$$

In other words, simulation-hard functions are inherent functions of a FSM M which can not efficiently be simulated or produced by P via Produce. That is, given a simulation-hard function f of a target FSM M_{trg} , then $M_{\text{chl}} = \text{Produce}(M_{\text{src}})$ will not have the function f , i.e., $F_{M_{\text{trg}}}^* \neq F_{M_{\text{chl}}}^*$, unless $M_{\text{trg}} = M_{\text{src}}$. It follows that this method allows us to distinguish FSMs.

Since RFP aims to determine a candidate set of possible software versions of M_{src} , we will write v_M to denote the software version v of a FSM M . Let $v_M \in \Gamma$ such that it can be an output of M . For the sake of readability, we define a software S to be the tuple of a FSM M and the corresponding version v_M , i.e. $S := (M, v_M)$. Let $\tilde{\mathcal{S}}$ be the set of all softwares and let

$$\mathcal{S} := \mathcal{S}_S = \{S_0, \dots, S_n\} \subset \tilde{\mathcal{S}}$$

denote the *software family* of S , i.e., the set of all valid softwares and corresponding versions belonging to the same software ancestor S , e.g., all PHP versions or all WordPress versions. We assume that the software family is always given by the environment, since the goal of RFP is to distinguish between different software versions, but not to determine the software family. Let further $\mathcal{V} := \mathcal{V}_S$ be the set of all software versions of S .

Recall that a distinguishing sequence $\text{DS}(S)$ is used by the verifier to distinguish between two FSMs of S (see Definition 5). However, due to the attacker model of P and the properties of Produce, a distinguishing sequence may not be able to distinguish between two completely different software versions. That is, a P may construct $M_{\text{chl}} = \text{Produce}(M_{\text{src}})$ by simulating functions of M_{chl} that are not given in the source FSM M_{src} . This motivates the extension of distinguishing sequences by simulation-hard functions given as follows:

Definition 7 (Distinguishing Sequence over Simulation-Hard Functions): Let $\mathcal{S}$ be a given software family and $S \in \mathcal{S}, S' \in \tilde{\mathcal{S}}$ over the same input alphabet Σ and output alphabet Γ . We call a sequence $\vec{\sigma} \in \Sigma^*$ a *distinguishing series over simulation-hard functions* such that $\omega_S(\vec{\sigma}) \neq \omega_{S'}(\vec{\sigma})$, where each output value γ_i depends on a simulation-hard function $f \in F_S^*$. We define by $\text{DSH}(S) \subseteq \Sigma^*$ the set of all distinguishing series over simulation-hard functions for a software S .

Next, we define the RFP scheme RFP that is initiated by the verifier V and consists of three procedures Setup, Test, and Output. An overview of RFP and its subsidiary procedures as well as protocols is depicted in Figure 2.

Definition 8 (RFP Scheme): Let $S_{\text{chl}} := (M_{\text{chl}}, v_{M_{\text{chl}}}) \in \tilde{\mathcal{S}}$ and $S_{\text{src}} := (M_{\text{src}}, v_{M_{\text{src}}}) \in \mathcal{S}$ with $M_{\text{chl}} = \text{Produce}(M_{\text{src}})$ be the softwares hosted by P. We define the *RFP scheme* RFP between V and P as the consecutive procedures Setup, Test, and Output. At the end, V outputs a software candidate set $C \subset \mathcal{S}$ with $S_{\text{src}} \in C$.

We say V is *RFP-correct* if it holds

$$\Pr[v_{S_{\text{src}}} \in C \mid S_{\text{chl}} = \text{Produce}(S_{\text{src}})] = 1$$

and V is called *RFP- ε_1 -sound* if it holds

$$\Pr[v_{S_{\text{src}}} \notin C \mid S_{\text{chl}} = \text{Produce}(S_{\text{src}})] \leq \nu(\varepsilon_1)$$

where ν is a negligible polynomial function in ε_1 depending the security parameter λ . We call RFP *secure* if it is RFP-correct, RFP- ε_1 -sound, Π_{RSI} -correct, and $\Pi_{\text{RSI}}\text{-}\varepsilon_0$ -sound.

In the optimal case, we get $|C| = 1$ in RFP. With the definition of RFP, we are now able to prove that the existing four fingerprinting classes presented in Section II-D are not secure, i.e., RFP-correctness or RFP-soundness are not given for a verifier V. This can immediately be seen since none of the classes relies on inputs of DSH, that is the verifier does not rely on intrinsic functions and hence can be fooled. Please refer to Appendix D1 a detailed analysis of all state of the art fingerprinting techniques. We will now describe the three procedures of Setup, Test, and Output in detail.




Fig. 2. Protocol representation of the RFP scheme RFP between verifier V (user) and prover P (service provider). A database entry $D[S]$ relies on at least one function $f \in \mathcal{F}_I^*(v_S) \cup \mathcal{F}_B^*(v_S) \cup \mathcal{F}_D^*(v_S)$, where v_S is the software version of S (see Section IV-F). The secret and public keys of each party are omitted, and the values of $\mathcal{I}$, S_{trg} , and $\mathcal{S}$ are agreed on in the SLA beforehand. Public values are the sets of all softwares $\tilde{\mathcal{S}}$ and all interfaces $\mathcal{I}^*$. Fingerprinting techniques are involved in the creation of $D_{\mathcal{S}}$.

C. The Setup Procedure

This randomized procedure generates for each the verifier V and provider P a public-private key pair. If a party only deploys symmetric key schemes, the public key is simply set to $\perp$. For the sake of brevity, we implicitly assume for each of the subsequent protocols and procedures that an involved party always uses as inputs its own secret key and the public key of the other party. Furthermore, the set of all softwares $\tilde{\mathcal{S}}$ is produced by the environment and the software family $\mathcal{S} \subset \tilde{\mathcal{S}}$ is given to both parties as well as a target software $S_{\text{trg}} \in \mathcal{S}$ (which, in practice, is chosen beforehand as part of an SLA). By I we denote an interface, that is a (possibly authenticated) communication channel between a party and a software. Let $\mathcal{I}^*$ be the set of all interfaces. We define the procedure Setup between a verifier V and prover P by

Setup: $[V: \perp; P: \perp] \longrightarrow [V: \mathcal{I}, \Phi, \mathcal{D}, \Theta; P: \mathcal{I}, S_{\text{src}}, S_{\text{chl}}]$.

During Setup, V and P first determine which interfaces $\mathcal{I} \subseteq \mathcal{I}^*$ they are able to use as communication channels between

V and S_{chl} and output them. For example, $\mathcal{I}$ may consist of FTP [20] and HTTP [21] with according authentication and implementation details. Different interfaces allow for different communication channels, that is, depending on the software and authorization, certain fingerprinting techniques and simulation-hard functions are available for certain interfaces only. For example, an authenticated channel grants usually more privileges compared to an unauthenticated channel, e.g. customer and guest, respectively. The prover P takes the source software $S_{\text{src}} \in \mathcal{S}$ and computes the challenge software $S_{\text{chl}} = \text{Produce}(S_{\text{src}}) \in \tilde{\mathcal{S}}$, where his goal is to convince the verifier that $S_{\text{chl}} = S_{\text{trg}}$. The verifier V obtains a source of randomness Φ , constructs a set of databases $\mathcal{D}$, and defines a set of strategies Θ . An database $D \in \mathcal{D}$ in RFP is defined as follows:

Definition 9 (Database): Let $\mathcal{S}$ be a given software family and $\mathcal{I} \subseteq \mathcal{I}^*$ be some interfaces agreed on by V and P. Let further $\text{DSH}(\mathcal{S}, I) \subseteq \Sigma_{\mathcal{S}}^*(I)$ be the set of distinguishing sequences over simulation-hard functions for a software S and

an interface $I \in \mathcal{I}$, where $\Sigma_S^*(I) \subseteq \Sigma_S^*$ is the restricted set of all input values for S in respect to I . By $\text{DSH}(S, I)$ we denote the restriction of $\text{DSH}(S)$ to an interface I .

We call $c(S, F_S^*, \Phi, I_c) \in \text{DSH}(S, I_c)$ a randomized *challenge* for a software $S \in \mathcal{S}$ and interface $I_c \in \mathcal{I}$ sent from V to S_{chl} , which employs a randomness source Φ as auxiliary input and depends on at least one simulation-hard function $f \in F_S^*$ of S . We will omit parameters from now on if they are clear from the context.

By $e(c, I_e) \in \omega_S(c)$ we denote the *expected response* from S_{chl} to the challenge c from V for a software $S \in \mathcal{S}$. In general, it holds $I_e \neq I_c$.

Finally, we define a *database* by:

$$D(\mathcal{S}, \mathcal{I}') := \{(c, e, t)_S \mid c = c(S, F_S^*, \Phi, I_c) \in \text{DSH}(S, I_c), \\ e = e(c, I_e) \in \omega_S(c), S \in \mathcal{S}, \\ I_c, I_e \in \mathcal{I}', t \in \mathbb{N}_0\},$$

where t is a number of time units and $\mathcal{I}' \subseteq \mathcal{I}$. A database D is called *perfect*, if it holds $|D| = |\mathcal{S}|$. We abbreviate by $\mathcal{D} := \mathcal{D}_{\mathcal{S}} = \{D(\mathcal{S}, \mathcal{I}') \mid \mathcal{I}' \subseteq \mathcal{I}\}$ the set of all databases for $\mathcal{S}$, and by $D[S] := (c, e, t)_S \in D(\mathcal{S}, \mathcal{I}')$ the database entry belonging to a software $S \in \mathcal{S}$ for some interface.

Note that since the verifier constructs $\mathcal{D}$, he also computes the expected responses. Also, two database entries for two different software versions in the same database may employ four different interfaces. A source of randomness allows to insert random values into a challenge depending on the coins of Φ , which makes the challenge and especially the according correct response hard to predict. Designing a database $D(\mathcal{S}, \mathcal{I}') \in \mathcal{D}$ represents the first task for V resulting from Theorem 1. In Section V-B, we describe how to design a database for RFP.

Finally, a strategy $\theta \in \Theta$ describes a way how to traverse entries in a database D to successively sort out candidates in C to reach S_{src} , depending on the responses given by S_{chl} . In other words, a strategy yields a distinguishing sequence over simulation-hard functions DSH for any $S \in \mathcal{S}$. We will give a formal definition of a strategy below, see Definition 11.

D. The Test Procedure

This randomized procedure takes as input the outputs of Setup, that is the set of interfaces $\mathcal{I}$ for V and P , the source of randomness Φ , set of databases $\mathcal{D}$, and set of strategies Θ for V , and the challenge software S_{chl} for P . At the end, the verifier outputs set of decisions Δ for each software version that has been tested against S_{chl} . We now formally define testing, that is on processing an entry of a database, the verifier performs a challenge-response protocol Π_{RFP} which we define as follows:

Definition 10 (RFP Protocol): Let $\mathcal{S}$ be a given software family, $\delta \in \{\text{true}, \text{false}\}$ be a decision set, and t' be a measure of time units. We define the *RFP protocol* between the verifier V and prover P as

$$\Pi_{\text{RFP}}: [V: D[S], \Phi; P: S_{\text{chl}}] \longrightarrow [V: \delta; P: \perp],$$

for a database entry $D[S] \in D(\mathcal{S}, \mathcal{I})$ with $S \in \mathcal{S}$ and a set of interfaces $\mathcal{I}$, and a randomness source Φ . Π_{RFP} consists of three steps for the verifier V , which we call an *RFP test*:

- 1) send a randomized challenge $c(\phi) \in D[S]$ with $\phi \in_R \Phi$;
- 2) receive a response e' from S_{chl} after t' time units, otherwise set $e' = \perp$ if t' passes some time threshold;
- 3) fetch $e \in D[S]$ and output δ , where $\delta \leftarrow \text{true}$ iff $e' = e$ and $t' \leq t$, otherwise $\delta \leftarrow \text{false}$.

We can now perform a single RFP test via Π_{RFP} , which yields a single outcome δ for a certain software S . First, observe that a challenge c of a database entry depends on S , which in fact means that the intrinsic behavior of S is being tested. However, as we have shown in Section II-D, state of the art fingerprinting techniques will not be sufficient. Hence, we introduce new fingerprinting techniques fulfilling RFP security, see Section V-A. Second, observe that Π_{RFP} will not yield the software version of S_{src} . That is, usually, the amount of software features grows over time with the software versions of $\mathcal{S}$, hence testing a single software S in Π_{RFP} will indeed yield true or false, i.e., if a certain simulation-hard function can be performed correctly, but is not sufficient to determine the software version of S_{src} . Consequently, if it holds $\delta = \text{false}$, we learn that the software version is smaller than the one of S , and in the case of $\delta = \text{true}$, S_{src} might be equal to S , but there might also be a newer version $S' \in \mathcal{S}$ with $v_{S'} > v_S$, for which Π_{RFP} also yields $\delta = \text{true}$. Hence, as a core part of RFP, Π_{RFP} is performed multiple times.

RFP leverages a database of challenges and expected responses in combination with a strategy to produce a certain distinguishing sequence of simulation-hard functions DSH for each $S \in \mathcal{S}$. In other words, each $S \in \mathcal{S}$ can be determined by testing the simulation-hard functions of multiple, different software versions in $\mathcal{S}$ until we get a lower and upper limit for the software version of S_{src} . When performing multiple tests using Π_{RFP} , the verifier tracks each software-decision-pair (S, δ) in a *decision log* Δ . We combine the multiple tests by defining the procedure Test as follows:

$$\text{Test}: [V: \mathcal{I}, \Phi, \mathcal{D}, \Theta; P: \mathcal{I}, S_{\text{chl}}] \longrightarrow [V: \Delta; P: \perp].$$

Essentially, Test consists of multiple executions of Π_{RFP} , where the order of the softwares that are being tested by Π_{RFP} is defined by a strategy $\theta \in \Theta$. We will now explain the general concept of a strategy in detail.

At the beginning, when performing Π_{RFP} for the first time, V needs to choose a $S_0 \in \mathcal{S}$ to start from. Then, depending on the outcome δ_0 of Π_{RFP} for S_0 and a given database, the task of choosing the next software S_1 is to be solved. In other words, V searches for S_1 depending on (S_0, δ_0) . In general, we want to determine the next software that has to be tested to reduce the set of possible software candidates for the source software S_{src} . More formally, we are looking for S_i for a given log $\Delta = \{(S_0, \delta_0), \dots, (S_{i-1}, \delta_{i-1})\}$. We solve this problem by using a strategy which we formally define as follows:

Definition 11 (Strategy): Let S_{chl} be the challenge software hosted by P and $\Delta = \emptyset$. We denote by $\delta_{\Pi_{\text{RFP}}(S)}$ the output of

Π_{RFP} for a software $S \in \mathcal{S}$, a given randomness source ϕ , a database $D(\mathcal{S}, \mathcal{I}) \in \mathcal{D}$ for a software family $\mathcal{S}$ and interfaces $\mathcal{I}$.

Then, a *strategy* is defined as a method that describes, based on Δ and $D(\mathcal{S}, \mathcal{I})$, which software $S \in \mathcal{S}$ is selected for the next run of Π_{RFP} .

Let $C, C' \subset \mathcal{S}$ be candidate sets of possible software versions containing S_{src} , deduced from the current decision log Δ and the upcoming one $\Delta \cup (S, \delta_{\Pi_{\text{RFP}}(S)})$, respectively. We call a strategy *efficient* if it holds $|C'| < |C|$.

If there exists no further $S \in \mathcal{S}$ such that the number of elements in C can be reduced (or a certain threshold of executions of Π_{RFP} has been performed), the strategy commands to end the procedure Test.

Please observe that the dependency on a database for a strategy is required, since the database may not be perfect, i.e., entries for some softwares may be missing. While selecting *any* software version for testing is easy, finding *efficient* strategies is desired since this reduces the time required as well as communication and storage overhead for V. Hence, we say an *optimal* strategy is represented by requiring the minimum amount of tests to find S_{src} , i.e., the distinguishing series of simulation-hard functions DSH for the optimal strategy is at most as long as any other one DSH'. Note that if $\Delta = \perp$, choosing the starting software version S_0 is crucial and influences the DSH strongly. For example, starting with the highest software version in D and successively testing step by step smaller software versions will only be an efficient strategy if S_{src} has a very recent software version. At the end, Test employs multiple executions of Π_{RFP} which produces over time a distinguishing sequence over simulation-hard functions of S_{src} , i.e., DSH(S_{src}). Creating a strategy $\theta \in \Theta$ represents the second task for V resulting from Theorem 1. We give more information on how to construct strategies in Section V-C.

Observe that given two softwares $S, S' \in \mathcal{S}$ with $v_S < v_{S'}$, this does not necessarily imply that S is older or more insecure than S' and furthermore it might hold $|F(S)| > |F(S')|$. This is important for the design of a strategy, since there is often more than one possible “next software version” to choose from, i.e., the DSH is not always continuous with respect to the software version number. We cope with the problem of software version hierarchies and software development in Section IV-F.

E. The Output Procedure

This procedure gathers the results that have been produced by Test and outputs a candidate set $C \subset \mathcal{S}$ which contains S_{src} . Since we have stored the decision outputs of all Π_{RFP} runs in Δ , this procedure consists of two steps: first, a lower and upper bound of software versions is computed based on Δ and the software version hierarchy. Second, given these bounds, we determine all $S \in \mathcal{S}$ that lie in between the bounds, finally resulting in C . We denote both steps as the procedure Output defined as follows:

Output: $[V: \Delta; P: \perp] \longrightarrow [V: C; P: \perp]$.

This procedure is performed by V and independent of P with the input being the log of decisions Δ coming from the procedure Test. With Output, the verifier V outputs a candidate set $C \subset \mathcal{S}$ with $S_{\text{src}} \in C$, solving the RSI-problem. Note that the cardinality of C may be greater than one, since there can be $S, S' \in S_{\text{src}}$ with $S \equiv S'$, as mentioned above in Section IV-C.

F. Distinguishing Software Hierarchies

Recall that the goal of the verifier is to leverage the set of simulation-hard functions of each software $S \in \mathcal{S}$ to construct a distinguish series, i.e., to distinguish between single software versions. However, as mentioned before, there exists no simple ordering of versions of the softwares of a software family. In other words, how does the verifier know which software version is based on other software versions? Here, two challenges arise due to software development properties, namely software branches and deprecated functions. Together with simulation-hard functions, these three describe a *software hierarchy* over $\mathcal{S}$. Usually, the set of functions of a newer software version contains all functions of older software versions. However, due to software hierarchies, the version number of one software may be smaller compared to another, while it might be a newer software. More formally, while there is a ordering on version numbers, this does not translate to the set of functions of a software, i.e., there exists $S, S' \in \mathcal{S}$ with $v_S > v_{S'} \not\Rightarrow F_S \supset F_{S'}$. Plus, when a strategy $\theta \in \Theta$ chooses the next software $S \in \mathcal{S}$ to test with Π_{RFP} , then this decision is based on a database $D \in \mathcal{D}$, which entries must reflect the software hierarchies. Therefore, this raises the question on how to map software hierarchies to version fingerprinting, since higher software versions does not always implicates more or newer functions. We will now describe how to distinguish between software versions in the presence of software hierarchy including software development properties.

Since we will now focus on the version properties of a software, we are using our existing notation but refer to a software via its version v_S instead the software S itself. Let $F(v_S) := F_S$ for a software $S \in \mathcal{S}$. In software development, usually the following holds: After implementing a functionality $f \in F_S$ in a software S , usually all following versions of the same software family will also have implemented f . More formally,

$$f \in F(v) \Rightarrow f \in (F(v) \cap F(v')) \quad \forall v' \geq v, \quad (1)$$

where $v = v_S$ and $v' \in \mathcal{V}$.

Recall that in the protocol Π_{RFP} , the verifier V sends a randomized challenge c , receives the response e' by S_{chl} , and measures the time passed in between as well as compares e' to the expected response e . Since V is essentially testing if S_{chl} can successfully perform a certain, inherent simulation-hard function of a software S , it follows due to equation (1) that if $\delta = \text{true}$ we have $v_{S_{\text{chl}}} \geq v_S$, i.e., the version of the software provided (S_{chl}) is at least the on of the software compared to (S). We denote by $\delta_{\Pi_{\text{RFP}}(S, f)}$ the output of Π_{RFP} depending

on software $S \in \mathcal{S}$ and an employed challenge derived from a function $f \in F_S$:

$$\delta_{\Pi_{\text{RFP}}(S,f)} \leftarrow \begin{cases} \text{true} & \text{if } v_{S_{\text{chl}}} \geq v_S, \\ \text{false} & \text{if } v_{S_{\text{chl}}} < v_S. \end{cases}$$

See Remark 5 on why we decided to use this specific definition of δ .

At the beginning, i.e., when no RFP test has been performed yet, the candidate set of all possible software versions C will be equal to all versions of S , i.e., $C = \mathcal{S}$. Employing Π_{RFP} multiple times to test for different softwares $S \in \mathcal{S}$ using a database will yield a reduced candidate set $C' \subset C$, since the V learns if S_{chl} supports a certain, version intrinsic function of S , or not. The final candidate set will be as small as possible, in the best case it contains only one element.

Definition 12 (Simulation-Hard Intrinsic Functions): For $S \in \mathcal{S}$, let

$$\mathcal{F}^*(S) := \left\{ F_S \setminus \bigcup_{\substack{S' \in \mathcal{S} \\ v_{S'} < v_S}} F_{S'} \right\}. \quad (2)$$

be the set of all *simulation-hard intrinsic* functions of S that are new for this software version, i.e., did not exist in a version before. We set $\mathcal{F}^*(v_S) := \mathcal{F}^*(S)$.

Observe that all next released software versions, i.e., with versions greater than v_S , also incorporate $\mathcal{F}^*(S)$, i.e., $\mathcal{F}^*(v) \subset \mathcal{F}^*(v')$ with $v < v'$, $v, v' \in \mathcal{V}$.

Besides checking for a certain simulation-hard intrinsic function $f \in \mathcal{F}^*(S)$ that is characteristic for that software version (and following), there are two properties of software versioning and development to take into account:

- 1) Software branches, i.e., same function changes are implemented for different version numbers, and
- 2) Deprecated and removed functions, i.e., functions that exist only for a few versions of S .

For each of both properties, equation (1) does not hold anymore. Hence, we will now give new ways to differentiate between all three cases to determine the outcome of Π_{RFP} .

For the following three subsections, we set $\delta_{\Pi_{\text{RFP}}(v_S,f)} := \delta_{\Pi_{\text{RFP}}(S,f)}$, where the challenge employed in Π_{RFP} depends on the function $f \in \mathcal{F}^*(S)$. Further, let $S \in \mathcal{S}$ be a given software and let $v = v_S$.

1) Intrinsic Functions: For a $f \in \mathcal{F}^*(v)$ let the challenge c in Π_{RFP} depend on f . Then, f is an intrinsic simulation-hard function introduced in version v of S , see also Definition 12. We define the *intrinsic set* of S as the set with the intrinsic properties, that is

$$\mathcal{F}_I^*(v) := \mathcal{F}^*(v). \quad (3)$$

Then, with $f \in \mathcal{F}_I^*(v)$, we get

$$\delta_{\Pi_{\text{RFP}}(v,f)} = \begin{cases} \text{true} & \text{if } v_{S_{\text{chl}}} \geq v, \\ \text{false} & \text{if } v_{S_{\text{chl}}} < v. \end{cases}$$

We now come to the other remaining cases.

2) Branch Handling: For $v > v'$ with $v' \in \mathcal{V}$, we might have $\mathcal{F}^*(v) = \mathcal{F}^*(v')$ because both versions are maintained at the same time, but live on different branches, e.g., same value for `Major` but different values for `Minor` or `Patch`. So given a function $f \in \mathcal{F}_I^*(v)$ as in the case for intrinsic functions, we now at the same time also have $f \in \mathcal{F}_I^*(v')$, which is a contradiction to Definition 12. Hence, we need to cope in a new way with this case which we dub *branch detection* for versions of S .

To solve this problem, we additionally store for the entry $D[S]$ in the database a set of branch detecting tests. These are referrers to other database entries, essentially to a version where the branch can be determined using $\mathcal{F}^*$. We now have the following relation between two versions:

$$\mathcal{F}^*(v) = \mathcal{F}^*(v'), \quad v > v'. \quad (4)$$

Recall that $\mathcal{F}^*(v)$ are all simulation-hard intrinsic functions that have been added in version v to S . Hence, equation (4) states that the same features were added to both software versions v and v' . First, let the database entries for v and v' contain a challenge depending on $f \in \mathcal{F}^*(v)$. Second, let the database entry for v contain a branch detecting test referring to version $\hat{v}$. Depending on the difference between v and v' , $\hat{v}$ has the same values `Major` and `Minor` as v , but `Patch` is set to zero; or same `Major` as v and both `Minor` and `Patch` are set to zero. Therefore, $\hat{v} \neq v'$ means that the softwares of v and v' refer to different branch detecting test versions as their ancestors. To illustrate this, example values can be as follows: $v = (7, 2, 9)$, $v' = (7, 1, 21)$, and $\hat{v} = (7, 2, 0)$. We define the *branched set* of S in respect to v' as

$$\mathcal{F}_B^*(v, v') := \left\{ f \in \mathcal{F}^*(v) \cap \mathcal{F}^*(v') \mid v > v', \hat{v} \neq v' \right\}. \quad (5)$$

Then, with $f \in \mathcal{F}_B^*(v, v')$, $g \in \mathcal{F}_I^*(\hat{v})$, we get

$$\delta_{\Pi_{\text{RFP}}(v,f)} = \begin{cases} \text{true} & \text{if } v_{S_{\text{chl}}} \geq v, \\ \text{true} & \text{if } v_{S_{\text{chl}}} \geq v', \\ \text{false} & \text{if } v_{S_{\text{chl}}} < v'. \end{cases}$$

In case of a `true` result, we perform Π_{RFP} a second time, but with parameters $\hat{v}$ and g , and get

$$\delta_{\Pi_{\text{RFP}}(\hat{v},g)} = \begin{cases} \text{true} & \text{if } v_{S_{\text{chl}}} \geq v, \\ \text{false} & \text{if } v_{S_{\text{chl}}} \geq v'. \end{cases}$$

Please note that if there is no $g \in \mathcal{F}_I^*(\hat{v})$, we recursively test $g \in \mathcal{F}_B^*(\hat{v}, v')$ or $g \in \mathcal{F}_D^*(\hat{v}, v')$ (see below) for according $\hat{v}'$ until we reach a version $g \in \mathcal{F}_I^*(\hat{v})$. Further note that if the branch detection test versions are equal of both versions, i.e., $\hat{v} \neq v'$, then both versions are indistinguishable, i.e., $S \equiv S'$ with $v = v_S$ and $v' = v_{S'}$.

3) Deprecated Functions: Suppose there exists an $f \in \mathcal{F}_I^*(v)$, but we also have $f \notin \mathcal{F}_I^*(v')$ with $v' > v$. This is a contradiction to the definition of $\mathcal{F}_I^*$. Furthermore, f also cannot be an element of $\mathcal{F}_B^*$. In other words, f is only implemented in v . Therefore, we are in the third case representing *deprecated simulation-hard* functions. These are

functions which only exist for a certain amount of consecutive versions, being removed from $\mathcal{S}$ afterwards.

In other words, f exists in a version v for all versions up to another version v'' , but not at any higher version v' . That is, we have $f \in F^*(v)$, $f \in F^*(v'')$, and $f \notin F^*(v')$ with $v \leq v'' < v'$. We define the *deprecated set of $\mathcal{S}$ with respect to v'* as

$$\mathcal{F}_D^*(v, v') := \mathcal{F}^*(v) \setminus \mathcal{F}^*(v'). \quad (6)$$

Note that a function $f \in \mathcal{F}_D^*(v, v')$ can be re-introduced after version v' later on, which requires to analogously adapt this equation.

To incorporate this case in Π_{RFP} , we add to the database for entry $D[S]$ a referrer to a function-deprecated test version, representing a test for version v' , being the version of the first released software S' where f is not anymore part of $\mathcal{S}$ anymore afterwards. Then, with $f \in \mathcal{F}_D^*(v, v')$, $g \in \mathcal{F}_I^*(v')$, we get

$$\delta_{\Pi_{\text{RFP}}(v, f)} = \begin{cases} \text{true} & \text{if } v \leq v_{S_{\text{chl}}} < v', \\ \text{false} & \text{if } v_{S_{\text{chl}}} < v, \\ \text{false} & \text{if } v_{S_{\text{chl}}} \geq v', \end{cases}$$

In case of a `false` result, we perform Π_{RFP} a second time, but with the parameters v' and g , which yields

$$\delta_{\Pi_{\text{RFP}}(v', g)} = \begin{cases} \text{true} & \text{if } v_{S_{\text{chl}}} \geq v', \\ \text{false} & \text{if } v_{S_{\text{chl}}} < v. \end{cases}$$

This may, as in the case for branch detection, be done recursively. Note that there may exist $f \in (\mathcal{F}_B^*(v, v') \cap \mathcal{F}_D^*(v, v'))$ for some $v' \in \mathcal{V}$, representing functions that have been added to different branches and are deprecated at the same time.

G. Security Analysis

For the security analysis of the RFP scheme RFP our goal is to show that it is secure as described in Definition 8. In other words, a verifier V of RFP must fulfill correctness and soundness in respect to both Π_{RSI} and RFP, respectively.

Proof: We first show that RFP is a building block for Π_{RSI} . Assume that V is correct and sound according to RFP. In the SLA, both parties agreed on the target software $S_{\text{trg}} \in \mathcal{S}$. At the end of RFP, V outputs a candidate set $C \subset \mathcal{S}$ with $S_{\text{src}} \in C$. Then, V can compare S_{trg} to C and outputs `true`, if it is contained therein, otherwise `false`. Hence, V is correct and sound according to Π_{RSI} .

Now we are left to show that RFP-correctness and RFP- ε_1 -soundness are given for V . Since RFP executes tests via Π_{RFP} successively for different softwares $S \in \mathcal{S}$, after some time (depending on the strategy) a certain amount of softwares have been tested such that Test yields a decision log Δ which, input into Output, results by computing upper and lower bounds of software versions in a final candidate set C . This is due to the upper and lower bounds reducing the cardinality of C for each step of an efficient strategy, enclosing only S_{src} at the end. This holds as long as the strategy reduces the cardinality

of C at any time, it must not be efficient, but it must be possible to eventually test any software version. Next, let us consider RFP leveraging Class 4 fingerprinting techniques, i.e., security flaw-depending techniques (see Section II-D). This may call a transition δ or output function ω of S_{chl} such that the software runs into an error state $\perp$ and abruptly halts before RFP ends. To prevent this, RFP only employs fingerprinting techniques without transitioning RFP into $\perp$, see Section V-A. Therefore, RFP-correctness is given due to successive tests of inherent functions of S_{trg} on S_{chl} based on named fingerprinting techniques producing a successively reduced candidate set C .

For RFP-soundness, we need to model the capabilities of P to act malicious. Essentially, there are the following three ways:

1) *Simulating Functions:* Recall that V communicates with S_{chl} , which the prover P uses to cover direct access to S_{src} and to mimic S_{trg} . To do so, he sets $S_{\text{chl}} = \text{Produce}(S_{\text{src}})$ and may simulate functions that are not part of S_{src} (but of S_{trg}). However, following from the Definitions 6 and 12, altering S_{src} is only possible for functions that are *not* simulation-hard. But altering or simulating such functions $f \notin \mathcal{F}^*$ will not affect Π_{RFP} , since it only tests for functions $f \in \mathcal{F}_I^* \cup \mathcal{F}_B^* \cup \mathcal{F}_D^*$ which are all simulation-hard. Hence, a malicious prover P can not fool the verifier V by simulating functions.

2) *Caching or Pre-Computation of Responses:* After V did audit P for a software S_{trg} once, the P can fool the verifier for the next audit as follows: He records all challenges and responses and stores them in a database. Next, he sets S_{src} and S_{chl} to any softwares he wants. Then, if V audits P again, e.g., in form of a regular scheduled auditing process, P just replies with the entries from his database. Recall that a challenge c in Π_{RFP} depends on the randomness source Φ that is either chosen by V . That is, two challenges for the same software version $S \in \mathcal{S}$, same interface $I_c \in \mathcal{I}$, and same simulation-hard function f will always be different, i.e., $c(S, \phi, I_c) \neq c(S, \phi', I_c)$, where $\phi, \phi' \in_R \Phi$ are different with overwhelming probability. Hence, a malicious prover P can not fool the verifier V using caching or pre-computation of responses.

3) *Proxy-Forwarding of Challenges:* Assume that in addition to P there exists another prover P' who has installed S_{trg} , that is the software in the version agreed on in the SLA. If V sends a challenge c to P , he forwards c to P' , who in turn computes the correct response e' . Latter is then sent over P to V , who would then come to the conclusion, that P indeed runs the correct software version. However, forwarding c and e' requires a certain amount of time t' . Since there is an upper time limit $t \in D[S]$ for each challenge (see Definition 9), this value can be set conservatively, such that forwarding is not possible anymore without being detected, i.e., taking too much time such that Π_{RFP} will output $\delta = \text{false}$. Hence, a malicious prover P can not fool the verifier V by forwarding challenges.

Since all malicious options for the prover P are not successful, the verifier V fulfills soundness in respect to RFP. In

conclusion, V is correct and sound with respect to both Π_{RSI} and RFP and therefore RFP is secure and also solves the RSI-problem. ■

V. DESIGN & IMPLEMENTATION OF RFP

In this section, we introduce three new fingerprinting techniques for RFP to design challenges and expected responses. We furthermore delve into the design of a database and strategies, giving examples each. Finally, we show the advantages of the RFP structure for implementation and employ our own prototype to remotely audit software.

A. Secure Fingerprinting Techniques

As we have shown in Section II-D, current state of the art fingerprinting techniques are not secure, that is they can be fooled by a malicious provider. In Appendix D1 we give a detailed security analysis for each class of the fingerprinting techniques. We have used these techniques directly as part of Π_{RSI} , but note that they still remain insecure when used as part of Π_{RFP} . This is due to missing features such as time constraints, randomization of challenge-response-pairs, and relying on simulation-hard functions. Consequently, none of these should be used to audit software.

We will now introduce three new fingerprinting techniques which all, implemented in Π_{RFP} , lead to a secure scheme RFP. Furthermore, these techniques belong to a new class which we call *Class 5: Dynamic Behavior-Depending Techniques*. Note that a fingerprinting technique can directly be seen as a design instruction for challenges and according expected responses.

1) *Dynamic Request Response*: The verifier requests the software S_{chl} to perform a certain simulation-hard function f in a specific way with some input parameters ϕ . This means that f can be nested, e.g., iterated, or that it is used as part of a larger function or control structure. At least one of the three components must be randomized and the response by S_{chl} must depend on this randomness. That is, the output space of Γ^* of S_{chl} must be polynomial in the size of the randomness space of the randomness source Φ in respect to f .

As an example, let $\text{diffDate}(a, b)$ be a simulation-hard function that returns the difference between two date objects a and b , where a date object is defined as in RFC 3339 [22]. Then, the challenge sends two random date objects a and b as challenge and checks if the response reflects the correct implementation of the function diffDate .

2) *Error Handling*: In contrast to Error Code, we are not interested in the error itself, but rather *when* the error occurs and *why*, i.e., which circumstances lead to cause the error. Here, the sent challenge depends on a simulation-hard function with parameters which produces an error for a given software version of the software family. Randomization is done as in Dynamic Request Response, and the response consists of the erroneous behavior of the called function. Note that Error Handling can be realized by using Dynamic Request Response in a certain way, hence they are in the same fingerprinting technique class.

As an example, let diffDate be a simulation-hard function as above but that does *not* support the input in RFC 3339 format for a $S \in \mathcal{S}$. Then, given a randomized input in RFP 3339 format, the function will throw a certain error depending on the input value which allows deducing the software version.

3) *Non-Destructive Security Exploit*: This technique exploits non-destructive security vulnerabilities in a software with randomized function parameters. If no update has been applied, the exploit will be successful and hence leak information about the installed software version. This deviates in two points compared to Security Exploit: First, we only use security vulnerabilities that are non-destructive, that is they do not damage the system and especially do not crash the system leading to an abrupt halt. Second, this allows for testing multiple non-destructive security flaws in order to retrieve information about the version number. Note that this fingerprinting technique can be realized by using Dynamic Request Response, hence they are in the same class of fingerprinting techniques.

As an example, an authentication check may not be performed correctly, i.e., with a security flaw, hence allowing access to otherwise protected information.

B. Database Design

A RFP database $D(\mathcal{S}, \mathcal{I})$ is defined over the software family $\mathcal{S}$ and a set of interfaces $\mathcal{I}$. It consists of triples (c, e, t) with challenge c , expected response e , and time constraint t , see Definition 9 for details. As stated in Section IV-D, designing such a database is one of the main tasks of the verifier. The design comprises four steps which we will now explain in detail.

1) *Finding Simulation-Hard Functions*: The first goal is to find at least one simulation-hard function $f \in \mathcal{F}^*(S)$ for each $S \in \mathcal{S}$ and a given set of interfaces $\mathcal{I} \subseteq \mathcal{I}^*$. Usually, the interfaces are known a priori to designing the database, that is how a user connects to the software or service. Therefore, we will focus on finding suitable functions.

Following from Section IV-F, determining software versions comes down to requiring intrinsic functions to distinguish between them, i.e., by relying on tests via Π_{RFP} employing functions out of $\mathcal{F}_I^*$, $\mathcal{F}_B^*$, and $\mathcal{F}_D^*$. Note that $\mathcal{F}_B^*$ and $\mathcal{F}_D^*$ will eventually also require intrinsic functions of $\mathcal{F}_I^*$. Hence, we will need simulation-hard intrinsic functions for each software version as basis for a RFP database, which also need to be able to be randomized in some way, e.g., by parametrization or structure. To find these functions, a good place to start is to research the version history or release notes of $\mathcal{S}$, that is the list of individual changes from one version to the next or previous one. They are often provided by the software developers, e.g., PHP changelog [23], but can also be extracted from repositories such as GitHub [24]. Additionally, compatibility changes also help finding intrinsic functions, e.g., Firefox site compatibility [25]. If $\mathcal{S}$ is closed source, i.e., the current software code and/or version history are not available, the verifier can try to build a version history by himself by

analyzing other sources such as news and developer blogs for S . At the end, the verifier might stick to the fingerprinting technique Non-Destructive Security Exploit based on known, e.g., leaked, security exploits.

By comparing the properties, functions, and behavior of distinct (especially consecutive) releases of the software versions, the verifier selects those functions which are only available up until a certain software version and are no longer available (deprecated functions), or which are beginning to be part of the software starting at a certain software version (new intrinsic functions). In addition to removed or new functions, one may also choose altered functions which then also possess new intrinsic properties. Recall that different interfaces allow for different functions being accessed, increasing or decreasing possibly the set of available functions to gather for a database. At the end, we have a set of simulation-hard functions $\mathcal{F}_I^*(S)$ for each $S \in \mathcal{S}$, or, if due to software hierarchies there is no such function for S , the sets $\mathcal{F}_B^*(S)$ and $\mathcal{F}_I^*(S)$ will complement the respective entry in the database. If, however, (i) there is no function available for a certain S , a test later on via Π_{RFP} will not return `false`, since the provider did not fail at the test, since for **RFP** it holds $S \equiv S'$ for some other software version S' . And (ii) we can not determine if S is *not* running, i.e., we set $\delta_{\Pi_{\text{RFP}}(S)} = \text{true}$ if $\mathcal{F}_I^*(S) = \emptyset$ (and $\mathcal{F}_B^*(S), \mathcal{F}_D^*(S)$ are also empty).

2) *Computing Challenges and Expected Responses:* Based on the functions of the set $\mathcal{F}_I^*(S)$, which have been gathered in the previous step, we compute the triple $(c, e, t)_S$ for each $S \in \mathcal{S}$. As mentioned in Section IV-C, a challenge also depends on a randomness source Φ . The verifier selects Φ to be a cryptographic secure random number generator, that is it is sufficiently difficult to guess the next output based on previous outputs. He includes Φ in the design of the challenge c to randomize the parameters or structure of f , or both, later on. The challenge itself is stored in the database with placeholders for the randomness $\phi \in \Phi$. They are being replaced dynamically as part of Π_{RFP} just before sending the challenge to P . Obviously, the details depend heavily on f itself. In general, the goal is to let the provider do some randomized work over f which can only be solved in the given time frame if f is implemented and working as intended.

Next, the verifier simulates a perfect software provider which runs a software with version S . This allows him to compute the expected response e by processing the previously computed c and storing the output. The randomness ϕ is input as placeholders which are evaluated when the reply of the provider arrives. Here, the verifier must ensure that possible influences by the interface channel, such as data encoding, are incorporated. The verifier also measures the time required to compute e and adds a certain estimated threshold to respect network latency yielding the maximal allowed time t to process the challenge c . Finally, the verifier stores all tuples in the database $D(S, \mathcal{I})$.

3) *Overcoming Software Version Hierarchy:* We will now explain how software development and version hierarchies influence the database design. Recall that two different versions

of the same software, i.e., $v_S < v_{S'}$ with $S, S' \in \mathcal{S}$, might have a very similar latest version history. That is, they differ from their respective preceding version by nearly the same changes which makes it difficult to distinguish between them a priori. As explained in Section IV-F, this occurs on different software branches that are maintained at the same time. However, there will be features which have been added to a predecessor of S , i.e., in the branch of S , but are not available in S' , since it exists on a different branch. Additionally, functions may only exist in the versions between S and S' , but not before or afterwards. These deprecated functions can not give any information about software that has a lower version number than S and a higher version number than S' . We will now explain how the verifier copes with these entries in the database and how he finds related branching and deprecated versions.

Coming from the previous step of computing challenges and expected responses, we now have at least one tuple $(c, e, t)_S$ for each $S \in \mathcal{S}$ in our database D . To respect and overcome the software properties and version hierarchies mentioned above, we will add additional tests for branch origins and deprecated functions to existing tests if required. In other words, there can be more than one test for a software version $S \in \mathcal{S}$.

Regarding branch detection, this follows from the version history of S and results in testing for a function of $\mathcal{F}_B^*$. That is, if two different software versions S and S' each have the same change log in respect to their previous version, the verifier determines the next lower branch origin $\hat{S}$ of the higher version, wlog. S' . Since we already added a test for this certain software version $\hat{S}$ to D in the previous step (recall that this was done for all softwares of S), we can simply add this test to the test of S' . As an example, let $D[S]$ denote the test for S stored in a database D . Then, if the changes between (i) 1.2.2 and $v_S = 1.2.3$ and (ii) 3.4.4 and $v_{S'} = 3.4.5$ are equal with respect to distinguishing sequences for simulation-hard functions, then the test entry in D is $D[S] = D[1.2.3]$ for S , while for S' it is $D[S'] = D[3.4.0] \wedge D[1.2.3] =: D[\hat{S}, S]$. Hence, **RFP** learns δ for either only one or two tests and can act accordingly, e.g., supported by a strategy. The verifier always wants to detect the branch origin *before* performing other tests, since if this test is not successful, he knows that he can jump immediately to another branch. Concatenating tests is not commutative and will be halted as soon as one $\delta = \text{false}$ is output by a single test. To find $v' = v_{S'}$ as given in equation (5), the verifier compares S' to each branch that has been active during the release time of S' . As a final note, a combination of tests as $D[S] = D[S', sw'']$ can also contain further tests, even for S itself (which then is *not* a circular reference since only S -related tests have to be executed). This is required if multiple consecutive releases on different branches have the same feature difference to its predecessor each.

For deprecated functions, we analogously get a function in $\mathcal{F}_D^*$ for S , and add a second test to determine the version range in which the function is available. That is, we later want to

perform a second test *after* testing the specific intrinsic function of S to determine its version including the information of deprecated functions. This way, we know if some $f \in \mathcal{F}_I^*(S)$ is available via $D[S]$, and can afterwards execute the second check $D[S']$ for a function $f' \in \mathcal{F}_D^*(v_S, v_{S'})$. This yields $D[S] = D[S, f] \wedge D[S', f']$. To find $v' = v_{S'}$ as given in equation (6), the verifier compares the functionality f of S to all adjacent versions to find the version range of f .

Please observe that executing the tests in a given order is possible since the verifier knows during the creation of the database if $f \in \mathcal{F}_B^*$ or $f \in \mathcal{F}_D^*$ for a functionality f of S . Note that this is not an exclusive or. If there are two different software versions S and S' with the same set of simulation-hard intrinsic functions, same branch origin and no deprecated function, i.e. $\mathcal{F}_I^*$, $\mathcal{F}_B^*$, and $\mathcal{F}_D^*$ are the same for both S and S' , we then have $S \equiv S'$, that is both versions are indistinguishable.

From a practical point of view, the referred tests must not be stored multiple times in the database, for example, a references should point to the entry of that version in the database. Additionally, the verifier should make sure that each test is only performed once, e.g., by employing Δ . Another important point in practice is that some tests require using features of a software that might not be implemented in the current running version of S_{chl} yet. That is, if the verifier is testing for some functionality of, e.g., software version 2, but actually the CSP hosts S_{chl} with software version 1, then it might be that S_{chl} is technically not capable of understanding a challenge for software version 2. Then, the S_{chl} will most likely throw an error (which is not a fingerprinting technique since this holds for *all* versions greater 1). In this case, software version 1 would be a predecessor that has to be tested before software version 2 is tested. In other words, software version 1 must be treated as a branch origin of software version 2, i.e., pointing via referer to the according database entry. As an example, testing for PHP version 7.1.20 only makes technically sense if there was beforehand a test for version 7.0.0. That is, RFP tests 7.0.0 and only if this test succeeds, the test for 7.1.20 is performed, i.e., $D[7.1.20] = D[7.0.0, 7.1.20]$ (note that this is not a circular reference: the latter test refers to the intrinsic functions of 7.1.20 only).

4) *Strategy Independence*: Following from the previous steps, we now have a database which consists of entries either with a single test for software versions that can be identified by an intrinsic simulation-hard function only, or with multiple tests if the software version shares common intrinsic functions with a software version from another branch or its intrinsic function is only available for a certain range of software versions.

In this final database design step, the verifier makes sure that the database D will later on work with any strategy $\theta \in \Theta$, i.e., D is independent of any reasonable θ . Ultimately, we do not want to restrict the set of possible strategies, i.e., be as flexible as possible. The reason is that different strategies require a different number of steps to determine the final software version. This depends on the software that is being audited

and the start software version of the strategy. For the database design it is important that any order of software version tests is applicable. For example, when a starting with a test for version 5.3.2 it is not sufficient to check for the intrinsic functions of this specific version. By applying the respective tests referred to in the database, the verifier also needs to check that the software is part of 5.3, and again as part of this he needs to make sure that the major branch 5 is indeed correct. Otherwise, it is possible that a test erroneously yields a correct output, for example when branching is involved. Therefore, the verifier has to make sure that any entry point of a strategy leads to the correct result (given the strategy is reasonable). Furthermore, software may change and branches as well as new versions will be added, requiring to alter existing entries in the database. Note that if the branch origin tests and deprecated function tests are included correctly in the database for each software version test, no matter where RFP starts in the database, there will always be a reference to one or more tests, yielding unique results. Hence, correctness is given for any reasonable strategy.

In conclusion, the main challenges for the verifier regarding creating a database are evaluating the version history, implementing probabilistic properties into intrinsic functions, reference versions in case of branching, deprecated functions, or technical dependencies, and to make the database sound such that any strategy can run on it. On top, the database should be updated whenever there is a software version S added to S , to allow distinguishing S from other software versions. We refer the reader to Section V-E1 for a brief explanation of the database format in practice and the general capabilities of our database implementation with example code included.

C. Strategy Design

A strategy $\theta \in \Theta$, as defined in Definition 11, is constructed by the verifier and consists of two parts: first, a start entry of a database $D(S, \mathcal{I})$, and second, how to select the next entry in the database based on previous tests and results stored in Δ . On top, a strategy may repeat tests, even the whole strategy itself overall. This is required, since anomalies in the network between the verifier and tested software can be mitigated by performing time- and function-critical processes multiple times. For example, a strategy could execute itself after completion of one run in order to test if the CSP behaves differently regarding latency or computation results.

In order to find a good strategy, we need to recall the three characteristic cases of software version hierarchy from before: intrinsic simulation-hard functions, version branching, and deprecated functions. For example, two different versions may share the same intrinsic functions but are part of different branches. Depending on the outcome of the individual tests, different actions need to follow. As an example, assume the verifier tests S_{chl} running at the CSP, and he tests against the PHP version S with $v_S = 7.1.1$. In the database we have $D[S] = D[7.1.0] \wedge D[7.0.15]$ which gives the following four cases for a strategy: (i) $\delta_{\Pi_{\text{RFP}}(7.1.0)} = \text{true} \wedge \delta_{\Pi_{\text{RFP}}(7.0.15)} = \text{true} \Rightarrow v_{S_{\text{chl}}} \geq 7.1.1$; (ii) $\delta_{\Pi_{\text{RFP}}(7.1.0)} = \text{false} \wedge$

$\delta_{\Pi_{\text{RFP}}(7.0.15)} = \text{true} \Rightarrow v_{S_{\text{chl}}} \geq 7.0.15$; (iii) $\delta_{\Pi_{\text{RFP}}(7.1.0)} = \text{true} \wedge \delta_{\Pi_{\text{RFP}}(7.0.15)} = \text{false} \Rightarrow v_{S_{\text{chl}}} = 7.1.0$; and (iv) $\delta_{\Pi_{\text{RFP}}(7.1.0)} = \text{false} \wedge \delta_{\Pi_{\text{RFP}}(7.0.15)} = \text{false} \Rightarrow v_{S_{\text{chl}}} < S_v \vee v_{S_{\text{chl}}} < S'_v$. In each case, the strategy has to decide what to do next, i.e., choose the following software version to be tested. Hence, the verifier has to keep in mind that combinations of tests will yield certain knowledge about the software version running at the cloud service provider. This is similar to the linked tests for branching and deprecated functions. However, in this case the verifier needs to know which version is newer than another one in order to process. He gains this information from the database, i.e., the version history of S , despite not having a well-defined order supported by the version numbers.

In our reference implementation of RFP, we implemented the following strategies which work very well for various use cases and at the same time demonstrate the capabilities and possibilities:

Binary Search (BS)

Classical binary search (see e.g. [26]) is based on the idea to, first, split a set of ordered items in half and, second, to choose the ‘correct’ half, i.e., the half where S_{src} is included. As already mentioned, there is no trivial way to order the software versions, but due to the structure built beforehand, we know if we are in the correct branch or not after a certain test via Π_{RFP} , no matter how we sort all software versions. Hence, we implemented the ordering over the version numbers, but kept the database structure to possibly jump in a half which was not chosen by the original binary search algorithm (another choice could be to sort by software version release date). In general, this algorithm is quite efficient in finding the correct software version. However, if due to software branches an older version number fails a test while a newer one succeeds (e.g., 7.1.0 is fine, while 7.0.15 is not), the binary search algorithm will take a software version that is older than the failed and newer than the succeeded version – in this case, this yields a non-existent version and has to be treated accordingly.

Cascading Binary Search (CBS)

For this strategy, we perform binary search three times: on the level of Major, Minor, and Patch each in this order. Depending on the number of different versions and branches, this reveals the target software version quicker than classical binary search.

High To Low (HTL)

If the verifier suspects that S_{src} at the CSP is running in a relatively recently released version of the highest version branch, then he might employ this strategy. The first version to test is the highest released version, the next one the second highest released one, and so on. This is done successively downwards until the correct software version has been found, i.e., Π_{RFP} yielded true for some $S \in S$.

However, note that a single software version test can reveal more information than just about the currently tested software. Due to the referred software versions via branching, deprecated functions, and technical dependencies, this strategy can skip a test, since it always selects for the next test the lowest version which has not yet been successfully tested. This optimistic strategy is less efficient, if the software version tested is one that was not recently published. Note that there are important details to be aware of: In the example of PHP, we have $\delta_{\Pi_{\text{RFP}}(7.2.9)} = \text{true} \Leftrightarrow \delta_{\Pi_{\text{RFP}}(7.1.21, 7.2.0)} = \text{true}$. Now assume that $\delta_{\Pi_{\text{RFP}}(7.2.9)} = \text{false}$. Then, this strategy *must not* select 7.1.20 as a next version to test if $\delta_{\Pi_{\text{RFP}}(7.1.21)} = \text{false}$, but it has to check version 7.2.8. However, if $\delta_{\Pi_{\text{RFP}}(7.1.21)} = \text{false}$ and $\delta_{\Pi_{\text{RFP}}(7.2.0)} = \text{false}$, then in fact $\Pi_{\text{RFP}}(7.1.20)$ must be the next test.

Low To High (LTH)

This strategy works analogously to High To Low, but starts from the oldest (e.g., lowest when ordered by version number) software version of S ever released.

Highest Major Step Up (HMSU)

The entry point in the database for this strategy is the software version with the highest Major, but lowest Minor and Patch values each. The strategy is optimistic in the sense that it jumps directly to the next higher Minor branch, if a test was successful. However, if a test was not successful, it will test the next higher Patch value. If both the test for Minor and Patch fail, a lower Major will be tested. This, of course, also holds, if the very first test fails. HMSU is well suited for software families which have a low amount of different Major values and when the CSP is not running the most recent version at the same time.

In conclusion, strategies define how the software versions in a database are traversed. The implemented strategies demonstrate just a small part of the bandwidth possible for the verifier to create a strategy. We will compare the listed strategies to each other in Section V-E, when testing a real-world scenario as part of the experiments, and give a thorough description of a single strategy (CBS). However, analyzing the runtime of the strategies, e.g., average and worst case, is out of scope of this paper.

D. Implementation Modularity of the RFP Framework

The structure and design of the RFP scheme RFP allows to have a modular implementation framework. That is, RFP consists of various components, such as databases and strategies, which encapsulate different tasks. In fact, the different building blocks of RFP interact with each other, but are independent developed components. This yields the following modules:

- 1) Databases $\mathcal{D}$, where a single database includes the pairs of challenges c and expected responses e together with a time limit t for each software $S \in S$ (and possibly

referrers to other entries, see Section IV-F). Fingerprinting techniques, which describe how to evaluate a certain functionality of S , can be developed independently of all other components, however, they are implemented as part of a database entry.

- 2) Interfaces $\mathcal{I}$, which represent communication channels and can be freely chosen for each challenge and each (expected) response. An interface may take as input authentication data negotiated with the software provider P .
- 3) Strategies Θ , dictating how to choose the next software version $S \in \mathcal{S}$ to be audited as part of Π_{RFP} , depending on earlier test results Δ .
- 4) A randomness source Φ , which is applied during runtime yielding an auxiliary input to each challenge.

This flexibility results in a very adaptive nature of RFP. The verifier is independent of the software family and software complexity (e.g., a forum runs on PHP, which runs on Apache, which runs on Ubuntu, etc.). Furthermore, due to the modularization, the verifier can construct databases independently of the software provider, as authentication data can be input as a parameter. Strategies are not only independent of the software family, but also of the database; latter may be an input parameter. Consequently, a RFP scheme is quickly extensible and a verifier can outsource the design of databases and strategies, exchange them efficiently for each software family if required and may even share them with further parties. Finally, note that RFP is not bound to any infrastructure or programming language, as long as it can be executed.

E. Experiments

After having defined RFP and its scheme RFP we want to test it in a real-world setting. Hence, we performed experiments with actual service providers and will also come back to the attack example of Section II-E. According to the database and strategy design explained above, we created multiple databases and strategies. The databases include tests for each software family PHP, MySQL, and WordPress, while the strategies are the ones mentioned in Section V-C and can be applied to any of the databases.

1) *Experiment Database*: For storing the databases, we used the lightweight data-interchange format JavaScript Object Notation (JSON, [27]), consisting in general of key-value pairs and ordered lists. A database is created by first fetching all available software version names from the developer of the software family. Next, some metadata is set, such as the timestamp for creation and last change (this info makes updating the database easier later on), the name of the software family, e.g., PHP, default values for software specific values, e.g., challenge and expected response appending start- and endstrings or default latency, default randomized variable type and format, and which interfaces should be applied by default, i.e., if none are specified for a specific test. See Appendix I for an example configuration. Next, the tests for each version of the software family is added according to the database design presented in Section V-B. Each software version may consist

of a set of intrinsic function tests, a set of branching version references (including technical dependencies as explained in Section V-B3), and a test for deprecated functions.

As an example, the test for PHP 7.2.12 can be given as seen in Listing 1. Hence, to check if at least PHP 7.2.12 is running as the provided software, versions 7.2.0 and 7.1.24 are tested, since 7.2.12 and 7.1.24 share the same intrinsic functions compared to their previous versions each, and 7.2.12 lives on branch 7.2.

Listing 1. RFP example database test entry for PHP 7.2.12.

```

1  "7.2.12": {
2    "test": {
3      "branching": {
4        "7.2.0": "1",
5        "7.1.24": "1"
6      }
7    }
8  }
```

We will now give an example for a test based on an intrinsic function. Assume that we send challenges via FTP (i.e., storing a file) and receive responses over HTTP (access an URL whose content is provided by PHP and a webserver). Then, the test for PHP 7.2.0 may be given as in Listing 2. First, a variable ax is defined as a random integer³ between 1 and 999999999. Next, the challenge payload calls the function `unserialize`, which unserializes the randomized string $d:\#ax\#e++2$, which has, by intention, not the correct format for a serialized float number. For example, $d:3e+2$ represents $3 \cdot 10^2 = 300$. Before PHP 7.2.0, the software replies with `float(3)` in the given example, which is not compliant to the definition and hence wrong. With the introduction of PHP 7.2.0, the response for such a string consists correctly solely of a (variable) error message. With this knowledge, we can test if the payload returns `false`, denoting that at least PHP 7.2.0 is running.⁴ We use the function `var_dump` to transform the output of any argument into a string. The expected payload contains the value that we are expected to get as a response from the CSP. Note that we are using the fingerprinting technique Error Handling with the intrinsic simulation-hard function `unserialize` to determine if at least version 7.2.0 is running here. Also, recall that due to the randomization and time-constrain, the software provider can not pre-compute, cache, or forward the challenge and has, in particular, to execute the challenge in the actual target environment.

Listing 2. RFP example database test entry for PHP 7.2.0.

```

1  "7.2.0": {
2    "test": {
3      "variables": {
4        "ax": {
5          "format": "integer",
```

³We implemented also randomized formats such as strings, binary values, version information, or directories and files.

⁴For this example we disabled error reporting, hence the output consist only of the boolean value `false`.

```

6      "min": 1,
7      "max": 999999999
8    },
9  },
10  "challenge": {
11    "payload": {
12      "var_dump(@unserialize('d:#ax#e++2;'))";
13    },
14    "expect": {
15      "payload": "bool(false)\n"
16    }
17  }
18 }

```

Note that, in comparison to RFP, the often used fingerprinting techniques of Class 1 merely query a version API, e.g., `phpversion()` in the case of PHP, `SELECT VERSION()` for most SQL databases, or a banner for command-line software. Recall that the response can then be freely chosen by the (malicious) service provider.

2) *Defying the Practical Attack*: We implemented the RFP scheme in PHP, allowing us to port it quickly to any other system. Of course, any high-level programming language will also work perfectly fine. Recall the practical attack on fingerprinting techniques from Section II-E: we set up a malicious server that is running PHP 7.1.1, but on challenging any version function, the server replies with `20.0.85-car`. The tested version scanners were convinced that this non-existent software version is indeed running.

We will now leverage RFP to determine the software version of this malicious server and compare the outcome to other tools. For easier use, we implemented an RFP-Wizard, which is part of RFP and can cover technical details such as the authentication and network setup as well as location of the database and service provider. The wizard is also available as API, e.g., via REST. To begin, we first specify the database D with software family $\mathcal{S} = \text{PHP}$ (378 versions, lowest is 4.0b1, and highest is 7.3.0rc5) and interfaces $\mathcal{I} = \{\text{FTP}, \text{HTTP}\}$, and next the credentials for the challenges sent via FTP and responses received over HTTP. Finally, we provide RFP with an a priori customer target version claim, for example version 7.3.0. In fact, this is the information the customer of the service provider usually gets from their customer web interface. In other words, this is the advertised or in an SLA agreed on software version the provider has promised to run. As mentioned in Section IV-A, we now have a RSI protocol Π_{RSI} with RFP as a building block. We perform RFP with the strategies Cascading Binary Search and Highest Major Step Up to compare both. The test procedure results are given in Table I, where “Version” denotes the PHP version tested, “Result” is the outcome of the test – either `true` (✓) or `false` (✗) –, and “Testorder” is the sequence in which the tests have been performed, i.e., the distinguishing sequence. While the strategies traverse different paths through the possible software versions, both determine correctly 7.1.1 as the software version running at the service provider. Hence, RFP overcomes the problems of existing tools and can detect software versions even in the presence of a malicious service provider. More formally, RFP yields $v_{S_{\text{src}}} = v_{M_{\text{src}}} = 7.1.1$,

Cascading Binary Search			Highest Major Step Up		
Version	Result	Testorder	Version	Result	Testorder
5.0.0b1	✓	1	7.0.0	✗	1
7.0.0	✓	2	7.1.0	✓	2
7.2.0	✗	3	7.2.0	✗	3
7.1.0	✓	4	7.0.15	✓	4
7.0.26	✗	5	7.1.1	✓	5
7.0.22	✗	6	7.1.2	✗	6
7.1.2	✗	7			
7.0.15	✓	8			
7.1.1	✓	9			

TABLE I

RFP TEST PROCEDURE RESULTS OF A MALICIOUS PHP SERVICE PROVIDER WITH THE FAKED SOFTWARE VERSION NUMBER `20.9.85-car`. RFP DETERMINES THE CORRECT VERSION `7.1.1`, EMPLOYING THE STRATEGIES CBS AND HMSU EACH FOR COMPARISON.

$v_{S_{\text{chl}}} = v_{M_{\text{chl}}} = 20.9.85\text{-car}$, and $v_{S_{\text{trg}}} = v_{M_{\text{trg}}} = 7.3.0$, while other tools yield erroneously $v_{M_{\text{src}}} = v_{M_{\text{chl}}}$. To complete an RSI, the verifier has to check if the CSP is compliant to the SLA, i.e., if it holds that $S_{\text{src}} = S_{\text{trg}}$ (which is not the case here).

3) *Evaluating Real-World Software Providers*: We tested various software providers regarding their promises of the running software version using RFP, e.g., Hetzner [28], Serverprofis [29], or Strato [30]. As a result, while no provider was really wrong, some of them promised to have “the newest version” installed, but did not provide a `Patch` value of the version number running in the customer web interface. This may be due to save content update time, since this reduces the text changes the providers have to make each time a new version is being released. However, at each point in time, the most recent version for a given `Major` and `Minor` branch is always clearly defined at the tested providers. We found that all but one of the providers indeed had the most recent version installed. The other was between a single up to five `Patch` versions behind. In contrast, for MySQL, no version number was provided in the customer web interface, but it got advertised by the `Major` version, leaving open both `Minor` and `Patch` versions. Not updating to the newest version will result in less secure software (except some edge cases). Hence, it is crucial to keep software up to date.

We will now use RFP to determine the most recent version of PHP 7.2 running at the platform as a service provider ‘Serverprofis’. In order to demonstrate how different strategies analyze the same software, we are performing this procedure for each strategy mentioned in Section V-C, except Low To High. The result is presented in Table II, where “R.” is short for “Result”, and the tests are listed in the order they have been performed. At the end, RFP proves that indeed the most current version of PHP 7.2 is running at the moment of testing, i.e., 7.2.14.

Finally, we want to explain in detail one strategy, such that the reader knows why the versions have been tested in the order presented in Table II. Hence, we will briefly describe Cascading Binary Search (CBS). The first goal of this strategy is to determine the correct `Major` version. The database contains 4, 5, and 7 as candidates, and CBS starts in the middle

BS		CBS		HTL		HMSU	
Version	R.	Version	R.	Version	R.	Version	R.
5.2.0	✓	5.0.0b1	✓	7.3.0rc4	✗	7.0.0	✓
7.1.0	✓	7.0.0	✓	7.2.14	✓	7.1.0	✓
7.0.15	✓	7.2.0	✓			7.2.0	✓
7.1.1	✓	7.3.0rc4	✗			7.3.0rc4	✗
7.1.21	✓	7.1.21	✓			7.1.13	✓
7.2.0	✓	7.2.9	✓			7.2.1	✓
7.0.0	✓	7.2.14	✓			7.1.14	✓
7.1.20	✓					7.2.2	✓
7.2.8	✓					7.1.20	✓
7.2.14	✓					7.2.8	✓
7.3.0rc4	✗					7.1.21	✓
						7.2.9	✓
						7.2.11	✓
						7.2.14	✓

TABLE II

RFP PROVES THAT THE SOFTWARE PROVIDER ‘SERVERPROFIS’ HAS INDEED RUNNING THE LATEST VERSION OF PHP 7.2 AT A CERTAIN POINT IN TIME. THE TABLE SHOWS A COMPARISON OF FOUR DIFFERENT STRATEGIES EMPLOYED IN THIS RFP TEST: BS, CBS, HTL, AND HMSU.

with Major version 5 and the lowest available version thereof, i.e., 5.0.0b1. In this case, we get `true` as a result, hence, the tested software might have with a higher Major version and we test for version 7, i.e., 7.0.0, which results in `true`, too. Next, we want to find the correct Minor version. For PHP 7, we have the following Minor versions in the database: 0, 1, 2, and 3. Choosing again the (optimistic, i.e., rounding up) middle, the test $\Pi_{RFP}(7.2.0)$ results in `true`. Note that we do not have to check 7.0.0 again. Next, however, testing for Minor version 3 fails. We now are looking for the final part, determining Patch out of the possible values in our database, i.e., 1, 2, 8, 9, 11, and 14. We want to show here that without a perfectly filled database, RFP still manages to find the correct version, as long as it is included. Observe that Patch value 0 was already tested. The last two steps are successfully testing for Patch version 9 and 14. Since there is no version of PHP between 7.2.14 and 7.3.x, we do not need to conduct further tests and CBS can output the final, correct software version as result: 7.2.14.

VI. EXTENSIONS OF RFP

In this section we describe two extensions of RFP: fingerprinting hardware and outsourcing the burden of creating databases and strategies of the verifier to an external auditor.

While a software provider simply might act as a verifier in the RFP scheme RFP in order to audit himself, this is not an extension of RFP.

A. Fingerprinting SD Cards

Until now, we presented RFP as a method to determine the identity of software, i.e., the software’s correct version. However, the same concept behind the RFP scheme can also be applied to verify the correctness of hardware features.

One case is the overall available storage on an SD card (Secure Digital Memory Card [31]). The maximum storage available is effectively just represented by a string of characters which is then consumed by other applications. Usually,

this string is not checked by any operating systems and is “believed” to be correct as it is stored on a certain, in general non-accessible part of the card. This scenario is very similar to software, whose version number string is also being “believed” to be correct without any checks.

The idea is now to extend RFP by testing for available space on the SD card until we find the maximum amount possible (or at least a close range thereof). To do so, we set the RFP database to not contain version numbers, but various magnitudes of storage sizes, e.g., 1 kilo byte (kB), 10kB, 100kB, and so on. For each challenge, the precise value of the storage size is chosen randomly (in the range of the chosen magnitude), as well as the content. Then, the data is transmitted to the previously erased SD card over an interface provided by the operating system or network. As in original RFP, various strategies may be applied, e.g., binary search (which is easy here, since a clear order on the target space exists – storage space). At some point in time, the SD card will stop taking data because it is full. Then, the verifier has learned the maximum capacity of the SD card.

This extension of RFP is especially of interest, since there are many SD cards which claim to have a higher storage capacity than they really possess. The motivation behind such products are manufacturers who buy cheap low-storage SD cards and replace only the string with the available space value in it. This, is quite easy given a certain interface, and allows selling cards of a Terabyte which identify as such, but can only store a few Gigabyte. The customer most often will only notice this fact when it’s too late. We want to point out that there exists software, that determines the size of a storage object reliably in different ways, if used correctly (e.g., formatting software), RFP complements these tools.

B. Outsourced RFP

We have presented RFP as a two-party protocol between a verifier V and a (cloud) software provider P. As we have seen in Sections V-B and V-C, the verifier has to construct a database for each software family $\mathcal{S}$, employ randomness, and implement strategies to perform RFP. However, a usual customer of the provider may not have the required resources, i.e., time, money, computing, or storage power. Hence, we introduce a third party to take away the burden of the customer: the auditor A. The goal of the auditor is to check on behalf of the customer if the provider behaves correctly, and in the case that something is not working as intended, i.e., as defined in according SLA, he informs the customer. In practice, however, the provider may detect based on the interface if a RFP challenge comes from a customer or from A, and act differently. That is, P will use a certain server instance to reply to challenges of A, where this server has installed the most recent software version of $\mathcal{S}$. Note that this is not proxy forwarding since this server can co-exist directly beside (virtual or non-virtual) the server the customer is using. In other words, A can not check P directly or independently of the customer. Observe that this is different for functionality than, e.g., storage. However, the auditor can nonetheless take




Fig. 3. Sketch of the ORFP scheme consisting of the customer, auditor, and (cloud) service provider. Each party generates values and stores signed values of all signed in- and outputs in a respective log file.

care of the expensive parts of RFP, i.e., building database and strategy.

We are now going to extend RFP by adding the auditor party A and new security definitions and measures to RFP. We dub this scheme *Outsourced RFP (ORFP)*, since the customer outsources above mentioned tasks to the auditor. This is similar to the ideas of Outsourced Proofs of Retrievability [32], where proofs of retrievability are outsourced to an auditor to verify outsourced data availability. Since three parties participate in an ORFP, more than one party may be malicious, and, additionally, two parties may collude to cheat the third one. Hence, each party must be able to prove that it did its job correctly at any given moment in time. That is, a customer must be able to audit the auditor to check if he did stick to the protocol while at the same time the auditor must be able to prove that he did everything correctly, i.e., prove his liability.

The core idea of ORFP is twofold: (i) the auditor generates the database and strategies for a software family (or multiple thereof) while the customer inputs the randomness into the challenge and sends it to the service provider; and (ii) each party keeps a log of all input and output values together with their respective timestamps signed by the generating party. The first point shifts the main burden of RFP from the customer to the auditor, while the second point allows to protect against malicious parties and to prove liability. The ORFP scheme is depicted in Figure 3.

1) ORFP Scheme Description: The ORFP scheme begins with a *setup phase* which corresponds to the procedure Setup of RFP, where private and public keys are generated and distributed for each party. Then, the customer/user U sends a interface set $\mathcal{I}$ to the auditor A together with the software family $\mathcal{S}$. Here, $\mathcal{I}$ is chosen such that the auditor does not learn the credentials of the user but latter will use it to send and receive data from the service provider P, e.g., FTP and HTTP. The user may also send a software version $v_{S_{trg}}$ representing the software version the provider should have running, otherwise the auditor can set $v_{S_{trg}}$ to the latest version of $\mathcal{S}$. Furthermore, U initializes a randomness source Φ . In the final part of the setup phase the auditor computes the database $D(\mathcal{S}, \mathcal{I})$, strategies Θ , and each party creates a respective log file Λ_U , Λ_A , or Λ_P .

Next, the *audit phase* extends the RFP procedure Test, where A begins by choosing a strategy $\theta \in \Theta$ which is used

for the whole phase. Next, A selects a challenge c from the database D according to θ and sends it to U together with a signature $S_1 := \text{Sign}_A(c, t_1)$ where t_1 is the current time. Please observe that we omit the private key inputs of the signature here. Then, U induces randomness $\phi \in \Phi$ into the challenge producing an altered challenge c' . He also computes the signature $S_2 := \text{Sign}_U(\phi, t_2, S_1)$ and sends it together with c' to P. The P then performs the computation of c' resulting in the response e' , determines t_3 , and computes the signature $S_3 := \text{signatureP}e', t_3, S_2$. He adds to his log Λ_P the values (c', e', t_3, S_2, S_3) . Next, the client fetches e' , t_3 , and S_3 , computes $S_4 := \text{Sign}_U(t_4)$ based on the current time t_4 , and forwards these values together with ϕ , t_2 , and S_2 to A. He furthermore adds to his log Λ_U the values $(c, \phi, e', t_2, t_3, t_4, S_2, S_3, S_4)$. In the last step, A validates e' dependent on both c and ϕ , and then decides to either start a next test (according to the protocol Π_{RFP} and strategy θ) or, when no further tests shall be done, he outputs a candidate set C via the procedure Output. If $v_S \notin C$, the auditor informs U. The auditor also updates his log Λ_A by adding the entry

$$(c, \phi, e', t_1, t_2, t_3, t_4, S_1, S_2, S_3, S_4).$$

2) ORFP Security Outline: The properties correctness and soundness of ORFP follow from Π_{RFP} -correctness and Π_{RFP} -soundness, since ORFP basically incorporates the RFP scheme RFP. For example, this can be seen by grouping A and U as the party verifier.

We begin by showing that U must draw $\phi \in_R \Phi$. An ORFP scheme employs randomness, as RFP, to prevent pre-computation or caching of the correct response by P. Hence, the value ϕ must be drawn by U or A. First, let's suppose A chooses the randomness value. He might collude with P and communicate with him the expected response such that P does not need to have any software installed at all. In comparison to OPOR, once deleted data can not be un-deleted and the answer depends on user chosen values, however, certain functionality can be cheated any time here and P has no data depending on U in RFP. If A colludes with U to fool P, they can challenge for some randomness value and afterwards pretend that they have asked for a different randomness value. However, since the CSP stores the challenge in his audit log Λ_P , he can provably show which challenge was actually sent to him. Overall, neither P nor A can securely input the randomness value into ORFP. Next, we investigate the user U selecting the randomness value. If he colludes with P, they do not have the correct response to send to A since U may choose the same randomness each time such that pre-computation or caching might be possible. However, they need to send this value to A such that he can compute the correct expected response. However, if U sends each time the same value to A, he will be alarmed. At the end, they are not able to fool A, since he can compute the expected response correctly based on his log Λ_A and hence show that he did his job correctly. On the other hand, if U colludes with A, again the audit log Λ_P allows P to show that he acted according to the protocol. In conclusion, the user U draws the value ϕ from Φ .

The randomness source Φ itself must not be a public external randomness source (as in OPOR), since A has also access to this source and could pre-compute the randomness values to share the expected responses with P, fooling U. However, U might employ any (pseudo-)randomness only known to him or he involves a private key in determining the randomness value.

We will now outline the third component of ORFP security: liability of each party. That is, a party can prove that it behaved correctly according to the ORFP protocol. Furthermore, other parties need to be able to verify this, e.g., the user must be able to audit the auditor. The reader is referred to OPOR, where thorough definition and security analysis of liability is given. However, the scheme implementation is different to ORFP.

First, assume the auditor A wants to prove his liability. He can do so due to the audit log Λ_A , which consists of all values of previous ORFP runs that are required for the auditor to compute his output. Since each value is signed by the generating party, the auditor can prove that he did his job correctly. Given the case that the auditor has not correctly generated the challenges and expected responses as part of the database, the user U can verify this by comparing the inputs and outputs of Λ_A and Λ_U . By performing RFP onto the data of the logs, U must come to the same output as A, otherwise liability is not given.

The same procedure can be applied for any liability proof of a party, since each party holds an audit file with values signed by the other parties. Note that this is applicable in both ways: a party can show that it has done everything correctly and that another party can verify this. In other words, if a version claim does not succeed, the user can check if the mistake was by the service provider (wrong response) or the auditor (wrong challenge/expected response). Also, each party signs the values sent to the succeeding party in order to manifest that these values were generated correctly, i.e., they may be tested against a neutral server.

For future research the auditor may fetch the response of the service provider directly. Here, the main challenge is that the customer and auditor must have synchronized clocks for precise time measurement.

VII. RELATED WORK

In the following, we name for different scenarios respective approaches the most prominent related work and explain the relation to Reverse Fingerprinting. We do not include discovery scanner who try to determine all running services on a system. In Table III, Appendix I, we give an overview at a glance of different tools and their employed fingerprinting techniques. Many of the tools presented advertise two different modes of fingerprinting techniques: normal and aggressive. Usually, normal translates to Version Claim or Version API and aggressive to a second guess by using another technique, often File Structure/Content. None of the analyzed tools is using a strategy to detect a version number as RFP does. Except of one, all tools rely on trusting fixed strings received from the tested software. Depending on the task of the tool,

fingerprinting is only one step in a chain of actions, e.g., determining a version number in order to select certain attack vectors for a given service like a network vulnerability test that checks a service for the presence of specific security problems.

Penetration testing aims to check if a system can be effectively attacked. Existing penetration test software relies on knowing the software and version number of the victim in order to perform the tests efficiently. Hence it may follow up after employing RFP. In fact, implementing RFP as a module is an interesting task for the future. A well known framework in this context is Metasploit [10]. However, by default it is relying on software version APIs to detect software version in the first place. For example, this holds for testing VMware Horizon [33] or PostgreSQL [16] via Metasploit. Armitage [34] is a graphical cyber attack management tool for Metasploit which visualizes targets, exploits, and provides advanced capabilities of the framework. It also uses the target software's API to determine the software version. The Pen-Testers Framework [35] is a tool to manage penetration testing tools, but does not employ own fingerprinting techniques.

Vulnerability scanners search for software and network vulnerabilities, such as known CVEs [36], unsecure configurations, or missing updates. Usually, they produce a list of technical security flaws and can be integrated into SIEM (security information and event management) software. The Burp suite [11] is a prominent tool for security testing of web applications. While it has the capabilities of testing public functions in general, it natively relies on the target software's version API when determining its version. Again, RFP could be implemented as an extension in the future to solve this problem. The Burp extension Software Version Reporter [37] scans passively for applications revealing software version numbers. The software version is determined by the version claim made by the target's service provider. Nessus [9] is a network and vulnerability scanner for operating systems that acts mainly as a port scanner, but also scans default passwords or configurations. That is, specific server software must run on the target server which clients can connect to in order to perform scans. However, Version Claim and Version API of the target are used to determine software version numbers. Greenbone/OpenVAS [38] is a fork of Nessus and is developed on its own over the last decade. It consists of vulnerability management and vulnerability scanners, focusing on network scanner, operating system, and configurations. Software versions are determined by employing Version API. Another tool in this category is nmap [39]. It scans ports, detects active firewalls, consists of a Remote-Procedure-Call scanner, but does not scan web- or cloud-services, and relies on Version Claim or Version API provided by the target entity. However, nmap sends specific crafted TCP packets to provoke error messages which in turn allows for OS and network version detection, if not handled correctly by the target server and software. w3af [40] is a scanner for vulnerabilities using a modular structure with the goal to identify, audit, and exploit vulnerabilities. While it performs attacks like cross-site scripting and SQL injection, the software version is not

determined but given by the user. Both tools Web Application Scanning [41] and FreeScan [42] by Qualys scan computers, websites, and apps for vulnerabilities. To determine a version number of a software, they rely on Version Claim and Version API. InsightVM [43] is a platform-based vulnerability scanner and management tool by Rapid7 and employs Version API to determine version numbers. Nexpose [44] is a similar tool but for on-premise use. OWASP Nettacker [45] is a network information gathering vulnerability scanner and relies on Version API for fingerprinting.

The goal of *version scanners* is to determine the version of multiple softwares employed at once in a web- or cloud-service, for example webserver and CMS. However, to the best of our knowledge, all of them rely on Version Claim and File Structure/Content. Popular version scanners are wapalyzer [46] (identifies technologies on websites including their version numbers), WhatRuns [19] (also identifies technologies and their version numbers on websites), WhatWeb [47] (a “next generation web scanner” to determine employed libraries, software, and versions), and Guess [48] (detects CMS, frameworks, webserver, libraries, and versions). Blind Elephant [49] by Qualys uses File Hash Digest to fingerprint web applications. Similar tools are WAFP [50] and Static File Fingerprinting tool [51] by Sucuri, both also comparing checksums of static files.

CMS scanners are specialized on detecting versions, vulnerabilities, and plugins of content management systems (CMS). The tool What CMS? [52] detects about 300 different content management systems, however, the CMS version relies on Version Claim and file structure (File Structure/Content). Similarly, wpscan [53] is a security scanner for WordPress, but identifies the version number based on Version Claim and File Structure/Content. The following four tools rely only on static file content (File Structure/Content) on the service host: Plecost [54] (WordPress fingerprinting tool), WPSeKu [55] (WordPress security scanner), JoomScan [56] (OWASP Joomla vulnerability scanner project), and CMSScanner [57] (general CMS scanner framework). Two further tools combine static files (File Structure/Content) and Version Claim: CMSmap [58] (open source python CMS scanner) and CMS-Garden CMSScanner [59] (assumes you to have full access over the target machine). droopescan [60] identifies issues with several content management systems, such as Drupal [61] and Silverstripe [62]. They determine the target’s software version by comparing md5-fingerprints of static files.

A surplus amount of *penetration tools* leverages various logical, security, or implementation faults to gain information about a system. From this realm of penetration testing tools stems sqlmap [17]. Its main task consists of detecting and exploiting SQL flaws. It also comes with a fingerprint function for databases and the servers they are running on. While the fingerprinting of the server is quite basic and relies on Version Claim and File Structure/Content, database versions can be determined using Version Specific Features or Static Function Output. This, of course, only works if the web application has an SQL injection flaw or the tool has direct access to the

database.

There are further tools on the market which have very few information about them, however, we want to list them for completeness. The vulnerability scanner by Crashtest Security [63] has no public available information about their scanner, similar holds for the web application security test tools Rapid7 or AppSpider [64]. Retina CS [65] is a vulnerability scanner and management tool by BeyondTrust. In comparison to RFP, none of the tools presented in this section provide a theoretical framework or security analysis.

Academic publications regarding software fingerprinting are quite rare. In [66], the authors detect running crypto libraries in the cloud by exploiting leakages on the hardware level. Another approach to this field is software attestation, e.g., see [67] for an overview. Examples are [68] for embedded devices, [69] for voting machines, and [70] for sensor networks. The core idea is to run a challenge-response protocol over the code of the software and to detect cheating systems by measuring the time effort for a responses. This limits this approach to devices with restricted capabilities. In particular, none of them is designed for web- or cloud applications.

VIII. CONCLUSION

Until now, as the comparison and analysis of employed fingerprinting techniques has shown (see Sections II-D and Appendix D1), existing software trusts the provider or its service to output correct software version values, which may not be the actual version of the running software. Therefore, it may occur that insecure software is believed to be secure. We have presented Reverse Fingerprinting which solves the RSI problem, i.e., determining which version of a software is running remotely, e.g., at a cloud service provider.

To achieve this, a database is employed which contains challenges and expected replies of the target software, where each challenge depends on inherent, probabilistic parametric functionalities of the version that is tested. Also, a strategy is utilized to efficiently choose the correct order of tests out of the database based on previous tests, producing a distinguishing sequence of challenge-response pairs based on intrinsic functions. Furthermore, we introduce and leverage a theoretical framework based on finite state machines to built RFP and yield its capabilities. Formalization of the framework as well as testing software and version hierarchies are also a key part of RFP. This includes new fingerprinting techniques and an according security analysis of RFP. Furthermore, RFP can be extended to work on hardware such as storage, but also to add an auditor to take away most of the burden of a regular user resulting in outsourced RFP, i.e., ORFP.

The RFP scheme does not rely on the support of the service provider. Since only the service or software itself is being tested, this enables direct verifiability of the running software. Plus, RFP can be applied independent of the software type, since intrinsic functions of the software are being leveraged and tested. For example, it does not matter if RFP tests forums, content management systems, programming languages, databases, or PaaS and SaaS in general. To execute RFP, two

steps are required: (i) identification of characteristic functionalities of certain software versions and (ii) communicating with a software followed by an evaluation. While (i) needs to be done manually, (ii) is performed automatically with a few queries to the target service. This allows to efficiently test multiple systems at once in a very short amount of time.

While the properties of RFP make it notably useful for the user, the CSP and auditor also gain benefits. Auditors can automate and schedule security analyses, additionally, they may share or sell their developed databases and strategies. Since RFP is resistant against software manipulation of the CSP, the trust of customers will increase if an RFP test has been performed successfully, e.g., by an auditor. This leads to an increased security overall, since a malicious CSP risks to be debunked to not have updated its software. For the CSP, this may result in an increasing number of customers.

The quality of an RFP scheme depends on the employed database and the interfaces used therein. Obviously, a software version can not be verified if the customer does not have access or a sufficiently populated database. For the future, RFP implementations for further software families are planned, e.g., Internet forums. Finally, it would be convenient to combine RFP with software detection, i.e., detecting the software family.

In summary, RFP reliably determines the actual software version S_{trg} running at a (cloud) service provider by employing a challenge-response protocol which requires the audited software $S_{\text{chl}} = \text{Produce}(S_{\text{src}})$ to perform randomized tasks based on intrinsic functionalities. Since it is not economical for the CSP to implement simulation-hard functions of S_{trg} into S_{chl} in order to pretend having installed S_{trg} , RFP yields based on a database of challenges, expected responses, time-constraints, and randomness parametrization the software version S_{trg} when auditing S_{chl} . This finally allows the verifier to validate if $S_{\text{src}} \equiv S_{\text{trg}}$, i.e., if the service provider is honest.

REFERENCES

- [1] WordPress Foundation, “WordPress.” [Online]. Available: <https://wordpress.org/>
- [2] The PHP Group, “PHP.” [Online]. Available: <https://php.net/>
- [3] W3Techs & Q-Success, “Usage statistics and market share of PHP for websites.” [Online]. Available: <https://w3techs.com/technologies/details/pl-php/all/all>
- [4] Oracle Corporation, “MySQL.” [Online]. Available: <https://www.mysql.com/>
- [5] D. J. C. Klensin, “Simple Mail Transfer Protocol,” RFC 5321, Oct. 2008. [Online]. Available: <https://rfc-editor.org/rfc/rfc5321.txt>
- [6] The MITRE Corporation, “CVE – Search Results for ‘PHP.’” [Online]. Available: <https://cve.mitre.org/cgi-bin/cvekey.cgi?keyword=php>
- [7] The PHP Group, “PHP: Supported Versions.” [Online]. Available: <http://php.net/supported-versions.php>
- [8] W. J. van der Laan and Bitcoin Core Dev Mailinglist, “Bitcoin Core 0.16.3 released.” [Online]. Available: <https://lists.linuxfoundation.org/pipermail/bitcoin-core-dev/2018-September/000060.html>
- [9] Tenable Network Security, “Nessus.” [Online]. Available: <https://www.tenable.com/products/nessus>
- [10] Rapid7 LLC, “Metasploit project.” [Online]. Available: <https://www.metasploit.com/>
- [11] PortSwigger Ltd., “Burp suite.” [Online]. Available: <https://portswigger.net/>
- [12] T. Preston-Werner, “Semantic Versioning 2.0.0.” [Online]. Available: <https://semver.org/>
- [13] P. Laperdrix, W. Rudametkin, and B. Baudry, “Beauty and the beast: Diverting modern web browsers to build unique browser fingerprints,” in *IEEE Symposium on Security and Privacy, SP 2016, San Jose, CA, USA, May 22-26, 2016*. IEEE Computer Society, 2016, pp. 878–894. [Online]. Available: <https://doi.org/10.1109/SP.2016.57>
- [14] Y. Cao, S. Li, and E. Wijmans, “(cross-)browser fingerprinting via OS and hardware level features,” in *24th Annual Network and Distributed System Security Symposium, NDSS 2017, San Diego, California, USA, February 26 - March 1, 2017*. The Internet Society, 2017. [Online]. Available: <https://www.ndss-symposium.org/ndss2017/ndss-2017-programme/cross-browser-fingerprinting-os-and-hardware-level-features/>
- [15] S. Kamkar, “Evercookie – virtually irrevocable persistent cookies.” 2010. [Online]. Available: <http://samyp.com/evercookie/>
- [16] PostgreSQL Global Development Group, “PostgreSQL.” [Online]. Available: <https://postgresql.org>
- [17] B. D. A. G. and M. Stampar, “sqlmap.” [Online]. Available: <http://sqlmap.org/>
- [18] Canonical Ltd., “Ubuntu.” [Online]. Available: <https://www.ubuntu.com>
- [19] Whatruns.com, “WhatRuns.” [Online]. Available: <https://www.whatruns.com/>
- [20] J. Postel and J. Reynolds, “File Transfer Protocol,” RFC 959, Oct. 1985. [Online]. Available: <https://rfc-editor.org/rfc/rfc959.txt>
- [21] H. F. Nielsen, J. Mogul, L. M. Masinter, R. T. Fielding, J. Gettys, P. J. Leach, and T. Berners-Lee, “Hypertext Transfer Protocol – HTTP/1.1,” RFC 2616, Jun. 1999. [Online]. Available: <https://rfc-editor.org/rfc/rfc2616.txt>
- [22] C. Newman and G. Klyne, “Date and Time on the Internet: Timestamps,” RFC 3339, Jul. 2002. [Online]. Available: <https://rfc-editor.org/rfc/rfc3339.txt>
- [23] The PHP Group, “PHP 7 ChangeLog.” [Online]. Available: <http://php.net/ChangeLog-7.php>
- [24] GitHub, Inc., “GitHub.” [Online]. Available: <https://github.com/>
- [25] K. Yoshino, “Firefox site compatibility.” [Online]. Available: <https://www.fxsitecompat.com/en-CA/>
- [26] T. H. Cormen, C. E. Leiserson, R. L. Rivest, and C. Stein, *Introduction to Algorithms, Third Edition*, 3rd ed. The MIT Press, 2009.
- [27] T. Bray, “The JavaScript Object Notation (JSON) Data Interchange Format,” RFC 8259, Dec. 2017. [Online]. Available: <https://rfc-editor.org/rfc/rfc8259.txt>
- [28] Hetzner Online GmbH, “Hetzner Online.” [Online]. Available: <https://www.hetzner.de>
- [29] Serverprofis GmbH, “Serverprofis.” [Online]. Available: <https://www.serverprofis.de>
- [30] Strato AG, “Strato.” [Online]. Available: <https://www.strato.de>
- [31] SD-3C LLC, “SD Association.” [Online]. Available: <https://www.sdcard.org/>
- [32] F. Armknecht, J. Bohli, G. O. Karame, Z. Liu, and C. A. Reuter, “Outsourced proofs of retrievability,” in *Proceedings of the 2014 ACM SIGSAC Conference on Computer and Communications Security, Scottsdale, AZ, USA, November 3-7, 2014*, G. Ahn, M. Yung, and N. Li, Eds. ACM, 2014, pp. 831–843. [Online]. Available: <http://doi.acm.org/10.1145/2660267.2660310>
- [33] VMware, “Horizon.” [Online]. Available: <https://www.vmware.com/products/horizon.html>
- [34] L. Louvre, “Armitage.” [Online]. Available: <http://www.fastandeasyhacking.com/>
- [35] TrustedSec, “PenTesters Framework.” [Online]. Available: <https://www.trustedsec.com/pentesters-framework/>
- [36] The MITRE Corporation, “CVE – Common Vulnerabilities and Exposures (CVE).” [Online]. Available: <http://cve.mitre.org/>
- [37] A. Detlefsen, “Software Version Reporter.” [Online]. Available: <https://portswigger.net/bappstore/ae62baff8fa24150991bad5eaf6d4d38>
- [38] Greenbone Networks GmbH, “OpenVAS.” [Online]. Available: <http://www.openvas.org/>
- [39] Nmap Developer Team, “nmap.” [Online]. Available: <https://nmap.org/>
- [40] A. Riancho, “w3af.” [Online]. Available: <http://www.w3af.org/>
- [41] Qualys Inc., “Web Application Scanning.” [Online]. Available: <https://www.qualys.com/apps/web-app-scanning/>
- [42] —, “FreeScan.” [Online]. Available: <https://www.qualys.com/forms/freescan/>
- [43] Rapid7 LLC, “InsightVM.” [Online]. Available: <https://www.rapid7.com/products/insightvm/>

- [44] —, “Nexpose.” [Online]. Available: <https://www.rapid7.com/products/nexpose/>
- [45] A. Razmjoo and M. R. Espargham, “OWASP Nettacker Project.” [Online]. Available: https://www.owasp.org/index.php/OWASP_Nettacker
- [46] E. Alias, “wappalyzer.” [Online]. Available: <https://www.wappalyzer.com/>
- [47] A. Horton and B. Coles, “WhatWeb.” [Online]. Available: <https://whatweb.net/>
- [48] m3r consultancy B.V., “Guess.” [Online]. Available: <http://guess.scriitch.org/>
- [49] Qualys Inc., “Blind Elephant.” [Online]. Available: <https://community.qualys.com/community/blindelephant>
- [50] R. Sammet, “WAFP: The Web Application FingerPrinter.” [Online]. Available: <http://www.mytty.org>
- [51] Sucuri, “Static File Fingerprinting tool.” [Online]. Available: <http://sucuri.net/?page=docs&title=fingerprinting-web-apps>
- [52] WhatCMS.org, “What CMS?” [Online]. Available: <https://whatcms.org/>
- [53] WPScan Team, “WPScan.” [Online]. Available: <https://wpscan.org/>
- [54] D. Garca and F. Franz, “Plecost.” [Online]. Available: <https://github.com/iniqua/plecost>
- [55] m4ll0k, “WPSeku.” [Online]. Available: <https://github.com/m4ll0k/WPSeku>
- [56] M. R. Espargham and A. Razmjoo, “JoomScan.” [Online]. Available: <https://github.com/rezasp/joomscan>
- [57] Erwan and WPScan Team, “CMSScanner.” [Online]. Available: <https://github.com/wpscanteam/CMSScanner>
- [58] Dionach and O. Vnnen, “CMSmap.” [Online]. Available: <https://github.com/Dionach/CMSmap>
- [59] CMS Garden, “CMS-Garden CMSScanner.” [Online]. Available: <https://github.com/CMS-Garden/cmsscanner>
- [60] P. Worcel, “droopescan.” [Online]. Available: <https://github.com/droope/droopescan/>
- [61] D. Buytaert and Drupal Community, “Drupal.” [Online]. Available: <https://www.drupal.org/>
- [62] SilverStripe Limited, “SilverStripe.” [Online]. Available: <https://www.silverstripe.org/>
- [63] Crashtest Security GmbH, “Crashtest Security.” [Online]. Available: <https://crashtest-security.com>
- [64] Rapid7 LLC, “AppSpider.” [Online]. Available: <https://www.rapid7.com/products/appspider/>
- [65] BeyondTrust, “Retina CS.” [Online]. Available: <https://www.beyondtrust.com/products/retina-cs/>
- [66] G. Irazoqui, M. S. Inci, T. Eisenbarth, and B. Sunar, “Know thy neighbor: Crypto library detection in cloud,” *PoPETs*, vol. 2015, no. 1, pp. 25–40, 2015. [Online]. Available: <http://www.degruyter.com/view/j/popets.2015.1.issue-1/popets-2015-0003/popets-2015-0003.xml>
- [67] F. Armknecht, A. Sadeghi, S. Schulz, and C. Wachsmann, “A security framework for the analysis and design of software attestation,” in *2013 ACM SIGSAC Conference on Computer and Communications Security, CCS’13, Berlin, Germany, November 4-8, 2013*, A. Sadeghi, V. D. Gligor, and M. Yung, Eds. ACM, 2013, pp. 1–12. [Online]. Available: <http://doi.acm.org/10.1145/2508859.2516650>
- [68] A. Seshadri, A. Perrig, L. van Doorn, and P. K. Khosla, “SWATT: software-based attestation for embedded devices,” in *2004 IEEE Symposium on Security and Privacy (S&P 2004)*, 9-12 May 2004, Berkeley, CA, USA. IEEE Computer Society, 2004, p. 272. [Online]. Available: <https://doi.org/10.1109/SECPRI.2004.1301329>
- [69] R. W. Gardner, S. Garera, and A. D. Rubin, “Detecting code alteration by creating a temporary memory bottleneck,” *IEEE Trans. Information Forensics and Security*, vol. 4, no. 4, pp. 638–650, 2009. [Online]. Available: <https://doi.org/10.1109/TIFS.2009.2033231>
- [70] A. Seshadri, M. Luk, and A. Perrig, “SAKE: software attestation for key establishment in sensor networks,” *Ad Hoc Networks*, vol. 9, no. 6, pp. 1059–1067, 2011. [Online]. Available: <https://doi.org/10.1016/j.adhoc.2010.08.011>
- [71] Oracle Corporation, “MySQL :: MySQL 5.7 Reference Manual :: 9.6 Comment Syntax.” [Online]. Available: <https://dev.mysql.com/doc/refman/5.7/en/comments.html>
- [72] D. Reed, “Fingerprint Fucker.” [Online]. Available: <https://packetstormsecurity.com/UNIX/misc/bsdspf.tar.gz>
- [73] D. B. Berrueta, “A practical approach for defeating Nmap OS-Fingerprinting.” [Online]. Available: <https://nmap.org/misc/defeat-nmap-osdetect.html>
- [74] M. Smart, G. R. Malan, and F. Jahanian, “Defeating TCP/IP stack fingerprinting,” in *9th USENIX Security Symposium, Denver, Colorado, USA, August 14-17, 2000*, S. M. Bellovin and G. Rose, Eds. USENIX Association, 2000. [Online]. Available: <https://www.usenix.org/conference/9th-usenix-security-symposium/defeating-tcpip-stack-fingerprinting>

APPENDIX

This is a thorough description of all employed fingerprinting techniques used by state of the art implementations of an RSI scheme Π_{RSI} , see Section II-D.

A. Class 1: Version Label-Depending Techniques

1) *Version Claim*: The most simple and intuitive fingerprinting technique is to send a challenge with the task to reply with the current software version inside the running environment. This information together with environmental data is sent as a response and evaluated, e.g., by extracting the version number using regular expressions. Usually, this method is available for any kind of interface I , e.g., may even be public information. For example, version number in the footer of a website or as part of a banner⁵.

One type of Version Claim is known as the information disclosure attack. In this attack, the remote software contains a usually publicly accessible resource that leaks internal information. For web services, many PHP installation tutorials instruct the administrator to create a PHP file that calls the function `phpinfo()` for debugging purposes. Various installed applications include such a file by default which can be accessed easily by a remote attacker, extracting a large amount of information about the software and server, e.g., PHP and operating system version, server IP address, configuration data, and so on. Keep in mind that a malicious service provider can put arbitrary information in such a file, placing a red herring for attackers and fingerprinting tools at the same time. See Remark 1 for a general description of an attack strategy for the software provider.

2) *Version API*: The verifier will send a challenge to the API (application programming interface) which in turn directly yields the version number, hence no further processing is necessary. For example, in PHP this can be realized by calling `phpinfo()` or in most SQL databases via `SELECT VERSION()`. It is very similar to Version Claim with the only difference that the employed challenge interface needs to have API access. The reason why we include and differentiate this technique from Version Claim is that in practice, either Version Claim or a combination of both is used, increasing the capabilities of implementations.

3) *Version Specific Features*: The idea of this fingerprinting technique is to challenge S_{chl} to reply with a function that is specific for a single software version only, i.e., that literally depends on the software version. Such a task consists of two steps: first, load the software version from storage, second, if the software version equals the specific version given in the challenge, perform a simple equation check of two randomly chosen equal numbers. As a result, this will only be true,

⁵Here, a banner means an ASCII rendering of text or an image with additional information like the version number and, e.g., the software authors.

if the stored version number is the same as the version number contained in the challenge. One example are MySQL queries which use comment execution [71], i.e., a comments is interpreted and executed as a command only if the version requirement is fulfilled. However, note that this technique can be reduced to Version Claim due to reading the version label from storage.

4) *Sub-Software*: This fingerprinting technique identifies the software version of a software S by identifying the software versions of some “sub-software” $\tilde{S} := S_1, \dots, S_n$ that can be part of S , such as plug-ins. In practice, implementations perform this test by using the techniques Version Claim, File Structure/Content (see below), or simply check for file existence for each $S \in \tilde{S}$. Note that this technique requires a sufficient populated list $\tilde{S}$ to deduce v_S . For example, a content management system can load multiple plugins to enhance its functionality. Then, each of them is placed in a certain subfolder which gets scanned by this fingerprinting technique for plugin versions or existence.

Note that this technique relies only on other techniques which are part of fingerprinting technique classes that are not secure, see Appendix D1. Even assuming these techniques would be secure, $\tilde{S}$ must be sufficiently large in order to conclude the version number of S , we currently see no software employing enough plugins in order to reliably determine its version. Since this fingerprinting technique can be reduced to Version Claim or File Structure/Content, it belongs to both fingerprinting technique classes one and two.

5) *Error Code*: Similar to Version Claim and Version API, V sends a query to S in order to retrieve a string containing the version number. However, in this case, the goal is to provoke an error in the software to output an error message containing the version number. For example, using a string as input for a function that is only defined for integer input. One of the tools relying on this technique is `nmap` [39]. incorporates this technique but can be defeated by appropriate tools [72]–[74]. Since this fingerprinting technique can be reduced to Version Claim or File Structure/Content, it belongs to both fingerprinting technique classes one and two.

If an error occurs in an underlying software S that acts as a platform for S_{chl} , for example, a database to run a forum, information about S can be retrieved through S_{chl} . We are not aware that any software uses this technique but list it here for completeness, please see Remark 2 for more details.

B. Class 2: Output Function-Depending Techniques

1) *File Structure/Content*: In this technique, a challenge of the verifier requests S_{chl} to respond with a certain file. The reply, i.e., a static file, is then parsed by the verifier, e.g., by using regular expressions or to check the structure of the file, e.g., order of configuration commands. The outcome is compared to certain previously computed values which belong to a software version each. For example, a verifier will search for certain text strings, HTML tag nesting, referenced URLs, simple key words, or the style of a readme file. As for Version Claim, a malicious provider can change the content of the

static files, i.e., strings. See Remark 1 for a general description of an attack strategy for the provider and Remark 3 for a note on file randomization.

2) *File Hash Digest*: This technique is sometimes referred to as “aggressive verification” by various implementations, since it checks every bit of a requested file. A hash algorithm is applied to the file retrieved by a response and afterwards this value is compared to a pre-computed hash value stored at the verifier. For example, the verifier may request a readme file and a configuration file. On retrieval, he computes the hash value for each file and compares the output with his pre-computed values. Note that this technique can be reduced to File Structure/Content.

C. Class 3: Transition Function-Depending Techniques

1) *Static Function Output*: The idea is to send challenges, where the according response depends on certain version-dependent functions to verify if these functions exist properly. Parameters p for a function f can be fixed or randomized. In essence, the challenges consists of performing the comparison $f(p) = f(p)$. For example, sending a query to execute `(content(var)=content(var))` with fixed values, will require the existence of the function `content` and the variable `var`. However, this technique will always return a static binary value, i.e. `true` or `false`.

D. Class 4: Security Flaw-Depending Techniques

1) *Security Exploit*: This technique exploits a security vulnerability of the audited software. If no update has been applied, the exploit will be successful. For example, an authentication check may not be performed correctly, allowing access to otherwise protected information.

While vulnerability scanners test for security vulnerabilities, to the best of our knowledge they do not use the outcome to determine the version number. Usually, first the version number is determined, e.g., by Version API, then one or more attacks are performed. Note that this may lead to an abrupt halt of the software, which allows for no further tests or audits.

Remark 1 (Regular Expression and Hash Digest Security): If Π_{RSI} is open source (or reversible) and it uses regular expressions and/or a hash function as a fingerprinting technique, then this provides a blueprint to P how to pretend any version number. The P only needs to investigate the regular expressions or possibly requested files and copy the required file from the software distributor’s original repository (or similar source). Then, he redirects any internal request to that file to a modified version of the file, while any external file access gets delivered the (original) file and hash value of the claimed version. Also observe that if a honest P changes a file in a way that it contains negligible changes (e.g., white spaces) or indeed certain file changes like specific configurations or style changes, the software version did not change but the Π_{RSI} employing the hash digest technique would yield a wrong result. If P knows that a regular expression is used to find a certain value in a given file, he can simply insert a forged value for the certain expression such that the regular

expression discovers the values the P wants to return. If an Π_{RSI} is not open source, P might learn over time which files are accessed, since usually only a very limited set (at most three) of specific files is part of Π_{RSI} .

In summary, this attack shows that neither regular expressions nor hash digests are suited for software version fingerprinting. Using hash functions may even yield false negatives.

Remark 2 (Using Underlying Structures to Determine a Software Version): Independent of software dependencies, only the software S_{chl} is queried during RFP. In RFP, we do not employ underlying or lower level software or structures (LL) as side-channel information for higher level software (HL). Furthermore, a customer usually has no access to LL, but in the case he does, it is trivial to determine the version numbers of HL since he has full control thereof.

For the other way around, using HL to retrieve information about LL, the verifier could provoke errors in HL to produce an error message from LL, e.g., PHP running under Wordpress and an error in PHP due to a false used function of Wordpress. However, this does not allow to precisely determine a version number of LL. The reason is that the error message is static, can be changed to an arbitrary string, and will not depend on different functionalities of LL. If HL is just a wrapper of LL, this comes down to testing LL directly by using another interface, for example, security flaws in HL allow accessing LL through HL. Recall that RFP employs interfaces which can be used to address different access levels.

Remark 3 (On Randomization for File Structure and File Content): To the best of our knowledge, in all current auditing softwares which rely on a technique based on static files such as File Structure/Content and File Hash Digest, usually only a very limited set (in fact, at most three) of specific files is requested in the challenge. Let us assume that any file of S_{chl} can be chosen by the verifier and S_{chl} provides enough files such that it is unfeasible for provider P to create a file-switch for each file, i.e., decide which version to deliver depending on the verifier's challenge. Then, randomization will not be economical, i.e., more expensive than running the agreed on software S_{trg} , and hence out of interest for P.

In this section we will provide a security analysis of the classes of fingerprinting techniques given in Section II-D.

E. Class 1: Version Label-Depending Techniques

During setup, $S_{\text{trg}} \in \mathcal{S}$ is chosen and P sets $S_{\text{chl}} = \text{Produce}(S_{\text{src}})$, where both softwares are identical except for $v_{S_{\text{chl}}} \neq v_{S_{\text{src}}}$ and $\Gamma_{S_{\text{chl}}} = \tilde{\gamma}_{S_{\text{src}}} \cup v_{S_{\text{chl}}}$. In the testing phase, V sends σ that requests S_{chl} to output the value of the software version. However, S_{chl} returns $\gamma \leftarrow v_{S_{\text{chl}}}$. Finally, V outputs $C = \gamma = v_{S_{\text{chl}}} \neq v_{S_{\text{src}}}$, which contradicts Π_{RFP} -soundness. Also note that due to $\sigma \notin \text{DSH}(S_{\text{trg}})$, it is immediately clear that the verifier can be fooled.

F. Class 2: Output Function-Depending Techniques

During setup, $S_{\text{trg}} \in \mathcal{S}$ is chosen and P sets $S_{\text{chl}} = \text{Produce}(S_{\text{src}})$, where both softwares are identical except for

$\Gamma_{S_{\text{chl}}} = \tilde{\Gamma}$ and $\omega_{S_{\text{chl}}} = \tilde{\omega}$, such that $\tilde{\omega}$ simulates a software with software version $\tilde{v} \in \tilde{\Gamma}$ by yielding certain elements of $\tilde{\Gamma}$. Note that the value of $v_{S_{\text{chl}}}$ does not matter, since the responses of S_{chl} will not depend on it. In the testing phase, V sends σ that requests S_{chl} to output a (very small) set $\Gamma'_{S_{\text{src}}} \subsetneq \Gamma_{S_{\text{src}}}$. However, S_{chl} returns $\gamma \leftarrow \Gamma'_{S_{\text{chl}}}$. Finally, V outputs $C = \tilde{v} \neq v_{S_{\text{src}}}$ derived from (σ, γ) , which contradicts Π_{RFP} -soundness. Also note that due to $\sigma \notin \text{DSH}(S_{\text{trg}})$, it is immediately clear that the verifier can be fooled.

G. Class 3: Transition Function-Depending Techniques

Let $\Gamma_{\delta} = \{\text{true}, \text{false}\}$. During setup, V selects $S_{\text{trg}} \in \mathcal{S}$ such that it has the highest version for all softwares in $\mathcal{S}$, i.e., $v_{S_{\text{trg}}} > v_S \forall S \in \mathcal{S}$. The P sets $S_{\text{chl}} = \text{Produce}(S_{\text{src}})$, where both softwares are identical except for $\Gamma_{S_{\text{chl}}} = \tilde{\Gamma}$ and $\delta_{S_{\text{chl}}} = \tilde{\delta}$, where $\tilde{\delta}$ simulates $\tilde{v} \in \tilde{\Gamma}$. Furthermore, he sets $v_{S_{\text{chl}}} \neq v_{S_{\text{src}}}$ with $\{v_{S_{\text{chl}}} \cup \Gamma_{\delta}\} \in \tilde{\Gamma}$. The testing phase is as follows:

- 1) V selects a function

$$f \in F_{S_{\text{trg}}} \setminus \bigcup_{\substack{S \in \mathcal{S} \\ v_S < v_{S_{\text{trg}}}}} F_S$$

and sends σ to S_{chl} , requesting the output of f which is defined for this fingerprinting technique as an element of Γ_{δ} .

- 2) S_{chl} returns $\gamma \in \Gamma_{\delta}$.
- 3) If $\gamma = \text{true}$, V sets S_{trg} to be the software with the next lower version in $\mathcal{S}$ and proceeds with step 2). If $\gamma = \text{false}$, V stops.

Since S_{chl} computed each γ according to $\tilde{v}$, V outputs $C = \tilde{v} \neq v_{S_{\text{src}}}$ derived from all tuples (σ, γ) , which contradicts Π_{RFP} -soundness.

Observe that S_{chl} does not need to evaluate f , he may output true and false according to any version $\tilde{v}$ he wants to simulate. This especially holds if f is a simulation-hard function of S_{src} , i.e., $f \notin F_{S_{\text{chl}}}$.

Also note that due to $\sigma \notin \text{DSH}(S_{\text{trg}})$ for all σ chosen in step 1), it is immediately clear that the verifier can be fooled. We refer the reader to Remark 4 where we discuss the property RFP-secure of the class 3 fingerprinting technique Static Function Output, also in respect to existing implementations.

Remark 4 (RFP Secure Static Function Output): We describe and analyze the fingerprinting technique Static Function Output in Appendix C1 and Appendix D1, respectively. To be secure according to RFP, see Definition 8, a fingerprinting technique needs also to be time-constrained, probabilistic, and employ intrinsic functions. Static Function Output might indeed access intrinsic functions and a time-constrained can be added easily. However, the response of S_{chl} is always taken from the decision set $\{\text{true}, \text{false}\}$. The probabilistic protocol Π_{RFP} requires the response to depend on the randomness of the challenge. This is not given in a correct manner for this fingerprinting technique, since no matter how good the randomness source of the verifier is, the malicious prover has always a 50% chance of correct guessing. Note that

the only existing implementation employing this fingerprinting technique [17], does not randomize the challenge. Hence, Static Function Output is not RFP-secure.

H. Class 4: Security Flaw-Depending Techniques

This fingerprinting technique was actually never used to determine a version number, however, it might yield an error state ($\perp$), e.g., due to a deadlock or software crash. In general, S_{chl} might unintentionally halt and V can not run Π_{RFP} until the end. Hence, Π_{RFP} -correctness is not given.

I. Overall Result

The presented classes of fingerprinting techniques violate Π_{RFP} -correctness or Π_{RFP} -soundness and, hence, can be successfully fooled by a malicious prover P .

The bash script presented in Listing 3 manipulates the software version of PHP by changing the configuration values before compiling. The idea is that the strings defining the software version are configuration parameters of the installing process, and hence, may be changed nearly arbitrarily. In Listing 3, these variables are set in Lines 3–7. Note that there is also a “real” version variable which, in RFP terminology, defines S_{src} while the fake ones change the software version string for S_{chl} . In other words, this script essentially performs Produce with $S_{\text{chl}} = \text{Produce}(S_{\text{src}})$. See Section III-C for more information about Produce. Then, PHP 7.1.1 runs as PHP 20.9.85-car on the host system, e.g., Ubuntu 16.04.3 and Apache 2.

Remark 5 (Definition of δ): According to equation (1), testing for a function f as part of Π_{RFP} will yield $\delta = \text{true}$ for all S with $v_{S_{\text{chl}}} \geq v_S$. Let us get an overview of the different equality tests that can be employed here, i.e., $<$, $\leq$, $=$, $\geq$, and $>$. For $=$ we have $\delta \leftarrow \text{true}$ iff $v_{S_{\text{chl}}} = v_S$. However, equality is the overall goal of RFP and can not be achieved by a single Π_{RFP} instance as explained in Section IV-D. Hence, this comparison does not make sense here. For $\geq$ we have $\delta \leftarrow \text{true}$ iff $v_{S_{\text{chl}}} \geq v_S$, naturally represents the fact described in equation (1). Testing for $<$ yields if f has not yet been introduced to $\mathcal{S}$, and complements the test for $\geq$ (and is reflected by $\delta \leftarrow \text{false}$ in Π_{RFP}). Using only $<$ would make testing for newest versions impossible. Similar, a test for $\leq$ and $>$ would also be suitable for Π_{RFP} , representing checking for removed functions. In practice, however, much more often functions will be added than removed, resulting in testing for $(\geq, >)$ being the best candidate.

In Listing 4 we give an example for metadata configuration of a RFP database for the software family PHP.

```

10 "version.test.variables.type": "rand",
11 "version.test.variables.format": "value",
12 "version.test.waittime.amount": 200,
13 "version.test.waittime.type": "milliseconds"
14 },
15 "settings": {
16   "interface.challenges": "ftp",
17   "interface.responses": "http",
18   "strategies": [
19     "BinarySearch",
20     "CascadingBinarySearch",
21     "HighToLow",
22     "LowToHigh",
23     "MajorHighestStepUp"
24   ]
25 },
26 "service": {
27   "name": "php",
28   "versions": { ... }
29 }

```

In Table III we give an overview of related work in comparison of fingerprinting techniques, their classes, and relevant related techniques which possibly could be used as fingerprinting techniques, such as exploiting security flaws.

Listing 4. Example metadata of a RFP database for PHP.

```

1 "creationTimestamp": "2018-10-17T03:32:29+02:00",
2 "lastUpdateTimestamp": "2018-11-14T04:17:18+01:00",
3 "defaultvalues": {
4   "version.test.challenge.setstarttag": "true",
5   "version.test.challenge.setendtag": "false",
6   "version.test.expect.setstarttag": "false",
7   "version.test.expect.setendtag": "false",
8   "version.test.expect.type": "string",
9   "version.test.label": "0",

```

Listing 3. Software version manipulation script in bash for PHP 7.1.1 running on Ubuntu 16.04.3 and Apache 2.

```
1
2 echo "Fetch and install PHP"
3
4 PHP_VERSION_REAL="7.1.1"
5 PHP_VERSION_FAKE_MAJOR="20"
6 PHP_VERSION_FAKE_MINOR="9"
7 PHP_VERSION_FAKE_RELEASE="85"
8 PHP_VERSION_FAKE_EXTRA="-car"
9
10 cd /usr/src
11 if [[ 'wget -S --spider "http://de2.php.net/get/php-$PHP_VERSION_REAL.tar.gz/from/
    this/mirror" 2>&1 | grep 'HTTP/1.1 200 OK' ' ]]; then
12     sudo wget -O "php-$PHP_VERSION_REAL.tar.gz" "http://de2.php.net/get/php-
        $PHP_VERSION_REAL.tar.gz/from/this/mirror"
13 else
14     PHP_VERSION_REAL_MAJOR=${PHP_VERSION_REAL%%.*}
15     sudo wget -O "php-$PHP_VERSION_REAL.tar.gz" "http://museum.php.net/
        php$PHP_VERSION_REAL_MAJOR/php-$PHP_VERSION_REAL.tar.gz"
16 fi
17 sudo tar -zxf "php-$PHP_VERSION_REAL.tar.gz"
18 sudo rm -rf "/usr/src/php-$PHP_VERSION_REAL.tar.gz"
19 sudo mv "php-$PHP_VERSION_REAL" "./php-$PHP_VERSION_FAKE"
20 cd "php-$PHP_VERSION_FAKE"
21 CONFIGFILE=$(ls configure.*) # file type string is not constant
22 sudo sed -i "/PHP_MAJOR_VERSION=/c\PHP_MAJOR_VERSION=$PHP_VERSION_FAKE_MAJOR"
    $CONFIGFILE
23 sudo sed -i "/PHP_MINOR_VERSION=/c\PHP_MINOR_VERSION=$PHP_VERSION_FAKE_MINOR"
    $CONFIGFILE
24 sudo sed -i "/PHP_RELEASE_VERSION=/c\PHP_RELEASE_VERSION=$PHP_VERSION_FAKE_RELEASE"
    $CONFIGFILE
25 sudo sed -i "/PHP_EXTRA_VERSION=/c\PHP_EXTRA_VERSION=$PHP_VERSION_FAKE_EXTRA"
    $CONFIGFILE
26 sudo ./buildconf --force
27 sudo ./configure "--prefix=$DIR_PHP" "--with-apxs2=$DIR_HTTPD/bin/apxs" "--with-
    config-file-path=$DIR_PHP" --with-mysql
28 sudo make
29 sudo make install
30 sudo libtool --finish ./libs
```

Implementation	FT Classes	Fingerprinting Techniques Employed	Relevant Related Techniques
Penetration Frameworks			
Metasploit [10]	1	Version Claim, Version API	Security Exploit
Armitage [34]	1	Version Claim, Version API	Security Exploit
PenTesters Framework [35]	–	–	–
Vulnerability Scanners			
Burp Suite [11]	1	Version Claim, Version API	Security Exploit
Nessus [9]	1	Version Claim, Version API	Security Exploit
Greenbone/OpenVAS [38]	1	Version Claim	Security Exploit
droopescan [60]	1, 2	File Hash Digest, Sub-Software	Security Exploit
nmap [39]	1	Version Claim, Version API, Error Code (TCP)	–
Software Version Reporter [37]	1	Version Claim	–
w3af [40]	–	–	Security Exploit
Web Application Scanning [41]	1	Version Claim, Version API	–
FreeScan [42]	1	Version Claim, Version API	–
Nexpose [44]	1	Version API	–
InsightVM [43]	1	Version API	–
OWASP Nettacker [45]	1	Version API	–
Online Version Scanners			
wappalyzer [46]	1	Version Claim	–
WhatRuns [19]	1	Version Claim	–
WhatWeb [47]	1, 2	Version Claim, File Hash Digest	–
Guess [48]	1, 2	Version Claim, File Structure/Content, Sub-Software	–
BlindElephant [49]	2	File Hash Digest	–
WAFp [50]	2	File Hash Digest	–
Static File Fingerprinting [51]	2	File Hash Digest	–
CMS Scanners			
What CMS? [52]	1	Version Claim	–
WPScan [53]	1, 2	Version Claim, File Structure/Content	–
Plecost [54]	2	File Structure/Content	–
WPSeKu [55]	2	File Structure/Content	–
JoomScan [56]	2	File Structure/Content	–
CMSScanner [57]	2	File Structure/Content	–
CMSmap [58]	1, 2	Version Claim, File Structure/Content	–
CMS-Garden CMSscanner [59]	1, 2	Version Claim, File Structure/Content	–
Other Tools			
sqlmap [17]	1, 3	Version Claim, Error Code, Version Specific Features, Static Function Output	–
This Work			
Reverse Fingerprinting	5	Error Handling, Dynamic Request Response, Non-Destructive Security Exploit	–

TABLE III

DIFFERENT TOOLS AND THEIR EMPLOYED FINGERPRINTING TECHNIQUES (FT). RELEVANT RELATED TECHNIQUES REPRESENT FT THAT A TOOL DOES SUPPORT, BUT ARE NOT USED FOR FINGERPRINTING. FT CLASS FIVE IS, IN CONTRAST TO FT CLASSES ONE TO FOUR, **RFP-SECURE**.