

Apparent modification of the jet-like yield in proton-proton collisions with large underlying event

Gyula Bencédi, Antonio Ortiz,* and Sushanta Tripathy
*Instituto de Ciencias Nucleares, Universidad Nacional Autónoma de México,
Apartado Postal 70-543, México Distrito Federal 04510, México*

(Dated: January 7, 2022)

This paper presents the production of charged particles associated with high- p_T trigger particles ($8 < p_T^{\text{trig.}} < 15$ GeV/ c) at midrapidity in proton-proton collisions at $\sqrt{s} = 5.02$ TeV simulated with PYTHIA 8.244. The study is performed as a function of the relative transverse activity classifier, R_T , which is the relative charged-particle multiplicity in the transverse region ($\pi/3 < |\phi^{\text{trig.}} - \phi^{\text{assoc.}}| < 2\pi/3$) of the di-hadron correlations, and it is sensitive to the Multi-Parton Interactions. The evolution of the yield of associated particles on both the towards and the away regions ($3 \leq p_T^{\text{assoc.}} < 8$ GeV/ c) as a function of R_T is investigated. We propose a strategy which allows for the modelling and subtraction of the underlying event contribution from the towards and the away regions in challenging environments like those characterised by large R_T . We found that the signal in the away region becomes broader with increasing R_T , while its corresponding yield is independent of R_T . Contrarily, the yield increases with R_T in the towards region. This effect is reminiscent of that seen in heavy-ion collisions, where an enhancement of the yield in the towards region for 0-5% central Pb-Pb collisions at $\sqrt{s_{\text{NN}}} = 2.76$ TeV was reported. A discussion on the origin of these effects in PYTHIA, as well as their implications for the interpretation of recent LHC results for pp collisions, is presented.

I. INTRODUCTION

High-energy proton-proton (pp) collisions exhibit heavy ion-like behavior, namely collectivity [1–3] and strangeness enhancement [4], raising the question whether a small drop of Quark-Gluon Plasma (QGP) is produced in such collisions [5]. In nucleus-nucleus (AA) collisions, the in-medium parton energy loss, i.e. the modification of the jet due to the interaction of the fast parton within the dense QCD matter, is among the key studied effects which indicates the presence of QGP [6]. To date no jet quenching [7] is found in small collision systems, however a first attempt has already been made recently to unveil it in high-multiplicity pp collisions at $\sqrt{s} = 13$ TeV [8]. That study consists of measurements of the semi-inclusive acoplanarity distribution of jets recoiling from a high- p_T trigger hadron. A significant broadening of the recoil jet acoplanarity distribution is observed in high-multiplicity pp collisions; the observation is characteristic of jet quenching. However, the effect is seen not only in the experimental data but in the PYTHIA 8.2 model [9] (tune Monash 2013 [10]), which lacks the mechanism of jet quenching. Therefore, studies using PYTHIA 8 with jets in high multiplicity pp events are important in order to understand the potential biases which could mimic jet quenching effects. It is also worth mentioning that recent results which use the PYTHIA/Angantyr model [11], to extend the PYTHIA model to heavy-ion collisions, have shown that hadronic re-scattering in such collisions can produce suppression patterns even without any partonic energy loss [12].

In this paper, we explore a quantity called I_{pp} which is motivated by the I_{AA} [13–15] commonly used in heavy-ion collisions to study jet quenching effects. I_{AA} is the ratio of jet-like yield from AA to the one from pp collisions, and it provides the interplay between the parton production spectrum, the relative importance of quark-quark, gluon-gluon and quark-gluon final states, and energy loss in the medium in heavy-ion collisions. In the towards region, the I_{AA} provides information about the fragmenting jet leaving the medium, while in the away region it additionally reflects the probability that the recoiling parton survives the passage through the medium. In Ref. [15], the ALICE collaboration studied the I_{AA} for central Pb-Pb collisions. They reported a significant suppression ($I_{\text{AA}} \approx 0.6$) in the away region, whereas a moderate enhancement ($I_{\text{AA}} \approx 1.2$) was observed in the towards region. It is worth mentioning that the CMS collaboration draw qualitatively similar conclusions in Ref. [16]. These effects indicate the presence of the medium produced in heavy-ion collisions with which the partons interact along their path.

In this work, we report an analogous study in pp collisions as a function of the underlying event (UE) activity. We study the towards and the away region of the di-hadron correlations of charged-particles associated with high- p_T trigger particles ($8 < p_T^{\text{trig.}} < 15$ GeV/ c). The study is based on Monte Carlo (MC) event samples generated using PYTHIA 8. The UE is the component of the collision which does not directly belong to the leading partonic interaction. At LHC energies, most of this activity originates from semi-hard Multi-Parton Interactions (MPI). Therefore, event classifiers sensitive to UE are important to understand the MPI dynamics and their impact on observables used in heavy-ion collisions to characterize the properties of the dense QCD

* antonio.ortiz@nucleares.unam.mx

medium [17, 18]. In our study, we use the Relative Transverse Activity Classifier, R_T , which has been recently introduced [19, 20] and successfully implemented in the analysis of the LHC data [21, 22]. R_T uses the conventional definition of the “transverse region”, which was adopted in the Underlying Event analysis originally introduced by the CDF collaboration [23, 24] and applied in experiments at RHIC [25] and at LHC [21, 26, 27]. Using the new variable R_T , our study is aimed at understanding the selection biases which could affect the measurement, as well as discussing a strategy to minimize such biases in order to have an observable more suitable for jet quenching searches in small systems.

The paper is organised as follows: section 2 is devoted to discuss the main aspects of the PYTHIA 8.2 model, section 3 describes the event classifier, R_T , and the procedure to extract the jet-like signal using the event mixing technique. Results are presented in section 4, and finally section 5 contains a summary and outlook.

II. EVENT GENERATION WITH PYTHIA 8

PYTHIA is a parton-based event generator, which is one of the most widely used Monte Carlo generators for high-energy collider physics with an emphasis on pp collisions.

The main event of a pp collision can be represented via 2-to-2 matrix elements with hard parton scatterings, defined at the leading order, and it is complemented by the leading-logarithm approximation of parton showers including Initial-State Radiation (ISR) and Final-State Radiation (FSR). The UE is everything except the two outgoing hard scattered partons, and it receives contributions from the beam-remnants, MPI, ISR and FSR. It is an unavoidable background to most of the studied hadron collider observables. The hadronization in PYTHIA is treated using the Lund string fragmentation model [28]. In the Color Reconnection (CR) picture of the model [29], the strings between partons can be rearranged so that the total string length is reduced; in effect, the total charged-particle multiplicity of the event is also reduced.

Besides the main event, events with other partonic interaction processes between the incoming partons are expected. These are called MPIs [30] and are usually soft in nature, although the momentum transfer may also reach the hard interaction energy scale. It was shown earlier that MPIs provide a natural way of explaining the increased activity in the UE in a hard scattering [10].

The results reported in this work are based on simulations of inelastic processes using PYTHIA version 8.244, which has the Monash 2013 tune as its default, and it will be labelled as Monash in the following. This tune has been created for a better description of minimum bias and underlying event observables in high-energy collisions.

III. EVENT ACTIVITY CLASSIFIER AND JET-LIKE SIGNAL EXTRACTION

In order to produce results accessible to the main LHC experiments, we have simulated inelastic pp collisions at $\sqrt{s} = 5.02$ TeV and only primary charged particles with transverse momentum $p_T > 0.5$ GeV/ c and within pseudorapidity $|\eta| < 0.8$ are considered in the analysis. Primary charged particles are defined as all final-state particles including decay products except those from weak decays of strange particles; this definition is similar to the one used by the ALICE experiment [31]. The charged-particle yields are obtained in three different regions defined by the relative azimuthal angle, $\Delta\phi = \phi^{\text{trig.}} - \phi^{\text{assoc.}}$, to the direction of the particle with the largest p_T of the event (trigger particle):

- Towards region: $|\Delta\phi| < \pi/3$,
- Transverse region: $\pi/3 < |\Delta\phi| < 2\pi/3$,
- Away region: $|\Delta\phi| > 2\pi/3$.

The towards and the away regions are dominated by string fragments originating from the hardest partonic process of the event, and are expected to be nearly insensitive to the softer UE. However, the transverse region is the most sensitive to UE and therefore can be used to build the event activity classifier R_T [19]. Above a certain p_T threshold ($p_T^{\text{trig.}} > 8-10$ GeV/ c) corresponding to the onset of the UE plateau in the transverse region, the mean charged-particle multiplicity in the transverse region, $\langle N_{\text{ch}}^{\text{trans.}} \rangle$, have less dependence on $p_T^{\text{trig.}}$ [21]. Therefore, we focus on events having $p_T^{\text{trig.}}$ above the onset of the plateau, and we classify events with a trigger particle in the range $8 \leq p_T^{\text{trig.}} < 15$ GeV/ c based on their per-event activity in the transverse region with respect to the mean:

$$R_T = \frac{N_{\text{ch}}^{\text{trans.}}}{\langle N_{\text{ch}}^{\text{trans.}} \rangle}. \quad (1)$$

The upper limit on $p_T^{\text{trig.}}$ is set in accordance with existing experimental results for central and peripheral Pb–Pb collisions at $\sqrt{s_{\text{NN}}} = 2.76$ TeV [15], which also guarantees a regime where jet-like correlations dominate over collective-like effects [32, 33]. The center-of-mass energy presented in our study has been chosen to motivate the development of this analysis using the unique pp, p–Pb and Pb–Pb LHC data at $\sqrt{s_{\text{NN}}} = 5.02$ TeV; such analysis would aim at unveiling the onset of jet quenching in high-energy hadronic interactions.

Given that we want to get an insight on how the event selection based on the activity in the transverse region biases the towards and the away region, the study is conducted considering the cases where the correlations at partonic level (due to gluon radiation or color reconnection) are disabled. On the one hand, the “hard scattering” component consists of the outgoing two “jets” plus




FIG. 1. Average number of Multi-Parton Interactions, $\langle N_{\text{mpi}} \rangle$, as a function of R_T in pp collisions at $\sqrt{s} = 5.02$ TeV. The results are shown with default settings, without ISR and FSR, and without CR.

initial and final-state radiation [34] which contribute to UE [24]. On the other hand, the high- p_T trigger selection also biases the sample towards events with a large amount of gluon radiation which is balanced on the away region by several low- p_T jet fragments [35]. Color reconnection is a mechanism which also produces correlations among final-state particles [32, 36]. Therefore, we decided to perform the study for three different settings of the Monash tune: a) without ISR and FSR, b) without CR and c) the default parameters of the Monash tune.

The correlation between the average number of MPI, $\langle N_{\text{mpi}} \rangle$, and R_T is shown in Fig. 1. For $R_T < 2$, the average N_{mpi} increases linearly with R_T . It is noteworthy that the correlation is nearly independent of ISR, FSR, and CR. Therefore, in this particular R_T region, we can control the amount of MPI and study potential non trivial soft QCD effects on the jet-like region of the di-hadron correlations. For higher R_T values, $\langle N_{\text{mpi}} \rangle$ exhibits a saturation which is stronger when ISR and FSR are included in the simulations. Having events with the same N_{mpi} but with different multiplicities in the transverse region, suggests that at some point particles from additional jets may be selected to enhance the activity in the transverse region. In turn, above a given R_T value, the activity in the transverse region can be biased towards harder processes due to the presence of a third jet in the transverse region [34].

In order to understand the effects of a potential bias, the di-hadron correlation is obtained for the R_T -integrated event class ($R_T \geq 0$) as well as for five R_T event classes: $0 \leq R_T < 0.5$, $0.5 \leq R_T < 1.5$, $1.5 \leq R_T < 2.5$, $2.5 \leq R_T < 3.5$ and $R_T \geq 3.5$. Events with high R_T (≥ 2.5) are chosen in order to study the impact on the di-hadron correlations when the MPI saturates (see Fig. 1). The left panel of Fig. 2 shows the di-hadron correlation as a function of $\Delta\eta$ ($= \eta^{\text{trigg.}} - \eta^{\text{assoc.}}$) and $\Delta\phi$. The distribution was built by correlating the trigger

particle with associated particles within the same event and with $4 \leq p_T^{\text{assoc.}} < 6$ GeV/c. Correlations for two R_T event classes ($1.5 \leq R_T < 2.5$ and $2.5 \leq R_T < 3.5$) are depicted in Fig. 2. As expected, the characteristic jet peak at $(\Delta\eta, \Delta\phi) = (0, 0)$ and the signal of the associated jet at $\Delta\phi = \pi/2$ are observed. In addition, given the selection on R_T , a third structure is present in the transverse region ($\pi/3 < |\Delta\phi| < 2\pi/3$), and its associated yield increases with R_T . This structure is a consequence of the event selection, therefore, its contribution to the towards and the away regions has to be removed. For this purpose mixed events are used to model the uncorrelated contribution as well as the acceptance effect. Mixed events are built correlating trigger and associated particles from different events. The mixed events are classified based on the multiplicity of their transverse region. The middle panel of Fig. 2 shows the di-hadron correlation for mixed events. As expected, the activity in the transverse region increases with R_T . By construction, for mixed events, we do not see the jet-like correlations. The jet signal $C(\Delta\eta, \Delta\phi)$ is extracted using the following procedure to correct for acceptance effects:

$$C(\Delta\eta, \Delta\phi) = B(0, 0) \frac{S(\Delta\eta, \Delta\phi)}{B(\Delta\eta, \Delta\phi)}, \quad (2)$$

where S (B) stands for the correlation function for same (mixed) events. The signals after the subtraction of the mixed-events correlation based on the method defined by Eq. 2 are shown in the right panel of Fig. 2. The shape of the towards region exhibits little or no dependence on R_T . However, the width of the signal in the away region increases with R_T . The evolution of the observed structures with R_T is further investigated by studying the projection of the $\Delta\eta$ - $\Delta\phi$ distribution along the $\Delta\eta$ axis.

Examining the transverse region of the $\Delta\eta$ - $\Delta\phi$ distributions one can observe that it is flat in $\Delta\eta$. Therefore, the underlying event contribution to the towards and away regions is subtracted with the zero yield at minimum (ZYAM) assumption [37].

IV. RESULTS

The $\Delta\phi$ distributions for various R_T event classes as well as for the R_T -integrated one ($R_T \geq 0$) are shown in Fig. 3. Although correlations using particles within $|\Delta\eta| < 0.8$ and $4 \leq p_T^{\text{assoc.}} < 6$ GeV/c are shown, the conclusions hold for $3 \text{ GeV}/c \leq p_T^{\text{assoc.}} < p_T^{\text{trigg.}}$. The left panel of Fig. 3 shows the distributions for simulations without ISR and FSR. One can observe that the different $\Delta\phi$ regions show no dependence on R_T in the region $0 \leq R_T < 2.5$. Moreover, it is noteworthy that within statistical uncertainties the shape of the jet peaks are independent of R_T . On the contrary, when ISR and FSR are included in the simulations, the away region exhibits a broadening which becomes more prominent for high R_T




FIG. 2. Charged particle yield as a function of $\Delta\eta$ - $\Delta\phi$ for two R_T event classes. The associated particles have a p_T in the range $4 \leq p_T^{\text{assoc.}} < 6 \text{ GeV}/c$. The distribution from the same event (left) exhibits the jet peaks in the towards and away regions at $\Delta\phi = 0$ and $\Delta\phi = \pi/2$. The structure observed in the transverse region can be reproduced using mixed events (middle). The signal (right) is obtained after removing the mixed event distribution from the same event distribution using the method defined in Eq. 2.

values. At the same time, the yield in the towards region increases with R_T . This effect is observed in simulations with (right panel) and without (middle panel) color reconnection. Therefore, CR produces very small effects on the observables which we investigate in the current study.

Regarding the remaining signal in the transverse region, as anticipated by Fig. 1, the presence of a third jet in the transverse region is expected in the R_T range where the average MPI activity saturates. In accordance with this observation, for $R_T > 2.5$, the distributions exhibit a peak at $\Delta\phi \sim 2 \text{ rad}$, which is closer to the peak in the away region. The effect is much stronger when ISR and FSR are included in the simulations. We can say that for full simulations the selection on high R_T (> 2.5) biases the sample towards multi-jet topologies. This effect is observed in experimental data, in particular, for the transverse region, the high- p_T particle production exhibits a strong increase with R_T [22].

In order to quantify the effects discussed above, we calculated the I_{pp} quantity, which is the ratio of yields from different R_T classes to the R_T -integrated one. In the absence of either selection bias or jet quenching, I_{pp} is expected to be consistent with unity. The influence on the jet-like signals of the remaining struc-

tures peaked at $\Delta\phi \sim 2 \text{ rad}$ are reduced by integrating the $\Delta\phi$ distribution within the interval $|\Delta\phi - \pi| < 0.8$ ($|\Delta\phi - \pi| < 0.8$) for the towards (away) region. Figure 4 shows the I_{pp} as a function of $p_T^{\text{assoc.}}$ for both the towards and the away region. Three $p_T^{\text{assoc.}}$ intervals are considered: $3 \leq p_T^{\text{assoc.}} < 4 \text{ GeV}/c$, $4 \leq p_T^{\text{assoc.}} < 6 \text{ GeV}/c$, and $6 \leq p_T^{\text{assoc.}} < 8 \text{ GeV}/c$. Results with and without underlying event subtraction are also presented.

a. Towards region In simulations without ISR and FSR, the I_{pp} is found to be around unity for all the studied $p_T^{\text{assoc.}}$ intervals and R_T event classes. Moreover, given the small selection bias discussed before, the subtraction of the underlying event produces a negligible difference. This suggests that the signal extraction method performs well, and it has negligible effect on the results. When ISR and FSR are included in the simulations, the I_{pp} systematically increases with R_T . The observed rise persists even after the subtraction of the underlying event, although it becomes less steep than in the case without UE subtraction. The evolution of the I_{pp} with R_T is similar for all the $p_T^{\text{assoc.}}$ bins, and it cannot be attributed to the mechanism of color reconnection. Given that this effect is produced by ISR and FSR, and that their contributions are significantly smaller at RHIC than at LHC energies [25], the enhancement in the towards region is




FIG. 3. Charged particle yield as a function of $\Delta\phi$. Results for simulation without radiation (ISR and FSR), without CR, and with default settings are shown in the left, middle, and right panels, respectively. R_T -integrated distributions are compared to those from different R_T classes. The lower panels are zoomed versions of the upper panels.

expected to be less pronounced in pp collisions at RHIC energies. This observation is reminiscent of the heavy-ion data, where I_{AA} was found to be around 1.2 for 0-5% central Pb-Pb collisions at $\sqrt{s_{NN}} = 2.76$ TeV [15], and was not observed at RHIC energies [13, 14]. Our results suggest that radiation in nucleon-nucleon interactions could play a role to explain the behavior of I_{AA} in the towards region from RHIC to LHC energies.

b. Away region: In simulations without ISR and FSR, the away region behaves similarly as the towards region, i.e., the data points sit around unity for the I_{pp} , and the effect of the underlying event is negligible. However, in simulations with ISR and FSR, the I_{pp} evolves, both quantitatively and qualitatively, in a different way with respect to the towards region. Only after the removal of UE from the away region, the I_{pp} is found to be unity within 5% for all the $p_T^{\text{assoc.}}$ and R_T intervals. This suggests that the event selection bias due to leading particle p_T and R_T selection is negligible for this observable. In particular, given the absence of any parton-energy loss mechanism in PYTHIA 8, the I_{pp} is expected to be unity in events with high UE. On the contrary, in central heavy-ion collisions I_{AA} was found to be significantly smaller than one as a consequence of parton energy loss.

Our proposed strategy allows for the extension of the existing results for pp collisions reported by the ALICE experiment at the LHC [38], which currently covers a very limited $R_T \leq 1.5$ interval. This is because in the quoted experiment, the event classification is done with forward detectors instead of the direct measurement of

R_T at midrapidity which causes a limited multiplicity reach [39]. In the measured R_T interval, I_{pp} is consistent with unity both in the towards and the away regions, suggesting the absence of jet quenching in small systems. Nevertheless, with our approach, the jet quenching search can be extended up to around $R_T = 4$.

V. CONCLUSIONS

In this work, we have investigated the azimuthal di-hadron correlations as a function of the so-called Relative Transverse Activity Classifier. High- p_T particles associated to trigger particles ($8 < p_T^{\text{trig.}} < 15$ GeV/c) are considered in the study. We propose to use mixed events followed by a ZYAM subtraction in order to remove the underlying event contribution from the towards and the away regions. The evolution of the jet-like yields with R_T is quantified by the I_{pp} quantity, which is expected to be consistent with unity in the absence of medium effects or selection biases. We observe that the di-hadron correlations, and therefore I_{pp} , are independent of R_T in simulations which do not include ISR and FSR. When ISR and FSR are included in the simulations, the yield in the towards region increases with R_T . This effect is reminiscent of the Pb-Pb data from the ALICE and CMS experiments, although in the PYTHIA 8 model it is driven by a bias. This bias originates from the interplay of two contributions. On the one hand, the transverse region (R_T) is very sensitive to ISR and FSR, therefore, in events




FIG. 4. I_{pp} , the ratio of yield from different R_T classes and from the R_T -integrated class as a function of R_T for the towards (top) and away region (bottom). Results for pp collisions at 5.02 TeV simulated using the Monash tune are presented for three cases: without ISR and FSR (left), without CR (middle) and the default settings (right). Four R_T event classes are shown, as well as three $p_T^{\text{assoc.}}$ intervals. I_{pp} is reported for the cases with (full markers) and without (empty markers) underlying event subtraction. For better visibility, the data points are slightly displaced on the $p_T^{\text{assoc.}}$ -axis. Dashed lines in each panel indicate $\pm 5\%$ deviation from unity.

with large R_T (large ISR and FSR) the transverse region often contains a third jet. On the other hand, it has been reported that the high- p_T trigger selection also biases the sample towards events with a large amount of gluon radiation. These effects produce a correlation between the activity in the transverse region and the leading p_T . We emphasize that this selection bias has to be taken into account in any analysis which use R_T as an event classifier. At the same time, the peak in the away region exhibits a broadening which becomes more evident for high R_T values. The I_{pp} in the away region, on the other hand, is found to be consistent with unity, and independent of R_T and $p_T^{\text{assoc.}}$. This suggests that PYTHIA 8 with ISR and FSR can partially mimic jet-quenching effects in small systems.

Last but not least, we found that our results are in quantitative agreement with the existing measurements at the LHC, i.e. $I_{pp} \approx 1$ for $R_T \leq 1.5$, indicating no hint of jet quenching in small collision systems. However,

our strategy can pave a way to extend the jet quenching searches up to around $R_T = 4$ for small collision systems in experiments at the LHC.

ACKNOWLEDGMENTS

We acknowledge the technical support of Luciano Diaz and Eduardo Murrieta for the maintenance and operation of the computing farm at ICN-UNAM. Support for this work has been received from CONACyT under the Grant No. A1-S-22917, PAPIIT-UNAM under Project No. IN102118. S. T. acknowledges the postdoctoral fellowship of DGAPA UNAM. G. B. acknowledges the postdoctoral fellowship of CONACyT under the Grant No. A1-S-22917, as well as support received during the pandemic by National Research, Development and Innovation Office (NRDIO) OTKA K120660 and FK131979, 2019-2.1.11-TET-2019-00078 (HuMex) and 2019-2.1.6-NEMZKI-2019-00011 (CERN).

- [1] V. Khachatryan *et al.* (CMS), JHEP **09**, 091 (2010).
- [2] V. Khachatryan *et al.* (CMS), Phys. Lett. **B765**, 193 (2017).
- [3] S. Acharya *et al.* (ALICE), Phys. Rev. **C99**, 024906 (2019).

- [4] J. Adam *et al.* (ALICE), Nature Phys. **13**, 535 (2017).
- [5] J. L. Nagle and W. A. Zajc, Ann. Rev. Nucl. Part. Sci. **68**, 211 (2018).
- [6] C. Loizides, Nucl. Phys. A **956**, 200 (2016), arXiv:1602.09138 [nucl-ex].

- [7] U. A. Wiedemann, “Jet Quenching in Heavy Ion Collisions,” in *Relativistic Heavy Ion Physics*, Vol. 23, edited by R. Stock (2010) p. 521, arXiv:0908.2306 [hep-ph].
- [8] P. Jacobs (ALICE), in *28th International Conference on Ultrarelativistic Nucleus-Nucleus Collisions* (2020) arXiv:2001.09517 [nucl-ex].
- [9] T. Sjöstrand, S. Ask, J. R. Christiansen, R. Corke, N. Desai, P. Ilten, S. Mrenna, S. Prestel, C. O. Rasmussen, and P. Z. Skands, *Comput. Phys. Commun.* **191**, 159 (2015).
- [10] P. Skands, S. Carrazza, and J. Rojo, *Eur. Phys. J. C* **74**, 3024 (2014).
- [11] C. Bierlich, G. Gustafson, L. Lönnblad, and H. Shah, *JHEP* **10**, 134 (2018), arXiv:1806.10820 [hep-ph].
- [12] A. V. da Silva, W. M. Serenone, D. Dobrigkeit Chinellato, J. Takahashi, and C. Bierlich, (2020), arXiv:2002.10236 [hep-ph].
- [13] J. Adams *et al.* (STAR Collaboration), *Phys. Rev. Lett.* **97**, 162301 (2006).
- [14] A. Adare *et al.* (PHENIX Collaboration), *Phys. Rev. Lett.* **104**, 252301 (2010).
- [15] K. Aamodt *et al.* (ALICE), *Phys. Rev. Lett.* **108**, 092301 (2012).
- [16] *Very high- p_T triggered dihadron correlations in PbPb and pp collisions at 2.76 TeV*, Tech. Rep. CMS-PAS-HIN-12-010 (CERN, Geneva, 2012).
- [17] A. Ortiz, A. Paz, J. D. Romo, S. Tripathy, E. A. Zepeda, and I. Bautista, (2020), arXiv:2004.03800 [hep-ph].
- [18] P. Palmi, A. Khuntia, and P. Bartalini, (2020), arXiv:2004.06056 [hep-ph].
- [19] T. Martin, P. Skands, and S. Farrington, *Eur. Phys. J. C* **76**, 299 (2016).
- [20] A. Ortiz and L. Valencia Palomo, *Phys. Rev. D* **96**, 114019 (2017).
- [21] S. Acharya *et al.* (ALICE), *JHEP* **04**, 192 (2020).
- [22] V. Zaccaro (ALICE), in *18th International Conference on Strangeness in Quark Matter* (2019) arXiv:1910.04457 [hep-ex].
- [23] R. Field (CDF), *Int. J. Mod. Phys. A* **16S1A**, 250 (2001).
- [24] T. A. Aaltonen *et al.* (CDF), *Phys. Rev. D* **92**, 092009 (2015), arXiv:1508.05340 [hep-ex].
- [25] J. Adam *et al.* (STAR), *Phys. Rev. D* **101**, 052004 (2020), arXiv:1912.08187 [nucl-ex].
- [26] V. Khachatryan *et al.* (CMS), *JHEP* **09**, 137 (2015), arXiv:1507.07229 [hep-ex].
- [27] M. Aaboud *et al.* (ATLAS), *JHEP* **03**, 157 (2017), arXiv:1701.05390 [hep-ex].
- [28] B. Andersson, G. Gustafson, G. Ingelman, and T. Sjöstrand, *Phys. Rept.* **97**, 31 (1983).
- [29] S. Argyropoulos and T. Sjöstrand, *JHEP* **11**, 043 (2014).
- [30] T. Sjöstrand and M. van Zijl, *Phys. Rev. D* **36**, 2019 (1987).
- [31] ALICE-PUBLIC-2017-005 (2017), <https://cds.cern.ch/record/2270008>.
- [32] A. Ortiz, P. Christiansen, E. Flores, I. Cervantes, and G. Paic, *Phys. Rev. Lett.* **111**, 042001 (2013).
- [33] T. Sjöstrand, *Nucl. Phys. A* **982**, 43 (2019).
- [34] R. D. Field (CDF), *eConf C010630*, P501 (2001), arXiv:hep-ph/0201192.
- [35] R. Field, G. Fox, and R. Kelly, *Phys. Lett. B* **119**, 439 (1982).
- [36] A. Ortiz and L. Valencia Palomo, *Phys. Rev. D* **99**, 034027 (2019).
- [37] N. Ajitanand, J. Alexander, P. Chung, W. Holzmann, M. Issah, R. A. Lacey, A. Shevel, A. Taranenko, and P. Danielewicz, *Phys. Rev. C* **72**, 011902 (2005), arXiv:nucl-ex/0501025.
- [38] Y. Mao (ALICE collaboration), <https://indico.cern.ch/event/751767/contributions/3860899/>, presented in the 10th International Conference on Hard and Electromagnetic Probes of High-Energy Nuclear Collisions. 31 May 2020 to 5 June 2020. Online. <https://alice-figure.web.cern.ch/node/17541>, <https://alice-figure.web.cern.ch/node/17542>.
- [39] S. Acharya *et al.* (ALICE), *Eur. Phys. J. C* **79**, 857 (2019), arXiv:1905.07208 [nucl-ex].