

The Direct-Method Oxygen Abundance of Typical Dwarf Galaxies at Cosmic High-Noon*

TIMOTHY GBUREK ¹, BRIAN SIANA ¹, ANAHITA ALAVI ², NAJMEH EMAMI ³, JOHAN RICHARD ⁴,
WILLIAM R. FREEMAN ¹, DANIEL P. STARK,⁵ AND CHRISTOPHER SNAPP-KOLAS¹

¹*Department of Physics & Astronomy, University of California, Riverside, CA 92521, USA*

²*IPAC, California Institute of Technology, 1200 E. California Boulevard, Pasadena, CA 91125, USA*

³*Minnesota Institute for Astrophysics, University of Minnesota, Minneapolis, MN, 55455, USA*

⁴*Univ Lyon, Univ Lyon1, Ens de Lyon, CNRS, Centre de Recherche Astrophysique de Lyon UMR5574, F-69230, Saint-Genis-Laval, France*

⁵*Steward Observatory, University of Arizona, 933 N Cherry Ave, Tucson, AZ 85721, USA*

ABSTRACT

We present a Keck/MOSFIRE, rest-optical, composite spectrum of 16 typical, gravitationally-lensed, star-forming, dwarf galaxies at $1.7 \lesssim z \lesssim 2.6$ ($z_{\text{mean}} = 2.30$), all chosen independent of emission-line strength. These galaxies have a median stellar mass of $\log(M_*/M_\odot)_{\text{med}} = 8.29$ and a median star formation rate of $\text{SFR}_{\text{H}\alpha}^{\text{med}} = 2.25 M_\odot \text{ yr}^{-1}$. We measure the faint, electron-temperature-sensitive, [O III] $\lambda 4363$ emission line at 2.5σ (4.1σ) significance when considering a bootstrapped (statistical-only) uncertainty spectrum. This yields a direct-method oxygen abundance of $12 + \log(\text{O}/\text{H})_{\text{direct}} = 7.87_{-0.22}^{+0.24}$ ($0.15_{-0.06}^{+0.11} Z_\odot$). We investigate the applicability at high- z of locally-calibrated, oxygen-based, strong-line metallicity relations, finding that the local reference calibrations of [Bian et al. \(2018\)](#) best reproduce ($\lesssim 0.15$ dex) our composite metallicity at fixed strong-line ratio. At fixed M_* , our composite is well-represented by the $z \sim 2.3$ direct-method stellar mass – gas-phase metallicity relation (MZR) of [Sanders et al. \(2020\)](#). When comparing to predicted MZRs from the IllustrisTNG and FIRE simulations, having recalculated our stellar masses with more realistic non-parametric star formation histories ($\log(M_*/M_\odot)_{\text{med}} = 8.92$), we find excellent agreement with the FIRE MZR. Our composite is consistent with no metallicity evolution, at fixed M_* and SFR, of the locally-defined fundamental metallicity relation. We measure the doublet ratio $[\text{O II}] \lambda 3729 / [\text{O II}] \lambda 3726 = 1.56 \pm 0.32$ (1.51 ± 0.12) and a corresponding electron density of $n_e = 1_{-0}^{+152} \text{ cm}^{-3}$ ($n_e = 1_{-0}^{+49} \text{ cm}^{-3}$) when considering the bootstrapped (statistical-only) error spectrum. This result suggests that lower-mass galaxies have lower densities than higher-mass galaxies at $z \sim 2$.

Keywords: galaxies: abundances - galaxies: dwarf - galaxies: evolution - galaxies: high-redshift - galaxies: ISM

1. INTRODUCTION

The gas-phase metallicity, or gas-phase oxygen abundance ($12 + \log(\text{O}/\text{H})$) of the interstellar medium (ISM) of galaxies, is a cornerstone in the study of galaxy formation and evolution. The metallicity traces the stellar mass buildup of galaxies through the enrichment over time of the ISM by heavy elements produced via stellar nucleosynthesis. Galaxies, however, are not closed boxes and have inflows of metal-poor gas – the fuel for star formation – from the circumgalactic medium (CGM) and intergalactic medium (IGM) as well as outflows of metal-laden gas triggered by feedback from supernovae and/or active galactic nuclei (AGN). This modulation of

Corresponding author: Timothy Gburek
timothy.gburek@email.ucr.edu

* The data presented herein were obtained at the W. M. Keck Observatory, which is operated as a scientific partnership among the California Institute of Technology, the University of California, and the National Aeronautics and Space Administration. The Observatory was made possible by the generous financial support of the W. M. Keck Foundation.

Based on observations made with the NASA/ESA *Hubble Space Telescope*, obtained from the Data Archive at the Space Telescope Science Institute, which is operated by the Association of Universities for Research in Astronomy, Inc., under NASA contract NAS5-26555. These observations are associated with programs #9289, #11710, #11802, #12201, #12931, #13389, #14209.

the enrichment of the ISM, via gas flows, shows metallicity to also be an important physical property in the study of the cycle of baryons into, out of, and within (baryon recycling) galaxies.

The combination of these processes is reflected in the scaling relation of the gas-phase metallicity (Z) with the stellar mass (M_*) of star-forming galaxies, known more succinctly as the mass–metallicity relation or MZR. This relation demonstrates that stellar mass and metallicity are positively and tightly correlated, whereby in the local Universe, below a characteristic mass of $M_* \approx 10^{10.0-10.5} M_\odot$, the MZR is described by a power-law. Above this characteristic mass, or “turnover” mass, the MZR flattens and asymptotically approaches an upper-limit oxygen abundance. Locally, the MZR has been shown to exist over five decades in M_* from $10^6 \lesssim M_*/M_\odot \lesssim 10^{11}$ (e.g., Tremonti et al. 2004; Lee et al. 2006; Kewley & Ellison 2008; Andrews & Martini 2013; Maiolino & Mannucci 2019; Curti et al. 2020; Sanders et al. 2021). The MZR has also been shown in numerous studies to exist at high- z out to $z > 3$, though with an evolution such that galaxies at fixed M_* have lower metallicities at higher redshifts (e.g., Erb et al. 2006; Maiolino et al. 2008; Henry et al. 2013a,b; Zahid et al. 2013, 2014a,b; Steidel et al. 2014; Maiolino & Mannucci 2019; Sanders et al. 2015, 2020, 2021; Strom et al. 2022). Additionally, at higher redshifts, the turnover mass is found to be larger than seen locally (Zahid et al. 2013, 2014a,b), and at $z > 2$, it is unknown whether the turnover mass exists at all. At $z > 2$ and $M_* \gtrsim 10^9 M_\odot$, the MZR has been described by a single power-law (e.g., Sanders et al. 2021).

In constraining the shape, scatter, and evolution in the MZR, insight is gained into the physics of how star formation processes and baryon flows are connected and how galaxy growth is structured and regulated (e.g., Finlator & Davé 2008; Davé et al. 2012; Ma et al. 2016; Torrey et al. 2014, 2019). For instance, the slope of the low-mass end of the MZR can relate galactic metal retention to how efficient outflows (which remove gas and metals from the ISM/galaxy) and stellar feedback are in regulating star formation and stellar mass growth (e.g., Torrey et al. 2014). Correlated scatter in the MZR can inform of secondary dependencies of the metallicity to properties such as gas-mass and SFR, giving further insight into current conditions of a galaxy as well as elucidating more fundamental relationships between mass, metallicity, and other properties (e.g., Ma et al. 2016; Torrey et al. 2019).

Through the empirical study of the scatter in the MZR, Mannucci et al. (2010) and Lara-López et al. (2010) found that metallicities of galaxies in the Sloan

Digital Sky Survey (SDSS) do in fact have a secondary dependence on SFR, a dependence reaffirmed in more recent work, albeit to varying degrees of the strength of that dependence (e.g., Yates et al. 2012; Andrews & Martini 2013; Maiolino & Mannucci 2019; Curti et al. 2020; Sanders et al. 2021). This $M_* - \text{SFR} - \text{O/H}$ relation is referred to as the fundamental metallicity relation (FMR) and displays a reduced scatter in metallicity of ~ 0.05 dex (compared to ~ 0.1 dex in the MZR; Tremonti et al. 2004). In effect, the FMR is a 3D surface that posits that metallicity is anti-correlated with SFR such that, at fixed M_* , galaxies with above-average (below-average) SFRs will have below-average (above-average) O/H. In addition to a reduction in the intrinsic scatter of metallicity, Mannucci et al. (2010) also suggested that the FMR is redshift-invariant out to $z \sim 2.5$. If true, this naturally explains the evolution in the normalization of the MZR to be observations at various redshifts of different regions of the locally-defined FMR; this is physically motivated by the anti-correlation of O/H with SFR and the observed increase of SFR with redshift at fixed M_* (e.g., Speagle et al. 2014; Whitaker et al. 2014; Sanders et al. 2021). As galaxy samples at high- z have increased in size, evidence has grown that the FMR is indeed redshift-invariant, at least to within ~ 0.1 dex, out to $z \sim 2.5$ and even possibly $z \sim 3.3$ (e.g., Henry et al. 2013a,b; Cresci et al. 2019; Maiolino & Mannucci 2019; Sanders et al. 2018, 2020, 2021). However, this evidence is largely based on metallicities indirectly-calculated via prescriptions calibrated in the local Universe, and it is unknown how accurate these methods are at high- z .

In order to properly assess the evolution of the MZR and FMR, metallicities must be estimated accurately at low- and high- z . This requires an accurate understanding of the nebular physical conditions of star-forming galaxies at different redshifts. Fortunately, a procedure that addresses both of these requirements exists and is applicable at various redshifts, this procedure being the “direct” method of oxygen abundance determination. This method relies on first estimating the electron temperature (T_e) and electron density (n_e) of the ionized nebular gas as these properties are responsible for the strength of the collisionally-excited oxygen emission lines needed for this procedure ([O II] $\lambda\lambda 3726, 3729$ and [O III] $\lambda\lambda 4959, 5007$). These properties are then considered together with flux ratios of the collisionally-excited lines to hydrogen Balmer recombination lines in order to estimate the total oxygen abundance (e.g., Izotov et al. 2006; Osterbrock & Ferland 2006). Unfortunately, this direct method relies on weak auroral emission lines to calculate T_e , which is determined from the flux ra-

tio of strong emission lines (e.g., [O III] $\lambda\lambda 4959, 5007$) to auroral emission lines (e.g., O III] $\lambda\lambda 1661, 1666$ or [O III] $\lambda 4363$) of the same ionic species. While use of [O III] $\lambda 4363$ is common in this methodology as it lies in the rest-optical with [O III] $\lambda\lambda 4959, 5007$, this line is $\sim 30 - 100\times$ fainter than [O III] $\lambda 5007$ (e.g., Jones et al. 2015, Figure 1), typically decreasing in strength with increasing galactic metallicity. As such, large, representative samples of [O III] $\lambda 4363$ -emitters (and thus direct metallicities) have been difficult to acquire with current facilities and instrumentation, especially at high O/H (and M_* by the MZR) and at $z > 1$ where only a handful of [O III] $\lambda 4363$ detections exist, mostly thanks to gravitational lensing (Brammer et al. 2012a; Christensen et al. 2012; Stark et al. 2013; James et al. 2014; Patrício et al. 2018; Gburek et al. 2019; Sanders et al. 2016a, 2020). Moreover, due to the faintness of the auroral lines, both in the UV and optical, the currently-detected auroral-line-emitters at $z > 1$ are clearly biased and are more representative of extreme emission line galaxies (EELGs) than of “typical” star-forming galaxies seen at these redshifts (Sanders et al. 2020). These high- z auroral-line-emitters tend to fall well above the mean $M_* - SFR$ relation defined by typical galaxies at a given redshift and have flux ratios indicative of higher ionization parameters and lower metallicities than average.

To overcome the current limitations of the direct-metallicity method, and therein study more representative samples of galaxies across a wider dynamic range of metallicities and redshifts, indirect “strong-line” methods of determining oxygen abundance were developed (Jensen et al. 1976; Alloin et al. 1979; Pagel et al. 1979). These methods allow for metallicity estimation when [O III] $\lambda 4363$ cannot be detected. Instead, strong-line methods rely on locally-calibrated empirically (e.g., Pettini & Pagel 2004; Jones et al. 2015; Bian et al. 2018; Curti et al. 2020) or theoretically-determined (e.g., McGaugh 1991; Kewley & Dopita 2002; Dopita et al. 2013) relations between metallicity and flux ratios of strong, rest-optical, nebular emission lines. However, while these strong-line methods have proven very useful in understanding the enrichment of local galaxies, they have several drawbacks of their own. For example, depending on the strong-line index and calibration used, metallicity estimates can vary by up to 0.7 dex (Kewley & Ellison 2008). In part, this is due to how the strong-line methods are calibrated. Calibrations based on photoionization models tend to produce higher metallicity estimates than empirical, T_e -based calibrations (Curti et al. 2020, Figure 3). Empirical calibrations can also suffer from sample selection effects whereby individually-

detected [O III] $\lambda 4363$ -emitters yield metallicities of more extreme star-forming regions whereas metallicities from galaxy samples stacked in order to detect [O III] $\lambda 4363$ may be more representative of “typical” galaxies (Curti et al. 2017; Sanders et al. 2020) that fall on the $M_* - SFR$ relation.

When considering high- z galaxies, it is unknown if these locally-calibrated strong-line relations, reflective of H II-region conditions in the local Universe, are applicable for estimating metallicity. Excitation diagrams have shown that star-forming region conditions likely evolve with redshift; this is most notably seen in the [O III] $\lambda 5007/H\beta$ vs. [N II] $\lambda 6583/H\alpha$ Baldwin – Phillips – Terlevich (N2-BPT; Baldwin et al. 1981) diagram, where the locus of star-forming, high- z galaxies is offset from the locus of local, star-forming, SDSS galaxies (e.g., Steidel et al. 2014; Shapley et al. 2015; Strom et al. 2017, 2018; Kashino et al. 2017, 2019; Runco et al. 2022). While it is a current matter of debate as to what is driving this evolution in the locus and thus the H II region physical conditions (see Kewley et al. (2013) for an analysis of several possibilities such as the ionization parameter, electron density, hardness of the ionizing spectrum, and N/O abundance ratio), it is clear that caution must be taken when applying strong-line metallicity methods at high redshift. Calibrations are needed that are derived from objects with analogous physical conditions to typical, star-forming, high- z galaxies.

In this paper, we analyze a $\langle z \rangle = 2.3$ composite spectrum of 16 gravitationally-lensed, typical, star-forming dwarf galaxies selected independent of emission-line strength. In particular, we study the direct-method metallicity from this composite, derived from a detection of the T_e -sensitive [O III] $\lambda 4363$ auroral-line. The paper is organized as follows: In Section 2, we discuss our observations, data reduction, and sample selection. In Section 3, we discuss our spectral-fitting and stacking methodologies, introduce our composite spectrum, and calculate physical properties of our stacking sample and composite. In Section 4, we present our analysis and discussion in regard to how representative our sample is of typical, $z \sim 2.3$, star-forming dwarf galaxies, the applicability of locally-calibrated strong-line metallicity diagnostics at high- z , the slope and normalization of the $z \sim 2.3$ MZR, and the redshift evolution of the FMR. In Section 5, we summarize our results. Finally, in Appendix A, we briefly describe the reasoning and methods behind our refitting of the Bian et al. (2018) strong-line metallicity relations. Throughout this paper, uncertainties reflect our bootstrapped error spectrum for the composite unless stated otherwise. We assume a

Λ CDM cosmology with $H_0 = 70 \text{ km s}^{-1} \text{ Mpc}^{-1}$, $\Omega_\Lambda = 0.7$, and $\Omega_m = 0.3$.

2. OBSERVATIONS, DATA REDUCTION, AND SAMPLE SELECTION

The focus of this paper is the careful analysis of a stack – from which the oxygen abundance is directly measured – of 16 gravitationally-lensed, star-forming, dwarf galaxies at the peak of cosmic star formation. These galaxies at $1.7 < z < 2.6$ have stellar masses of $\log(M_*/M_\odot) < 9.0$ and probe typical dwarf galaxies in this epoch, complimenting the recent large statistical studies of more massive galaxies at these redshifts, such as the Keck Baryonic Structure Survey (KBSS-MOSFIRE; Steidel et al. 2014) and the MOSFIRE Deep Evolution Field survey (MOSDEF; Kriek et al. 2015). In this section, we detail the photometric and spectroscopic observations and data reduction of these galaxies and the larger parent surveys from which the galaxies are drawn. We also discuss the selection strategy of these 16 objects chosen for stacking.

2.1. Photometric Data and Reduction

The galaxy stacking sample is drawn from a spectroscopic follow-up survey of the photometric *Hubble Space Telescope* (*HST*) survey of Alavi et al. (2014, 2016), which was conducted to study faint, low-mass, star-forming galaxies gravitationally-lensed by the foreground galaxy clusters Abell 1689, MACS J0717.5+3745, and MACS J1149.5+2223, among others (hereafter A1689, MACS J0717, and MACS J1149, respectively). This *HST* survey compliments the *Hubble* Frontier Fields (HFF; Lotz et al. 2017) survey of lensing clusters by both adding deep near-ultraviolet (UV) images of the HFF clusters (of which MACS J0717 and MACS J1149 are members) to the deep HFF optical and near-infrared (IR) datasets as well as by adding or including deep near-UV to near-IR photometry of another lensing cluster, A1689.

For galaxies lensed by A1689, near-UV images were taken over two programs in the F225W, F275W, and F336W bandpasses with the Wide Field Camera 3 (WFC3)/UVIS channel on the *HST*. As part of Program ID 12201 (PI: B. Siana), F275W was observed for 30 orbits, and F336W was observed for 4 orbits. As part of Program ID 12931 (PI: B. Siana), F336W was observed for an additional 14 orbits (18 orbits total), and F225W was observed for 10 orbits. In the optical, we used existing *HST* photometry, taken with the Advanced Camera for Surveys (ACS)/WFC channel, in the F475W, F625W, F775W, and F850LP bandpasses (PID: 9289; PI: H. Ford) as well as in the F814W bandpass (PID: 11710; PI: J. Blakeslee). A summary of the

number of orbits for each near-UV and optical filter, as well as the 5σ depths for a $0''.2$ radius aperture, can be found in Alavi et al. (2016, Table 1). In the near-IR, existing images taken over 1-2 orbits with the F125W and F160W filters and the *HST* WFC3/IR channel (PID: 11802; PI: H. Ford) were used. We note that the near-IR footprint for A1689 is smaller than the near-UV and optical footprints, covering 10 of the 13 stacking sample galaxies (see sample selection in Section 2.3) lensed by A1689.

Galaxies behind the lensing clusters MACS J0717 and MACS J1149 were observed with the WFC3/UVIS channel for 8 orbits in both the F275W and F336W bandpasses as part of the Alavi et al. (2016) *HST* survey under Program ID 13389 (PI: B. Siana). In the optical and near-IR, these clusters were observed with *HST* Director’s Discretionary time as part of the Hubble Frontier Fields survey (Lotz et al. 2017). As with all clusters in this survey (6 total), MACS J0717 and MACS J1149 were observed for 70 orbits with each ACS/WFC and WFC3/IR (140 orbits total). These HFF clusters are observed in the F435W, F606W, and F814W filters with ACS/WFC and the F105W, F125W, F140W, and F160W filters with WFC3/IR (PID: 13498 for MACS J0717; PID: 13504 for MACS J1149; PI: J. Lotz). As for the optical and near-UV photometry of A1689, the depths and orbits (both from the HFF survey and other projects) for each filter are listed for MACS J0717 in Alavi et al. (2016, Table 1). This information can be found for MACS J1149 via the Mikulski Archive for Space Telescopes (MAST) website for the HFF survey.¹

The data reduction, calibration, and photometric measurements for MACS J0717 and MACS J1149 are detailed in Alavi et al. (2016), as is the UV data reduction and calibration for A1689. The reduction and calibration of the optical data from A1689, as well as the photometric measurements for this cluster, are discussed in Alavi et al. (2014). The near-IR photometry of A1689 was reduced in the same way as the UV and optical data with the exception that a larger pixel scale of $0''.08$ was used in the final drizzled images. As described in Alavi et al. (2014, 2016), our main photometric catalog for A1689 is built on the UV and optical images with a pixel scale of $0''.04$. For the areas of A1689 with near-IR coverage, the multi-band photometry (from UV to near-IR) was remeasured on images with larger pixel scales and that are PSF-matched to the F160W data. The estimations of photometric redshifts, which were used to select the spectroscopic follow-up survey sam-

¹ <https://archive.stsci.edu/prepds/frontier/mac1149.html>

ple detailed in Section 2.2, are described in Alavi et al. (2016).

2.1.1. Lens Models

When working with objects gravitationally-lensed by foreground galaxy clusters, accurate lens models are imperative for correcting observed photometry and spectroscopy for the lensing magnification. This correction is necessary for the determination of an object’s intrinsic properties (e.g., stellar mass, SFR, etc.). Alavi et al. (2016) detail the lens models considered and used for the HFF clusters and A1689, all of which, while constructed with different assumptions and methodologies, are constrained by the location and redshift of known multiply-imaged systems. As stated in Alavi et al. (2016), for the HFF clusters we use the lens models derived by the Clusters As TelescopeS (CATS) collaboration,² specifically the models of Limousin et al. (2016) and Jauzac et al. (2016) for MACS J0717 and MACS J1149, respectively. For A1689, we use the lens model of Limousin et al. (2007). These parametric models are all derived via mass reconstruction done with the LENSTOOL³ software (Jullo et al. 2007).

2.2. Spectroscopic Data and Reduction

As a follow-up to the photometric *HST* survey of Alavi et al. (2014, 2016), a spectroscopic survey was conducted between 2014 January and 2017 March to obtain near-IR (rest-optical) spectroscopy of select galaxies with the Multi-Object Spectrometer For InfraRed Exploration (MOSFIRE; McLean et al. 2010, 2012) on the 10 m Keck I telescope. Galaxies for this survey were selected to have high magnifications, observed optical magnitudes (F606W or F625W) less than 26.0 (AB), and photometric redshifts in three redshift ranges, $1.37 \leq z \leq 1.70$, $2.09 \leq z \leq 2.61$, and $2.95 \leq z \leq 3.80$, so that the strong, rest-optical, nebular emission lines of the galaxies lie in the near-IR atmospheric transmission windows. Early selection of galaxies in MACS J0717 and MACS J1149 used photometric redshifts from the CLASH survey (Postman et al. 2012). In all, 151 sources were observed across 9 masks. For galaxies that fall into the two lowest redshift ranges, the strong, nebular emission lines targeted are [O II] $\lambda\lambda 3726, 3729$, H β , [O III] $\lambda\lambda 4959, 5007$, H α , and [N II] $\lambda\lambda 6548, 6583$. To this end, observations of galaxies in the lowest redshift range were conducted using the *Y*-, *J*-, and *H*-band filters, whereas the *J*-, *H*-, and *K*-band filters were used for the two highest redshift ranges. We note that while we targeted

the strong, nebular emission lines in the highest redshift range as well, H α and the [N II] doublet were not observed as they fall outside of the *K*-band’s wavelength coverage.

Observations used an ABBA dither pattern with a 2''5 dither spacing. The individual exposure time for *J*-band and *H*-band data was 120 s and was 180 s for *Y*-band and *K*-band data. In total, across the 9 masks, the *J*-band was observed between 48 m and 112 m, the *H*-band between 56 m and 112 m, and the *K*-band between 60 m and 120 m, for average total exposure times of 81 m, 85 m, and 82 m, respectively. Data in the *Y*-band were taken for one mask in A1689 for a total of 96 m. In each mask, we used 0''7-wide slits, yielding spectral resolutions of $R = 3388, 3318, 3660, \text{ and } 3610$ for the *Y*-, *J*-, *H*-, and *K*-bands, respectively.⁴ Our typical FWHM seeing for a given mask/filter combination was 0''71.

The spectroscopic data obtained with MOSFIRE were reduced with the MOSFIRE Data Reduction Pipeline⁵ (DRP). This DRP returns a 2D flat-fielded, wavelength-calibrated, background-subtracted, and rectified spectrum for each slit in a given mask. This output spectrum is a composite of the multiple spectra taken at each nod position. For *Y*-, *J*-, and *H*-band spectra, wavelength calibration is performed using the night-sky lines, whereas a combination of night-sky lines and a neon arc lamp is used for *K*-band spectra owing to the faintness of the sky lines and the dominance of thermal noise at the red end of the band. Once the 2D spectra were produced, the 1D spectra were extracted using the custom IDL software BMEP⁶ from Freeman et al. (2019). Each spectrum is flux-calibrated with two stars. A standard star of spectral type B9 V to A2 V is first used to apply a wavelength-dependent calibration. It is ensured that this standard star was observed at an air mass similar to that of the mask under consideration. Following this step, an absolute flux calibration is conducted using a star that was included in the corresponding mask.

2.3. Sample Selection for Dwarf Galaxy Stack

The galaxies that comprise the stack mentioned in the opening of this section are drawn from the photometric and spectroscopic surveys detailed above. These galaxies are required to have a robust spectroscopic redshift and spectroscopic coverage of the strong, rest-optical, nebular emission lines: [O II] $\lambda\lambda 3726, 3729$, H β , [O III]

² <https://archive.stsci.edu/prepds/frontier/lensmodels/>

³ <https://projets.lam.fr/projects/lenstool/wiki>

⁴ <https://www2.keck.hawaii.edu/inst/mosfire/grating.html>

⁵ <https://keck-datareductionpipelines.github.io/MosfireDRP/>

⁶ <https://github.com/billfreeman44/bmep>

$\lambda 4959$, $H\alpha$, and $[\text{N II}] \lambda\lambda 6548, 6583$. Additionally, these galaxies must have spectroscopic coverage of $H\gamma$ and the faint $[\text{O III}] \lambda 4363$ auroral emission line. The auroral line is essential for determining gas-phase metallicity directly as it is a component of the emission-line ratio used to estimate electron temperature (T_e ; see Section 3.5 for more details). These redshift and coverage requirements yield a sample of 18 galaxies and 24 total spectra when accounting for multiply-imaged systems, of which we have four in our sample. A final cut is made on stellar mass (see Section 3.2 on mass estimation) to ensure that our sample lies in the dwarf galaxy regime ($\log(M_*/M_\odot) < 9.0$). With this cut, two galaxies are removed from our sample, yielding a final count of 16 galaxies (22 total spectra) ranging in redshift from $z = 1.70$ to $z = 2.59$ ($z_{\text{mean}} = 2.30$).

We note here that $H\gamma$ coverage is included as a requirement so as to provide another Balmer decrement with which to estimate the dust extinction from the stack. Due to the close proximity of $H\gamma$ (4340 Å) to $[\text{O III}] \lambda 4363$, this inclusion does not affect our sample size. We also note here that we do not require spectroscopic coverage of the $[\text{O III}] \lambda 5007$ line of the $[\text{O III}] \lambda\lambda 4959, 5007$ doublet so as to maximize our galaxy count by including those sources for which $[\text{O III}] \lambda 5007$ falls just redward of a given filter. Instead, when necessary, we make use of the T_e -insensitive intrinsic intensity ratio of the doublet: $[\text{O III}] \lambda 5007 / [\text{O III}] \lambda 4959 = 2.98$ (Storey & Zeippen 2000). Lastly, while we do not select galaxies based on the strength of any given emission line, we do note that each spectrum has a signal-to-noise ratio (S/N) for $[\text{O III}] \lambda 5007$ of $\text{S/N} > 5$, ensuring accurate normalization of each spectrum (by $[\text{O III}] \lambda 5007$) during the stacking process (see Section 3.3). A summary of our sample, and some of the galaxies’ physical properties, are listed in Table 1.

3. MEASUREMENTS AND STACKING METHODOLOGY

In this section, we detail our methodologies for fitting the spectroscopy and photometry of the dwarf galaxies in our stacking sample. We also discuss how various physical properties are estimated either for the individual galaxies or for the “sample-average” dwarf galaxy, represented by a composite spectrum of these dwarfs. We begin by discussing the measurements made for individual galaxies and then proceed to the construction and analysis of the composite spectrum.

3.1. Fitting the Individual Emission-Line Spectra

Each emission-line spectrum in our stacking sample (22 total), corresponding to either the single image of a galaxy or one of a multiply-imaged galaxy, is fit using the Markov Chain Monte Carlo Ensemble sampler **emcee**⁷ (Foreman-Mackey et al. 2013). Lines are fit to each spectrum’s continuum, and single-Gaussian profiles are fit to the emission lines. To minimize the impact on the spectral-fitting from pixels contaminated by sky lines, we removed, prior to fitting, any pixels with a corresponding error spectrum value $> 3\times$ the median error value over the range of the fit.

When fitting, each spectroscopic band (Y, J, H, K) was considered separately. For each spectrum, the slope and intercept of the continuum were free parameters. In the band containing $H\alpha$ and the $[\text{N II}]$ doublet (the H - or the K -band), the free parameters also included the redshift of the spectrum, the width of the emission lines (each line having the same width), and the amplitudes of the $H\alpha$ and $[\text{N II}] \lambda 6583$ lines, with the amplitude of $[\text{N II}] \lambda 6583$ constrained such that $[\text{N II}] \lambda 6583 / [\text{N II}] \lambda 6548 = 2.95$ (Acker et al. 1989).

In the band containing $H\gamma$, $[\text{O III}] \lambda 4363$, $H\beta$, and $[\text{O III}] \lambda 4959$ (the J - or H -band), two fits were conducted due to the large wavelength separation between $[\text{O III}] \lambda 4363$ and $H\beta$. The portion of the spectrum containing $H\beta$ and $[\text{O III}] \lambda 4959$ (and $[\text{O III}] \lambda 5007$ if covered) was fit first, having the free parameters of line-width for the filter, redshift, and emission-line amplitudes. If $[\text{O III}] \lambda 5007$ is within the spectrum’s wavelength coverage, its amplitude was fit with the constraint that $[\text{O III}] \lambda 5007 / [\text{O III}] \lambda 4959 = 2.98$ (Storey & Zeippen 2000). Otherwise, the amplitude of $[\text{O III}] \lambda 4959$ was fit, and the line’s flux was multiplied by the aforementioned intensity ratio in order to estimate the $[\text{O III}] \lambda 5007$ flux. With a best-fit width and redshift in-hand from the first fit to the filter, the fainter $H\gamma$ and $[\text{O III}] \lambda 4363$ lines were then fit with these two parameters fixed.

Finally, in the band containing the $[\text{O II}] \lambda\lambda 3726, 3729$ doublet (the Y - or J -band), the redshift and line-width were fixed to the values fit to the complete spectrum’s highest S/N line in order to avoid complications resulting from the doublet lines’ small wavelength separation. In addition to the continuum parameters, only the $[\text{O II}]$ lines’ amplitudes were free parameters in these fits.

Ultimately, the final redshift given to the full spectrum is the weighted average of the redshifts fit to the J (H)- and H (K)-bands.

3.1.1. Slit-Loss Correction

⁷ <https://emcee.readthedocs.io/en/v2.2.1/>

Table 1. Summary and Properties of $\langle z \rangle = 2.3$ Dwarf Galaxy Stacking Sample

Galaxy	Spec. ID	z^a	R.A. ^b	Dec. ^b	$\log(\frac{M_*}{M_\odot})_{\text{fid}}^c$	$\log(\frac{M_*}{M_\odot})^d$	$\frac{\text{SFR}}{M_\odot \text{ yr}^{-1}}^e$	$\log(\frac{L_{\text{H}\alpha}}{\text{erg s}^{-1}})^f$
1	A1689-1037	1.70089	13:11:35.197	-01:20:25.040	$7.71_{-0.37}^{+0.20}$	$8.12_{-0.23}^{+0.22}$	0.151 ± 0.004	$40.511_{-0.013}^{+0.013}$
2	A1689-1197	1.70261	13:11:29.689	-01:20:08.769	$8.45_{-0.05}^{+0.05}$	$8.87_{-0.10}^{+0.13}$	— ^h	— ^h
	A1689-370	1.70257	13:11:32.406	-01:21:16.027	$8.31_{-0.05}^{+0.05}$	$8.71_{-0.11}^{+0.12}$	1.779 ± 0.020	$41.583_{-0.005}^{+0.005}$
	<i>Composite</i> ^g	1.70259	—	—	$8.36_{-0.04}^{+0.03}$	$8.79_{-0.08}^{+0.08}$	1.779 ± 0.020	$41.583_{-0.005}^{+0.005}$
3	A1689-280	1.70316	13:11:31.886	-01:21:26.014	$7.91_{-0.05}^{+0.04}$	$8.70_{-0.21}^{+0.23}$	0.692 ± 0.011	$41.173_{-0.007}^{+0.007}$
4	A1689-257	1.70355	13:11:26.426	-01:21:31.277	$7.81_{-0.10}^{+0.08}$	$8.47_{-0.14}^{+0.18}$	1.809 ± 0.027	$41.590_{-0.007}^{+0.006}$
5	A1689-1751	2.38159	13:11:31.333	-01:19:18.559	$8.82_{-0.09}^{+0.07}$	$9.23_{-0.12}^{+0.17}$	3.071 ± 0.145	$41.820_{-0.021}^{+0.020}$
6	A1689-232	2.38709	13:11:32.794	-01:21:27.893	$7.06_{-7.06}^{+1.10}$	$8.70_{-0.19}^{+0.20}$	2.368 ± 0.185	$41.707_{-0.035}^{+0.033}$
7	M0717-3958	2.39329	07:17:27.442	+37:45:25.475	$8.69_{-0.16}^{+0.11}$	$9.42_{-0.12}^{+0.09}$	2.072 ± 0.139	$41.649_{-0.030}^{+0.028}$
	M0717-4517	2.39330	07:17:27.050	+37:45:09.695	$8.99_{-0.09}^{+0.07}$	$9.46_{-0.09}^{+0.09}$	2.350 ± 0.128	$41.704_{-0.024}^{+0.023}$
	<i>Composite</i> ^g	2.39329	—	—	$8.84_{-0.08}^{+0.07}$	$9.44_{-0.07}^{+0.07}$	2.223 ± 0.094	$41.680_{-0.019}^{+0.018}$
8	A1689-1059	2.41141	13:11:25.228	-01:20:19.309	$8.40_{-0.03}^{+0.03}$	$9.03_{-0.21}^{+0.17}$	5.041 ± 0.464	$42.035_{-0.042}^{+0.038}$
9	A1689-1467	2.51903	13:11:26.118	-01:19:42.837	$8.21_{-0.13}^{+0.10}$	$8.76_{-0.17}^{+0.18}$	2.287 ± 0.441	$41.692_{-0.093}^{+0.077}$
10	A1689-1216	2.54082	13:11:31.981	-01:20:07.173	$8.70_{-0.07}^{+0.06}$	$9.07_{-0.15}^{+0.15}$	0.822 ± 0.144	$41.248_{-0.084}^{+0.070}$
	A1689-1292	2.54064	13:11:26.528	-01:19:55.146	$8.90_{-0.07}^{+0.06}$	$9.07_{-0.13}^{+0.11}$	0.667 ± 0.097	$41.157_{-0.068}^{+0.059}$
	A1689-537	2.54046	13:11:29.795	-01:21:05.969	$8.60_{-0.10}^{+0.08}$	$9.05_{-0.19}^{+0.17}$	1.725 ± 0.397	$41.570_{-0.114}^{+0.090}$
	<i>Composite</i> ^g	2.54065	—	—	$8.70_{-0.04}^{+0.04}$	$9.07_{-0.08}^{+0.08}$	0.755 ± 0.079	$41.211_{-0.048}^{+0.043}$
11	A1689-470	2.54112	13:11:26.213	-01:21:09.695	$7.28_{-7.28}^{+0.31}$	$8.49_{-0.21}^{+0.22}$	1.235 ± 0.160	$41.425_{-0.060}^{+0.053}$
12	A1689-1451	2.54201	13:11:28.682	-01:19:42.849	$8.22_{-0.09}^{+0.08}$	$9.10_{-0.16}^{+0.17}$	0.756 ± 0.128	$41.211_{-0.080}^{+0.068}$
13	A1689-722	2.54247	13:11:33.915	-01:20:52.526	$8.78_{-0.36}^{+0.20}$	$8.81_{-0.24}^{+0.22}$	3.771 ± 0.291	$41.910_{-0.035}^{+0.032}$
14	M0717-1531	2.55185	07:17:32.547	+37:45:02.348	$9.08_{-0.14}^{+0.11}$	$9.94_{-0.06}^{+0.25}$	5.558 ± 0.441	$42.078_{-0.036}^{+0.033}$
	M0717-3187	2.55159	07:17:35.089	+37:45:48.120	$8.90_{-0.14}^{+0.10}$	$9.67_{-0.15}^{+0.17}$	5.965 ± 0.268	$42.109_{-0.020}^{+0.019}$
	M0717-5970	2.55167	07:17:30.613	+37:44:22.798	$8.82_{-0.29}^{+0.17}$	$9.66_{-0.10}^{+0.08}$	3.969 ± 0.283	$41.932_{-0.032}^{+0.030}$
	<i>Composite</i> ^g	2.55168	—	—	$8.93_{-0.09}^{+0.07}$	$9.72_{-0.07}^{+0.07}$	5.109 ± 0.178	$42.041_{-0.015}^{+0.015}$
15	A1689-217	2.59181	13:11:27.623	-01:21:35.622	$8.23_{-0.04}^{+0.04}$	$9.22_{-0.18}^{+0.17}$	9.194 ± 0.313	$42.297_{-0.015}^{+0.015}$
16	M1149-2185	2.59366	11:49:40.162	+22:25:07.571	$8.83_{-0.06}^{+0.05}$	$9.33_{-0.04}^{+0.04}$	33.602 ± 3.037	$42.859_{-0.041}^{+0.038}$

^aSpectroscopic redshift – all uncertainties are $\sigma_z \lesssim 6 \times 10^{-5}$.

^bRight Ascension: hh:mm:ss.sss; Declination: dd:mm:ss.sss; Equinox: J2000

^cOur fiducial de-magnified stellar mass estimates assuming constant star formation histories (SFH). See Section 3.2.

^dDe-magnified stellar masses estimated assuming non-parametric SFHs. These estimates are considered in Section 4.3.2.

^eStar formation rates calculated from H α luminosities assuming a Chabrier (2003) IMF. See Section 3.4 and Equation 1.

^fAll H α luminosities are corrected for slit-loss (Section 3.1.1), magnification (Section 2.1.1), and dust extinction (Section 3.4). The dust extinction correction applied to each luminosity is the same and is derived from the composite spectrum of the total sample. The luminosities are not corrected for stellar absorption, which on average would result in an increase of $< 1\%$.

^gThe redshift, stellar masses, and H α luminosity are weighted-averages. The SFR is calculated from this luminosity.

^hH α was not used here or in the composite of A1689-1197 and A1689-370 because it is at the edge of our Y-band spectrum of this image (with [N II] $\lambda 6583$ falling outside of our coverage).

When measuring the emission-line fluxes from spectra observed through slit masks, care must be taken to account for loss of flux outside of the slits in order to recover the full integrated flux values. To this end, our emission-line fluxes were slit-loss-corrected on a galaxy-by-galaxy basis using the methodology of [Emami et al. \(2020\)](#).

3.2. SED-Fitting and Stellar Mass Estimation

To determine the stellar masses of the galaxies in our stacking sample, we fit spectral energy distributions (SEDs) to our *HST* near-UV to near-IR photometry (we note that three galaxies lensed by A1689 lack near-IR photometry; see Section 2.1). At high redshift, observations suggest that high equivalent width emission lines are fairly common, particularly in lower-mass galaxies like those in our sample ([Reddy et al. 2018](#)). Therefore, prior to SED-fitting, we subtracted off any contribution to the photometry from the slit-loss-corrected, nebular emission lines. We also added an additional 3% flux error, in quadrature, to all bands in order to account for systematic errors in the photometry ([Alavi et al. 2016](#)). To this emission-line-corrected photometry, we then fit [Bruzual & Charlot \(2003\)](#) stellar population synthesis models using the SED-fitting code **FAST**⁸ ([Kriek et al. 2009](#)). We assume constant star formation histories (SFH), a [Chabrier \(2003\)](#) initial mass function (IMF), stellar metallicities of $0.2 Z_{\odot}$ or $0.4 Z_{\odot}$, and a [Calzetti et al. \(2000\)](#) dust attenuation curve. The redshifts of the galaxies are fixed to their fit spectroscopic values.

Uncertainties on the properties estimated by **FAST** (e.g., stellar mass, SFR, A_V , etc.) are derived using a Monte Carlo approach where the photometry being fit is perturbed within its uncertainties and is then re-fit, this process being repeated 300 times. From these 300 realizations of the SED, 68% confidence intervals are determined for each estimated property. In Table 1, we list the best-fit stellar mass, and its uncertainty, of each galaxy in our stacking sample. The stellar mass associated with our full-sample composite, detailed below, is taken to be the median of these individual masses, $\log(M_*/M_{\odot})_{\text{med}} = 8.29$. We note that the best-fit SEDs, stellar masses, and all other affected properties are demagnified based on the lensing models discussed in Section 2.1.1.

3.3. The Composite Spectrum

While the individual galaxies in our sample display several nebular emission lines at high-S/N (e.g., [O III],

H α), the galaxies are still inherently faint even with high magnification via gravitational-lensing. As a result, many other useful, fainter lines are undetected or marginally-detected in our individual spectra. Such lines can include H β and H γ for estimating extinction from dust, the [O II] doublet for calculating electron density, and especially [O III] $\lambda 4363$ for estimating electron temperature and metallicity directly. A composite spectrum, or stacked spectrum, of all of our sample galaxies offers a solution to this problem by including in our study both galaxies for which we have individual line detections and galaxies for which we only have upper limits. This composite gives the advantages of both increasing the S/N of faint spectral features and displaying the average spectrum and properties of dwarf galaxies like those in our sample. Additionally, we use composites of the individual spectra of galaxies multiply-imaged by lensing in order to increase the effective exposure times and S/N of those galaxies' spectroscopy.

Our methodology for creating composite spectra is similar when stacking multiple images of sources (4 multiply-imaged galaxies; see Table 1) or all of the galaxies in our sample (16 total). We first create the composites for our multiply-imaged galaxies as these composites represent their corresponding galaxies in the full-sample stack. We begin by shifting the slit-loss-corrected, observed spectra to the rest-frame and converting the flux densities into luminosity densities. Each spectrum is then normalized by its slit-loss-corrected, [O III] $\lambda 5007$ emission-line luminosity. This normalization serves two purposes. It de-magnifies each spectrum implicitly by dividing the magnified spectrum by its magnified [O III] $\lambda 5007$ luminosity. It also, in the case of stacking our full sample, prevents our composite electron temperature (see Section 3.5) from being biased by the brightest [O III] $\lambda 5007$ source ([Sanders et al. 2020](#)). We note here that, prior to normalizing, the spectra and [O III] $\lambda 5007$ luminosities are not corrected for dust extinction both due to the faintness of H β and H γ and the sky line contamination of these lines in several of our individual sources. Following normalization, each spectroscopic band's science spectrum and corresponding error spectrum are resampled with the Python tool, **SpectRes**^{9,10} ([Carnall 2017](#)), onto a common wavelength grid with a rest-frame dispersion – for the full-sample stack – of $0.38 \text{ \AA pix}^{-1}$ in the band (*Y* or *J*) containing [O II], $0.47 \text{ \AA pix}^{-1}$ in the band (*J* or *H*) containing H γ through [O III] $\lambda 4959$, and $0.63 \text{ \AA pix}^{-1}$ in the band (*H* or *K*)

⁹ <https://spectres.readthedocs.io/en/latest/>

¹⁰ <https://github.com/ACCarnall/SpectRes>

⁸ <https://w.astro.berkeley.edu/~mariska/FAST.html>

containing H α and [N II]. (Hereafter, these bands will be referred to as the *YJ*-band, *JH*-band, and *HK*-band, respectively.) These rest-frame dispersions are computed by shifting the MOSFIRE *J*-, *H*-, and *K*-band observed-frame dispersions⁴ to the median redshift of the stacking sample, $z_{\text{med}} \approx 2.465$. Once resampled, the spectra from the full galaxy sample are combined at each wavelength element by taking the median value of all luminosity densities at that point. When stacking the spectra of a multiply-imaged galaxy, the average at each pixel is taken instead, with luminosity densities weighted by their associated uncertainty values. Finally, the composite spectrum of the full stacking sample is multiplied by the median [O III] $\lambda 5007$ luminosity of the sample, whereas the composite for a multiply-imaged galaxy is multiplied by the lowest-luminosity [O III] $\lambda 5007$ measurement (a proxy for the least magnified measurement). We note that, in this work, only ratios of emission lines are used from the composite of the full stacking sample since individual luminosity measurements rely on a normalization dependent on our stacking methodology.

The uncertainty spectrum of the stack of all of our sample galaxies is derived via a Monte Carlo approach with bootstrapping. We first create a bootstrapped sample of number count $N_{\text{boot}} = 16$, the number of galaxies in our full stack, by randomly drawing galaxies for the sample with replacement. For each galaxy in this bootstrapped sample, its science spectrum (already shifted and converted to the rest-frame and luminosity densities, respectively) is perturbed according to its error spectrum. This perturbed spectrum is then normalized by its corresponding [O III] $\lambda 5007$ emission-line luminosity, which has been perturbed based on its own uncertainty value. The normalized, perturbed spectra are then resampled and stacked according to the procedure detailed above. This process is repeated 500 times in order to create an array of composite luminosity densities at each wavelength element. Our uncertainty spectrum is then comprised of the standard deviations of the values in each of these arrays. By constructing our error spectrum via bootstrapping, our uncertainties represent both our measurement errors and sample variance. The composite spectrum of our full stacking sample, as well as its bootstrapped uncertainty spectrum (the light-gray-shaded region), are shown in Figure 1. In Figure 1, we also show the statistical-only uncertainty spectrum (the dark-gray-shaded region), which was created as described above, but without bootstrap-resampling each iteration. We note that, unless specified otherwise, the stated uncertainties on measurements derived from the composite spectrum reflect the use of the bootstrapped

uncertainty spectrum and its consideration of sample variance.

3.3.1. Fitting the Composite Emission-Line Spectrum

Prior to their inclusion in the full-sample stack, the composite spectra of the multiply-imaged galaxies are fit in the same manner as the spectra of individual galaxy images (see Section 3.1). For the full-sample composite, we adopt a slightly different fitting methodology. While spectral-fitting is still facilitated with *emcee*, and the continuum is still fit with a line, the emission lines are fit with a combination of two Gaussian profiles due to the non-Gaussian shape of the high-S/N lines (Steidel et al. 2016). The resultant profiles fit to the emission lines consist of a “broad” Gaussian component and a “narrow” Gaussian component, both of which are centered on the rest-frame wavelength of the emission line in question. In order to maintain consistent line profiles for all emission lines in a given spectral band (*YJ*, *JH*, or *HK*), the fitting of these profiles, and the spectrum, is done in two rounds.

In the first round, the two Gaussian components are fit to the brighter, higher-S/N lines in the composite: H β and [O III] $\lambda 4959$ in the *JH*-band and, separately, H α in the *HK*-band. For each spectral band, the broad Gaussian has its 1σ -width fixed at 100 km s^{-1} while the narrow-Gaussian 1σ -width is left as a free parameter.¹¹ Additionally, the free parameters for each fit include the slope and intercept of the continuum, the amplitude(s) of the narrow-Gaussian profile(s), and a narrow-to-broad amplitude ratio for the spectral band.

In the second round, each spectral band is fit in its entirety. The broad Gaussian keeps its 1σ -width fixed to 100 km s^{-1} in all bands. In the *JH*- and *HK*-bands, the narrow 1σ -widths and amplitude ratios fit in the first round are held fixed and applied to all lines in the corresponding bands: H γ , [O III] $\lambda 4363$, H β , [O III] $\lambda 4959$ in the *JH*-band and H α and [N II] $\lambda \lambda 6548, 6583$ in the *HK*-band. Free parameters in these bands are the narrow-Gaussian amplitudes of each line and the linear continuum parameters. (The [N II] $\lambda 6583$ narrow-Gaussian amplitude is constrained in the same manner

¹¹ We tested the validity of fixing the broad-Gaussian 1σ -width by comparing luminosities fit to H β , [O III] $\lambda 4959$, and H α with either a fixed broad-width ($\sigma_b = 100 \text{ km s}^{-1}$) or the broad-width left as a free parameter. When comparing the luminosities assuming a fixed-width to the weighted-average luminosities of three runs where the broad-width was left free, we found an average percentage difference of $\sim 0.4\%$ and $\sim 1.0\%$ when assuming the bootstrapped or statistical-only uncertainty spectrum, respectively. The weighted-average luminosities fell well within the uncertainties of the fixed-width luminosities. We therefore find our choice of fixed broad-Gaussian 1σ -width to be robust.




Figure 1. The rest-optical composite spectrum of the 16 typical, star-forming, $\langle z \rangle = 2.30$ dwarf galaxies in our stacking sample. The stacked spectrum is shown as the blue unfilled histogram, and its best-fit model is displayed in red. Here we show two offset uncertainty spectra (see Section 3.3), one estimated via bootstrapping in order to account for cosmic variance (the light blue-gray-filled histogram), and the other a statistical-only error spectrum (the dark blue-gray-filled histogram). We note that the bootstrapped uncertainty spectrum was used when fitting the model shown here. In the inset box corresponding to the green-shaded spectral region, we show a zoom-in of the weak [O III] $\lambda 4363$ auroral line, measured at 2.5σ (4.1σ) significance when considering the bootstrapped (statistical-only) uncertainty spectrum. We note that, as a result of our stacking procedure (see Section 3.3), the luminosity density values (L_λ) of the composite have a constant but arbitrary magnification. While this makes individual emission-line luminosities unreliable, it does not affect strong-line ratios.

as in the individual spectra; see Section 3.1.) In the YJ -band containing [O II] $\lambda\lambda 3726, 3729$, the amplitude ratio from the JH -band is adopted, but the narrow 1σ -width is left as a free parameter. Like with the other bands, the narrow-Gaussian amplitudes and linear continuum parameters are also fit.

The spectral model from these two rounds of fitting can be seen as the red line in Figure 1. The total luminosity of each emission line, representing the addition of the broad- and narrow-Gaussian component luminosities, is given in Table 2 relative to the total $H\beta$ luminosity. Of particular interest for this study is the 2.5σ (4.1σ) detection of [O III] $\lambda 4363$ in our composite with the bootstrapped (statistical-only) error spectrum, which will be used in Sections 3.5 and 3.6 to estimate the electron temperature and gas-phase metallicity directly.

3.4. Dust Extinction and SFRs of the Sample

In order to estimate a galaxy’s intrinsic emission-line luminosities, from which its galactic properties and

interstellar medium (ISM) conditions are derived, a wavelength-dependent correction to the observed luminosities must be made to account for extinction from nebular dust. This correction is typically quantified via Balmer recombination-line ratios of observed hydrogen emission-line luminosities. Ideally, dust extinction would have been compensated for on a galaxy-by-galaxy basis prior to stacking our sample. Unfortunately, many of our individual galaxy spectra have Balmer lines that are too faint or too impacted by sky lines for this approach to be used. Instead, the nebular dust extinction “typical” of star-forming, dwarf galaxies like those in our sample is estimated via our full-sample composite spectrum.

Prior to using Balmer decrements to estimate dust extinction, corrections to Balmer emission-line luminosities must be made to account for Balmer absorption in the atmospheres of (primarily A-type) stars. Using the Balmer emission lines from our individual spectra and the model continua from our SED-fitting, we estimated

Table 2. Emission-Line Luminosities of the Composite Spectrum

Line	λ_{rest}^a	L_{meas}^b	$L_{\text{corr}}^{b,c}$	A_λ^d
[O II]	3726.032	0.61 ± 0.12	0.70 ± 0.13	0.67
[O II]	3728.815	0.95 ± 0.16	1.09 ± 0.19	0.67
H γ	4340.459	0.40 ± 0.08	0.44 ± 0.09	0.59
[O III]	4363.209	0.11 ± 0.05	0.11 ± 0.05	0.58
H β	4861.321	1.00 ± 0.16	1.00 ± 0.16	0.51
[O III]	4958.910	1.95 ± 0.30	1.89 ± 0.29	0.49
H α	6562.794	3.14 ± 0.48	2.70 ± 0.42	0.36
[N II]	6583.448	0.13 ± 0.07	0.11 ± 0.06	0.35

NOTE—The luminosity of [O III] $\lambda 5007$ can be calculated via the intrinsic ratio [O III] $\lambda 5007$ /[O III] $\lambda 4959 = 2.98$.

^aRest-frame wavelengths in air (Å).

^bLuminosities relative to $L_{\text{H}\beta}$. We only use ratios of the luminosities from the composite spectrum since the spectrum’s normalization is dependent on our stacking methodology.

^cAll luminosities are dust-corrected using the corresponding extinction magnitude (A_λ) given in the last column. Balmer lines are corrected for stellar absorption. See Section 3.4. The listed uncertainties do not include systematic errors associated with the dust correction, though these errors are propagated throughout all of our calculations.

^dDust extinction magnitudes at λ_{rest} .

the sample-median stellar absorption corrections for H γ , H β , and H α and applied them to our composite Balmer emission-line luminosities, increasing the measured values by $\sim 5.0\%$, $\sim 1.7\%$, and $\sim 0.4\%$, respectively.

To calculate the nebular dust extinction with our composite spectrum, we assumed Case B intrinsic Balmer ratios of H α /H $\beta = 2.79$ and H α /H $\gamma = 5.90$ for an electron temperature and electron density of $T_e([\text{O III}]) = 15,000$ K and $n_e = 100 \text{ cm}^{-3}$, respectively¹² (Dopita & Sutherland 2003). Further assuming the extinction curve of Cardelli et al. (1989) with $R_V = 3.1$, we find a “typical” color excess of $E(B-V)_{\text{gas}} = A_V/R_V = 0.14_{-0.09}^{+0.11}$. This result allows us to correct our composite emission-

¹²We note that while an electron temperature is assumed when selecting Balmer ratio values, the dependence of those ratios on T_e is weak for typical temperatures in H II regions. To confirm that our assumption of $T_e = 15,000$ K is valid, we dust-corrected the composite spectrum then calculated T_e (see Section 3.5) assuming intrinsic Balmer ratios corresponding to $T_e = 10,000$ K, 12,500 K, 15,000 K, and 20,000 K (Dopita & Sutherland 2003). With each variation, we consistently calculated from our dust-corrected composite spectrum a $T_e \sim 15,000$ K.

line luminosities for extinction due to dust, yielding the typical intrinsic values of these lines in star-forming, dwarf galaxies at high redshift. The dust-corrected (and stellar-absorption-corrected in the case of the Balmer lines) emission-line luminosities of the composite spectrum, relative to H β , are listed in Table 2.

When considering SFRs, similar to how our stellar masses are being reported, we calculate the SFR for each individual galaxy and report the composite SFR as the median value of the sample. These SFRs are calculated with slit-loss-corrected, dust-corrected, H α luminosities ($L_{\text{H}\alpha}$), de-magnified according to the lensing models in Section 2.1.1. The dust-extinction correction of each $L_{\text{H}\alpha}$ value is conducted with the “typical” extinction estimate for the sample found via the composite spectrum. The $L_{\text{H}\alpha}$ values are not corrected for stellar absorption, which on average would result in an increase of $< 1\%$. The $L_{\text{H}\alpha}$ values are converted to SFRs using Equation 1 below:

$$\text{SFR} (\text{M}_\odot \text{ yr}^{-1}) = 4.645 \times 10^{-42} L_{\text{H}\alpha} (\text{ergs s}^{-1}) \quad (1)$$

This equation is of the same form as the relation in Kennicutt (1998) for calculating SFRs from recombination lines. However, the conversion factor here has been recalculated assuming a metallicity of $0.2 Z_\odot$ and a Chabrier (2003) IMF. Our estimates for the SFRs of the individual galaxies are given in Table 1, and the SFR associated with the composite spectrum is taken to be the sample-median value of $\text{SFR}_{\text{med}} = 2.25 \text{ M}_\odot \text{ yr}^{-1}$.

3.5. Electron Temperature and Electron Density

The “direct” calculation of metallicity relies on collisionally-excited oxygen emission lines and the nebular properties of electron temperature (T_e) and electron density (n_e), which are responsible for the strength of the collisionally-excited lines. Electron temperature is calculated in two ionization zones of the star-forming, H II regions. In the O⁺⁺ zone, $T_e([\text{O III}])$ is calculated using the electron-temperature-sensitive emission-line ratio [O III] $\lambda\lambda 4959, 5007$ /[O III] $\lambda 4363$ and the IRAF routine NEBULAR.TEMDEN (Shaw & Dufour 1994). We note that while $T_e([\text{O III}])$ does have a dependence on electron density, n_e , below $n_e \approx 10^3 \text{ cm}^{-3}$, $T_e([\text{O III}])$ is insensitive to n_e (Osterbrock & Ferland 2006; Izotov et al. 2006) and can be calculated assuming the typical $z \sim 2$ H II region electron density of a few hundred per cubic centimeter (Sanders et al. 2016b). For our calculation, we assume $n_e = 150 \text{ cm}^{-3}$ and obtain an electron temperature in the O⁺⁺ region of $T_e([\text{O III}]) = 15,800 \pm 3,100$ K. We note in regard to the assumed n_e that Gburek et al. (2019) studied a galaxy in our

present stacking sample, A1689-217, that had a similar electron temperature of $T_e([\text{O III}]) = 14,300$ K. When calculating this temperature, they found that assuming any $n_e < 10^3 \text{ cm}^{-3}$ changed their result by $< 0.5\%$, suggesting our current assumption is robust.

Ideally, the electron temperature in the O^+ ionization region is calculated using measurements of the $[\text{O II}] \lambda\lambda 7320, 7330$ auroral emission-line doublet. Unfortunately, for the galaxies in our stacking sample, we do not have spectroscopic coverage of these lines. Instead, we calculate $T_e([\text{O II}])$ via the $T_e([\text{O III}]) - T_e([\text{O II}])$ relation of [Campbell et al. \(1986\)](#), reprinted here in Equation 2:

$$T_e([\text{O II}]) = 0.7 T_e([\text{O III}]) + 3000 \text{ K} \quad (2)$$

Use of this equation gives us an electron temperature in the O^+ region of $T_e([\text{O II}]) = 14,100 \pm 2,200$ K.

The electron density, n_e , can be derived with the doublet ratio $[\text{O II}] \lambda 3729 / [\text{O II}] \lambda 3726$, the $T_e([\text{O II}])$ electron temperature, and the IRAF routine `NEBULAR.TEMDEN`. For our composite spectrum, we calculate $[\text{O II}] \lambda 3729 / [\text{O II}] \lambda 3726 = 1.56 \pm 0.32$ (1.51 ± 0.12 when using the statistical-only uncertainty spectrum and associated fits). This corresponds to an electron density of $n_e = 1_{-0}^{+152} \text{ cm}^{-3}$ ($n_e = 1_{-0}^{+49} \text{ cm}^{-3}$), where the “best-fit” n_e value is set to the low-density limit of $n_e = 1 \text{ cm}^{-3}$ as a result of the best-fit $[\text{O II}]$ ratio exceeding the maximum theoretical bound of $[\text{O II}] \lambda 3729 / [\text{O II}] \lambda 3726 \lesssim 1.5$ ([Osterbrock & Ferland 2006](#); [Sanders et al. 2016b](#)).

We note that we have significantly detected the component emission lines of the $[\text{O II}] \lambda\lambda 3726, 3729$ doublet and resolved their individual peaks ($\text{S/N}(3726, 3729) = (6.4, 7.8)$; see Figure 1). The electron density associated with our dwarf galaxy sample and with the best-fit ratio of these lines is significantly lower than the densities found in more massive galaxies at $1.5 \lesssim z \lesssim 2.5$, which typically lie in the range of $n_e \approx 100 - 300 \text{ cm}^{-3}$ ([Steidel et al. 2014](#); [Sanders et al. 2016b](#); [Kashino et al. 2017](#); [Kaasinen et al. 2017](#); [Davies et al. 2021](#)).

3.6. Direct Oxygen Abundance

We directly calculate the oxygen abundance, or gas-phase metallicity, of our composite spectrum using the ionic abundance equations of [Izotov et al. \(2006\)](#). These equations utilize the values of $T_e([\text{O II}])$, $T_e([\text{O III}])$, and n_e given in the preceding section as well as the dust-corrected emission-line ratios of $[\text{O II}] \lambda\lambda 3726, 3729 / \text{H}\beta$ and $[\text{O III}] \lambda\lambda 4959, 5007 / \text{H}\beta$. We assume that the total oxygen abundance is the summation of the ionic abundances in the H II region O^+ and O^{++} ionization zones

Table 3. Properties of the Dwarf Galaxy Composite

Property	Value
z_{mean}^a	2.30
$\log(M_*/M_\odot)_{\text{fiducial}}^{\text{med } a, b}$	8.29
$\log(M_*/M_\odot)_{\text{med}}^{\text{med } a, c}$	8.92
$\text{SFR}_{\text{H}\alpha}^{\text{med}} (M_\odot \text{ yr}^{-1})^a$	2.25
$E(B-V)_{\text{gas}}$	$0.14_{-0.09}^{+0.11}$
$n_e^{\text{boot}} (\text{cm}^{-3})^d$	1_{-0}^{+152}
$n_e^{\text{stat}} (\text{cm}^{-3})^d$	1_{-0}^{+49}
$T_e([\text{O II}])$ (K)	$14,100 \pm 2,200$
$T_e([\text{O III}])$ (K)	$15,800 \pm 3,100$
$12 + \log(\text{O}^+/\text{H}^+)$	$7.27_{-0.19}^{+0.28}$
$12 + \log(\text{O}^{++}/\text{H}^+)$	$7.71_{-0.20}^{+0.27}$
$12 + \log(\text{O}/\text{H})_{\text{direct}}$	$7.87_{-0.22}^{+0.24}$
$Z (Z_\odot)$	$0.15_{-0.06}^{+0.11}$

NOTE—All uncertainties here (except for n_e^{stat}) derive from the composite bootstrapped error spectrum. See Figure 1.

^aMean and median values of the individual galaxies in the stacking sample. See Table 1. All other values derive from the composite spectrum.

^bOur fiducial median stellar mass assuming constant SFHs.

^cThe median stellar mass assuming non-parametric SFHs. See Section 4.3.2.

^d n_e^{boot} and n_e^{stat} assume the bootstrapped and statistical-only error spectrum (and associated fits), respectively. Both “best-fit” values are set as the low-density limit of $n_e = 1 \text{ cm}^{-3}$. See Section 3.5.

as seen in Equation 3. Any higher ionization states of oxygen are deemed to have a negligible contribution to the metallicity.

$$\frac{\text{O}}{\text{H}} \approx \frac{\text{O}^+}{\text{H}^+} + \frac{\text{O}^{++}}{\text{H}^+} \quad (3)$$

From our composite spectrum, we report a typical gas-phase metallicity for high-redshift, star-forming, dwarf galaxies of $12 + \log(\text{O}/\text{H}) = 7.87_{-0.22}^{+0.24}$ ($0.15_{-0.06}^{+0.11} Z_\odot$; [Asplund et al. 2021](#)). This metallicity estimate, as well as the calculations from our composite spectrum of the other physical properties detailed in Section 3, are summarized in Table 3.

4. RESULTS AND DISCUSSION

This section of the manuscript will take the measurements derived in the previous section from our dwarf galaxy sample and composite spectrum and analyze them in the context of strong-line abundance diagnostics

and global galaxy scaling relations. Prior to this, however, it is crucial to look at our sample and stack compared to the broader galaxy population at $1.7 \lesssim z \lesssim 2.6$ in order to assess how representative our sample is of typical, dwarf galaxies at this epoch.

4.1. How Representative is our Sample?

Here we will consider two main diagnostics, the [N II] Baldwin-Phillips-Terlevich diagram (N2-BPT; Baldwin et al. 1981) and the M_* – SFR relation, or “star-forming main sequence.”

4.1.1. N2-BPT Diagnostic Diagram

In Figure 2, we show the location of our $\langle z \rangle = 2.30$ stack of star-forming, dwarf galaxies on the [O III] $\lambda 5007/H\beta$ vs. [N II] $\lambda 6583/H\alpha$ BPT diagnostic diagram. This diagram is a useful tool for distinguishing between star-forming galaxies (SFGs) and AGN through optical strong-line ratios (Kewley et al. 2001; Kauffmann et al. 2003; Kewley et al. 2013, K01, K03, K13, respectively), all without needing to apply a dust correction to the line fluxes. The SFG locus of the BPT is also a probe of changing physical conditions in star-forming regions with redshift (e.g., Kewley et al. 2013, Figure 2). This has been an active area of research in numerous high-redshift statistical studies (e.g., Steidel et al. 2014; Shapley et al. 2015, S14, S15, respectively) which have shown that high- z SFGs cluster around a locus offset toward higher [O III] $\lambda 5007/H\beta$ and/or [N II] $\lambda 6583/H\alpha$ when compared to the star-forming locus of $z \sim 0$ SDSS galaxies. We show this in Figure 2, where the SFG locus of $z \sim 0$ SDSS galaxies is given by the solid red line (Kewley et al. 2013), and the offset SFG loci of the $z \sim 2.3$ KBSS-MOSFIRE and MOSDEF surveys are displayed by the purple (Steidel et al. 2014) and magenta (Shapley et al. 2015) lines, respectively. Recent work by Runco et al. (2022) has shown that these high- z SFG loci actually converge with consistent emission-line-fitting applied to each sample and reaffirm the existence of an offset in the BPT between local and high- z SFGs.

We show, via the black star in Figure 2, that our stack of $z \sim 2.3$ star-forming galaxies is also offset from the SDSS SFG locus, lying in parameter space consistent with KBSS-MOSFIRE and MOSDEF. While we cannot place each individual galaxy in our sample on this plot due to skyline contamination, particularly of $H\beta$, we note that our stack lies below the “maximum starburst” demarcation (dotted black line) of Kewley et al. (2001), the empirical demarcation (dashed brown line) between SFGs and AGN of Kauffmann et al. (2003), and the theoretical, $z = 2.30$, upper-limit SFG locus (red dotted-dashed line) of Kewley et al. (2013). We also note that the large uncertainty of our stack in $\log([\text{N II}] / H\alpha)$




Figure 2. The [O III] $\lambda 5007/H\beta$ vs. [N II] $\lambda 6583/H\alpha$ BPT diagnostic diagram. Our $\langle z \rangle = 2.30$ dwarf galaxy composite is shown as the black star. The $z \sim 2.3$ M_* -binned stacks of star-forming (SF) MOSDEF galaxies from Sanders et al. (2021, S21) are shown as gray squares. The median M_* of each of these stacks, and of our composite (in bold), is listed in the upper right-hand corner of the plot by order of increasing [N II]/ $H\alpha$ of the stacks, highlighting that our stack is an extension to lower M_* (and O/H via the MZR) of the MOSDEF survey. The $z \sim 2.3$ SF sequences of the MOSDEF (Shapley et al. 2015, S15) and KBSS-MOSFIRE (Steidel et al. 2014, S14) surveys are shown by the magenta and purple lines, respectively. Like these sequences and the MOSDEF stacks, our composite also lies offset from the $z \sim 0$ mean SF sequence given by the red line and parameterized by Kewley et al. (2013, K13). We plot the $z = 2.30$ SF sequence upper-limit from K13 as the red dot-dashed line. The demarcation between SF galaxies and AGN of Kauffmann et al. (2003, K03) is given by the dashed brown line, and the “maximum starburst” curve of Kewley et al. (2001, K01) is given by the dotted black line.

is the result of [N II] $\lambda 6583$ only being detected in the composite spectrum with 2σ significance.

While the [N II] $\lambda 6583$ measurement in our composite is fairly uncertain, the location of our stack along the x -axis of the N2-BPT is interesting when compared to the M_* -binned stacks of SFGs (the blue-gray squares) from the MOSDEF survey and Sanders et al. (2021, S21). This is because of the monotonic relationship that exists between $\log([\text{N II}] \lambda 6583/H\alpha)$ and metallicity; as this strong-line ratio increases, metallicity increases (Pettini & Pagel 2004; Maiolino et al. 2008; Curti et al. 2017; Bian et al. 2018; Sanders et al. 2021). By the mass-metallicity relation (e.g., Tremonti et al. 2004; Sanders et al. 2021), as this ratio increases, the stellar mass of galaxies should then also increase on average. We

see this with the MOSDEF stacks, where in the upper right-hand section of the plot, we list the median stellar masses of the stacks in order of increasing $[\text{N II}]/\text{H}\alpha$. Here in this list we have also included, in bold, the median stellar mass of our dwarf galaxy stack, which, based on its positioning in the BPT, predictably has the lowest listed median stellar mass. In this, we show that our sample is a complementary extension in stellar mass to the MOSDEF (and KBSS-MOSFIRE) survey, extending its mass range into the dwarf galaxy regime ($M_* < 10^9 M_\odot$).

4.1.2. The Star-Forming Main Sequence

One of the primary goals of this study is to analyze our dwarf galaxy composite relative to the $z \sim 2.3$ mass-metallicity relation (MZR) of star-forming galaxies (see Section 4.3), which is a scaling relation between galaxy stellar mass (M_*) and gas-phase oxygen abundance, or metallicity (O/H). However, in order to properly contextualize our findings in relation to the broader $z \sim 2.3$ dwarf galaxy population, we must consider the SFRs associated with the stack and the sample that comprises it. This is due to the existence of the fundamental metallicity relation (FMR) between M_* , SFR, and O/H which has been demonstrated locally at $z \sim 0$ (e.g., Mannucci et al. 2010, 2011; Lara-López et al. 2010; Andrews & Martini 2013; Curti et al. 2020) and at high redshift out to $z \sim 3.3$ (e.g., Henry et al. 2013a,b; Cresci et al. 2019; Sanders et al. 2018, 2021). The FMR demonstrates that, at a fixed M_* , a galaxy with an above-average (below-average) SFR will typically have a below-average (above-average) metallicity. Therefore, if our stacking sample (and thus composite spectrum) is biased in SFR, it will not have an average metallicity representative of typical dwarf galaxies at $z \sim 2.3$. This would be problematic when comparing the metallicity of our composite to the low-mass end of the MZR.

To investigate whether our stacking sample has a bias in SFR, we plot our sample and its median values against the $M_* - \text{SFR}$ star-forming main sequence (SFMS) in Figure 3. Galaxies that lie on this relation, which is redshift-dependent, are considered to be representative of the typical galaxy at that corresponding stellar mass and redshift. In Figure 3, we compare to the $z \sim 2.3$ SFMS parameterizations of Sanders et al. (2021) and Whitaker et al. (2014).

In comparing to the $z \sim 2.3$ SFMS of Sanders et al. (2021), we do so with stellar masses and SFRs calculated in a manner highly consistent with the methodologies adopted in Sanders et al. The stellar masses of our stacking sample and the MOSDEF galaxies used to calibrate the SFMS both rely on emission-line-corrected




Figure 3. M_* vs. dust-corrected $L_{\text{H}\alpha}$ on the left-hand axis and SFR on the right-hand axis. Our stacking sample is shown by the colored circles, with blue circles representing our four $z \sim 1.7$ galaxies and red circles our twelve $2.4 \lesssim z \lesssim 2.6$ galaxies. The purple star lies at the median M_* and $L_{\text{H}\alpha}$ (or SFR) of our $z \sim 2.3$ sample. The black squares show the $z \sim 2.3$ M_* -binned stacks of MOSDEF galaxies from Sanders et al. (2021). We compare our sample median values against the $M_* - \text{SFR}$ relations, or “star-forming main sequences” (SFMS), of Sanders et al. (2021, black line) and Whitaker et al. (2014, orange and green lines) to determine how representative our sample is of typical, $z \sim 2.3$ dwarf galaxies. The Sanders et al. (2021) relation is a power-law derived from $\text{H}\alpha$ SFRs. The orange and green relations of Whitaker et al. (2014) are parameterized by a broken power-law and second-order polynomial, respectively; both relations derive from UV+FIR SFRs. Dashed portions of the SFMSs are extrapolations.

photometry and the SED-fitting (with FAST; Kriek et al. 2009) assumptions of constant star formation histories, the Calzetti et al. (2000) attenuation curve, and the Chabrier (2003) IMF. The SFRs in both studies are calculated from dust-corrected (via the Cardelli et al. 1989 extinction curve) $\text{H}\alpha$ luminosities ($L_{\text{H}\alpha}$). We note that the conversion factor between $L_{\text{H}\alpha}$ and SFR (see, for example, Equation 1) is dependent on assumptions such as the stellar metallicity and can vary between different authors. Therefore, we plot dust-corrected $L_{\text{H}\alpha}$ on the left-hand axis of Figure 3 so that our stacking sample (red and blue circles) and the Sanders et al. (2021) MOSDEF stacks (black squares) can be directly compared without the additional SFR conversion. Ultimately, however, we find that the SFR conversion factor used by both studies is very similar, and we continue our analysis of how representative our stacking sample is via SFR, given on the right-hand axis of Figure 3.

The $z \sim 2.3$ SFMS of Sanders et al. (2021) is parameterized as a power-law over the stellar mass range 9.0

$< \log(M_*/M_\odot) < 11.0$. In Figure 3, we plot their best-fit relation¹³ over this range as a solid black line and extrapolate into the dwarf galaxy regime as seen by the dashed black line. In plotting our stacking sample in the $M_* - \text{SFR}$ parameter space, we differentiate the $z \sim 1.7$ galaxies from the $2.4 \lesssim z \lesssim 2.6$ galaxies by blue and red points, respectively. We note that three of the four $z \sim 1.7$ galaxies lie along or above the extrapolation of the $z \sim 2.3$ SFMS. These objects are biased high in SFR relative to typical $z \sim 1.7$ galaxies that have a lower SFR at fixed M_* due to the redshift evolution of the SFMS (Speagle et al. 2014; Whitaker et al. 2014; Sanders et al. 2021). The other group of $z > 2.38$ galaxies are found to scatter around the Sanders et al. extrapolation. Considered together, at the median mass of the complete $\langle z \rangle = 2.3$ stacking sample, $\log(M_*/M_\odot)_{\text{med}} = 8.29$, the median SFR of the sample, $\log(\text{SFR}/M_\odot \text{ yr}^{-1})_{\text{med}} = 0.35$, lies $\Delta \log(\text{SFR}) \sim 0.19$ dex above the extrapolation of the $z \sim 2.3$ SFMS of Sanders et al. (2021). This median point is shown as the purple star.

With the relative offset in SFR of our stacking sample in hand, we estimate the bias in O/H, resulting from the FMR, of our composite spectrum. Considering the strength of the SFR dependence of direct-method O/H at fixed M_* from Sanders et al. (2020),

$$\Delta \log(\text{O}/\text{H}) \approx -0.29 \times \Delta \log(\text{SFR} / M_\odot \text{ yr}^{-1}) \quad (4)$$

our sample stack is biased by $\Delta \log(\text{O}/\text{H}) \sim -0.06$ dex, a value half the statistical uncertainty of our composite direct-method metallicity estimate ($\sigma_{\text{stat}} \approx 0.12$ dex). We therefore conclude that, when comparing to the SFMS of Sanders et al. (2021), our stacking sample of dwarf galaxies does not have a major bias in SFR or O/H and, on average, is representative of typical dwarf galaxies at $z \sim 2.3$ with $M_* \gtrsim 10^8 M_\odot$.

In Figure 3, we also plot the $2.0 < z < 2.5$ SFMS parameterizations of Whitaker et al. (2014), which were fit to M_* -binned stacks above a mass-completeness limit of $10^{9.2} M_\odot$. Whereas Sanders et al. (2021) fit the SFMS with a power-law, Whitaker et al. (2014) fit the SFMS with both a second-order polynomial (green line) and a broken power-law (orange line) for which a separate slope was fit above and below a characteristic mass of $\log(M_*/M_\odot) = 10.2$. We note that in our recreation of the second-order polynomial fit, we use the more precise polynomial coefficients given in the erra-

tum (Whitaker et al. 2020) to Whitaker et al. (2014, Table 1), in order to more accurately portray the curve. Similar to Sanders et al. (2021) and the MOSDEF survey, the sample of Whitaker et al. (2014) is composed of star-forming galaxies from the CANDELS fields (Grogin et al. 2011; Koekemoer et al. 2011), though has a larger galaxy count and different sample selection. Like with the MOSDEF galaxies and our stacking sample, the stellar masses are determined with FAST assuming a Calzetti et al. (2000) attenuation curve and Chabrier (2003) IMF; however, the star-formation histories are taken to be exponentially declining. Unlike in Sanders et al. (2021) and our stacking sample though, the SFRs are estimated from the combination of rest-frame ultraviolet (UV) light and light re-radiated by dust in the far-infrared (FIR).

Figure 3 shows that, at least qualitatively, the parameterizations from Whitaker et al. (2014) generally agree with the power-law fit ($\beta = 0.75$) and MOSDEF stacks of Sanders et al. (2021), though begin to diverge as a result of steeper slopes near unity below $\log(M_*/M_\odot) \lesssim 10$. This divergence, in part due to the choices of parametric form made by each author, is particularly pronounced in the dwarf galaxy mass regime where our sample lies. Unfortunately, there does not currently exist a high-redshift statistical sample in this regime that would allow us to confidently use a given parameterization. Therefore, we determine the most applicable SFMS based on consistency with our study in physical property estimation as well as the selection approach of our stacking sample. As detailed above, our methodologies for estimating M_* and SFR are most analogous to those of Sanders et al. (2021), mitigating systematic uncertainties between estimations of physical properties calculated with different techniques. Additionally, when selecting our stacking sample, we did not require a detection of [O III] $\lambda 5007$, H α , or [O III] $\lambda 4363$ which typically bias a sample toward higher SFR at fixed M_* . Our sample selection instead suggests a more representative sample like we see when comparing to the SFMS of Sanders et al. (2021). We therefore conclude that the SFMS of Sanders et al. (2021) is the most applicable comparison and that our stacking sample is representative of typical, star-forming, dwarf galaxies at $z \sim 2.3$.

4.2. Strong-Line Metallicity Calibrations at High- z

A major outstanding issue and active area of research in high- z astronomy is how to accurately calculate the gas-phase metallicities of the star-forming galaxies in the various large, statistical, spectroscopic surveys at $z > 1$ and $M_* \gtrsim 10^9 M_\odot$ (e.g., 3D-*HST*; Brammer et al. 2012b, KBSS-MOSFIRE; Steidel et al. 2014, MOSDEF; Kriek

¹³ The fitting of the SFMS was done with the four lowest-mass bins. Additionally, there is evidence that the lowest-mass ($M_* < 10^{9.5} M_\odot$) bin may be biased high in SFR (Shivaei et al. 2015; Sanders et al. 2021).




Figure 4. Strong emission-line ratios as a function of direct-method metallicity. From left-to-right and top-to-bottom we consider the oxygen-based strong-line ratios of O_{32} , O_3 , O_2 and R_{23} . Our $z \sim 2.3$ composite is displayed via the black star in each panel. For reference, we also include the $z \sim 2.4$ KBSS-LM1 composite of 30 star-forming galaxies also selected independent of emission-line strength (gray diamond; Steidel et al. 2016), as well as the median values of the $z \sim 2.2$ auroral-line sample of Sanders et al. (2020, gray square). We compare these points to the locally-calibrated, strong-line metallicity relations of Maiolino et al. (2008, orange line), Jones et al. (2015, green line), Curti et al. (2017, cyan line), Bian et al. (2018, both the local reference – purple line – and high- z analog – red line – relations), and Sanders et al. (2021, DIG-corrected; brown line). We note the metallicity-insensitivity of the O_3 and R_{23} indices at the oxygen abundances considered here. We find that our composite and KBSS-LM1 have their metallicities best reproduced by the local reference relations of Bian et al., in contrast to the auroral-line sample of Sanders et al. that favors the high- z analog relations.

et al. 2015, FMOS-COSMOS; Kashino et al. 2019). The cause of this problem is two-fold. For one, auroral lines such as [O III] $\lambda\lambda 1661, 1666$ or [O III] $\lambda 4363$, needed for direct, T_e -based metallicity estimation, are exceedingly faint, especially at high-redshift and with increasing galaxy stellar mass. Additionally, it is not fully understood how changing physical conditions with redshift in star-forming regions affect locally-calibrated, strong-line ratio metallicity diagnostics for indirect metallicity estimation. In other words, the accuracy and applicability of these strong-line metallicity calibrations at high-redshift is an open question which several studies have tried to address (Jones et al. 2015; Sanders et al. 2016a; Patrício et al. 2018; Gburek et al. 2019; Sanders et al. 2020).

In Figure 4, we revisit this issue with our $z \sim 2.3$ dwarf galaxy composite. Here we plot our stack (the black stars) in the parameter space of T_e -based oxygen abundance versus various commonly-used, oxygen-based, strong emission-line ratios. The dust-corrected emission-line ratios and direct metallicity ($12 + \log(\text{O}/\text{H}) = 7.87^{+0.24}_{-0.22}$) of our stack are measured (see Section 3) from the composite spectrum in Figure 1. Our stack in these plots is compared to several locally-calibrated strong-line metallicity diagnostics from the literature (Maiolino et al. 2008; Jones et al. 2015; Curti et al. 2017; Bian et al. 2018; Sanders et al. 2021) in an attempt to shed light on which strong-line ratios are serviceable at the typical metallicity of our stacking sample as well as which calibrations most favorably reproduce our composite metallicity at fixed strong-line ratio. While we cannot comment on the shape or slope of the various calibrations, we can get a sense of the appropriate normalization of these relations when considering high- z dwarf galaxies. In Figure 4, we consider four strong-line ratios: $\text{O}_{32} = \log([\text{O III}] \lambda 5007 / [\text{O II}] \lambda\lambda 3726, 3729)$, $\text{O}_3 = \log([\text{O III}] \lambda 5007 / \text{H}\beta)$, $\text{O}_2 = \log([\text{O II}] \lambda\lambda 3726, 3729 / \text{H}\beta)$, and $\text{R}_{23} = \log([\text{O III}] \lambda\lambda 4959, 5007 + [\text{O II}] \lambda\lambda 3726, 3729) / \text{H}\beta)$. We do not consider strong-line metallicity calibrations based on [N II] in this work due to our low detection significance ($\sim 2\sigma$) of [N II] $\lambda 6583$ in the composite spectrum as well as concerns in the literature (e.g., Masters et al. 2014, 2016) of elevated N/O abundance ratios at high-redshift.

Of immediate note when considering the location of our stack relative to the O_3 - and R_{23} -based calibrations in the right-hand panels of Figure 4 is that our stack lies at or near the apex of these relations in what is called the “turnover” between the high and low metallicity branches of these calibrations. In these turnover regimes, the strong-line ratio is insensitive to the metal-

licity of a galaxy, giving these relations little value as useful metallicity indicators over the oxygen abundance range spanned by the turnover region (somewhere roughly between $7.7 \lesssim 12 + \log(\text{O}/\text{H}) \lesssim 8.3$ depending on the strong-line index – O_3 or R_{23} – and calibration used). We therefore do not recommend the use of these strong-line indices for $z \sim 2$ dwarf galaxies similar to our those in our stacking sample. These results and conclusion are not particularly surprising as [O III] $\lambda 4363$ -emitter studies (Sanders et al. 2016a; Gburek et al. 2019; Sanders et al. 2020) and photoionization modeling (e.g., Steidel et al. 2014) have shown that it is quite common for $z \sim 2$ star-forming galaxies, over a couple orders of magnitude in stellar mass, to have metallicities that lie within these insensitive turnover regions.

A more interesting result is revealed when looking at the dwarf galaxy stack relative to the O_{32} - and O_2 -based calibrations in the left-hand panels of Figure 4. In particular, we focus on the comparisons with the strong-line metallicity relations of Bian et al. (2018), who used stacked SDSS spectra to create T_e -based, empirical metallicity calibrations over the metallicity range $7.8 < 12 + \log(\text{O}/\text{H}) < 8.4$. These calibrations were created from two distinct SDSS samples, a reference sample of galaxies lying within ± 0.05 dex of the $z \sim 0$ star-forming sequence of the N2-BPT diagram (parameterized by Kewley et al. 2013) and a high-redshift analog sample of SDSS galaxies lying within ± 0.04 dex of the offset $z \sim 2.3$ star-forming sequence of the BPT diagram (Steidel et al. 2014). With these selection criteria based on nebular emission-line ratios, the calibrations of Bian et al. (2018) should represent the conditions of star-forming regions in low- and high-redshift galaxies, respectively. We note that the Bian et al. calibrations presented in Figure 4 were re-fit for this study for the reasons, and via the methods, described in Appendix A.

When comparing our stack (black stars) to the strong-line metallicity relations of Bian et al. (2018), we find that our stack favors the local reference calibrations (purple curves), such that when considering the O_{32} and O_2 indices, the local reference relations reproduce our composite metallicity to within $\lesssim 0.15$ dex at fixed strong-line ratio. The high- z analog relations of Bian et al. (red curves) and the calibrations of Maiolino et al. (2008, orange curves), Jones et al. (2015, green curves), and Curti et al. (2017, cyan curves) are all $\gtrsim 1\sigma$ inconsistent with our stack in the O_{32} and O_2 panels, the lone exception being the O_{32} relation of Maiolino et al. This result of inconsistency with these relations has added significance in that we are analyzing a composite of 16 galaxies rather than an individual source. Also, our uncertainties here take into account sample variance in ad-

dition to statistical error (see Section 3.3). We note that, in all panels other than that of the O_2 index, our composite is also highly inconsistent with the calibrations of Sanders et al. (2021, brown curves). At metallicities below $12 + \log(O/H) < 8.4$, the Sanders et al. (2021) relations are calibrated with the H II region spectra of dwarf galaxies from Berg et al. (2012) and the *Spitzer* Local Volume Legacy survey (Dale et al. 2009). These dwarf galaxies have been shown in previous studies to not follow the other strong-line metallicity relations considered in this work, possibly as a result of biases from the selection methods of the various calibration samples or an incompleteness in low-metallicity, high-excitation H II regions (Gburek et al. 2019; Sanders et al. 2020, 2021).

It is interesting that our $z \sim 2.3$ stack generally best agrees with the local reference calibrations of Bian et al. (2018), particularly when compared to the findings of Sanders et al. (2020), who compiled O III] $\lambda\lambda 1661, 1666$ and [O III] $\lambda 4363$ -detected sources at $z > 1$ from the literature and the MOSDEF survey and conducted a similar study of strong-line metallicity diagnostics at the median redshift of the compiled sample, $z_{\text{med}} \sim 2.2$. These authors found that at the median metallicities and median line ratios of the galaxies in their $z > 1$ sample (gray squares in Figure 4; each median limited to galaxies with detections of the respective line ratio), the high-redshift analog calibrations of Bian et al. (2018) best reproduced their metallicities at fixed line-ratio. Moreover, Sanders et al. (2020) found general agreement between their median points and the Curti et al. (2017) calibrations as well as general agreement with the calibration sample ($z \sim 0$ SDSS galaxies from Izotov et al. 2006) of the Jones et al. (2015) relations. Consequently, when considering the results of our work and those of Sanders et al. (2020), both studies at similar redshift and metallicity, a tension exists in regard to the evolution with redshift of strong-line metallicity diagnostics and therefore which calibrations are reliable at high- z .

A likely source of the discrepancy and tension seen between the results of this work and that of Sanders et al. (2020) lies in how each galaxy sample was selected. For our dwarf galaxy stacking sample, we did not select galaxies based on the strength of any particular rest-optical emission-line (see Section 2.3). This is important particularly when considering [O III] $\lambda 4363$, [O III] $\lambda 5007$ ([O III] $\lambda 4959$ in our case), and $H\alpha$. By avoiding selection based on line-strength, we mitigate biases in our sample such as high sSFRs (SFR / M_*) and high excitation, resulting in a sample which very nearly falls on an extrapolation of the mean $z \sim 2.3 M_* - SFR$ relation (see Section 4.1.2 and Figure 3). In contrast, the $z \sim 2.2$

sample of Sanders et al. (2020) comprises galaxies selected on auroral-line detection (either O III] $\lambda\lambda 1661, 1666$ or [O III] $\lambda 4363$, detected at $(S/N)_{\text{med}} = 6.0_{-2.5}^{+1.5}$) for T_e -based metallicity estimation. Due to the faintness of these auroral lines – [O III] $\lambda 5007$ is $\sim 30 - 100\times$ brighter than [O III] $\lambda 4363$ (Jones et al. 2015) – this detection requirement preferentially selects younger galaxies with high-excitation, highly-ionized star-forming regions. These galaxies lie well above the $M_* - SFR$ relation. In fact, the sample of Sanders et al. (2020) lies an average ~ 0.6 dex above the best-fit $z \sim 2.3 M_* - SFR$ relation of Sanders et al. (2018) (which is very similar to the fit of the same relation in Sanders et al. 2021) and has O_{32} values ~ 0.5 dex higher on average than typical $z \sim 2.3$ star-forming MOSDEF galaxies at fixed M_* (Sanders et al. 2020, Figure 16). Sanders et al. shows that this auroral-line sample is not representative of typical $z \sim 2.3$ star-forming galaxies, but rather coincident with $z \sim 2$ extreme emission-line galaxies (EELGs). In effect, at roughly fixed O/H in Figure 4, we are comparing two galaxy samples that differ significantly in the ionization state and extremity of their star-forming regions. As such, both samples are not well-represented by one single strong-line metallicity calibration.

When considering the sample selection methodologies for our stacked sample and the $z > 1$ auroral-line sample of Sanders et al. (2020) against those for the calibration samples used to parameterize the relations shown in Figure 4, it is perhaps not surprising that several relations appear to agree with the Sanders et al. auroral-line sample while being $> 1\sigma$ inconsistent with our stacked sample. In the low-metallicity regime ($12 + \log(O/H) \lesssim 8.4$), the locally-calibrated strong-line metallicity relations are generally defined by *individual* galaxies with [O III] $\lambda 4363$ detections. This is the case for the relations of Maiolino et al. (2008), Jones et al. (2015), and Curti et al. (2017). This requirement of an [O III] $\lambda 4363$ detection in individual galaxies, as well as the BPT-related requirement of the Bian et al. (2018) high- z analog calibration (detailed above), selectively probe galaxies with ISM conditions more extreme than in typical $z \sim 0$ star-forming galaxies. Rather, ISM conditions more akin to those in the $z > 1$ auroral-line sample are probed, leading to low-metallicity strong-line calibrations that are likely biased high in O_3 and O_{32} (and low in O_2) and that closely predict the Sanders et al. (2020) $z > 1$ sample metallicity at fixed strong-line ratio. Meanwhile, the selection criterion for the Bian et al. (2018) local reference calibrations (detailed above) selectively probes galaxies with less extreme star-forming conditions and better predicts the

metallicity at fixed strong-line ratio of our dwarf galaxy stack, which is not reliant on emission-line detections.¹⁴

4.2.1. *The KBSS-LM1 Composite of Steidel et al. (2016)*

In this subsection, we briefly discuss the $z \sim 2.4$ composite spectrum of Steidel et al. (2016) in the context of the strong-line ratio – direct metallicity relations displayed in Figure 4. This composite, referred to in Steidel et al. (2016) as “KBSS-LM1,” is derived from the rest-frame far-UV and optical spectra of 30 star-forming galaxies from the KBSS-MOSFIRE spectroscopic survey. The galaxies comprising KBSS-LM1 were notably selected to have emission-line measurements or limits (not detections) of, among other lines, [O II] $\lambda\lambda 3726, 3729$, H β , [O III] $\lambda\lambda 4959, 5007$, and H α . The sample of galaxies was also selected such that it broadly represents the full KBSS-MOSFIRE sample in SFR, M_* , and O/H, the latter of which was calculated via the T_e -sensitive UV emission-line doublet, O III] $\lambda\lambda 1661, 1666$. The median M_* and derived T_e -based metallicity of KBSS-LM1 are, as reported by Sanders et al. (2020), $\log(M_*/M_\odot) = 9.8 \pm 0.3$ and $12 + \log(\text{O}/\text{H}) = 8.14 \pm 0.03$, respectively. With these selection criteria, KBSS-LM1 is therefore similar to our $z \sim 2.3$ dwarf galaxy composite in the sense that both samples should be representative of typical $z \sim 2.3$ galaxies at their respective stellar masses. Indeed, Sanders et al. (2020, Figure 16) find KBSS-LM1 to lie just above the $z \sim 2.3$ star-forming main sequence as well as amongst the typical $z \sim 2.3$ MOSDEF galaxies in O₃₂ at fixed M_* .

In Figure 4, along with our $z \sim 2.3$ dwarf galaxy stack (black stars) and $z \sim 2.2$ auroral-line sample of Sanders et al. (2020, gray squares), we plot KBSS-LM1 as a gray diamond in each panel. As with our dwarf galaxy stack, albeit at higher O/H owing to its higher M_* , we see that KBSS-LM1 is best represented by the local reference calibrations of Bian et al. (2018) instead of the high-redshift analog calibrations, though note the small statistical error bars (not bootstrapped) of KBSS-LM1. This result suggests that $z \sim 2.3$ star-forming galaxies with $8.4 \lesssim \log(M_*/M_\odot) \lesssim 9.8$ that lie on the M_* -SFR relation will, on average, have their metallicities most accurately predicted at fixed strong-line ratio via the local reference strong-line metallicity calibrations of Bian et al. (2018). In contrast, $z \sim 2.3$ EELGs and galaxies with more extreme ISM conditions, like the $z \sim 2.2$ auroral-line sample, may require independently-

calibrated strong-line metallicity relations more akin to the high- z analog calibrations of Bian et al. (2018).

4.3. *The Stellar Mass – Gas-Phase Metallicity Relation*

This section explores our $z \sim 2.3$ dwarf galaxy sample in relation to the low-mass end of the stellar mass – gas-phase metallicity relation (MZR). The MZR, shown to exist both locally and at high redshift, displays a positive correlation, parameterized as a power-law, between galaxy stellar mass (M_*) and gas-phase oxygen abundance (O/H) at lower stellar masses before flattening asymptotically at higher masses ($M_* \gtrsim 10^{10.5} M_\odot$ locally; Tremonti et al. 2004; Erb et al. 2006; Maiolino et al. 2008; Andrews & Martini 2013; Steidel et al. 2014; Curti et al. 2020; Sanders et al. 2020, 2021; Strom et al. 2022). The MZR also evolves with time, such that at higher redshifts, the average metallicity of star-forming galaxies is lower at fixed M_* than it is locally (Erb et al. 2006; Maiolino et al. 2008; Zahid et al. 2013, 2014a,b; Steidel et al. 2014; Sanders et al. 2020, 2021). Here we compare our dwarf galaxy composite against recent empirical and theoretical parameterizations of the MZR in an effort to better constrain the low-mass slope and normalization of the relation at $z \sim 2.3$.

4.3.1. *Comparison to MZR Derived from Observations*

In the left-hand panel of Figure 5, we plot our $z \sim 2.3$ dwarf galaxy composite against the $z \sim 2.2$ direct-method MZR of Sanders et al. (2020), the $z \sim 2.3$ strong-line MZR of Sanders et al. (2021), and the $z \sim 2.3$ MZR of Strom et al. (2022), who calculated their metallicities via photoionization modelling. The direct-method MZR shown here (black line) is derived from the Sanders et al. (2020) $z > 1$ ($z_{\text{med}} \sim 2.2$) auroral-line sample considered in Section 4.2 above. However, as previously mentioned, this sample of galaxies lies $\langle \Delta \log(\text{SFR}) \rangle \sim 0.6$ dex above the $z \sim 2.3$ M_* – SFR relation, which has the effect, via the FMR, of yielding a MZR biased low in O/H relative to the MZR expected for typical galaxies that fall on the star-forming main sequence at this redshift. As such, the direct-method MZR displayed in Figure 5 was parameterized by Sanders et al. (2020) *after* applying SFR-corrections to the $z > 1$ sample metallicities via Equation 4. Additionally, Sanders et al. (2020) adjusted this MZR to account for a low-redshift bias in the low-mass $z > 1$ galaxies. These galaxies (low-mass black square; 5 galaxies) were found to have a median redshift $\Delta z_{\text{med}} \sim 0.5$ lower than the high-mass sample galaxies (high-mass black square; 9 galaxies), and were estimated, on average, to have a metallicity biased 0.1 dex high due to the redshift evolution of O/H at fixed M_* ($d \log(\text{O}/\text{H})/dz \approx -0.2$;

¹⁴ A more detailed study of the biases in certain locally-calibrated strong-line metallicity relations (particularly of Curti et al. 2017), and how those biases factor into the observed evolution of strong-line metallicity relations with redshift, can be found in Sanders et al. (2020).




Figure 5. The stellar mass – gas-phase metallicity relation (MZR). *Left:* We compare our $z \sim 2.3$ dwarf galaxy stack (green star) at our sample’s median mass, $\log(M_*/M_\odot)_{\text{med}} = 8.29$, against the $z \sim 2.2$ direct-method MZR of Sanders et al. (2020, black line) and the extrapolations of the $z \sim 2.3$ strong-line MZR of Sanders et al. (2021, blue solid/dashed line) and the $z \sim 2.3$ photoionization-model-based MZR of Strom et al. (2022, purple solid/dashed line). We find excellent agreement between our stack and the direct-method MZR, the most comparable of the relations. For reference, we also include the mean values of the $z > 1$ auroral-line sample split into two M_* bins (black squares; Sanders et al. 2020), the MOSDEF galaxy stacks from Sanders et al. (2021, blue squares), and the $z \sim 2.4$ KBSS-LM1 composite of Steidel et al. (2016, orange diamond). *Right:* We compare our $z \sim 2.3$ stack (green star; same as in left panel) to the predicted $z = 2$ and $z = 3$ MZR of the IllustrisTNG100 simulations (Torrey et al. 2019) and the $z = 2.3$ MZR of the FIRE simulations (red dot-dashed line; Ma et al. 2016), finding consistency, within errors, with both sets of MZR. When comparing our stack after recalculating the sample stellar masses assuming more realistic non-parametric SFHs (red unfilled square; $\log(M_*/M_\odot)_{\text{med}} = 8.92$), we find excellent agreement with the MZR from FIRE. The MZR from the left-hand panel are recreated here for reference. We note that for each display of our stack, the x -axis error bar corresponds to the M_* range of our sample.

Sanders et al. 2020). With these adjustments, the direct-method MZR reproduced in Figure 5 is an estimation of the MZR – on the T_e -based abundance scale – of typical galaxies lying on the star-forming main sequence at a redshift of $z \sim 2.2$.

The blue line (and its extrapolation) in the left-hand panel of Figure 5 is a recreation of the $z \sim 2.3$ strong-line MZR of Sanders et al. (2021), fit as a power-law to the four lowest-mass bins of MOSDEF galaxies displayed here as blue squares (The highest-mass bin suffers from incompleteness and was excluded from the fit (Sanders et al. 2021, Section 2.4)). These MOSDEF stacks were also used by Sanders et al. to parameterize their M_* – SFR relation (see Section 4.1.2 and Figure 3). The metallicities of the MOSDEF stacks were calculated via the high- z analog calibrations of Bian et al. (2018) and the α -element-based strong-line ratios of O_{32} , O_3 , and $\log([\text{Ne III}] \lambda 3869/[\text{O II}] \lambda \lambda 3726, 3729)$. These relations were chosen so as to use calibrations that most closely reproduce the excitation sequences, and thus likely ISM conditions, of the MOSDEF $z \sim 2.3$ star-forming sample.

The $z \sim 2.3$ MZR of Strom et al. (2022), and its extrapolation, are shown as the purple line in the left-hand panel of Figure 5. This relation was fit to 195 individual star-forming galaxies from the KBSS survey. The metallicities in this study were estimated with photoionization models, described in Strom et al. (2018, 2022), that are able to reproduce the rest-UV and rest-optical spectroscopic properties of high- z , star-forming galaxies.

When comparing our $z \sim 2.3$ dwarf galaxy stack (green star; x -axis error bar represents the M_* range of the stacking sample) against the direct-method and strong-line MZR of Sanders et al. (2020) and Sanders et al. (2021), respectively, we find that at the median stellar mass of our stacking sample, $\log(M_*/M_\odot)_{\text{med}} = 8.29$, and the direct-method metallicity calculated from the composite spectrum, $12 + \log(\text{O}/\text{H}) = 7.87^{+0.24}_{-0.22}$, the stack lies virtually on top of the $z \sim 2.2$ direct-method MZR. Within uncertainties, our stack (and the mean values of the low- and high-mass bins of the $z > 1$ auroral-line sample; Sanders et al. 2020, black squares) is also consistent with the extrapolation of the strong-line MZR, lying below this extrapolation by ~ 0.13

dex. Correcting the metallicity of our composite for the slightly-high SFR bias of the stacking sample (increasing $\log(\text{O}/\text{H})$ by ~ 0.06 dex; see Section 4.1.2) reduces the offset of the stack from the extrapolation of the strong-line MZR while moving the stack ~ 0.06 dex above the direct-method MZR. This consistency with both MZRs supports their fit power-law parameters, in particular the slope, which was fit by Sanders et al. (2020) to be $\beta = 0.37$ and by Sanders et al. (2021) to be $\beta = 0.30$. However, while we are comparing to the strong-line MZR of Sanders et al. (2021) due to the authors' careful consideration in selecting applicable strong-line calibrations for high- z star-forming regions, we note that systematic uncertainties still exist between metallicities calculated directly versus with strong-line proxies. Therefore, in constraining the slope of the $z \sim 2.3$ MZR, our results and direct-method of metallicity estimation most favorably suggest the slope fit to the direct-method MZR of Sanders et al. (2020), $\beta = 0.37$.

When considering the $z \sim 2.3$ photoionization-model-based MZR of Strom et al. (2022), we find that our stack lies $\approx 1\sigma$ below the extrapolation of this relation, in disagreement with the shallow slope ($\beta = 0.14$) proposed by Strom et al. However, we must again take into account the difference in methods of abundance estimation between the two studies. As discussed in the literature (e.g., Kewley & Ellison 2008; Maiolino & Mannucci 2019), photoionization models typically overestimate metallicities by ~ 0.2 dex or more compared to direct metallicities. In general, this is due to a poorly-constrained combination of factors, such as photoionization models accounting for dust depletion or T_e -based metallicities potentially being biased low due to temperature fluctuations or gradients in star-forming regions leading to nebular spectra dominated by brighter auroral lines from high- T_e zones. While the discrepancy between direct and theoretical metallicity estimates is stronger at higher metallicities (e.g., Kewley & Ellison 2008; Maiolino & Mannucci 2019; Curti et al. 2020), Steidel et al. (2016) found that photoionization models predict an oxygen abundance 0.25 dex higher than their T_e -based estimate of $12+\log(\text{O}/\text{H}) = 8.14$ ($0.29 Z_\odot$) for KBSS-LM1, a composite of 30 star-forming KBSS galaxies that we briefly discussed in Section 4.2.1. If we apply this same offset to the T_e -based metallicity of our dwarf galaxy composite, our stack will lie very near the extrapolation of the Strom et al. (2022) MZR. This said, there are too many systematic uncertainties involved to accurately compare our composite against this MZR at present, and we conclude that the best estimate for the

slope of the $z \sim 2.3$ MZR is $\beta = 0.37$, given by the direct-method MZR of Sanders et al. (2020).

We note that the stellar masses of the samples and studies considered here are calculated via SED-fitting with consistent assumptions in star-formation history, IMF, and extinction law. We also note that the KBSS-LM1 composite of Steidel et al. (2016) lies significantly below the displayed MZRs, including the direct-method MZR, when plotted at its reported direct metallicity of $12+\log(\text{O}/\text{H}) = 8.14 \pm 0.03$. However, we do acknowledge the very small *statistical-only* uncertainty of this metallicity.

4.3.2. Comparison to MZRs from Cosmological Simulations

In the right-hand panel of Figure 5, we now compare our $z \sim 2.3$ dwarf galaxy stack against predicted MZRs from well-known cosmological simulations, the Feedback in Realistic Environments simulations¹⁵ (FIRE; Hopkins et al. 2014) and The Next Generation Illustris simulations¹⁶ (IllustrisTNG; Weinberger et al. 2017; Pillepich et al. 2018), which are the successor to the Illustris simulation (Vogelsberger et al. 2014a,b; Genel et al. 2014). Our stack, with the median mass ($\log(M_*/M_\odot) = 8.29$) and direct metallicity ($12 + \log(\text{O}/\text{H}) = 7.87^{+0.24}_{-0.22}$) as reported throughout this paper, is shown by the green star, with the x -axis error bar representing the M_* range of our stacking sample. The predicted MZR from FIRE, given by the redshift-dependent, fixed-slope ($\beta = 0.35$), gas-phase MZR fitting function in Ma et al. (2016), is evaluated at $z = 2.30$ (the mean redshift of our stacking sample) and is represented by the red dot-dashed line. The $z = 2$ and $z = 3$ MZRs from IllustrisTNG (Torrey et al. 2019), specifically from the TNG100 simulation volume, are displayed by the solid dark-red and light-red lines, respectively. For reference to MZRs derived from observations, in the right-hand panel we reproduce, from the left-hand panel, the $z \sim 2.2$ direct-method MZR of Sanders et al. (2020, black line), the $z \sim 2.3$ strong-line MZR of Sanders et al. (2021, blue line), and the $z \sim 2.3$ photoionization-model-based MZR of Strom et al. (2022, purple line).

Properly assessing the predicted MZRs considered in this section requires a reliable and accurate empirical metallicity estimation method such as the direct-method, which estimates oxygen abundances through directly probing physical properties (T_e and n_e) of star-forming regions. We find that at fixed M_* , the direct metallicity of our stack (green star) is consistent within

¹⁵ FIRE: <https://fire.northwestern.edu/>

¹⁶ IllustrisTNG: <https://www.tng-project.org/>

uncertainties with both the $z = 2.3$ FIRE MZR and $2 \leq z \leq 3$ MZR of IllustrisTNG. We also observe that the $z \sim 2.2$ direct-method MZR agrees favorably in slope and normalization with the IllustrisTNG MZR above $M_* \approx 10^9 M_\odot$. Below this mass, the IllustrisTNG MZR deviates away from this slope and the direct-method MZR toward higher metallicity values, displaying a “bump” in the low-mass regime. This bump is the result of the minimum wind velocity ($v_{\min} = 350 \text{ km s}^{-1}$) enforced in the stellar feedback models of IllustrisTNG, with v_{\min} put in place so that the simulations match the low-end of the galaxy stellar mass function (Pillepich et al. 2018). As Torrey et al. (2019) explain, while v_{\min} is not directly a function of M_* , it is generally set as the wind velocity in galaxies with $M_* \lesssim 10^9 M_\odot$ due to the low dark matter velocity dispersions in their halos. The higher metallicities at these masses that we see as the bump in the MZR then arise because these fixed-velocity winds eject less gas, and therefore fewer metals, than would be the case if the wind velocity were allowed to be $v < 350 \text{ km s}^{-1}$. While further observations are needed to either confirm or deny this bump in the MZR, as well as evaluate the applicability of the minimum wind velocity assumption, the direct-method MZR of Sanders et al. (2020) suggests that such a bump likely does not exist and that wind velocities in low-mass galaxies can extend lower than $v < 350 \text{ km s}^{-1}$. This suggestion is reinforced below when revisiting our dwarf galaxy stacking sample with stellar masses recalculated under more realistic assumptions.

In this work, in order to facilitate fair comparisons of our empirical results to those in the literature, when estimating the stellar masses of our stacking sample via SED-fitting, we made assumptions consistent with those generally found in the literature; in particular, we assumed constant star formation histories (SFH). However, the SFHs of galaxies, particularly of galaxies at high- z owing to their higher-EW emission lines, are likely not well-described by such simple parameterizations. Instead, stellar masses are likely more accurate if calculated assuming non-parametric SFHs which can better reveal the presence of older stellar populations that are hidden in the rest-UV and rest-optical by brighter, younger stars (Gburek et al. 2019; Tang et al. 2022; Whitler et al. 2022; Topping et al. 2022). Having these more realistic, typically larger stellar masses is important when comparing to simulation results. Therefore, we recalculated the stellar masses of our stack-

ing sample, via the PROSPECTOR^{17,18} SED-fitting code (Johnson et al. 2021), assuming non-parametric SFHs. The resultant median stellar mass of our sample under these assumptions becomes $\log(M_*/M_\odot) = 8.92$, an increase to our fiducial median stellar mass of 0.63 dex. Our dwarf galaxy stack, shifted to this recalculated median M_* , is shown in Figure 5 as the red unfilled square. As with the x -axis error bar of our fiducial point (the green star), the x -axis error bar of the red square represents the recalculated range of M_* in our stacking sample.

When comparing our $z \sim 2.3$ dwarf galaxy stack to the simulated MZRs following recalculating the sample stellar masses under the assumption of more realistic non-parametric SFHs, we find excellent agreement between our composite and the $z = 2.3$ FIRE MZR of Ma et al. (2016), especially if we apply the metallicity correction ($\Delta \log(\text{O}/\text{H}) \sim 0.06$ dex) to our stack to account for our bias high in SFR. In comparison to the $z = 2$ and $z = 3$ IllustrisTNG MZRs of Torrey et al. (2019), we find that our composite lies $\sim 1.6\sigma$ below the $z = 2$ MZR and $\sim 1.3\sigma$ below the $z = 3$ MZR, suggesting that a stronger O/H evolution at fixed M_* with redshift (like that seen in Figure 7 of Ma et al. 2016 relative to other simulations of the time – including the original Illustris simulation Torrey et al. 2014) and/or tuning of the $z = 0$ MZR normalization is needed. Like the direct-method MZR of Sanders et al. (2020), our composite also disagrees with the existence of a metallicity bump in the MZR at $M_* \lesssim 10^9 M_\odot$, suggesting that the minimum wind velocity assumption in IllustrisTNG should be revisited.

4.4. $M_* - \text{SFR} - \text{O}/\text{H}$ Relation at $z \sim 2.3$

The $M_* - \text{SFR} - \text{O}/\text{H}$ relation, or fundamental metallicity relation (FMR), posits that the MZR has a secondary dependence on SFR such that, when considering all three properties, the scatter in metallicity at fixed M_* and SFR is reduced compared to the scatter in metallicity at fixed M_* alone (Mannucci et al. 2010; Lara-López et al. 2010; Andrews & Martini 2013; Sanders et al. 2018; Curti et al. 2020; Sanders et al. 2021). Also as a result of this secondary dependence, at fixed M_* , a higher (lower) than average SFR yields a lower (higher) than average O/H. Of further interest is that numerous studies have shown that the FMR is redshift-invariant to within ~ 0.1 dex in metallicity out to $z \sim 3.3$ (e.g., Mannucci et al. 2010; Henry et al. 2013a,b; Sanders et al. 2018, 2021). In effect, the observation of the evolution

¹⁷ <https://prospect.readthedocs.io/en/latest/>

¹⁸ <https://github.com/bd-j/prospector>

of the MZR over this redshift range, whereby O/H decreases with increasing redshift at fixed M_* , is actually the observation at different redshifts of different portions of the locally-defined FMR since SFR increases with redshift at fixed M_* (Whitaker et al. 2014; Speagle et al. 2014; Sanders et al. 2021). Unfortunately, however, this redshift-invariance of the FMR is still a matter of debate owing to the uncertainties regarding the applicability of locally-calibrated, strong-line metallicity calibrations at high-redshift (see Section 4.2), widely-used in lieu of hard-to-measure direct metallicities.

Fortunately, in this work we have a direct, T_e -based oxygen abundance from our dwarf galaxy composite spectrum with which we can evaluate the redshift evolution of the FMR. Additionally, given the properties of our sample, we are able to probe $M_* - \text{SFR} - \text{O/H}$ parameter space that to-date has been poorly-sampled at $z \sim 2.3$. We do so via the commonly-used 2D planar projection of the 3D FMR, established by Mannucci et al. (2010). In this projection, the metallicity is a function of the linear combination of M_* and SFR, denoted by μ_α and described by the equation

$$\mu_\alpha = \log(M_*/M_\odot) - \alpha \log(\text{SFR}/M_\odot \text{ yr}^{-1}) \quad (5)$$

where α is the parameter which denotes the strength of the SFR-dependence of the FMR as well as the value which minimizes the scatter in O/H at fixed μ_α . This parameter, α , is generally found to be lower (a weaker SFR dependence) when determined with strong-line metallicities (e.g., $\alpha = 0.32$; Mannucci et al. 2010) and higher (a stronger SFR dependence) when determined with direct-method metallicities (e.g., $\alpha = 0.66$; Andrews & Martini 2013), though recent estimations via strong-line metallicities by Curti et al. (2020, $\alpha = 0.55$) and Sanders et al. (2021, $\alpha = 0.60$) have brought these α -estimates into better agreement. For this work, we use the value of $\alpha = 0.63$, which derives from the SDSS $M_* - \text{SFR}$ stacks of Andrews & Martini (2013), with their direct-method metallicities corrected for diffuse ionized gas (DIG) contamination by Sanders et al. (2017).

In Figure 6, we show our $z \sim 2.3$ dwarf galaxy stack (green star; x -axis error bar represents the $\mu_{0.63}$ range of the stacking sample) in the direct-method O/H $- \mu_{0.63}$ parameter space, plotted at the $\mu_{0.63}$ value ($\mu_{0.63} = 8.07$) given by the stacking sample’s median stellar mass ($\log(M_*/M_\odot) = 8.29$) and median SFR ($\log(\text{SFR}) = 0.353$). We compare our composite to the Sanders et al. (2017) best-fit linear representation of the FMR (black line) tracing the $z \sim 0$, DIG-corrected, Andrews & Martini (2013) $M_* - \text{SFR}$ stacks. We also include in Figure 6 the two mass bins of the Sanders et al. (2020) $z > 1$




Figure 6. The direct-method $M_* - \text{SFR} - \text{O/H}$ fundamental metallicity relation (FMR), represented here by the O/H $- \mu_\alpha$ planar projection (Mannucci et al. 2010). Referencing Equation 5 for μ_α , we take $\alpha = 0.63$, the value determined by Sanders et al. (2017) using the DIG-corrected, T_e -based metallicities of the Andrews & Martini (2013) SDSS $M_* - \text{SFR}$ stacks. The best-fit linear relation by Sanders et al. (2017) to these $z \sim 0$ stacks is shown here by the black line. Our $z \sim 2.3$ composite is displayed as the green star with $\mu_{0.63}$ calculated from our sample’s median M_* ($\log(M_*/M_\odot) = 8.29$) and SFR ($\log(\text{SFR}) = 0.353$). The x -axis error bar represents our sample’s range in $\mu_{0.63}$. Our stack lies ~ 0.11 dex or $\sim 0.5\sigma$ below the direct-method FMR, though is consistent with a redshift-invariant FMR within uncertainties. For reference, we also show the M_* -binned, $z > 1$ auroral-line sample of Sanders et al. (2020, black squares) and the $z \sim 2.4$ KBSS-LM1 composite of Steidel et al. (2016, orange diamond).

auroral-line sample (black squares), which these authors found to be consistent, within ~ 0.1 dex at fixed $\mu_{0.63}$, with lower redshift samples in the $\mu_{0.63}$ direct-method FMR projection. Adding to these results, we find our dwarf galaxy composite to have a T_e -based metallicity that lies $\sim 0.5\sigma$ or ~ 0.11 dex below the linear relation representing the direct-method FMR. We therefore join numerous other authors in suggesting, via direct-method metallicities, that the FMR evolves at most by ~ 0.1 dex in O/H at fixed M_* and SFR from $z = 0$ to at least $z \sim 2.3$, though note that within the uncertainties on the metallicity, our stack is consistent with a redshift-invariant FMR.

5. SUMMARY

In this study, we analyze the median composite spectrum of 16 typical, star-forming, dwarf galaxies ($7.06 \leq \log(M_*/M_\odot) \leq 8.93$; $\log(M_*/M_\odot)_{\text{median}} = 8.29$) at red-

shifts $1.7 < z < 2.6$ ($z_{\text{mean}} = 2.30$) selected independent of the strength of any particular emission line. These galaxies are gravitationally-lensed by the foreground clusters Abell 1689, MACS J0717.5+3745, and MACS J1149.5+2223. In our composite spectrum, we find a 2.5σ (4.1σ) detection of the faint, T_e -sensitive, [O III] $\lambda 4363$ auroral line when considering our bootstrapped (statistical-only) error spectrum, allowing us to directly calculate an oxygen abundance from the composite of $12 + \log(\text{O}/\text{H})_{\text{direct}} = 7.87^{+0.24}_{-0.22}$ ($0.15^{+0.11}_{-0.06} Z_{\odot}$). We summarize the results using this T_e -based metallicity, and other conclusions, in this final section.

1. To determine how representative our dwarf galaxy sample is of typical, star-forming, $z \sim 2.3$ dwarf galaxies, we first considered our composite in the context of the N2-BPT diagram, where we found that our stack lies offset from the $z \sim 0$ SDSS star-forming sequence in the same parameter space as the $z \sim 2.3$ star-forming galaxies of larger statistical surveys (e.g., MOSDEF; Shapley et al. 2015). We also show that our composite lies at higher [O III] $\lambda 5007/\text{H}\beta$ and lower [N II] $\lambda 6583/\text{H}\alpha$ than any of the M_* -binned MOSDEF stacks of Sanders et al. (2021); our composite extends the trend seen with these MOSDEF stacks of lower stellar mass and metallicity at higher [O III]/ $\text{H}\beta$ and lower [N II]/ $\text{H}\alpha$.
2. We also considered our stacking sample against an extrapolation of the $z \sim 2.3$ $M_* - \text{SFR}$ SFMS of Sanders et al. (2021), finding the sample to scatter on either side of this relation. Our stacking sample has a median $\text{SFR} = 2.25 M_{\odot} \text{yr}^{-1}$, which lies $\Delta \log(\text{SFR}) \approx 0.19$ dex above this SFMS at fixed M_* ($\log(M_*/M_{\odot})_{\text{med}} = 8.29$), corresponding to a bias in O/H of $\Delta \log(\text{O}/\text{H}) \approx -0.06$ dex via the FMR, well within even our statistical metallicity uncertainty ($\sigma \sim 0.12$ dex). We conclude that our stacking sample is not largely biased in SFR or O/H and is thus, on average, representative of typical, star-forming, $z \sim 2.3$ dwarf galaxies with stellar masses between $10^8 \lesssim M_*/M_{\odot} \lesssim 10^9$. Our sample serves as an initial extension of representative, statistical, spectroscopic surveys at $z \sim 2.3$ into the dwarf galaxy mass regime.
3. We analyzed the applicability at $z \sim 2.3$ of several locally-calibrated, oxygen-based, strong-line metallicity relations from the literature. We find that at $12 + \log(\text{O}/\text{H})_{\text{direct}} = 7.87^{+0.24}_{-0.22}$, our stack lies in the metallicity-insensitive “turnover” region of the O_3 and R_{23} calibrations, signalling their ineffectiveness for metallicity estimation of typical,

$z \sim 2.3$, dwarf galaxies. When considering the O_{32} and O_2 indices together, our stack’s metallicity is most accurately reproduced (within $\lesssim 0.15$ dex) at fixed strong-line ratio by the local reference calibrations of Bian et al. (2018), in agreement with that seen for the $z \sim 2.4$ KBSS-LM1 composite of Steidel et al. (2016), who also selected their sample independent of line-strength. We generally disagree with the conclusions of Sanders et al. (2020), who argue that their $z \sim 2.2$ auroral-line sample favors the high- z analog calibrations of Bian et al. (2018). While both samples are at similar redshift and metallicity, we argue that our discrepancy in conclusion is due to sample selection effects as well as biases in the low-metallicity strong-line calibration samples. Indeed, by being selected for having a detection of a T_e -sensitive auroral-line, the sample of Sanders et al. (2020) is strongly biased in SFR, O_{32} , and $\text{EW}_0([\text{O III}] \lambda 5007)$ relative to typical, $z \sim 2.3$, star-forming galaxies.

4. At the median stellar mass of our stacking sample, $\log(M_*/M_{\odot}) = 8.29$, we compared our composite direct metallicity, $12 + \log(\text{O}/\text{H}) = 7.87^{+0.24}_{-0.22}$, against the $z \sim 2.2$ direct-method MZR of Sanders et al. (2020), the $z \sim 2.3$ strong-line MZR of Sanders et al. (2021), and the $z \sim 2.3$ photoionization-model-based MZR of Strom et al. (2022). After correcting for the slight SFR bias of the stacking sample, we find that our $z \sim 2.3$ stack lies ~ 0.06 dex above the direct-method MZR and ~ 0.07 dex below the strong-line MZR at fixed M_* , well within our uncertainties. Our stack lies $\approx 1\sigma$ below the Strom et al. MZR. In constraining the slope of the MZR, we defer to the direct-method MZR, with which we show excellent agreement, as metallicities for this relation and our composite were calculated consistently. Therefore, we suggest that the slope of the $z \sim 2.3$ MZR is that given by this direct-method relation of Sanders et al. (2020), $\beta = 0.37$.
5. We also compared our composite, and the MZR derived from observations, to the $z = 2.30$ MZR from the FIRE simulations (Ma et al. 2016) as well as to the $z = 2$ and $z = 3$ MZR from the IllustrisTNG100 simulations (Torrey et al. 2019). At the stack’s fiducial median stellar mass, $\log(M_*/M_{\odot}) = 8.29$, our composite is consistent within uncertainties with both sets of simulations. However, when recalculating our sample stellar masses assuming more realistic non-parametric SFHs, the median stellar mass is increased to

$\log(M_*/M_\odot) = 8.92$, moving the stack into excellent agreement with the FIRE MZR and $\sim 1.5\sigma$ below the $2 \leq z \leq 3$ IllustrisTNG MZR. This tension with IllustrisTNG is in part caused by a “bump” in its MZR deriving from a constant minimum wind velocity ($v_{\min} = 350 \text{ km s}^{-1}$) applied to galaxies with $M_* \lesssim 10^9 M_\odot$. Between our stack with recalculated masses and the direct-method MZR of Sanders et al. (2020), we suggest that the low-mass end of the MZR does not contain this bump.

6. Our $z \sim 2.3$ dwarf galaxy composite was compared to the locally-defined, direct-method FMR in order to test the relation’s redshift-invariance. We made this comparison via the FMR projection proposed by Mannucci et al. (2010) and given in Equation 5, with $\alpha = 0.63$ (Sanders et al. 2017). At $\mu_{0.63} = 8.07$, calculated with the stacking sample’s median stellar mass, $\log(M_*/M_\odot) = 8.29$, and median SFR, $\log(\text{SFR}) = 0.353$, we find our composite to lie $\sim 0.5\sigma$ or ~ 0.11 dex below the Sanders et al. (2017) best-fit linear relation in direct-method $\text{O}/\text{H} - \mu_{0.63}$ space; this relation is fit to the $z \sim 0$ DIG-corrected stacks of Andrews & Martini (2013). We therefore agree with many in the literature who suggest that the FMR is redshift-invariant within ~ 0.1 dex at fixed M_* and SFR from $z \sim 0 - 2.3$.

This study compliments other larger spectroscopic surveys of representative, star-forming galaxies at $z \sim 2$ and $M_* \gtrsim 10^9 M_\odot$ by serving as an initial extension into the dwarf galaxy mass regime. In analyzing our sample of representative dwarf galaxies, we are able to use a direct oxygen abundance to provide initial constraints on the low-mass slope of the high- z MZR and probe scarcely-studied parameter space of the FMR. While our sample size is small, our work provides a reference point for future statistical studies of high- z dwarf galaxies with the newly-operational *James Webb Space Telescope*, which will greatly increase our understanding of the processes responsible for galaxy formation and evolution.

This material is based upon work supported by the National Science Foundation under Grant No. 1617013.

The authors wish to recognize and acknowledge the very significant cultural role and reverence that the summit of Maunakea has always had within the indigenous Hawaiian community. We are most fortunate to have the opportunity to conduct observations from this mountain.

Facilities: Keck:I (MOSFIRE), *HST* (WFC3, ACS)

APPENDIX

A. CONSISTENT FITS OF THE STRONG-LINE METALLICITY CALIBRATIONS OF BIAN+18

We note that while Bian et al. (2018) provide fits to their high- z analog stacks for the strong-line indices of R_{23} , O_{32} , and O_3 (with $[\text{O III}] \lambda 4959$ added to $[\text{O III}] \lambda 5007$ in the latter two indices unlike in this work; see Bian et al. (2018) and Sanders et al. (2021), Footnote 17), they do not provide fits for the O_2 index or to the local reference stacks. Therefore, we used orthogonal distance regression and the stated flux and T_e -based metallicity values given in Bian et al. (2018) to consistently fit both samples for each line index considered in Figure 4 and Section 4.2. As in Bian et al. (2018), third-order polynomials were assumed for the R_{23} and O_3 high- z analog fits; we adopted the same functional form for the O_2 high- z analog fit as well. For the fits of the local reference stacks and these same strong-line indices, we instead assumed second-order polynomial functions due to there only being 4 bins with estimated direct metallicities compared to 6 bins for the high- z analog sample. For the O_{32} index, as in Bian et al. (2018), we fit a linear functional form to both the local reference and high- z analog stacks. The coefficients of our fits are given in Table 4 below.

Table 4. Coefficients of the Refit Bian+18 Relations

Ratio	c_0	c_1	c_2	c_3
Local Reference Relations				
O_{32}	11.1767	-1.3414		
O_3	-57.7632	14.9708	-0.9578	
O_2	-25.2699	5.3889	-0.2750	
R_{23}	-26.4726	6.9012	-0.4345	
High- z Analog Relations				
O_{32}	14.5895	-1.7287		
O_3	117.8668	-48.8336	6.7607	-0.3107
O_2	-80.9802	14.1526	0.0755	-0.0723
R_{23}	263.2135	-101.2448	13.0313	-0.5591

NOTE—Ratio definitions given in Section 4.2.

REFERENCES

- Acker, A., Köppen, J., Samland, M., & Stenholm, B. 1989, *The Messenger*, 58, 44
- Alavi, A., Siana, B., Richard, J., et al. 2014, *ApJ*, 780, 143, doi: [10.1088/0004-637X/780/2/143](https://doi.org/10.1088/0004-637X/780/2/143)
- . 2016, *ApJ*, 832, 56, doi: [10.3847/0004-637X/832/1/56](https://doi.org/10.3847/0004-637X/832/1/56)
- Alloin, D., Collin-Souffrin, S., Joly, M., & Vigroux, L. 1979, *A&A*, 78, 200
- Andrews, B. H., & Martini, P. 2013, *ApJ*, 765, 140, doi: [10.1088/0004-637X/765/2/140](https://doi.org/10.1088/0004-637X/765/2/140)
- Asplund, M., Amarsi, A. M., & Grevesse, N. 2021, *A&A*, 653, A141, doi: [10.1051/0004-6361/202140445](https://doi.org/10.1051/0004-6361/202140445)
- Baldwin, J. A., Phillips, M. M., & Terlevich, R. 1981, *Publications of the Astronomical Society of the Pacific*, 93, 5, doi: [10.1086/130766](https://doi.org/10.1086/130766)
- Berg, D. A., Skillman, E. D., Marble, A. R., et al. 2012, *ApJ*, 754, 98, doi: [10.1088/0004-637X/754/2/98](https://doi.org/10.1088/0004-637X/754/2/98)
- Bian, F., Kewley, L. J., & Dopita, M. A. 2018, *ApJ*, 859, 175, doi: [10.3847/1538-4357/aabd74](https://doi.org/10.3847/1538-4357/aabd74)
- Brammer, G. B., Sánchez-Janssen, R., Labbé, I., et al. 2012a, *ApJ*, 758, L17, doi: [10.1088/2041-8205/758/1/L17](https://doi.org/10.1088/2041-8205/758/1/L17)
- Brammer, G. B., van Dokkum, P. G., Franx, M., et al. 2012b, *ApJS*, 200, 13, doi: [10.1088/0067-0049/200/2/13](https://doi.org/10.1088/0067-0049/200/2/13)
- Bruzual, G., & Charlot, S. 2003, *MNRAS*, 344, 1000, doi: [10.1046/j.1365-8711.2003.06897.x](https://doi.org/10.1046/j.1365-8711.2003.06897.x)
- Calzetti, D., Armus, L., Bohlin, R. C., et al. 2000, *ApJ*, 533, 682, doi: [10.1086/308692](https://doi.org/10.1086/308692)
- Campbell, A., Terlevich, R., & Melnick, J. 1986, *MNRAS*, 223, 811, doi: [10.1093/mnras/223.4.811](https://doi.org/10.1093/mnras/223.4.811)
- Cardelli, J. A., Clayton, G. C., & Mathis, J. S. 1989, *ApJ*, 345, 245, doi: [10.1086/167900](https://doi.org/10.1086/167900)
- Carnall, A. C. 2017, arXiv e-prints, arXiv:1705.05165. <https://arxiv.org/abs/1705.05165>
- Chabrier, G. 2003, *Publications of the Astronomical Society of the Pacific*, 115, 763, doi: [10.1086/376392](https://doi.org/10.1086/376392)
- Christensen, L., Laursen, P., Richard, J., et al. 2012, *MNRAS*, 427, 1973, doi: [10.1111/j.1365-2966.2012.22007.x](https://doi.org/10.1111/j.1365-2966.2012.22007.x)
- Cresci, G., Mannucci, F., & Curti, M. 2019, *A&A*, 627, A42, doi: [10.1051/0004-6361/201834637](https://doi.org/10.1051/0004-6361/201834637)
- Curti, M., Cresci, G., Mannucci, F., et al. 2017, *MNRAS*, 465, 1384, doi: [10.1093/mnras/stw2766](https://doi.org/10.1093/mnras/stw2766)
- Curti, M., Mannucci, F., Cresci, G., & Maiolino, R. 2020, *MNRAS*, 491, 944, doi: [10.1093/mnras/stz2910](https://doi.org/10.1093/mnras/stz2910)
- Dale, D. A., Cohen, S. A., Johnson, L. C., et al. 2009, *ApJ*, 703, 517, doi: [10.1088/0004-637X/703/1/517](https://doi.org/10.1088/0004-637X/703/1/517)
- Davé, R., Finlator, K., & Oppenheimer, B. D. 2012, *MNRAS*, 421, 98, doi: [10.1111/j.1365-2966.2011.20148.x](https://doi.org/10.1111/j.1365-2966.2011.20148.x)
- Davies, R. L., Förster Schreiber, N. M., Genzel, R., et al. 2021, *ApJ*, 909, 78, doi: [10.3847/1538-4357/abd551](https://doi.org/10.3847/1538-4357/abd551)
- Dopita, M. A., & Sutherland, R. S. 2003, *Astrophysics of the Diffuse Universe* (Berlin: Springer)

- Dopita, M. A., Sutherland, R. S., Nicholls, D. C., Kewley, L. J., & Vogt, F. P. A. 2013, *The Astrophysical Journal Supplement Series*, 208, 10, doi: [10.1088/0067-0049/208/1/10](https://doi.org/10.1088/0067-0049/208/1/10)
- Emami, N., Siana, B., Alavi, A., et al. 2020, *ApJ*, 895, 116, doi: [10.3847/1538-4357/ab8f97](https://doi.org/10.3847/1538-4357/ab8f97)
- Erb, D. K., Shapley, A. E., Pettini, M., et al. 2006, *ApJ*, 644, 813, doi: [10.1086/503623](https://doi.org/10.1086/503623)
- Finlator, K., & Davé, R. 2008, *MNRAS*, 385, 2181, doi: [10.1111/j.1365-2966.2008.12991.x](https://doi.org/10.1111/j.1365-2966.2008.12991.x)
- Foreman-Mackey, D., Hogg, D. W., Lang, D., & Goodman, J. 2013, *PASP*, 125, 306, doi: [10.1086/670067](https://doi.org/10.1086/670067)
- Freeman, W. R., Siana, B., Kriek, M., et al. 2019, *ApJ*, 873, 102, doi: [10.3847/1538-4357/ab0655](https://doi.org/10.3847/1538-4357/ab0655)
- Gburek, T., Siana, B., Alavi, A., et al. 2019, *ApJ*, 887, 168, doi: [10.3847/1538-4357/ab5713](https://doi.org/10.3847/1538-4357/ab5713)
- Genel, S., Vogelsberger, M., Springel, V., et al. 2014, *MNRAS*, 445, 175, doi: [10.1093/mnras/stu1654](https://doi.org/10.1093/mnras/stu1654)
- Grogin, N. A., Kocevski, D. D., Faber, S. M., et al. 2011, *ApJS*, 197, 35, doi: [10.1088/0067-0049/197/2/35](https://doi.org/10.1088/0067-0049/197/2/35)
- Henry, A., Martin, C. L., Finlator, K., & Dressler, A. 2013a, *ApJ*, 769, 148, doi: [10.1088/0004-637X/769/2/148](https://doi.org/10.1088/0004-637X/769/2/148)
- Henry, A., Scarlata, C., Domínguez, A., et al. 2013b, *ApJL*, 776, L27, doi: [10.1088/2041-8205/776/2/L27](https://doi.org/10.1088/2041-8205/776/2/L27)
- Hopkins, P. F., Kereš, D., Oñorbe, J., et al. 2014, *MNRAS*, 445, 581, doi: [10.1093/mnras/stu1738](https://doi.org/10.1093/mnras/stu1738)
- Izotov, Y. I., Stasińska, G., Meynet, G., Guseva, N. G., & Thuan, T. X. 2006, *A&A*, 448, 955, doi: [10.1051/0004-6361:20053763](https://doi.org/10.1051/0004-6361:20053763)
- James, B. L., Pettini, M., Christensen, L., et al. 2014, *MNRAS*, 440, 1794, doi: [10.1093/mnras/stu287](https://doi.org/10.1093/mnras/stu287)
- Jauzac, M., Richard, J., Limousin, M., et al. 2016, *MNRAS*, 457, 2029, doi: [10.1093/mnras/stw069](https://doi.org/10.1093/mnras/stw069)
- Jensen, E. B., Strom, K. M., & Strom, S. E. 1976, *ApJ*, 209, 748, doi: [10.1086/154773](https://doi.org/10.1086/154773)
- Johnson, B. D., Leja, J., Conroy, C., & Speagle, J. S. 2021, *ApJS*, 254, 22, doi: [10.3847/1538-4365/abef67](https://doi.org/10.3847/1538-4365/abef67)
- Jones, T., Martin, C., & Cooper, M. C. 2015, *ApJ*, 813, 126, doi: [10.1088/0004-637X/813/2/126](https://doi.org/10.1088/0004-637X/813/2/126)
- Jullo, E., Kneib, J. P., Limousin, M., et al. 2007, *New Journal of Physics*, 9, 447, doi: [10.1088/1367-2630/9/12/447](https://doi.org/10.1088/1367-2630/9/12/447)
- Kaasinen, M., Bian, F., Groves, B., Kewley, L. J., & Gupta, A. 2017, *MNRAS*, 465, 3220, doi: [10.1093/mnras/stw2827](https://doi.org/10.1093/mnras/stw2827)
- Kashino, D., Silverman, J. D., Sanders, D., et al. 2017, *ApJ*, 835, 88, doi: [10.3847/1538-4357/835/1/88](https://doi.org/10.3847/1538-4357/835/1/88)
- . 2019, *ApJS*, 241, 10, doi: [10.3847/1538-4365/ab06c4](https://doi.org/10.3847/1538-4365/ab06c4)
- Kauffmann, G., Heckman, T. M., Tremonti, C., et al. 2003, *MNRAS*, 346, 1055, doi: [10.1111/j.1365-2966.2003.07154.x](https://doi.org/10.1111/j.1365-2966.2003.07154.x)
- Kennicutt, Robert C., J. 1998, *Annual Review of Astronomy and Astrophysics*, 36, 189, doi: [10.1146/annurev.astro.36.1.189](https://doi.org/10.1146/annurev.astro.36.1.189)
- Kewley, L. J., & Dopita, M. A. 2002, *The Astrophysical Journal Supplement Series*, 142, 35, doi: [10.1086/341326](https://doi.org/10.1086/341326)
- Kewley, L. J., Dopita, M. A., Leitherer, C., et al. 2013, *ApJ*, 774, 100, doi: [10.1088/0004-637X/774/2/100](https://doi.org/10.1088/0004-637X/774/2/100)
- Kewley, L. J., Dopita, M. A., Sutherland, R. S., Heisler, C. A., & Trevena, J. 2001, *ApJ*, 556, 121, doi: [10.1086/321545](https://doi.org/10.1086/321545)
- Kewley, L. J., & Ellison, S. L. 2008, *ApJ*, 681, 1183, doi: [10.1086/587500](https://doi.org/10.1086/587500)
- Koekemoer, A. M., Faber, S. M., Ferguson, H. C., et al. 2011, *ApJS*, 197, 36, doi: [10.1088/0067-0049/197/2/36](https://doi.org/10.1088/0067-0049/197/2/36)
- Kriek, M., van Dokkum, P. G., Labbé, I., et al. 2009, *ApJ*, 700, 221, doi: [10.1088/0004-637X/700/1/221](https://doi.org/10.1088/0004-637X/700/1/221)
- Kriek, M., Shapley, A. E., Reddy, N. A., et al. 2015, *The Astrophysical Journal Supplement Series*, 218, 15, doi: [10.1088/0067-0049/218/2/15](https://doi.org/10.1088/0067-0049/218/2/15)
- Lara-López, M. A., Cepa, J., Bongiovanni, A., et al. 2010, *A&A*, 521, L53, doi: [10.1051/0004-6361/201014803](https://doi.org/10.1051/0004-6361/201014803)
- Lee, H., Skillman, E. D., Cannon, J. M., et al. 2006, *ApJ*, 647, 970, doi: [10.1086/505573](https://doi.org/10.1086/505573)
- Limousin, M., Richard, J., Jullo, E., et al. 2007, *ApJ*, 668, 643, doi: [10.1086/521293](https://doi.org/10.1086/521293)
- . 2016, *A&A*, 588, A99, doi: [10.1051/0004-6361/201527638](https://doi.org/10.1051/0004-6361/201527638)
- Lotz, J. M., Koekemoer, A., Coe, D., et al. 2017, *ApJ*, 837, 97, doi: [10.3847/1538-4357/837/1/97](https://doi.org/10.3847/1538-4357/837/1/97)
- Ma, X., Hopkins, P. F., Faucher-Giguère, C.-A., et al. 2016, *MNRAS*, 456, 2140, doi: [10.1093/mnras/stv2659](https://doi.org/10.1093/mnras/stv2659)
- Maiolino, R., & Mannucci, F. 2019, *A&A Rv*, 27, 3, doi: [10.1007/s00159-018-0112-2](https://doi.org/10.1007/s00159-018-0112-2)
- Maiolino, R., Nagao, T., Grazian, A., et al. 2008, *A&A*, 488, 463, doi: [10.1051/0004-6361:200809678](https://doi.org/10.1051/0004-6361:200809678)
- Mannucci, F., Cresci, G., Maiolino, R., Marconi, A., & Gnerucci, A. 2010, *MNRAS*, 408, 2115, doi: [10.1111/j.1365-2966.2010.17291.x](https://doi.org/10.1111/j.1365-2966.2010.17291.x)
- Mannucci, F., Salvaterra, R., & Campisi, M. A. 2011, *MNRAS*, 414, 1263, doi: [10.1111/j.1365-2966.2011.18459.x](https://doi.org/10.1111/j.1365-2966.2011.18459.x)
- Masters, D., Faisst, A., & Capak, P. 2016, *ApJ*, 828, 18, doi: [10.3847/0004-637X/828/1/18](https://doi.org/10.3847/0004-637X/828/1/18)
- Masters, D., McCarthy, P., Siana, B., et al. 2014, *ApJ*, 785, 153, doi: [10.1088/0004-637X/785/2/153](https://doi.org/10.1088/0004-637X/785/2/153)
- McGaugh, S. S. 1991, *ApJ*, 380, 140, doi: [10.1086/170569](https://doi.org/10.1086/170569)
- McLean, I. S., Steidel, C. C., Epps, H., et al. 2010, in *Ground-based and Airborne Instrumentation for Astronomy III*, Vol. 7735, 77351E, doi: [10.1117/12.856715](https://doi.org/10.1117/12.856715)

- McLean, I. S., Steidel, C. C., Epps, H. W., et al. 2012, in *Ground-based and Airborne Instrumentation for Astronomy IV*, Vol. 8446, 84460J, doi: [10.1117/12.924794](https://doi.org/10.1117/12.924794)
- Osterbrock, D. E., & Ferland, G. J. 2006, *Astrophysics of Gaseous Nebulae and Active Galactic Nuclei* (Sausalito, CA: University Science Books)
- Pagel, B. E. J., Edmunds, M. G., Blackwell, D. E., Chun, M. S., & Smith, G. 1979, *MNRAS*, 189, 95, doi: [10.1093/mnras/189.1.95](https://doi.org/10.1093/mnras/189.1.95)
- Patrício, V., Christensen, L., Rhodin, H., Cañameras, R., & Lara-López, M. A. 2018, *MNRAS*, 481, 3520, doi: [10.1093/mnras/sty2508](https://doi.org/10.1093/mnras/sty2508)
- Pettini, M., & Pagel, B. E. J. 2004, *MNRAS*, 348, L59, doi: [10.1111/j.1365-2966.2004.07591.x](https://doi.org/10.1111/j.1365-2966.2004.07591.x)
- Pillepich, A., Springel, V., Nelson, D., et al. 2018, *MNRAS*, 473, 4077, doi: [10.1093/mnras/stx2656](https://doi.org/10.1093/mnras/stx2656)
- Postman, M., Coe, D., Benítez, N., et al. 2012, *ApJS*, 199, 25, doi: [10.1088/0067-0049/199/2/25](https://doi.org/10.1088/0067-0049/199/2/25)
- Reddy, N. A., Shapley, A. E., Sanders, R. L., et al. 2018, *ApJ*, 869, 92, doi: [10.3847/1538-4357/aaed1e](https://doi.org/10.3847/1538-4357/aaed1e)
- Runco, J. N., Reddy, N. A., Shapley, A. E., et al. 2022, *MNRAS*, 513, 3871, doi: [10.1093/mnras/stac1115](https://doi.org/10.1093/mnras/stac1115)
- Sanders, R. L., Shapley, A. E., Zhang, K., & Yan, R. 2017, *ApJ*, 850, 136, doi: [10.3847/1538-4357/aa93e4](https://doi.org/10.3847/1538-4357/aa93e4)
- Sanders, R. L., Shapley, A. E., Kriek, M., et al. 2015, *ApJ*, 799, 138, doi: [10.1088/0004-637X/799/2/138](https://doi.org/10.1088/0004-637X/799/2/138)
- . 2016a, *ApJ*, 825, L23, doi: [10.3847/2041-8205/825/2/L23](https://doi.org/10.3847/2041-8205/825/2/L23)
- . 2016b, *ApJ*, 816, 23, doi: [10.3847/0004-637X/816/1/23](https://doi.org/10.3847/0004-637X/816/1/23)
- . 2018, *ApJ*, 858, 99, doi: [10.3847/1538-4357/aabcbcd](https://doi.org/10.3847/1538-4357/aabcbcd)
- Sanders, R. L., Shapley, A. E., Reddy, N. A., et al. 2020, *MNRAS*, 491, 1427, doi: [10.1093/mnras/stz3032](https://doi.org/10.1093/mnras/stz3032)
- Sanders, R. L., Shapley, A. E., Jones, T., et al. 2021, *ApJ*, 914, 19, doi: [10.3847/1538-4357/abf4c1](https://doi.org/10.3847/1538-4357/abf4c1)
- Shapley, A. E., Reddy, N. A., Kriek, M., et al. 2015, *ApJ*, 801, 88, doi: [10.1088/0004-637X/801/2/88](https://doi.org/10.1088/0004-637X/801/2/88)
- Shaw, R. A., & Dufour, R. J. 1994, in *Astronomical Data Analysis Software and Systems III*, ed. D. R. Crabtree, R. J. Hanisch, & J. Barnes, Vol. 61, 327
- Shivaei, I., Reddy, N. A., Shapley, A. E., et al. 2015, *ApJ*, 815, 98, doi: [10.1088/0004-637X/815/2/98](https://doi.org/10.1088/0004-637X/815/2/98)
- Speagle, J. S., Steinhardt, C. L., Capak, P. L., & Silverman, J. D. 2014, *ApJS*, 214, 15, doi: [10.1088/0067-0049/214/2/15](https://doi.org/10.1088/0067-0049/214/2/15)
- Stark, D. P., Auger, M., Belokurov, V., et al. 2013, *MNRAS*, 436, 1040, doi: [10.1093/mnras/stt1624](https://doi.org/10.1093/mnras/stt1624)
- Steidel, C. C., Strom, A. L., Pettini, M., et al. 2016, *ApJ*, 826, 159, doi: [10.3847/0004-637X/826/2/159](https://doi.org/10.3847/0004-637X/826/2/159)
- Steidel, C. C., Rudie, G. C., Strom, A. L., et al. 2014, *ApJ*, 795, 165, doi: [10.1088/0004-637X/795/2/165](https://doi.org/10.1088/0004-637X/795/2/165)
- Storey, P. J., & Zeppen, C. J. 2000, *MNRAS*, 312, 813, doi: [10.1046/j.1365-8711.2000.03184.x](https://doi.org/10.1046/j.1365-8711.2000.03184.x)
- Strom, A. L., Rudie, G. C., Steidel, C. C., & Trainor, R. F. 2022, *ApJ*, 925, 116, doi: [10.3847/1538-4357/ac38a3](https://doi.org/10.3847/1538-4357/ac38a3)
- Strom, A. L., Steidel, C. C., Rudie, G. C., Trainor, R. F., & Pettini, M. 2018, *ApJ*, 868, 117, doi: [10.3847/1538-4357/aae1a5](https://doi.org/10.3847/1538-4357/aae1a5)
- Strom, A. L., Steidel, C. C., Rudie, G. C., et al. 2017, *ApJ*, 836, 164, doi: [10.3847/1538-4357/836/2/164](https://doi.org/10.3847/1538-4357/836/2/164)
- Tang, M., Stark, D. P., & Ellis, R. S. 2022, *MNRAS*, 513, 5211, doi: [10.1093/mnras/stac1280](https://doi.org/10.1093/mnras/stac1280)
- Topping, M. W., Stark, D. P., Endsley, R., et al. 2022, arXiv e-prints, arXiv:2203.07392. <https://arxiv.org/abs/2203.07392>
- Torrey, P., Vogelsberger, M., Genel, S., et al. 2014, *MNRAS*, 438, 1985, doi: [10.1093/mnras/stt2295](https://doi.org/10.1093/mnras/stt2295)
- Torrey, P., Vogelsberger, M., Marinacci, F., et al. 2019, *MNRAS*, 484, 5587, doi: [10.1093/mnras/stz243](https://doi.org/10.1093/mnras/stz243)
- Tremonti, C. A., Heckman, T. M., Kauffmann, G., et al. 2004, *ApJ*, 613, 898, doi: [10.1086/423264](https://doi.org/10.1086/423264)
- Vogelsberger, M., Genel, S., Springel, V., et al. 2014a, *MNRAS*, 444, 1518, doi: [10.1093/mnras/stu1536](https://doi.org/10.1093/mnras/stu1536)
- . 2014b, *Nature*, 509, 177, doi: [10.1038/nature13316](https://doi.org/10.1038/nature13316)
- Weinberger, R., Springel, V., Hernquist, L., et al. 2017, *MNRAS*, 465, 3291, doi: [10.1093/mnras/stw2944](https://doi.org/10.1093/mnras/stw2944)
- Whitaker, K. E., Franx, M., Leja, J., et al. 2014, *ApJ*, 795, 104, doi: [10.1088/0004-637X/795/2/104](https://doi.org/10.1088/0004-637X/795/2/104)
- . 2020, *ApJ*, 896, 175, doi: [10.3847/1538-4357/ab98fc](https://doi.org/10.3847/1538-4357/ab98fc)
- Whitler, L., Stark, D. P., Endsley, R., et al. 2022, arXiv e-prints, arXiv:2206.05315. <https://arxiv.org/abs/2206.05315>
- Yates, R. M., Kauffmann, G., & Guo, Q. 2012, *MNRAS*, 422, 215, doi: [10.1111/j.1365-2966.2012.20595.x](https://doi.org/10.1111/j.1365-2966.2012.20595.x)
- Zahid, H. J., Dima, G. I., Kudritzki, R.-P., et al. 2014a, *ApJ*, 791, 130, doi: [10.1088/0004-637X/791/2/130](https://doi.org/10.1088/0004-637X/791/2/130)
- Zahid, H. J., Geller, M. J., Kewley, L. J., et al. 2013, *ApJ*, 771, L19, doi: [10.1088/2041-8205/771/2/L19](https://doi.org/10.1088/2041-8205/771/2/L19)
- Zahid, H. J., Kashino, D., Silverman, J. D., et al. 2014b, *ApJ*, 792, 75, doi: [10.1088/0004-637X/792/1/75](https://doi.org/10.1088/0004-637X/792/1/75)