

Heterogeneous Position Effects and the Power of Rankings

Rafael P. Greminger^{*}

This version: January 1, 2024

First version: June 30, 2021

Abstract

Many online retailers and search intermediaries present products on ranked product lists. Because changing the ordering of products influences their revenues and consumer welfare, these platforms can design rankings to maximize either of these two metrics. In this paper, I study how rankings serving these two objectives differ and what determines this difference. First, I highlight that when position effects are heterogeneous, rankings can increase both revenues and consumer welfare by increasing the overall conversion rate. Second, I provide empirical evidence for this heterogeneity, highlighting that cheaper alternatives have stronger position effects. Finally, I quantify revenue and consumer welfare effects across the different rankings. To this end, I develop an estimation procedure for the search and discovery model of Greminger (2022) that yields a smooth likelihood function by construction. The results from the model show that rankings designed to maximize revenues can also increase consumer welfare. Moreover, these revenue-based rankings reduce consumer welfare only to a limited extent relative to a consumer-welfare-maximizing ranking.

^{*}UCL School of Management, r.greminger@ucl.ac.uk.

[†]I am deeply grateful to my advisors, Tobias Klein and Jaap Abbring, for their thoughtful guidance and support. I also thank Ilya Morozov, Yufeng Huang, Dorothee Hillrichs, Bart Bronnenberg, Stephan Seiler, Raluca Ursu, Maarten Janssen, José L. Moraga, Brad Shapiro, and seminar participants at Kellogg School of Management, Simon School of Business, Berkeley Haas, and members of the Structural Econometrics Group in Tilburg for excellent comments. Finally, I am grateful to the Nederlandse Organisatie voor Wetenschappelijk Onderzoek (NWO) for financial support through Research Talent grant 406.18.568.

1 Introduction

Many consumers purchase products from online retailers or search intermediaries. These online platforms typically present consumers with ranked product lists that have been shown to entail substantial position effects: products shown in higher positions are more often clicked on and bought (e.g., Ghose et al., 2014; De Los Santos and Koulayev, 2017; Ursu, 2018). These position effects allow online platforms to increase their revenues by changing the ranking (e.g., Choi and Mela, 2019). At the same time, changing the ranking also affects consumers; it can help them find better-matching alternatives and save them time and effort going down the list. Hence, platforms concerned about customer churn can also use rankings to make consumers better off (e.g., Ursu, 2018). However, following one of these objectives potentially comes at the expense of the other. A ranking that maximizes the platform’s revenues could end up harming consumers, whereas a consumer-welfare-maximizing ranking may reduce the platform’s revenues.

In this paper, I ask whether this is the case and study how rankings serving the two objectives differ in their impact on consumers and the platform’s revenues. First, I use a simple example to highlight a crucial factor determining such differences: heterogeneous position effects. If a platform takes a price-based commission or markup, shifting demand to more expensive alternatives will increase the platform’s revenues. Hence, a ranking can increase the platform’s revenues by exploiting position effects and moving more expensive alternatives higher up on the list. However, suppose position effects are heterogeneous and cheaper alternatives have stronger position effects. In this case, moving expensive alternatives up on the list also decreases the conversion rate. As a result, maximizing the platform’s revenues requires balancing the two effects.

Whether position effects are heterogeneous such that a platform needs to balance the two effects is an empirical question and not clear *a priori*. To address it, I use experimental ranking variation to identify heterogeneous position effects in data from a large online search intermediary. The results show that cheaper alternatives indeed have stronger position effects. More broadly, I find that product attributes and the position on the list complement each other such that alternatives with desirable attributes have stronger position effects. Hence, moving products with a lower price and other desirable attributes higher up on the list will increase the conversion rate on average, potentially increasing both revenues and consumer welfare.

Analyzing whether this will occur requires quantifying how the different rankings affect the platform’s revenues and consumer welfare. To this end, I build on and estimate

the search and discovery (SD) model of Greminger (2022). In the model, consumers decide between discovering more products by scrolling down the list and learning more about an already-discovered product by going to its detail page. I argue that this model is well-suited to study the consumer welfare effects of different rankings because it provides a micro-foundation for position effects: consumers decide to stop scrolling before ever reaching the lower positions on the list. Moreover, I show that this discovery mechanism implies position effects that closely match the pattern revealed by the descriptive evidence. As a result, the estimated model predicts heterogeneous position effects that closely match those in the data and, hence, fits the moments determining the trade-off between the different rankings notably well.

Building on the model, I introduce two heuristics for the revenue-maximizing ranking, the “bottom-up” and the “Position-1” ranking, and analyze their effects in a counterfactual analysis. The results show that these revenue-based rankings increase total revenues by up to 14.93% over a randomized ranking. Notably, this revenue increase does not come at a cost to consumers. Instead, the proposed rankings increase consumer welfare over a randomized ranking by up to 0.92%, conditional on consumers searching at least one alternative. These consumer welfare gains come close to the 0.98% gain achieved by the utility-based ranking, which I prove to maximize consumer welfare. These results show that revenue-based rankings are closer to the consumer-welfare-maximizing ranking than to a randomized ranking due to how heterogeneous position effects stem from consumers’ search decisions. Hence, both consumers and the platform can benefit from rankings that maximize revenues.

By studying the effects of different rankings, this paper also offers two managerial insights. First, a concern for online platforms is that revenue-based rankings could lead to a bad search experience for consumers, thus increasing customer churn. My results suggest that this is not the case. Because high-utility alternatives have stronger position effects, revenue-based rankings increase conversions by moving them higher up on the list, thus also benefiting consumers relative to various other rankings. Second, I also show that a utility-based ranking maximizes consumer welfare and the overall purchase probability. Hence, platforms that explicitly want to increase consumer welfare can do so by maximizing conversions, an observable outcome that ranking algorithms can directly target.

To address the substantive research question, I also make several methodological contributions. First, I develop an estimation approach for the SD model that yields a smooth

likelihood by construction and avoids computationally expensive steps during estimation. Second, I extend the analysis of Greminger (2022) to show how the SD model captures position effects conditional on the observed product attributes. Finally, I use this result to show how the observed position effects are sufficient to identify the model parameters without observing how many products consumers discover.

2 Related Literature

This paper contributes to the literature examining the effects of different rankings on consumer welfare, search behavior, and platform revenues. Several studies in this literature focus on the effects of utility-based rankings (Ghose et al., 2012, 2014; Ursu, 2018). More recent studies additionally consider the effects of rankings designed to increase platform revenues, documenting possible trade-offs between making consumers better off and increasing platform revenues (Choi and Mela, 2019; Zhang et al., 2021; Compiani et al., 2023; Donnelly et al., 2023). I add to this literature by highlighting how this trade-off stems from heterogeneous position effects, deriving how these heterogeneous position effects arise in a micro-founded model,¹ and quantifying this trade-off by estimating the same model. By focusing on the effects of rankings, this paper also differs from recent work by Zhang et al. (2023), who estimate the SD model to study how different search routes affect consumers’ search behavior.

By providing empirical evidence that shows how position effects depend on product attributes like price, I also add to the empirical literature that documents position effects on ranked product lists (Ghose et al., 2012, 2014; De Los Santos and Koulayev, 2017; Ursu, 2018) and in search advertising (Goldman and Rao, 2014; Athey and Imbens, 2015; Jeziorski and Segal, 2015; Jeziorski and Moorthy, 2018).² Unlike Ghose et al. (2014), who also consider how position effects vary with product attributes, I use experimental variation in rankings to account for endogeneity in rankings and consistently find that desirable attributes amplify position effects.

The methodological contributions in this paper add to the empirical search literature that has used a range of alternative models to rationalize position effects (e.g., Chan and

¹While heterogeneous position effects may also arise in other empirical search models, prior work has not shown whether this is the case and how these alternative models generate heterogeneous position effects. Hence, it remains unclear whether these models would also fit these crucial moments in the data.

²These studies find that ads with a larger click-through rate on any position have weaker position effects. The difference to my results suggests that consumers use a general-purpose search engine like Google with a specific outcome already in mind instead of using the list to compare different alternatives. This is corroborated by results of Blake et al. (2015), who find that search advertising is not effective for a well-known platform like eBay.

Park, 2015; Chen and Yao, 2017; De Los Santos and Koulayev, 2017; Ursu, 2018; Choi and Mela, 2019; Gibbard, 2022b; Compiani et al., 2023; Donnelly et al., 2023). The SD model has several features that make it particularly useful to capture position effects and quantify the effects of different rankings. I highlight these features and relate them to other sequential search models after introducing the model. As they are nested in the SD model, my estimation approach can also be used to estimate directed search models *à la* Weitzman (1979) and, hence, adds to the recent literature introducing estimation approaches without researcher-chosen smoothing parameters for these models (Jiang et al., 2021; Chung et al., 2023). However, unlike these approaches, my approach does not require observing the search order and requires fewer computations.³

By showing that a utility-based ranking maximizes consumer welfare in the SD model and introducing two heuristics for maximizing revenues in the short-term, I also add to the literature deriving algorithms to optimally choose in which order to display alternatives to consumers (e.g., Ryzin and Mahajan, 1999; Talluri and Van Ryzin, 2004; Davis et al., 2014; Ursu and Dzyabura, 2020; Chu et al., 2020; Derakhshan et al., 2022; Compiani et al., 2023). Whereas this literature motivates this paper’s empirical evaluation of how revenue-maximizing rankings affect consumers, it tends to rely on more stylized demand models and,⁴ except for Compiani et al. (2023), does not quantify the different effects.

3 Heterogeneous Position Effects and Ranking Objectives

To motivate the empirical analysis, I first use a simple example to highlight a crucial factor determining how a revenue-maximizing ranking orders alternatives and, hence, how such a ranking will affect consumers.

Consider an online retail platform that offers two products, A and B . B is more expensive ($p_B > p_A$), and the platform decides whether to move it to the first position. The platform takes the same price-based commission from both products and, therefore, wants to maximize revenues across both positions. Hence, whether the platform will

³The approaches of Jiang et al. (2021) and Chung et al. (2023) grow in computational complexity in the number of clicks each consumer makes, which is not the case with my approach.

⁴Early work in this literature did not consider search. The model of Chu et al. (2020) precludes position effects for consumers who do not buy an alternative, contrasting what I observe in the data. Derakhshan et al. (2022) consider heterogeneous position effects in the context of maximizing the conversion rate (as opposed to revenues). Their model implies that consumers inspect all of the alternatives on the product list up to some rank, which contrasts the data as almost all consumers skip clicking on some alternatives. Ursu and Dzyabura (2020) instead focus on a retailer deciding how to place independent categories within a retailer.

display B first depends on how total revenues change following the switch. This change is given by

$$\Delta R = \underbrace{(p_B - p_A)\Delta d_A}_{\text{price effect}} + \underbrace{p_B(\Delta d_B - \Delta d_A)}_{\text{demand effect}}, \quad (1)$$

where p_j denotes the price of alternative j and Δd_j denotes its position effect, defined as the absolute demand change when moving from the second to the first position. In line with ample empirical evidence (e.g. Ursu, 2018), these position effects will be non-negative ($\Delta d_j \geq 0 \forall j$).

The two parts in equation (1) reveal that changing the ranking can increase revenues by shifting demand to more expensive alternatives through a “price effect”, increasing the conversion rate through a “demand effect”, or a combination of both. Crucially, the demand effect reveals that heterogeneous position effects play an important role in determining which alternatives a revenue-maximizing ranking will move to the top and, hence, how it will affect consumers. If position effects are homogeneous ($\Delta d_A = \Delta d_B$), there is no demand effect such that moving the more expensive alternative B to the top necessarily increases revenues. In contrast, if the cheaper alternative A has a stronger position effect ($\Delta d_A > \Delta d_B$), the demand effect will be negative such that choosing a ranking to maximize revenues becomes similar to a monopolist pricing problem.

Which of the two cases applies and how the resulting ranking affects consumers is not clear *a priori*. For example, suppose the two products are homogeneous and consumers never choose the alternative in the second position because the costs of looking at the second position are prohibitively high. If consumers are not too price-sensitive and choose whichever product is in the first position, then $\Delta d_B = \Delta d_A > 0$ such that moving B to the top maximizes revenues while harming consumers who are now getting the more expensive alternative. Now suppose that consumers instead are so price-sensitive that they will not buy B even when it is shown in the first position. In this case, $\Delta d_A > \Delta d_B = 0$ such that moving A to the top maximizes revenues while also maximizing consumer welfare. Finally, suppose products are not homogeneous and all consumers prefer B to A despite the higher price, while only some consumers are not willing to buy A . In this case, $\Delta d_B > \Delta d_A > 0$ such that moving B to the top maximizes revenues and consumer welfare.

As these examples highlight, heterogeneous position effects determine how the different rankings will affect consumers and the platform’s revenues.⁵ Moreover, they can be

⁵For simplicity, I focus only on two products. With more than two products, the revenue change would also depend on demand changes for alternatives other than the ones being moved. Nonetheless, the

informative of consumers’ preferences and how they interact with ranked product lists. Hence, in a first step to show how the different rankings affect consumers and platform revenues, I now provide empirical evidence that shows whether position effects are heterogeneous and how they vary with product attributes like price.

4 Data and Descriptive Evidence

I use click-stream data from a leading online travel agency, Expedia. The data can be obtained from Kaggle.com and contains information on clicks and purchases for 166,039 search sessions between November 2012 and June 2013.⁶ A search session starts at the point where a consumer has submitted a query for a hotel stay on Expedia. Following this query, Expedia presents a list of the available options on which consumers observe various hotel characteristics, such as the price per night and the review score. They then can scroll down to reveal more hotels on the list or click on a particular item they already see on the list. Clicking on an item leads to the hotel’s detail page, which reveals further information and allows booking the hotel. Ursu (2018) provides a more comprehensive discussion of the dataset, and I apply similar criteria to prepare the final sample (see Appendix E).

4.1 Summary

The main feature of the data is that for about 30% of search sessions, Expedia randomly assigned hotels that fit the query to positions on the list. This exogenous variation is essential to identify position effects without convoluting the effect of more desirable hotels being ranked higher. Suppose hotels instead are positioned on top of the list based on unobservable characteristics that also lead to more clicks and purchases. In that case, it is challenging to disentangle correlations with such unobservables, potentially leading to an overestimation of position effects (Ursu, 2018). For the other 70% of consumers in the sample, Expedia used its ranking algorithm to assign hotels to positions.⁷

Table 1 summarizes the dataset on a hotel and session level for consumers who observed the randomized ranking.⁸ In total, there are 51,510 sessions in this sample. On

logic would be largely the same and rankings would continue to increase revenues by shifting demand to more expensive alternatives or increasing conversions, with the latter being mainly determined through heterogeneous position effects.

⁶The data is available under the following link: <https://www.kaggle.com/c/expedia-personalized-sort/data>.

⁷It is not possible to get the specifics of the Expedia ranking algorithm used during the sample period. Most likely, it used observable hotel and query characteristics to create a ranking that maximized predicted clicks or bookings.

⁸Appendix E provides a detailed description of each variable. The “no reviews” variable is a dummy

TABLE 1 – Summary Statistics (Random Ranking)

	N	Mean	Median	Std. Dev	Min.	Max.
Hotel-level						
Price (in \$)	1,357,106	171.70	141.04	114.03	10.00	1000.00
Star rating	1,333,734	3.34	3	0.89	1	5
Review score	1,354,996	3.81	4.00	0.97	0.00	5.00
No reviews	1,354,996	0.04	0	0.19	0	1
Chain	1,357,106	0.62	1.00	0.48	0.00	1.00
Location score	1,357,106	3.26	3	1.53	0	7
On promotion	1,357,106	0.24	0	0.43	0	1
Session-level						
Number of items	51,510	26.35	31	8.46	5	38
Number of clicks	51,510	1.14	1	0.66	1	25
Made booking	51,510	0.08	0	0.27	0	1
Trip length (in days)	51,510	3.07	2	2.42	1	40
Booking window (in days)	51,510	53.67	31	62.49	0	498
Number of adults	51,510	2.08	2	0.94	1	9
Number of children	51,510	0.43	0	0.82	0	9
Number of rooms	51,510	1.14	1	0.46	1	8

Notes: Summary statistics for sessions under random ranking.

average, there are 1.14 clicks per session, and about 8% of sessions ended with a hotel booking. The number of alternatives on the product list of a session varies between 5 and 38. This variation does not result from consumers not browsing further but from these queries being for hotels in destinations or on dates where only a few hotels had available rooms. Some destinations may also offer more alternatives, but the data contains only the results displayed on the first page. As Ursu (2018) notes, this imposes little restriction as position effects are identified from differences across positions. Ursu (2018) also discusses two other limitations, that the data does not contain sessions without a click and that sessions with bookings were over-sampled, and how they can be circumvented.

4.2 Expedia Benefits from Increasing Total Revenues

By offering hotel bookings on its website, Expedia makes revenues through two different models typical for online travel agents.⁹ First, Expedia offers hotel stays through a merchant model. Under this model, Expedia negotiates with individual hotels the rooms made available through its website and each room’s respective pricing. Second, Expedia also offers hotel stays through an agency model. Under this model, Expedia takes a commission and only passes on reservations and payments to the individual hotels that set prices themselves. With the data, it is not possible to determine under which revenue

indicating whether a hotel has no reviews. This is coded as a “review score” of zero in the raw data. However, given that it differs from a “review score” of zero and a missing “review score”, I treat this dummy separately.

⁹Expedia also offers other services, such as car rentals or flights, that are not part of the data.

model a specific hotel is listed.¹⁰ However, under both models, Expedia makes revenues through a price-based commission, i.e., by taking a share of the price the consumer pays when booking the hotel. As a result, Expedia increases its own revenues by increasing total revenues across all hotels on the list. Moreover, if commissions are the same for all hotels, maximizing total revenues also maximizes Expedia’s profits.

4.3 Descriptive Evidence of Heterogeneous Position Effects

I estimate the following linear probability model (LPM) to analyze whether position effects are heterogeneous and how they depend on product attributes:

$$\mathbb{P}(Y_{ij} = 1|z_{ij}) = x_j'\beta_1 + w_i'\beta_2 + pos_{ij}\gamma + pos_{ij}x_j'\theta + \tau_d . \quad (2)$$

Each observation is a hotel j in destination d displayed on position $pos_{ij} = 1, 2, \dots$ in a consumer query i . A larger position means that the hotel is shown further down the list such that a negative coefficient for γ implies that hotels further down are less likely to be clicked on or booked. Hotel attributes (e.g., price) are gathered in column vector x_j , whereas query characteristics (e.g., trip length) are gathered in column vector w_i . Depending on the specification, y_{ij} is a dummy indicating whether j was clicked on or booked in session i . τ_d indicates fixed effects on a destination level. Finally, z_{ij} gathers x_j , w_i , pos_{ij} and the fixed effects τ_d . Throughout, I denote random variables with capital letters.

The main parameters of interest are γ and θ . These parameters jointly capture how a hotel’s position affects its probability of being clicked on or booked. Specifically, given some hotel characteristics x_j , I define the *position effect* as the marginal effect of the position on the CTR or booking probability, conditional on hotel attributes:

$$\frac{\partial \mathbb{P}(Y_{ij} = 1|x_{ij})}{\partial pos_{ij}} = \gamma + x_j'\theta . \quad (3)$$

Given this specification, the position effect captures absolute changes, which are the relevant measures for changes to platform revenues as highlighted in Section 3. Because of the randomized ranking, hotel attributes of all hotels in the list are uncorrelated with any of the positions. Hence, these position effects can be estimated consistently.

Table 2 presents the results, where coefficient estimates are scaled to represent changes in terms of percentage points.¹¹ Columns 1 and 4 show the results of a baseline model

¹⁰In 2013 (the sample period), Expedia made 70% of its worldwide revenue through the merchant model and 24% through the agency model. The income from the merchant model primarily is from hotel bookings, whereas the agency model also includes flights and other products. See the annual report https://s27.q4cdn.com/708721433/files/doc_financials/2013/ar/EXPE_2013_Annual_Report.PDF

¹¹Standard errors are clustered on a consumer level, capturing that search behavior can induce correlation

TABLE 2 – Coefficient Estimates (LPM, Random Ranking)

	Clicks			Bookings		
	(1)	(2)	(3)	(4)	(5)	(6)
Position	-0.1864*** (0.0019)	-0.1424*** (0.0121)	-0.1427*** (0.0123)	-0.0116*** (0.0005)	-0.0028 (0.0028)	-0.0028 (0.0029)
Price	-0.0125*** (0.0002)	-0.0173*** (0.0004)	-0.0190*** (0.0004)	-0.0011*** (0.0000)	-0.0017*** (0.0001)	-0.0017*** (0.0001)
On promotion	1.1578*** (0.0497)	1.4961*** (0.1100)	1.5318*** (0.1229)	0.1261*** (0.0130)	0.1436*** (0.0287)	0.1463*** (0.0332)
Star rating	1.6211*** (0.0317)	2.1556*** (0.0657)		0.1051*** (0.0079)	0.1227*** (0.0163)	
Review score	0.0810** (0.0351)	0.0287 (0.0813)		0.0366*** (0.0082)	0.0794*** (0.0193)	
No reviews	-0.2488 (0.1622)	-0.7767** (0.3839)		0.0872** (0.0345)	0.1412* (0.0825)	
Chain	0.2227*** (0.0459)	0.3105*** (0.0966)		0.0248** (0.0113)	0.0641*** (0.0240)	
Location score	0.4381*** (0.0168)	0.5602*** (0.0321)		0.0529*** (0.0036)	0.0556*** (0.0071)	
Position \times Price		0.0003*** (0.0000)	0.0003*** (0.0000)		0.0000*** (0.0000)	0.0000*** (0.0000)
Position \times Star rating		-0.0318*** (0.0028)	-0.0270*** (0.0029)		-0.0011 (0.0007)	-0.0005 (0.0007)
Position \times Review score		0.0028 (0.0035)	0.0044 (0.0035)		-0.0025*** (0.0008)	-0.0024*** (0.0008)
Position \times No reviews		0.0295* (0.0164)	0.0338** (0.0166)		-0.0032 (0.0035)	-0.0026 (0.0036)
Position \times Chain		-0.0053 (0.0041)	-0.0047 (0.0042)		-0.0023** (0.0010)	-0.0017 (0.0010)
Position \times Location score		-0.0071*** (0.0013)	-0.0083*** (0.0013)		-0.0002 (0.0003)	-0.0004 (0.0003)
Position \times On promotion		-0.0201*** (0.0048)	-0.0209*** (0.0049)		-0.0010 (0.0012)	-0.0010 (0.0013)
FE Hotel	no	no	yes	no	no	yes
N	1,220,917	1,220,917	1,219,253	1,220,917	1,220,917	1,219,253
R2 (adj.)	0.0149	0.0152	0.0267	0.0026	0.0026	-0.0019

Notes: A larger position means being displayed lower on the product list. Coefficient estimates are scaled to represent changes in terms of percentage points. Estimates for query characteristics and interaction of the squared position with other covariates are omitted. Standard errors are shown in parenthesis and are clustered at the query level. Star ratings are adjusted so that the position effect from the first row is for a hotel with 1 star and other characteristics equal to the minimum observed value.

that does not include the interaction term and, hence, assumes that position effects are homogeneous. Columns 2 and 5 show the main results. Notably, the interaction coefficient of price and position is positive and significant. This implies that cheaper hotels have stronger position effects on average and conditional on other attributes. For other characteristics, such as the star rating or the review score, the sign of the interaction term also opposes the sign of the direct effect of the characteristics. Hence, desirable attributes that lead to more clicks and bookings on average amplify position effects.

Figure 1 highlights that the resulting differences in position effects are sizable: they are in the error terms. A large draw in one alternative can mean that consumers are less likely to click on or book another alternative, suggesting a potential negative correlation in the error terms.




FIGURE 1 – Cheaper Hotels Have Stronger Position Effects

Notes: Position effects as defined in (3) and expressed in percentage points. Other characteristics are set to their respective average. The bars indicate 95% confidence intervals calculated from standard errors clustered on the session level.




FIGURE 2 – Hotel Attributes and Position Effects Complement Each Other

Notes: Position effects as defined in (3) and expressed in percentage points. Values in x_j are set to respective percentile, ordered based on the sign of coefficients in columns 2 and 5 in Table 2. The bars indicate 95% confidence intervals calculated from standard errors clustered on the session level.

increase by about 50% (CTR) or 100% (booking probability) when increasing the price from the 10th to the 90th percentile of the price distribution while keeping other attributes fixed at their respective mean.

Figure 2 shows that there are also sizable differences across different percentiles of the distribution of hotel characteristics x_j in the data. Whereas the estimated position effect for clicks is around 0.08 percentage points for a hotel at the 10th percentile, its magnitude doubles for a hotel at the median and more than triples for a hotel at the 90th percentile. Similarly, the position effect for bookings increases from close to zero to around 0.015 percentage points across these percentiles.

While the results so far show that desirable characteristics amplify position effects,




FIGURE 3 – Position Effects Vary across Hotels in the Data

Notes: Position effects defined in (3) at hotel attributes x_j as observed in the data.

they do not yet quantify the degree of heterogeneity in the data. Opposing effects from different attributes may offset each other such that the degree of heterogeneity across hotels observed in the data depends on the joint distribution of attributes. Figure 3 accounts for these potentially opposing effects by depicting the distribution of the estimated average position effects across the hotels in the data. It highlights that position effects differ substantially between hotels in the data. For clicks, the estimated position effects range from below -0.25 to above -0.1, indicating that position effects for some hotels are more than two to three times larger than those of other hotels. Similarly, the estimated position effects for bookings range from below -0.015 to above zero, again highlighting substantial heterogeneity. Though the positive position effects suggest that these hotels could have a demand increase when being moved further down the list, I attribute these few cases to the small size and less precision in coefficient estimates for bookings, as also indicated by the large standard errors reported in Table 2.

4.4 Robustness of Results

The experimental ranking variation ensures that a hotel’s position is exogenous. However, its price may not be. To address this endogeneity concern, Table 2 additionally reports estimates for a specification that adds fixed effects on a hotel level (columns 3 and 6).¹² The estimates overall are close to the baseline and confirm the results: desirable characteristics on average amplify position effects. Moreover, the price coefficient is close

¹²Several hotels are displayed only to a single consumer and therefore are excluded from this specification. Only price and whether the hotel is on promotion vary across different search sessions such that the coefficients in β_1 cannot be estimated for other characteristics. Nonetheless, the interaction between hotel characteristics and position can be estimated as it is identified by within-hotel variation of the position.

to the baseline, alleviating price endogeneity concerns.¹³

Appendix F.3 further shows that the results are also robust to using a Probit model and to a range of alternative specifications that treat position more flexibly.

Overall, these results highlight an important interaction of position effects with hotel characteristics: cheaper hotels have stronger position effects and, more broadly, hotel attributes and the position on the list complement each other. The resulting variation in position effects suggests that moving hotels with a lower price and other desirable attributes higher up on the list will increase the conversion rate on average, potentially increasing both revenues and consumer welfare. However, to what degree a revenue-maximizing ranking will utilize these demand effects depends on how strong they are relative to the price effect, which is not directly observable in the data. To quantify this trade-off and the effects of the different rankings on platform revenues and consumers, I now estimate a structural search model that micro-founds these heterogeneous position effects.

5 Model and Estimation Approach

To model how consumers interact with a ranked product list, I adapt the search and discovery (SD) model of Greminger (2022). In this model, utility-maximizing consumers sequentially decide between discovering products, searching among already-discovered alternatives, and ending their search by taking the best option found so far or the outside option. The resulting decision process closely matches how consumers interact with ranked product lists: they discover alternatives by scrolling down the list, reveal more information on an alternative by going to its detail page, and end their search by choosing an alternative or leaving the page.

5.1 The Empirical Search and Discovery Model

To be able to estimate the model, I implement the following empirical specification. Consumer i faces a ranked product list displaying a finite number of hotels $j \in J_i$ in positions $h_{ij} \in \{1, \dots, |J_i|\}$. When booking a hotel, the consumer receives utility

$$u_{ij} = -\alpha p_j + x_j' \beta + \nu_{ij} + \varepsilon_{ij} , \quad (4)$$

where p_j is the price of hotel j , x_j is a vector of hotel attributes observed in the data

¹³Ursu (2018) argues that with frequent pricing experiments on online travel agencies, there is little concern for price endogeneity. This is also in line with previous studies that used data from online travel agencies. Chen and Yao (2017) and De Los Santos and Koulayev (2017) use control function approaches to account for price endogeneity and find that it makes little difference.

(e.g., star rating), and α and β are the respective preference weights. $\nu_{ij} \sim N(\mu_\nu, \sigma_\nu^2)$ and $\varepsilon_{ij} \sim N(\mu_\varepsilon, \sigma_\varepsilon^2)$ are normally distributed idiosyncratic taste shocks that are independent across consumers and hotels. The utility of not booking any hotel, i.e., the outside option, is given by $u_{i0} = \beta_0 + \eta_i$, where η_i follows a standard uniform distribution. In estimation, I normalize $\mu_\nu = \mu_\varepsilon = 0$ and $\sigma_\nu = 1$ and set $\sigma_\varepsilon = 10$. I discuss the implications of and sensitivity to these assumptions in Section 5.5.

Initially, consumers know their preference weights α and β and the value of the outside option, but not the attributes and the taste shocks of hotels on the list. Instead, consumers reveal these values by sequentially deciding between scrolling down the list (discovering) and clicking on hotels to view their detail pages (searching). By scrolling down the product list, consumer i reveals (p_j, x_j, ν_{ij}) for the next hotel on the list.¹⁴ By searching j , i reveals the idiosyncratic taste shock ε_{ij} . I also impose two precedence constraints: consumers cannot search a hotel before discovering it and they cannot book a hotel before searching it.¹⁵ These constraints naturally apply in the present setting because Expedia does not allow booking hotels from the list, and it is not possible to click on a hotel listing that is not in view of the screen.

Both clicking and scrolling are costly actions. When scrolling to discover additional hotels, consumers incur discovery costs c_d . As I do not observe consumers not visiting Expedia and discovering at least the first hotel on the list, I assume that the first discovery is free.¹⁶ When clicking on a hotel on the list to search it, consumers incur search costs c_s . I further assume that there is free recall: going back and searching a previously discovered listing or booking a previously searched hotel does not add extra costs.

Consumers have beliefs about the joint distribution from which the hotel attributes and taste shocks are drawn. For the taste shocks ε_{ij} and ν_{ij} , I assume that consumers have rational expectations such that they know their distributions. For the joint distribution of hotel attributes, I assume that consumers believe that the pre-search expected utilities $u_j^e = -\alpha p_j + x_j' \beta$ are independent draws from a distribution that changes as they scroll down the list. I further impose three conditions on the shape of these beliefs. First, consumers believe that the variance of u_j^e does not depend on the position on the list.

¹⁴Expedia's website currently reveals one alternative at a time and also did so during the sample period (see online appendix C of Ursu, 2018). Moreover, Appendix C provides results of a specification where consumers discover three alternatives with each discovery, highlighting that such a specification fits the data worse.

¹⁵Greminger (2022) highlights that these constraints are necessary to obtain a reservation-value-based optimal policy.

¹⁶Expedia initially reveals up to three alternatives, depending on the screen size. However, assuming that consumers discover the first three alternatives for free leads to a worse model fit, as I show in Appendix C.

Second, consumers have rational expectations for the attribute distribution in the middle of the list. Finally, consumers believe that the mean of u_j^e depends on the position h in the following form:

$$\mu_u(h) = \mu_u(1) - \exp(\rho) \log(h + 1) . \quad (5)$$

These assumptions imply that consumers' beliefs about the ranking algorithm are fully captured by $\mu_u(1)$ and ρ . Hence, I can recover these beliefs from the data by estimating the respective parameters instead of imposing that consumers know the ranking algorithm. Whereas the functional form implies that consumers cannot expect alternatives to improve as they scroll down the list, this does not restrict the estimation in the present case. If $\mu_u(h)$ instead were increasing in h , the model would be inconsistent with the data, as I show in Section 5.3. Hence, if the model instead would be estimated without this restriction, the estimates would remain the same. Besides, the imposed functional form allows the model to fit the non-linear decrease in clicks across positions, as opposed to a linear functional form (see Appendix C).

5.2 Optimal Policy

Consumers maximize their expected utility by sequentially choosing one of the available actions. Greminger (2022) proves that the optimal policy for this dynamic decision process is fully characterized by the following simple decision rule: in each period, choose the available action with the largest reservation value.

These reservation values are defined by the value of a hypothetical outside option that sets the myopic net benefit of taking the respective action over immediately taking the hypothetical outside option to zero. Crucially, the myopic net gain does not depend on any other available alternatives or the availability of future discoveries. Hence, the reservation value for an action can be obtained in isolation from other actions and without having to consider myriad future periods. In my empirical specification, the reservation values for the three different actions are given by:¹⁷

Purchase value: $z_{ij}^p = u_{ij} = -\alpha p_j + x_j' \beta + \nu_{ij} + \varepsilon_{ij}$.

Search value: $z_{ij}^s = -\alpha p_j + x_j' \beta + \nu_{ij} + \xi$, where ξ solves

$$\int_{\xi}^{\infty} [1 - F(t)] dt = c_s \quad (6)$$

and F is the CDF of ε_{ij} . For the outside option, the search value is given by $z_{i0} = \infty$.

Discovery value: $z^d(h) = \mu_u(h) + \Xi$, where Ξ solves

¹⁷Greminger (2022) provides details of how to derive these reservation values in the online appendix.

$$\int_{\Xi}^{\infty} [1 - G(t)] dt = c_d \quad (7)$$

and G is the CDF of $U_j^e - \mu_u(h) + \nu_{ij} + \min\{\xi, \varepsilon_{ij}\}$ implied by consumers' beliefs.

To operationalize the optimal policy and show how it determines which alternatives consumers discover, which ones they search and which options they eventually choose, I additionally introduce *effective values*. These effective values combine the different reservation values and fully characterize which alternative a consumer eventually chooses (Greminger, 2022). The effective values of an option j are given by $w_{ij} = \min\{z^d(h_{ij} - 1), \tilde{w}_{ij}\}$ and $\tilde{w}_{ij} = \min\{z_{ij}^s, z_{ij}^p\}$, where the second one does not depend on the position. For the outside option, the effective values are given by $w_{i0} = \tilde{w}_{i0} = u_{i0}$.

Using these effective values, I can summarize the optimal policy in four implications. Specifically, given effective values w_{ij} and \tilde{w}_{ij} of the chosen option j , the optimal policy of always choosing the action with the largest reservation value implies the following for a consumer i who eventually chooses j :

Stopping: i discovers all alternatives $k \in A_i(\tilde{w}_{ij})$, where the awareness set $A_i(\tilde{w}_{ij}) = \{k : h_{ik} \leq \bar{h}_i, \bar{h}_i \geq h_j, z^d(\bar{h}_i - 1) \geq \tilde{w}_{ij} > z^d(\bar{h}_i)\}$ implicitly defines the position \bar{h}_i at which i stops discovering.

Search and early discovery: i searches all alternatives in $S_{i-} = \{k : z_{ik} \geq w_{ij}, k \in A_i(\tilde{w}_{ij}), h_{ik} < h_{ij}\}$ and no other alternatives.

Search and late discovery: i searches all alternatives in $S_{i+} = \{k : z_{ik} \geq \tilde{w}_{ij}, k \in A_i(\tilde{w}_{ij}), h_{ik} \geq h_{ij}\}$ and no other alternatives.

Choice: i chooses $j \in S_{i-} \cup S_{i+} \cup \{0\}$ if $u_{ik} < w_{ij} \forall k \in S_{i-}$ and $u_{ik} \leq \tilde{w}_{ij} \forall k \in S_{i+} \cup \{0\}$.

The stopping implication highlights that the effective value of the chosen alternative determines how many alternatives the consumer will discover. The two search implications show how the alternatives' search values determine whether the consumer will search them given that they were discovered either before or after j . Finally, the choice implication highlights the conditions that guarantee that, given its effective value and the searched products in the two sets, the consumer also chooses j . Appendix A.1 shows how these implications follow from the optimal policy.

5.3 Heterogeneous Position Effects in the SD Model

Using these implications, I now show how the SD model generates heterogeneous position effects consistent with those observed in the data. To this end, I expand the analysis

of Greminger (2022) and derive short-term position effects conditional on observable attributes. I focus on short-term position effects where consumers do not adjust their beliefs because (i) it is unlikely that consumers adjust beliefs to switching only two alternatives, as opposed to the whole ranking; (ii) I follow the literature in constructing rankings for short-term objectives where only these short-term position effects are considered (see Section 6.3); and (iii), it will allow showing how parameters are identified in the data conditional on consumers' beliefs.¹⁸

I define the position effect for an alternative j as the change in demand when switching the position with the alternative right above it. Formally, this position effect is given by $\Delta d_j(h) = d_j(h) - d_j(h+1)$, where $d_j(h)$ denotes the expected demand of alternative j when in position h , conditional on all observable hotel attributes and the ranking. Similarly, I define the position effect for searches as $\Delta s_j(h)$, where $s_j(h)$ denotes the expected number of clicks for alternative j in position h . To simplify exposition, let $\bar{w}_h = \max_{k \in \{k: h_k \leq h\}} w_k$ denote the maximum effective value of alternatives in positions up to h , and let $z^d(0) = \infty$ such that the bounds are properly defined.

Lemma 1, proven in Appendix A.2, provides expressions for these short-term position effects. The result reveals that position effects in the SD model directly result from differences in the probability that consumers reach specific positions, as implied by the stopping implication. In other words, the SD model explains position effects through consumers deciding to stop discovering alternatives without seeing the alternatives further down the list.

Lemma 1. *Conditional on the observable attributes and consumers' beliefs, the position effect for the demand of an alternative B switching with alternative A on the previous position is given by*

$$\Delta d_B(h) = \mathbb{P}(\bar{W}_{i,h-1} \in (z^d(h), z^d(h-1)]) \mathbb{P}(\tilde{W}_{iB} > \bar{W}_{i,h-1} | \bar{W}_{i,h-1} \in (z^d(h), z^d(h-1)]) + \mathbb{P}(\bar{W}_{i,h-1} \leq z^d(h)) \mathbb{P}(\tilde{W}_{iB} > z^d(h)) \mathbb{P}(\tilde{W}_{iA} > z^d(h)) . \quad (8)$$

¹⁸Whereas the mechanism of how position effects generally arise in the model remains the same, Proposition 1 may not always hold when consumers adjust beliefs. Specifically, if consumers adjust their mean belief $\mu_u(h)$ so that they are more likely to continue scrolling when a high-utility hotel is moved down the list, high-utility hotels can have weaker position effects in the model. However, these belief adjustments would need to be very large for this to occur, given that the variance also determines the discovery values. As such large belief adjustments are unlikely to occur when only two alternatives are switched, and because I focus on short-term rankings, I leave it for future research to determine the conditions under which this occurs.

Similarly, the position effect in searches is given by

$$\Delta s_B(h) = \mathbb{P}(\bar{W}_{i,h-1} \in (z^d(h), z^d(h-1)]) \mathbb{P}(Z_{iB}^s > \bar{W}_{i,h-1} | \bar{W}_{i,h-1} \in (z^d(h), z^d(h-1)]) + \mathbb{P}(\bar{W}_{i,h-1} \leq z^d(h)) \mathbb{P}(Z_{iB}^s > z^d(h)) \mathbb{P}(\tilde{W}_{iA} > z^d(h)) . \quad (9)$$

The different parts in the expressions reveal multiple channels through which consumers not discovering all alternatives helps an alternative gain demand when being moved higher on the list. The first part in (8) shows that when consumers reach position h but do not discover beyond it, B gains demand by potentially becoming the best alternative within the ones discovered before the search ends. The second part of the expression captures the case where $\bar{W}_{i,h-1} \leq z^d(h)$ such that consumers will discover beyond h , unless the alternative in h is so good that it induces consumers to stop. In this case, B gains through two channels. First, moving to h , B can induce some consumers to stop before discovering A , which happens with probability $\mathbb{P}(\tilde{W}_{iB} > z^d(h))$. Second, B can also avoid that consumers stop and choose A when it is shown on h , which happens with probability $\mathbb{P}(\tilde{W}_{iA} > z^d(h))$.

To show how this mechanism generates position effects that match the data in how they depend on product attributes, I first focus on the case with only two products. For this case, Lemma 1 implies that

$$\Delta d_B - \Delta d_A = \mathbb{P}(U_{i0} > z^d(1)) [\mathbb{P}(\tilde{W}_{iB} > U_{i0} | U_{i0} > z^d(1)) - \mathbb{P}(\tilde{W}_{iA} > U_{i0} | U_{i0} > z^d(1))] . \quad (10)$$

As the dependency on $\mathbb{P}(U_{i0} > z^d(1))$ highlights, the model generates heterogeneous position effects only when some consumers never discover the second alternative, independent of which one is shown on the first position. This happens because as long as consumers who would only buy B (but not A) continue to discover B in the second position, moving B to the first position increases its demand only by taking it away from A . However, if the same consumers do not discover B on the second position and leave the list without buying an alternative, then moving B to the first position helps these consumers discover and buy B , such that B can have a stronger position effect.

These position effects depend on a product's attributes through the probability of choosing it over the outside option, $\mathbb{P}(\tilde{W}_{ij} > U_{i0})$. Because high-utility alternatives are more likely to be chosen over the outside option, they gain relatively more demand from the share of consumers who otherwise would have stopped scrolling before discovering it. As a result, position effects increase in any attribute k that increases the pre-search

utility such as, for example, a low price.

This result generalizes to the case with more than two alternatives, as proven in Appendix A.2 and summarized in Proposition 1. Hence, attributes that increase the pre-search utility amplify position effects. Combined with the fact that the model also predicts that a higher pre-search utility leads to more searches and clicks, this implies that the model predicts heterogeneous position effects that match the pattern highlighted in the descriptive evidence: alternatives with desirable attributes that increase clicks and purchases have stronger position effects.

Proposition 1. *Position effects increase in the expected pre-search utility u_B^e of the alternative being moved up.*

The analysis so far shows that the SD model produces position effects through consumers deciding to stop discovering. However, this decision is based on their beliefs, where I imposed the assumption that consumers expect to discover worse alternatives further down the list. If consumers instead expected to discover better alternatives down the list, the model-implied position effects would be different and contrast the data. This is highlighted in Proposition 2, which follows from the fact that when consumers expect to discover better and better alternatives as they go down the list, they will not stop discovering until they either buy an alternative or reach the end of the list. Hence, consumers who do not buy an alternative will discover the whole list, so there will be no position effects for these consumers. This prediction sharply contrasts the data which reveals sizable position effects in clicks for consumers who do not book a hotel, i.e., the vast majority of consumers in the data.¹⁹ Hence, the data is inconsistent with consumers expecting to discover better alternatives further down the list.

Proposition 2. *If $\mu_u(h)$ weakly increases in h and the ranking is randomized, there are no position effects in searches for consumers who take the outside option.*

Proposition 2 also provides some insight into whether consumers updated their beliefs when faced with the randomized ranking during the experiment. If consumers fully adjusted their beliefs to the randomized ranking, $\mu_u(h)$ would be constant such that there should be no position effects in clicks for consumers who do not book a hotel. As I do observe such position effects, I conclude that the consumers in the data do not search in a way consistent with such a belief adjustment.

¹⁹Focusing only on sessions ending without booking a hotel also leads to strong position effects in the CTR.

5.4 Estimation Approach

The goal of the estimation is to recover the model parameters $\theta = (\alpha, \beta, c_s, c_d, \rho)$ given data for N consumers. The data for each consumer i contain the chosen alternative j ; the consideration set S_i tracking the alternatives the consumer clicked on; and the positions h_{ij} , attributes x_{ij} and prices p_j for all alternatives in J_i , the set of products on the consumer's product list. Given these data, the estimation procedure solves

$$\max_{\theta} \mathcal{L}(\theta) = \max_{\theta} \sum_{i=1}^N \log \mathbb{P}(\text{click all } k \in S_i, \text{ choose } j \in S_i | (p_j, x_j, h_{ij}) \forall j \in J_i; \theta) . \quad (11)$$

The relevant probability depends on the parameters gathered in θ and conditions on the hotel attributes and the ranking observed in the data. To simplify exposition, I omit highlighting this dependence in the remainder of this section.

5.4.1 Likelihood Contributions

The likelihood contribution of a consumer i is given by the probability of the observed choices under the optimal policy. This probability follows from the four implications of the optimal policy because they fully characterize a consumer's choice conditional on the chosen alternative's effective value. Specifically, given an effective value \tilde{w}_{ij} for the chosen option j , the four implications specify how many alternatives a consumer discovers (stopping), which alternatives she searches conditional on discovery (search and early&late discovery), and under which conditions i chooses j out of the consideration set S_i (choice). As a result, the individual likelihood contribution $\mathcal{L}_i(\theta)$ can be calculated by taking expectations over the shocks determining the effective value \tilde{w}_{ij} of the chosen option j and computing the probability of the inequalities implied by the four implications holding. More formally, the individual likelihood contribution of a consumer who eventually chooses j is given by

$$\begin{aligned} \mathcal{L}_i(\theta) = \log \int & \underbrace{1(k \in A(\tilde{w}_{ij}) \forall k \in S_i)}_{\text{Stopping}} \times \\ & \underbrace{\prod_{k \in S_i \cup \{0\}} \mathbb{P}(Z_{ik}^s \geq w_{ij} \cap U_{ik} \leq w_{ij})}_{\text{Search and early discovery \& choice}} \times \underbrace{\prod_{k \in S_{i+}} \mathbb{P}(Z_{ik}^s \geq \tilde{w}_{ij} \cap U_{ik} \leq \tilde{w}_{ij})}_{\text{Search and late discovery \& choice}} \times \\ & \underbrace{\prod_{k \in A(\tilde{w}_{ij}) \setminus S_i} \mathbb{P}(Z_{ik}^s \leq \tilde{w}_{ij})}_{\text{Search and early\&late discovery}} dH(\eta_i, \nu_{ij}, \varepsilon_{ij}) , \quad (12) \end{aligned}$$

where $H(\eta_i, \nu_{ij}, \varepsilon_{ij})$ is the joint CDF of the shocks that form the effective values \tilde{w}_{ij} w_{ij} ,

and the utility u_{ij} of the chosen option.²⁰ $1(\cdot)$ denotes the indicator function, implemented in the expression to reflect that the consumer cannot have stopped scrolling before having discovered all alternatives she clicked on. Moreover, $S_{i-} = \{k : k \in S_i, h_{ik} < h_{ij}\}$ is the set of clicked alternatives discovered before j and S_{i+} is the set of clicked alternatives discovered after j . The outside option enters the likelihood through the union with S_{i-} , where $z_{i0} > w_{ij}$ holds by definition.

5.4.2 Smooth Monte Carlo Integration

Calculating the likelihood contribution (12) poses two challenges. First, it requires calculating a probability of the form $\mathbb{P}(Z_{ik}^s \geq q \cap U_{ik} \leq q)$, where q is some constant. In general, computing this probability would require using a numerical integration routine because Z_{ij}^s is not independent of U_{ij} . However, Proposition 3 decomposes $\mathbb{P}(Z_{ik}^s \geq q \cap U_{ik} \leq q)$ into the CDF of a standard normal distribution and the CDF of a bivariate normal distribution under the imposed normalizations. As these functions can be computed using standard numerical methods,²¹ the proposition allows me to compute this part of the likelihood without a computationally costly numerical integration routine.

Proposition 3. *If $\mu_\nu = \mu_\varepsilon = 0$ and $\sigma_\nu = 1$,*

$$\mathbb{P}(Z_{ik}^s \geq q \cap U_{ik} \leq q) = \mathbb{P}\left(R \leq \frac{q - u_k^e}{\tilde{\sigma}}\right) - \mathbb{P}\left(R_1 \leq \frac{q - u_k^e}{\tilde{\sigma}} \cap R_2 \leq q - \xi - u_k^e\right), \quad (13)$$

where R follows a standard normal distribution, (R_1, R_2) follow a bivariate normal distribution with correlation $-\frac{1}{\tilde{\sigma}\sigma_\varepsilon}$, and $\tilde{\sigma} = \sqrt{1 + \frac{1}{\sigma_\varepsilon^2}}$.

The second challenge arises because there is no closed-form expression for the integral over the joint distribution of the different shocks in $\mathcal{L}_i(\theta)$. Hence, computing the expression requires Monte Carlo integration. A naive procedure might work by averaging the inner probability across draws η_i^d or $(\nu_{ij}^d, \varepsilon_{ij}^d)$ from the respective distributions. However, such a procedure would lead to a non-smooth likelihood function, making it difficult to solve (11) numerically. Specifically, the awareness set $A(\tilde{w}_{ij}^d)$ depends on the draws through the inequality $z^d(\bar{h}_i - 1) \geq \tilde{w}_{ij}^d > z^d(\bar{h}_i)$. As a result, small changes in the parameters will leave these inequalities unaffected such that $\mathcal{L}_i(\theta)$ is non-smooth. Moreover, the effective value \tilde{w}_{ij}^d for a consumer who eventually chooses j also depends on the term $\min\{\xi, \varepsilon_{ij}^d\}$, which is non-smooth in ξ and, as a result, in c_s .

²⁰The independence of the shocks implies that if $j = 0$, only η_i enters the CDF, whereas if $j > 0$, η_i does not enter it.

²¹To calculate the bivariate normal CDF, I use the method by Drezner and Wesolowsky (1990) as implemented in the Julia StatsFuns.jl package.

I circumvent these issues and develop a simulation procedure yielding a smooth likelihood function. First, I use the stopping implication to partition the real line into intervals so that $A_i(\tilde{w}_{ij}^d)$ is fixed for all draws \tilde{w}_{ij}^d within a given interval. Second, I partition on $\varepsilon_{ij} \geq \xi$ so that $\min\{\xi, \varepsilon_{ij}^d\}$ is either ε_{ij}^d or ξ within the respective intervals. I then use a procedure similar to the well-known GHK simulator for the Probit model to take draws that fall in each probability region defined by this partitioning: first, draw ε_{ij}^d from a distribution truncated at ξ , then draw ν_{ij}^d from a distribution truncated so that \tilde{w}_{ij}^d falls within the respective interval that keeps $A_i(\tilde{w}_{ij}^d)$ fixed. As $\tilde{w}_{i0} = u_{i0}$ when the consumer takes the outside option, the simulation procedure simplifies for this case and only requires drawing η_i^d so that \tilde{w}_{i0}^d falls in the respective interval. Appendix B.1 provides further details on this procedure.

Beyond leading to a smooth likelihood function, partitioning the probability space also has the advantage of focusing on positive probabilities, providing higher accuracy at fewer draws. Specifically, for any draw that does not satisfy that consumers only clicked on alternatives that they also discovered, $1(k \in A(\tilde{w}_{ij}^d) \forall k \in S_i) = 0$ such that the likelihood is zero. By ignoring any intervals where this condition is not satisfied, the procedure only takes draws that produce the observed searches with positive probability.²²

5.5 Identification and Normalizations

The exogenous ranking variation allows me to identify the mean utility parameters α , β , and β_0 and search costs c_s separately from the discovery parameters c_d and ρ . I first provide the identification argument for the mean utility parameters and search costs conditional on how many alternatives consumers discover and then show how the discovery parameters are identified by the observed position effects.

Conditional on discovery, the model simplifies to a Weitzman directed search model such that the same identification arguments apply for the mean preference parameters and the search costs (see, e.g., Ursu, 2018; Ursu et al., 2023). The mean utility parameters α and β are identified by the correlation between hotel characteristics and the associated click and booking frequency. For example, with a smaller price coefficient, consumers click on and book more expensive hotels on average. β_0 is identified by the baseline purchase probability conditional on clicking. If consumers are likely to buy alternatives conditional on having searched them, β_0 must be small given the distribution of ε_{ij} . Search costs c_s are identified by the number of clicks consumers make; given the distribution of ε_{ij} , a small

²²If the data additionally contained information on how far consumers scrolled, this could be implemented in the same way, discarding all but the one relevant intervals where $A(\tilde{w}_{ij}^d)$ equals the observed awareness set, creating an even more efficient procedure.

c_s implies larger search values z_{ik}^s through (6), which, in turn, implies that consumers are more likely to search alternatives.

The discovery parameters c_d and ρ are identified by the position effects observed in the data. Hence, when position effects are identified by experimental ranking variation, it is sufficient to observe at which positions clicks and bookings occur to identify the discovery parameters. Notably, this allows identifying the discovery parameters without the need for data tracking how many alternatives consumers discover.

To show this more formally, I now focus on consumers who take the outside option. For across these consumers, the expected difference in clicks across two positions can be written as

$$\mathbb{E}[\Delta s_j(h)] = \begin{cases} (1 + \beta_0 - z^d(1))\mathbb{P}(Z_{ih}^s > U_{i0} | U_{i0} \geq z^d(1)) & \text{if } h = 1 \\ \exp(\rho) \log(\frac{h+1}{h})\mathbb{P}(Z_{ih}^s > U_{i0} | U_{i0} \in (z^d(h), z^d(\bar{h} - 1)]) & \text{else} \\ (z^d(1) - \beta_0 - \exp(\rho) \log(\bar{h} + 1))\mathbb{P}(Z_{ih}^s > U_{i0} | U_{i0} \geq z^d(\bar{h})) & \text{if } h = \bar{h} - 1, \end{cases} \quad (14)$$

where \bar{h} denotes the last position on the list. The expectation operator integrates over hotels j on position h such that the expression follows from Lemma 1 and the fact that the ranking is randomized (see Appendix D.1).

Whereas c_d does not appear in (14), it is identified as long as $z^d(1)$ is identified. This is because the beliefs in (5) imply that the discovery value is given by $z^d(h) = z^d(1) - \exp(\rho) \log(h + 1)$ such that c_d only affects $z^d(1)$ and, hence, enters the likelihood only through this term. Moreover, the definition of the discovery value given in (7) provides a unique $z^d(1)$ for any $c_d \geq 0$. It also implies that $z^d(1)$ is decreasing in c_d (see EC.1 in Greminger, 2022). Hence, to show that c_d is identified, it is only necessary to show that $z^d(1)$ is identified.

The first case in (14) reveals how $z^d(1)$ is identified given β_0 . If the position effect on the first position is large, the initial discovery value must be small so that few consumers discover the second position. The third case shows that the position effect on the last position further helps identify $z^d(1)$ given ρ . If it is small, $z^d(1)$ must be small so that few consumers reach the second-to-last position. Hence, $z^d(1)$ and, as a result, c_d are identified given β_0 and ρ .

The belief parameter ρ is identified by the observed differences in the number of clicks across positions beyond the first one, as highlighted by the second and third cases in (14). These expressions use the functional form from (5) that determines how consumers perceive the ranking. If it were instead a linear specification, the log terms would equal one such that the change in the position effect across positions would only depend on the

second part of the expression. In that sense, assuming a functional form for consumers' beliefs (5) is akin to imposing a functional form for how search costs depend on the position on the list, as is common for directed search models. Nonetheless, to analyze the sensitivity to this functional form, I also estimate a model where $z^d(h)$ linearly depends on h . The results are provided in Appendix C and show that this alternative functional form effectively leads to position effects that are linear and, hence, do not fit the non-linear decrease in clicks observed in the data.

5.5.1 Recovering Consumers' Beliefs

Computing $z^d(h)$ from c_d through (7) requires knowing the consumers' beliefs over the distribution of effective values. Given the preference parameters α and β and the modeling assumptions, I can recover these beliefs from the data. Specifically, my assumptions imply that consumers believe that the hotel they will discover in the middle of the list is a random draw from the joint distribution of hotel attributes. Hence, I can recover these beliefs by sampling from the empirical joint distribution of hotel attributes without having to impose parametric restrictions. Given the beliefs at the middle of the list, I then obtain the beliefs at other positions through $\mu(h)$ defined in (5).²³ Appendix D.3 provides further details.

5.5.2 Parameterizing Discovery and Search values

Using the above procedure to recover beliefs and then computing $z^d(h)$ during estimation is computationally costly because it requires numerically finding a root.²⁴ I circumvent this computationally costly step by estimating a parameter $\Xi = z^d(1)$ instead of c_d and backing out c_d only post-estimation. This approach works because c_d and consumers' beliefs about the average alternative enter the likelihood only through $z^d(1)$. Hence, with an estimate for $\Xi = z^d(1)$, c_d can be computed after recovering consumers' beliefs. Barring small numerical differences that might arise from using a numerical optimizer, the resulting estimate for c_d will be the same as an estimate obtained by directly estimating c_d and computing $z^d(1)$ during estimation.

I also apply the same technique to the search costs. Instead of estimating a parameter c_s , I estimate ξ in (6) and back out c_s post-estimation. This approach again has the advantage of not having to numerically solve for a root during estimation, as also highlighted by Morozov (2023).

²³Gibbard (2022b) imposes similar restrictions on beliefs. However, my approach differs in that I do not need to impose parametric restrictions on the joint distribution of attributes.

²⁴An exception is the case where search values are normally distributed, as described in the replication package to Greminger (2022).

5.5.3 Distributions of the Idiosyncratic Shocks

The three expressions in (14) are derived using the assumption that η_i in the outside option follows a standard uniform distribution. Hence, similar to the functional form assumption on consumers' beliefs, assuming a specific distribution of the outside option directly impacts the position effects and how they change across positions. Such an assumption is not particular to this model; virtually all empirical search models that include an outside option impose a distribution on the outside option. In the present model, I assume a standard uniform distribution because it (i) allows to highlight better the implications of the functional form (5) on the shape of position effects in (9), (ii) allows the model to fit the data well as shown below, and (iii) is fast to take truncated draws from.

Whereas using a bounded distribution such as the uniform distribution might seem restrictive, the results from the model are not sensitive to using alternative bounds. The lower bound on u_0 is given by β_0 and, hence, is estimated. The upper bound is not estimated, but still has little influence, as I show in Appendix C. The reason is that increasing the upper bound on the distribution of the outside option mainly leads to predicting a larger share of consumers who will not click on any alternative. As this moment is not observed in the present data and because I condition the likelihood and model results on consumers searching at least one hotel, changes in this moment have little to no effect on model fit or my counterfactual results.²⁵

In estimation, I normalize $\mu_\nu = \mu_\varepsilon = 0$ and $\sigma_\nu = 1$. In this, I follow Ursu et al. (2023) who show that σ_ν scales all relevant parameters in a Weitzman model. Conditional on discovery, the present model effectively simplifies to a Weitzman model so that their arguments also apply in the SD model.²⁶ I also set $\sigma_\varepsilon = 10$ in estimation, which is not a normalization. As I show in Appendix C, the estimated search costs and the predicted consumer welfare effects in dollar terms are very sensitive to the choice of σ_ε . In contrast, the consumer welfare effects measured in percentage terms, the estimated discovery costs, and the model's ability to fit the data are not very sensitive to the choice of σ_ε , as long as it is set sufficiently large. The reason for this insensitivity is that the estimates for preference parameters β and the differences $\xi - \beta_0$ and $\Xi - \beta_0$ remain almost the same

²⁵If instead the number of consumers who do not click on any alternative were observed, this upper bound could be estimated.

²⁶The likelihood averages over the different potential discovery sets determined by the discovery value. However, the discovery value implicitly depends on the distribution of ν_{ij} ; a larger σ_ν increases the chance of finding a good match, making discovering more attractive. By directly estimating the discovery value (see Section 5.5.2), σ_ν does not affect discovery in the likelihood such that the derivations of Ursu et al. (2023) directly apply.

once σ_ε is set to be large enough. This means that while the estimate for c_s depends on σ_ε , the net benefits of the different search actions over immediately taking the outside option, which ultimately affect consumers' choices, remain unaffected by σ_ε as long as it is sufficiently large. Given these results, I set $\sigma_\varepsilon = 10$ for the main analysis and refrain from reporting search costs and consumer welfare effects in dollar terms.

5.5.4 Monte Carlo Simulation

I perform a Monte Carlo simulation exercise to confirm that parameters can be identified with the present data. I first generate two datasets by simulating searches and purchases for different parameter values and then verify whether the estimation procedure can recover these parameter values. For the observable hotel characteristics and positions, I use the estimation sample described below so that the variation in hotel characteristics across positions is the same as in the model estimation. Appendix B.3 presents the results, highlighting that the estimation procedure precisely recovers all parameters, including the discovery and search costs that are backed out post-estimation.

5.6 Estimation Sample

To estimate the model, I restrict the sample to the fifty largest destinations. Moreover, following Ursu (2018), I only include sessions with at least 30 hotel listings in the results, the most commonly observed case across destinations, and omit opaque offers from the analysis. The resulting estimation sample captures typical search sessions for the most popular destinations and consists of 18,541 sessions with an average of 1.13 clicks per session and a conversion rate of 5.56%.

Given that the data only contains sessions with at least one click, I further follow Compiani et al. (2023) to account for this selection. Specifically, I condition each likelihood contribution on the event that the consumer searches at least one hotel. This adjustment can be done by dividing the likelihood contribution of i by the likelihood of i making at least one click, which can be readily obtained because it is the complement to a consumer making no clicks. Moreover, given the selection, I also focus on fit and consumer welfare measures conditional on consumers searching at least one alternative.²⁷

²⁷Not accounting for the sample selection would lead to underpredicting the number of clicks compared to the ones observed in the data. This is because the estimated model predicts a large share of consumers not clicking on any listing, which are excluded in the data.

5.7 Relation to Directed and Other Search Models

The SD model I estimate has several features that make it particularly useful to quantify the effects of different rankings. Specifically, the SD model extends directed search models *à la* Weitzman (1979) in three important ways. First, the SD model micro-founds position effects by modeling scrolling, the additional costly action required to reach the lower positions. A directed search model instead produces position effects through differences in position-specific search costs without a mechanism producing these cost differences. Second, the SD model does not impose the assumption that consumers are aware of and can directly search any alternative at the beginning of the search. As Greminger (2022) shows in simulations, using such an assumption can bias estimates for preference and search cost parameters when it does not hold, as is the case when consumers initially only observe the top of the list.²⁸ Finally, by explicitly modeling consumers’ beliefs about the ranking, the SD model allows quantifying the effects of ranking changes when consumers update their beliefs.

Nonetheless, I also highlight that my estimation approach also works to estimate directed search models, where it has the advantage of not requiring choosing a smoothing parameter or observing the search order. Specifically, by assuming that consumers initially are aware of all alternatives, the likelihood contribution reduces to

$$\mathcal{L}_i^W(\theta) = \log \int \prod_{k \in S_i} \mathbb{P}(Z_{ik}^s \geq \tilde{w}_{ij} \cap U_{ik} \leq \tilde{w}_{ij}) \prod_{k \notin S_i} \mathbb{P}(Z_{ik}^s \leq \tilde{w}_{ij}) dH(\eta_i, \nu_{ij}, \varepsilon_{ij}) , \quad (15)$$

which can be calculated using the same simulation procedure described in Section 5.4.

The SD model also provides some advantages over “top-down” and “two-stage” sequential search models. Specifically, whereas the “top-down” search models estimated by Chan and Park (2015) and Choi and Mela (2019) also capture position effects through consumers deciding to stop scrolling, they preclude consumers from going back up on the list and require reduced-form approximations or value function iterations to solve a consumer’s dynamic decision problem. The SD model instead does not impose such an assumption and features a tractable optimal policy. More recently, Gibbard (2022b) estimates the “two-stage” directed search model of Gibbard (2022a), without considering the consumer welfare effects of different rankings or heterogeneous position effects. That

²⁸This provides one possible explanation of why Compiani et al. (2023) finds that revenue-maximizing rankings harm consumers using the same data. However, Compiani et al. (2023) also extend directed search models by allowing some products to provide positive surprises post-search. To conclusively evaluate where the difference stems from, future work may incorporate post-search surprises into the SD model.

model produces position effects by consumers stopping to “browse”, a second stage in a directed search model. This differs from the SD model in that consumers decide on the order to browse alternatives instead of scrolling down and discovering products along a ranked product list.²⁹

6 Estimation Results and Counterfactual Analysis

I estimate the model using $n_r = 100$ simulation draws. Table 3 reports the parameter estimates. All preference parameters have the expected sign and are statistically significant, except whether the hotel belongs to a chain.

The estimated discovery costs suggest that consumers would be willing to pay 7¢ to reveal an additional alternative. These seemingly small discovery costs are sufficient to rationalize the observed position effects. The model correctly captures that it is unlikely that the next discovery will reveal a hotel that is so good that it will be eventually booked. Hence, the implied expected benefits of discovering an additional hotel on the list are small and consumers are unwilling to pay even small discovery costs to continue scrolling.³⁰ As a result, these small discovery costs do not imply that product discovery is not relevant when studying how rankings affect consumers or the platform: as long as consumers do not discover all alternatives, rankings will influence which alternatives consumers eventually choose by determining which ones they discover, independent of whether consumers stop discovering due to low expected benefits or high discovery costs.

6.1 The Model Fits the Data Well

To evaluate how well the model fits the data, I simulate clicks and bookings from the model and compare them with those observed in the data. The results in Figure 4 reveal that the model fits the data well, closely matching the number of bookings and clicks across all positions. Notably, the model fits the decrease in clicks and bookings across positions, highlighting that the small discovery costs are sufficient to rationalize the observed position effects. Appendix B.4 reports additional fit measures that highlight that the model also predicts various other moments well.

²⁹The SD model can also be adapted so that consumers learn about the distribution of products that will be discovered, which the two-stage model of Gibbard (2022a) does not allow for. Moreover, Gibbard (2022b) describes the estimation approach for consumers with a purchase for only up to three clicks, requiring the author to exclude sessions with a purchase and more than three clicks. In contrast, my approach does not impose such a limit and does not become more complex as the number of clicks by consumers who buy a product grows.

³⁰As I highlight in Section 5.5, the estimates for c_s are highly depend on the choice of σ_ε , while estimates for c_d depend little on this choice. Hence, the relative size of the costs should not be directly compared.

TABLE 3 – Parameter Estimates

	Estimate	Std. error
Price (in 100\$)	-0.24***	(0.01)
Star rating	0.21***	(0.01)
Review score	0.03***	(0.01)
No reviews	0.10***	(0.04)
Location score	0.07***	(0.00)
Chain	-0.02	(0.01)
Promotion	0.09***	(0.01)
Outside option	19.88***	(0.19)
Ξ	20.26***	(0.19)
ξ	16.91***	(0.19)
ρ	-2.48***	(0.06)
Discovery costs (\$)	0.07	
$c_d \times 100$	0.02	
c_s	0.19	
Log likelihood	-48,924.64	
N consumers	11,467	

Notes: Estimation based on 100 simulation draws. Asymptotic standard errors in parentheses. Discovery costs are calculated using 100,000 draws of effective values.

As the motivating example revealed, how revenue-maximizing rankings order alternatives and affect consumers depends on how position effects differ across the heterogeneous alternatives. Hence, for the validity of the counterfactual analysis, the model should be able to fit how an alternative’s position effect depends on its price and other attributes. To analyze whether this is the case, I first simulate clicks and bookings and then run the same analysis from Section 4.3 on these simulated data.

Figure 5 presents the results of this analysis.³¹ The top panel shows that the model generates position effects across the different percentiles of the price distribution that match those in the data remarkably well. The bottom panel shows that the same also holds across the attribute distribution, again closely matching the magnitudes observed in the data.

Given these results, I conclude that the model fits the data well, including the moments that are crucial for the counterfactual analysis.

6.2 Demand and Price Effects

To compare the demand and price effects implied by the model, I now use the model to predict hotels’ revenue changes when moving them to higher positions. As the predicted booking probabilities for each hotel are very small, this analysis requires a precise

³¹The overall magnitude of position effects differs from those in Figure 2 due to the different sample.




FIGURE 4 – The Model Fits Observed Clicks and Bookings across Positions
Notes: Clicks and bookings averaged across 20,000 draws per consumer, conditional on consumers searching at least one hotel. The shaded areas indicate the 95% percentile of the minimum and maximum number of clicks or bookings across draws and consumers.




FIGURE 5 – The Model Captures Heterogeneous Position Effects
Notes: Heterogeneous position effects for clicks and bookings as in Figure 2, estimated on the estimation sample with clicks and bookings either as observed or simulated from the model conditional on consumers searching at least one hotel.




FIGURE 6 – The Model Implies Substantial Demand and Price Effects

Notes: \$ changes in the expected revenues of randomly selected hotels when moved from the 15th to the top position.

calculation of booking probabilities. To avoid having to take many draws to accurately simulate the booking probabilities, I use a simulation procedure similar to the one for the likelihood contributions (see Appendix D.4). To reduce the number of hotels in the analysis while capturing that different consumers face different hotels on the product list, I randomly sample 1,000 consumers from the estimation sample, randomize the ranking and move the hotel that is in the middle of the list to the top position. This ensures that both the hotel that is moved and the hotels in other positions are randomized.

Figure 6 presents the results. The left panel shows how the revenue changes vary with the price of the focal hotel and reveals the trade-off between the price and the demand effect. Among the cheap hotels, a higher price leads to larger revenue increases. In contrast, among the expensive hotels, the opposite is the case because they gain little demand when being moved higher up. The right panel further highlights this demand effect by showing how the revenue change varies with the utility of the focal hotel. It reveals that high-utility hotels tend to have a larger revenue increase. Nonetheless, the relationship is not perfect: hotels that offer the highest utility do not necessarily gain the most revenue. Instead, the price effect revealed in the left panel allows more expensive hotels offering lower utility to gain more revenues when they are moved to the top.

Combined, these results suggest that there are substantial price and demand effects. Hence, a ranking needs to balance the two effects to increase revenues. If the price effect is stronger, a revenue-based ranking will move more expensive hotels to the top as they gain the most revenue. In contrast, if the demand effect is stronger, a revenue-based ranking will move high-utility alternatives higher up on the list, which will also benefit consumers.

6.3 The Six Rankings

To quantify whether this will occur and how well the interests of a revenue-maximizing platform and consumers are aligned, I construct and then compare the effects of six different rankings designed to either benefit consumers or increase the platform’s revenues. Table 4 provides an overview of the six rankings. To construct the rankings, I focus on short-term effects where consumers do not adjust their beliefs about the ranking algorithm. In that sense, I assume that the platform optimizes the rankings for short-term objectives. This is in line with much of the literature deriving and studying the effects of optimal rankings,³² while the data also suggests that consumers do not immediately adjust their beliefs (see Section 5.3). Nonetheless, I analyze the long-term effects in Section 6.5 and find that all rankings continue to serve their intended objective when consumers adjust their beliefs.

The first ranking I evaluate is Expedia’s own, as observed in the data. This ranking provides a benchmark for how much alternative rankings may improve upon Expedia’s ranking during the sample period, both in terms of revenues and consumer welfare.

TABLE 4 – The Six Rankings

ER	Expedia ranking	Expedia’s own ranking.
UR	Utility-based ranking	Ranking that is best for consumers.
R1R	Position 1 revenue ranking	Heuristic to maximize total revenues.
BUR	Bottom-up revenue ranking	Heuristic to maximize total revenues.
PR	Price-decreasing ranking	Heuristic to maximize total revenues if position effects did not depend on price.
-UR	Reverse utility-based ranking	Ranking that is worst for consumers.

6.3.1 The Consumer-Welfare-Maximizing Ranking

The second ranking I evaluate is designed to benefit consumers. Such a ranking should help consumers find better-suited alternatives, save on discovery costs, or do both simultaneously. Intuitively, this can be achieved by first showing high-utility alternatives so that consumers do not miss out on them and can choose them before paying a lot of discovery costs. Proposition 4, proven in Appendix A.4, confirms this intuition and establishes that in the present model, such a utility-based ranking maximizes consumer welfare and, hence, is best for consumers.

³²See, for example, Chen and Yao (2017), Ursu (2018), Chu et al. (2020), Donnelly et al. (2023), or Compiani et al. (2023). An exception is Choi and Mela (2019) who account for consumers updating beliefs based on the ranking.

Proposition 4. *A ranking that orders alternatives in decreasing order of u_j^e maximizes consumer welfare and the overall purchase probability.*

Beyond showing that a utility-based ranking maximizes consumer welfare, Proposition 4 also has an implication for platforms that aim to increase consumer welfare: maximizing conversions is equivalent to maximizing consumer welfare. Hence, targeting consumer welfare does not require estimating a structural search model to evaluate welfare effects. Instead, deploying a ranking algorithm that maximizes conversions automatically will maximize consumer welfare as long as it is based on a demand model that captures the position-specific demand for each alternative.

6.3.2 Revenue-Based Rankings

The next two rankings are designed to benefit Expedia by increasing total revenues across the whole list (see Section 4.2). As established in Section 4.3, cheaper hotels have stronger position effects such that increasing revenues entails trading off the demand and price effects highlighted in Section 3. However, with more than 30 alternatives to rank, deriving a revenue-maximizing ranking is difficult and goes beyond the scope of this paper. Instead, these two rankings are heuristics for maximizing total revenues motivated by the model structure.

The first heuristic orders alternatives based on the revenues they generate in the first position. I choose the first position in this “position 1 revenue-based ranking” (R1R) because all consumers discover the alternative displayed on it. As a consequence, the top generates the most demand across all positions and, hence, should be the most relevant. This heuristic entails two simple steps. The first step is to iterate over and calculate each alternative’s revenues when shown on the top position while sorting all other alternatives using a utility-based ranking. The second step is to sort the alternatives based on the revenues calculated in the first step. As the first step only requires computing the revenues for each alternative once, this ranking is fast to compute even if there are many alternatives consumers can discover.

The second heuristic is a “bottom-up ranking” (BUR) that first chooses which alternative to put in the last position, then the second-to-last, and so on. This approach is motivated by the fact that the demand for an alternative is unaffected by the ordering of alternatives discovered in previous positions; only the identity of these products matters. This bottom-up heuristic entails multiple steps and is computationally more expensive than the first one. The first step is to iterate over all available alternatives and compute total revenues when that alternative is shown at the last position while the alternatives

above are sorted using the utility-based ranking. The second step is to choose the alternative that maximizes total revenues computed in the first step to be shown in the last position. Third, start again with the first step, but now use the second-to-last position, and so on. Given this iterative procedure, computing the BUR for a consumer requires computing total revenues $\sum_{k=1}^{\bar{h}_i} (\bar{h}_i - k)$ times, where \bar{h}_i is the last position i can discover. Hence, the BUR takes substantially more computations than the R1R.

Neither heuristic is revenue-maximizing because they take the order of other alternatives as given. If that order is already revenue-maximizing, both heuristics will maximize revenues. If this is not the case, then the heuristics do not necessarily maximize revenues. To get some measure of how well these heuristics do in the present case, I compare them with the revenue-maximizing ranking I compute with a brute-force algorithm for a reduced set of alternatives. The results in Appendix F.1 show that the BUR heuristic performs very well and reduces revenues by less than 0.4% from the revenue maximum. The R1R performs worse, reducing revenues by up to 5.1%, but still outperforming the UR, which reduces revenues by 6.4%.

6.3.3 Other rankings

To quantify the effects of a revenue-based ranking that ignores heterogeneous position effects, I also evaluate a ranking that shows the most expensive alternatives first. As Proposition 5, proven in Appendix A.5, highlights, this ranking maximizes revenues in the SD model when position effects are homogeneous (as in Chu et al., 2020). The reason is that with homogeneous position effects, the demand effect highlighted in the motivating example is shut down and only the price effect matters. Hence, the price-decreasing ranking is the ranking a revenue-maximizing platform would implement when disregarding that position effects are heterogeneous.

Proposition 5. *If position effects are homogeneous, a price-decreasing ranking maximizes revenues.*

Finally, I also evaluate the worst-case scenario for consumers, which is given by the reverse to the utility-maximizing ranking. By providing the worst-case scenario, this ranking allows to better assess how much revenue-based rankings hurt consumers relative to other rankings.

6.4 Short-Term Ranking Effects

To compare the different rankings, I use the model to quantify their effects on Expedia’s revenues and consumer welfare. For this analysis, I use the sample where consumers

TABLE 5 – Short-Term Ranking Effects

	ER	UR	R1R	BUR	PR	-UR
Expedia						
Total revenues	3.79	9.66	14.17	14.93	3.73	-8.45
Number of transactions	3.98	13.77	9.36	8.55	-5.02	-11.91
Avg. price of booking	-0.19	-3.61	4.40	5.88	9.22	3.94
Consumers						
Consumer welfare	0.35	0.98	0.79	0.92	-0.78	-1.25
Discovery costs	-2.68	-8.20	-5.78	-5.84	4.01	8.30

Notes: Percentage changes relative to a randomized ranking obtained by averaging across 100 randomizations.

observed Expedia’s ranking and simulate consumers’ searches, purchases, and consumer welfare.³³ To compute consumer welfare more efficiently, I build on the extended eventual purchase theorem of Greminger (2022) to obtain an expression for consumer welfare that circumvents the need to simulate different search paths. Appendix D.2 provides further details on this procedure.

Table 5 shows the results of the comparison when consumers do not adjust their beliefs. All effects are shown as percentage changes relative to a randomized ranking. To compute consumer welfare more efficiently, I build on the extended eventual purchase theorem of Greminger (2022) to obtain an expression for consumer welfare that circumvents the need to simulate different search paths. Appendix D.2 provides further details on this procedure. I apply this method using 100,000 simulation draws.

The ER, UR, BUR, R1R, and the PR all manage to increase revenues over the randomized ranking. As intended, the R1R and the BUR increase revenues the most, with the BUR slightly outperforming the R1R, and both outperforming Expedia’s own ranking. Despite not targeting revenues, the UR also leads to a substantial increase in revenues of 9.46%. However, the UR achieves this revenue increase solely by increasing the number of bookings. The two revenue-based rankings instead trade-off the demand with the price effect and additionally induce consumers to book more expensive hotels. This allows them to generate even stronger revenue increases despite reducing the number of bookings relative to the UR.

The PR instead ignores the demand effect and would be revenue-maximizing if position effects were homogeneous. As the results show, this is not the case: the PR increases revenues only by 3.73% and decreases consumer welfare by 0.78%. Hence, disregarding

³³Though consumers were sampled differently from the estimation sample, using only predicted choices ensures that the comparison is based on the same consumer population. Appendix F.2 shows that the results are qualitatively comparable for the randomized sample.

heterogeneous position effects would lead to a ranking that substantially harms consumers and Expedia.

Comparing the increases in consumer welfare between the UR and the two heuristics reveals that Expedia’s and consumers’ interests are not perfectly aligned. The UR increases consumer welfare, conditional on clicking, by 0.98%. The two revenue-based rankings also benefit consumers, increasing consumer welfare by 0.79% and 0.92%, respectively. Whereas these increases are not as large as the one from the UR, they get relatively close, especially when considering the large welfare increases over the random ranking or the worst-case ranking for consumers. Hence, revenue-based rankings reduce consumer welfare only to a limited extent relative to the consumer-welfare-maximizing ranking.

Finally, the last row in Table 5 reveals that all welfare-increasing rankings reduce discovery costs by 2.68% up to 8.20%, highlighting that these rankings help consumers find and book a suitable hotel earlier on the list, saving them the time and effort to scroll down the page.

6.5 Long-Term Ranking Effects

Whereas I derive the rankings for a short-term horizon where consumers do not adjust their beliefs, it is possible to quantify long-term ranking effects where consumers adjust their beliefs. For this analysis, it is first necessary to derive consumers’ beliefs about the different rankings. Given that these beliefs are fully captured in $\mu_u(1)$ and ρ , they can be recovered from the data given the new ranking. Specifically, after re-ordering with a ranking, I calculate the expected utilities $u_j^e = -\alpha p_j + x_j' \beta$ for all alternatives and then regress these on positions using the functional form for beliefs (5). This yields an estimate $\hat{\rho}$ for the new ranking, which I then use to compute $\mu_u(1)$ and all discovery values (see Appendix B.2). As the PR and -UR lead consumers to expect better alternatives as they scroll down the list, I do not compute these results and focus only on the main rankings.

Table 6 shows the differences in the ranking effects between the short- and the long-term. Throughout, the long-term effects are stronger than the short-term effects such that Expedia and consumers benefit even more from the respective rankings in the long-term. Hence, the proposed rankings continue to serve their intended objectives in the long-term.

Because the effects of the UR increase more strongly in the long-term, the results also imply that the differences between the revenue-based rankings and the utility-based ranking will become larger. Nonetheless, the revenue-based rankings continue to provide

TABLE 6 – Long-Term Ranking Effects

	UR	R1R	BUR
Total revenues	4.59	3.35	1.45
Consumer welfare	2.17	1.13	0.69

Notes: Percentage changes relative to the short-term ranking effects.

substantial welfare gains over the randomized rankings and I conclude that they are also not detrimental to consumer welfare when consumers adjust their beliefs.

7 Conclusions

In this paper, I quantify how consumer-welfare-maximizing rankings differ from rankings designed to maximize platform revenues. I find that focusing on either objective is not detrimental to the other: the utility-based ranking substantially increases revenues, and revenue-based rankings substantially increase consumer welfare over alternative rankings. I highlight and corroborate with descriptive evidence that this is because heterogeneous position effects allow a platform to increase revenues by moving high-utility hotels to the top, which increases both conversions and consumer welfare. Hence, I conclude that revenue-based rankings are not detrimental to consumer welfare and that a revenue-maximizing platform’s and consumers’ interests are not strongly misaligned.

Whereas I follow prior work and design rankings focusing on short-term effects, the approach poses several limitations. First, although I show that the rankings continue to serve their intended purpose when consumers adjust their beliefs, rankings that account for these long-term effects potentially differ in how they order alternatives. Second, hotels may adapt their pricing rules to different ranking algorithms in the long term. Similarly, online retailers can adjust their pricing more directly to different rankings. Extending this paper and quantifying the effects of rankings that account for consumers’ long-term belief adjustments and sellers implementing rank-dependent pricing rules poses an exciting avenue for future research.

Another promising avenue for future research is to use more comprehensive data to study how rankings work within consumers’ broader discovery process and to quantify search cost and preference heterogeneity. I do not observe consumers searching across multiple search sessions, making identifying search cost and preference heterogeneity difficult (Yavorsky et al., 2021). Moreover, I only observe how consumers interact with a ranked product list on one search intermediary, while consumers may also visit other platforms and use price aggregators or filtering tools to discover more products. Data

that tracks how consumers search for and compare products over time and across multiple platforms will allow future research to introduce search cost and preference heterogeneity in the search and discovery model and study the effects of rankings in a broader context.

References

- Athey, S. and G. Imbens (2015). Machine Learning Methods for Estimating Heterogeneous Causal Effects. Technical report.
- Blake, T., C. Nosko, and S. Tadelis (2015). Consumer Heterogeneity and Paid Search Effectiveness: A Large-Scale Field Experiment. *Econometrica* 83(1), 155–174.
- Chan, T. Y. and Y.-H. Park (2015). Consumer Search Activities and the Value of Ad Positions in Sponsored Search Advertising. *Marketing Science* 34(4), 606–623.
- Chen, Y. and S. Yao (2017). Sequential Search with Refinement: Model and Application with Click-Stream Data. *Management Science* 63(12), 4345–4365.
- Choi, H. and C. F. Mela (2019). Monetizing Online Marketplaces. *Marketing Science*, mksc.2019.1197.
- Chu, L. Y., H. Nazerzadeh, and H. Zhang (2020). Position ranking and auctions for online marketplaces. *Management Science* 66(8), 3617–3634.
- Chung, J. H., P. K. Chintagunta, and S. Misra (2023). Simulated Maximum Likelihood Estimation of the Sequential Search Model. *SSRN Electronic Journal*.
- Compiani, G., G. Lewis, S. Peng, and P. Wang (2023). Online Search and Product Rankings: A Double Index Approach.
- Davis, J. M., G. Gallego, and H. Topaloglu (2014). Assortment Optimization Under Variants of the Nested Logit Model. *Operations Research* 62(2), 250–273.
- De Los Santos, B. and S. Koulayev (2017). Optimizing Click-Through in Online Rankings with Endogenous Search Refinement. *Marketing Science* 36(4), 542–564.
- Derakhshan, M., N. Golrezaei, V. Manshadi, and V. Mirrokni (2022). Product Ranking on Online Platforms. *Management Science* (forthcoming).
- Donnelly, R., A. Kanodia, and I. Morozov (2023). Welfare Effects of Personalized Rankings. *Marketing Science*, mksc.2023.1441.
- Drezner, Z. and G. O. Wesolowsky (1990). On the computation of the bivariate normal integral. *Journal of Statistical Computation and Simulation* 35(1-2), 101–107.
- Ghose, A., P. G. Ipeirotis, and B. Li (2012). Designing Ranking Systems for Hotels on Travel Search Engines by Mining User-Generated and Crowdsourced Content. *Marketing Science* 31(3), 493–520.
- Ghose, A., P. G. Ipeirotis, and B. Li (2014). Examining the Impact of Ranking on Consumer Behavior and Search Engine Revenue. *Management Science* 60(7), 1632–1654.
- Gibbard, P. (2022a). A Model of Search with Two Stages of Information Acquisition and Additive Learning. *Management Science* 68(2), 1212–1217.
- Gibbard, P. (2022b). Search with two stages of information acquisition: A structural econometric model of online purchases.

- Goldman, M. and J. M. Rao (2014). Experiments as Instruments: Heterogeneous Position Effects in Sponsored Search Auctions. Technical report.
- Greminger, R. P. (2022). Optimal Search and Discovery. *Management Science* 68(5), 3904–3924.
- Jeziorski, P. and S. Moorthy (2018). Advertiser prominence effects in search advertising. *Management Science* 64(3), 1365–1383.
- Jeziorski, P. and I. R. Segal (2015). What Makes Them Click: Empirical Analysis of Consumer Demand for Search Advertising. *American Economic Journal: Microeconomics* 7(3), 24–53.
- Jiang, Z., T. Chan, H. Che, and Y. Wang (2021). Consumer search and purchase: An empirical investigation of retargeting based on consumer online behaviors. *Marketing Science* 40(2), 219–240.
- Morozov, I. (2023). Measuring Benefits from New Products in Markets with Information Frictions. *Management Science*, mns.2023.4729.
- Owen, D. B. (1980). A table of normal integrals. *Communications in Statistics - Simulation and Computation* 9(4), 389–419.
- Ryzin, G. V. and S. Mahajan (1999). On the Relationship Between Inventory Costs and Variety Benefits in Retail Assortments. *Management Science* 45(11), 1496–1509.
- Talluri, K. and G. Van Ryzin (2004). Revenue Management Under a General Discrete Choice Model of Consumer Behavior. *Management Science* 50(1), 15–33.
- Ursu, R., S. Seiler, and E. Honka (2023). The Sequential Search Model: A Framework for Empirical Research.
- Ursu, R. M. (2018). The Power of Rankings: Quantifying the Effect of Rankings on Online Consumer Search and Purchase Decisions. *Marketing Science* 37(4), 530–552.
- Ursu, R. M. and D. Dzyabura (2020). Retailers’ product location problem with consumer search. *Quantitative Marketing and Economics* 18, 125–154.
- Weitzman, M. L. (1979). Optimal Search for the Best Alternative. *Econometrica* 47(3), 641–654.
- Yavorsky, D., E. Honka, and K. Chen (2021). Consumer search in the {U.S.} auto industry: The role of dealership visits. *Quantitative Marketing and Economics* 19(1), 1–52.
- Zhang, X., P. Ferreira, M. Godinho De Matos, and R. Belo (2021). Welfare Properties of Profit Maximizing Recommender Systems: Theory and Results from a Randomized Experiment. *MIS Quarterly* 45(1), 1–43.
- Zhang, X., R. Ursu, E. Honka, and Y. Yao (2023). Product Discovery and Consumer Search Routes: Evidence from a Mobile App. *SSRN Electronic Journal*.

Appendix

A Proofs

A.1 Proof of the Implications of the Optimal Policy

The stopping implication follows from the optimal policy prescribing to stop discovering alternatives whenever $\tilde{w}_{ij} > z^d(h)$ for the chosen alternative j and the fact that the consumer must discover j to be able to choose it.

The two search implications follow from the fact that when k is in the awareness set, $z_{ik}^s \geq u_{ij}$ implies that the optimally searching consumer searches k before ending search, and $z_{ik}^s \geq z_{ij}^s$ implies that she searches k before j . The search and early discovery implication additionally accounts for the fact that consumer searches k before discovering j as long as $z_{ik}^s \geq z^d(h_{ij} - 1)$, leading to a weaker condition when $w_{ij} = z^d(h_{ij} - 1) < \tilde{w}_{ij}$.

The choice implication is implied by the generalized eventual purchase theorem of Greminger (2022) that states that an optimally searching consumer eventually chooses the option with the largest effective value w_{ij} . For $k \in S_{i-}$, the search and early discovery implication implies that $z_{ik}^s \geq w_{ij}$ holds. Moreover, k being discovered before j implies that $z^d(h_{ik} - 1) > z^d(h_{ij} - 1)$. Hence, $z_{ik}^s \geq w_{ij}$ and $z^d(h_{ik} - 1) \geq w_{ik}$ such that $w_{ik} < w_{ij}$ can only hold when $w_{ik} = u_{ik} < w_{ij}$ for these alternatives. For $k \in S_{i+}$, $z^d(h_{ik} - 1) \leq z^d(h_{ij} - 1)$ such that $w_{ik} \leq \tilde{w}_{ij}$ is sufficient for $w_{ik} < w_{ij}$ to hold. The search and late discovery implication then implies $z_{ik}^s \geq \tilde{w}_{ij}$, such that $w_{ik} \leq w_{ij}$ holds as long as $u_{ik} \leq \tilde{w}_{ij}$ for these alternatives. This inequality is weak because S_{i+} also contains j .

A.2 Proof of Lemma 1 and Propositions 1 and 2

The stopping implication of the optimal policy implies that the consumer stops whenever $\bar{w}_h = \max_{k \in \{k: h_k \leq h\}} w_k \geq z^d(h)$. Hence, by partitioning the probability space, the position effect can be written as

$$\begin{aligned} \Delta d_B &= d_B(h) - d_B(h+1) \\ &= \mathbb{P}(\bar{W}_{i,h-1} \in [z^d(h), z^d(h-1))) \mathbb{P}(\tilde{W}_{iB} > \bar{W}_{i,h-1} | \bar{W}_{i,h-1} \in [z^d(h), z^d(h-1))) + \\ &\quad \mathbb{P}(\bar{W}_{i,h-1} \leq z^d(h)) [\mathbb{P}(\tilde{W}_{iB} > z^d(h)) (1 - \mathbb{P}(\tilde{W}_{iA} \leq z^d(h))) + C], \end{aligned} \quad (16)$$

where

$$\begin{aligned} C &= \mathbb{P}(\tilde{W}_{iB} \leq z^d(h)) [\mathbb{P}(\tilde{W}_{iB} \geq \bar{W}_{i,h+1} | \tilde{W}_{iB} \leq z^d(h)) - \\ &\quad \mathbb{P}(\tilde{W}_{iA} \leq z^d(h)) \mathbb{P}(\tilde{W}_{iB} \geq \bar{W}_{i,h+1} | \tilde{W}_{iB} \leq z^d(h), \tilde{W}_{iA} \leq z^d(h))] . \end{aligned} \quad (17)$$

Because $\mathbb{P}(\tilde{W}_{iB} \geq \bar{W}_{i,h+1} | \tilde{W}_{iB} \leq z^d(h), \tilde{W}_{iA} > z^d(h)) = 0$, we get $C = 0$ and immediately obtain equation (8). As consumers always click a discovered alternative j whenever

$z_{ij}^s \geq \bar{w}_{ih}$, the second part for clicks can be derived the same way.

Proposition 1 follows immediately from these position effects because the sizes of the two position effects of B depend on the distribution of $\tilde{W}_{iB} = u_B^e + \nu_{ij} + \min\{\xi, \varepsilon_{iB}\}$ and the distribution of $Z_{iB}^s = u_B^e + \nu_{ij} + \xi$. If larger values of Z_{iB}^s or \tilde{W}_{iB} become more likely, then the respective position effect is stronger. Hence, the position effects increase in u_B^e .

Proposition 2 follows because $\mu_u(h) \geq \mu_u(h+1)$ and the fact that the consumer takes the outside option imply that the probability of stopping on position h is zero. Hence, the first term drops out. The fact that the consumer takes the outside option also implies $\mathbb{P}(\tilde{W}_{iA} > z^d(h-1)) = 0$, such that the second term also drops out.

A.3 Proof of Proposition 3

As $\nu_{ij} \sim N(0, 1)$ and $\varepsilon_{ij} \sim N(0, \sigma_\varepsilon)$, we can write $\mathbb{P}(Z_{ik} \geq l \cap U_{ik} \leq u)$ as

$$\mathbb{P}(Z_{ik}^s \geq l \cap U_{ik} \leq u) = \int_{l-u_k^e-\xi}^{\infty} \Phi\left(\frac{u-u_k^e-\nu}{\sigma_\varepsilon}\right) \phi(\nu) d\nu \quad (18)$$

$$= \int_{-\infty}^{\infty} \Phi\left(\frac{u-u_k^e-\nu}{\sigma_\varepsilon}\right) \phi(\nu) d\nu - \int_{-\infty}^{l-u_k^e-\xi} \Phi\left(\frac{u-u_k^e-\nu}{\sigma_\varepsilon}\right) \phi(\nu) d\nu. \quad (19)$$

The result follows by applying (10,010.8) and (10,010.1) of Owen (1980) to rewrite the normal integrals.

A.4 Proof of Proposition 4

Because there are a finite number of alternatives, a finite (albeit extremely large) number of possible rankings exists, which implies that a consumer-welfare- or bookings-maximizing ranking exists. Hence, to show that the two claims hold, it suffices to show that whenever they do not hold, an improvement exists.

To show whether an improvement exists, I use that consumer welfare given a ranking is given by

$$\mathbb{E} \left[1(\bar{W}_{i,h-1} < z^d(h-1)) 1(\bar{W}_{ih} > z^d(h)) \times \sum_{j \in A_h} 1(\tilde{W}_{ij} \geq \bar{W}_{ih}) \tilde{W}_{ij} \right] - \mathbb{E} \left[\sum_{h=0}^{\bar{h}} 1(\bar{w}_{ih} < z^d(h)) c_d \right], \quad (20)$$

as shown in Appendix D.2.

Suppose the first claim does not hold, i.e., a ranking where $u_A^e < u_B^e$, with $h_A = h$ and $h_B = h+1$ for two alternatives A and B maximizes welfare.³⁴ In this case, switching

³⁴Whenever $u_B^e < u_A^e$ and $h_B > h_A + 1$, then there must be some \tilde{A} and \tilde{B} such that $u_{\tilde{B}}^e < u_{\tilde{A}}^e$ and $h_{\tilde{B}} = h_{\tilde{A}} + 1$.

the two alternatives leads to a change in consumer welfare that consists of two parts in equation (20).

The first part changes with three possible cases for realized effective values:³⁵

1. $\tilde{w}_{iA} > z^d(h), \tilde{w}_{iB} > z^d(h)$: in this case, the consumer stops before discovering the second product such that the realized change is $\Delta = \tilde{w}_{iB} - \tilde{w}_{iA}$.
2. $\tilde{w}_{iA} > z^d(h), \tilde{w}_{iB} < z^d(h)$: in this case, the consumer never books B , such that $\Delta = w_{iA} - w_{iA} = 0$.
3. $\tilde{w}_{iA} < z^d(h), \tilde{w}_{iB} > z^d(h)$: same logic as 2 such that $\Delta = 0$.

Because $u_A^e < u_B^e$, larger realizations of \tilde{w}_{iB} are more likely such that the first case implies that the first part in equation (33) increases if positions of A and B are switched.

The second part in equation (33) also increases with the switch; $u_A^e < u_B^e$ immediately implies that the probability of stopping on position h increases, making it less likely to pay the additional discovery costs.

Hence, the switch increases consumer welfare, which implies that whenever a ranking does not order alternatives in decreasing order of u_j^e , an improvement exists.

To prove the second claim, suppose again the opposite; a ranking where $u_A^e < u_B^e$, with $h_A = h$ and $h_B = h + 1$ maximizes demand. Switching the two alternatives leads to a change in demand equal to³⁶

$$\mathbb{P}(U_{i0} \geq z^d(h))[\mathbb{P}(\tilde{W}_{iB} \geq U_{i0}) - \mathbb{P}(\tilde{W}_{iA} \geq U_{i0})] . \quad (21)$$

$u_A^e < u_B^e$ then directly implies that larger values \tilde{w}_{iB} are more likely than those of \tilde{w}_{iA} , such that this is positive. Hence, the switch increases demand such that an improvement exists.

A.5 Proof of Proposition 5

Similar to the proof for the consumer-welfare maximizing ranking, I prove this proposition by showing that under any alternative ranking, there exists a switch that increases revenues. I again use the notation that B is the alternative being moved up.

Proposition 1 implies that position effects are only homogeneous in the SD model when alternatives are homogeneous in the expected pre-search utilities u_j^e . This implies that switching two alternatives only shifts demand from A to B , leaving the demand for other alternatives unaffected. Hence, the total change in revenues following a switch is given by

$$\Delta R = (p_B - p_A)\Delta d_A . \quad (22)$$

The expression shows that for any ranking that is not decreasing in price such that

³⁵Alternatives discovered before h and after $h + 1$ do not need to be considered for this analysis, as the probability of reaching h and the probability of continuing beyond $h + 1$ are not affected by switching A and B .

³⁶With $u_{i0} < z^d(h)$ the consumer either books a hotel or discovers the hotel in position $h + 1$, such that switching the two alternatives does not influence demand.

$p_B > p_A$ is possible, there exists a switch that increases revenues as long as there are position effects such that $\Delta d_A = \Delta d_B > 0$. If there are no position effects, then $\Delta R = 0$ such that any ranking, including the price-decreasing ranking, maximizes revenues.

B Additional Details on the Estimation

This appendix provides additional details on how to calculate the likelihood function and the adjusted beliefs, as well as the results of the Monte Carlo simulations.

B.1 Smooth Monte Carlo Integration

Given the stopping implication, the following intervals of the real line are such that $A_i(\tilde{w}_{ij})$ remains fixed for any draw within a given interval:

$$B = \{(-\infty, z^d(|J_i|)], (z^d(|J_i|), z^d(|J_i| - 1)], \dots, (z^d(1), \infty]\} \quad (23)$$

Using these intervals and the second partitioning on $\varepsilon_{ij} \geq \xi$, I calculate the likelihood contributions as

$$\begin{aligned} \mathcal{L}_i(\theta) = \sum_{b \in B} \mathbb{P}(\tilde{W}_{ij} \in b \cap \varepsilon_{ij} \leq \xi) \mathbb{E}[p(\tilde{W}_{ij}) | \tilde{W}_{ij} \in b \cap \varepsilon_{ij} \leq \xi] + \\ \sum_{b \in B} \mathbb{P}(\tilde{W}_{ij} \in b \cap \varepsilon_{ij} > \xi) \mathbb{E}[p(\tilde{W}_{ij}) | \tilde{W}_{ij} \in b \cap \varepsilon_{ij} > \xi] , \quad (24) \end{aligned}$$

where $p(\tilde{w}_{ij})$ is short-hand for the product in the integral in (12). As it has no closed-form, I use Monte Carlo integration to compute $\mathbb{E}[p(\tilde{W}_{ij}) | \tilde{W}_{ij} \in b \cap \varepsilon_{ij} \leq \xi]$, i.e., I take draws from distributions truncated so that the draws satisfy the respective conditions. This then produces a smooth likelihood because $p(\tilde{w}_{ij}^d)$, $\mathbb{P}(\tilde{W}_{ij} \in b \cap \varepsilon_{ij} > \xi)$ and $\mathbb{P}(\tilde{W}_{ij} \in b \cap \varepsilon_{ij} \leq \xi)$ are smooth functions of the parameters.

If the outside option is chosen, $\tilde{w}_{ij} = \beta_0 + \eta_i$ such that simulating the expression can be done by taking draws η_i^d from its distribution, truncated so that $\beta_0 + \eta_i \in b$ is satisfied.

If instead an alternative $j > 0$ is chosen, the expression further depends on the condition $\varepsilon_{ij} \geq \xi$. This case can be simulated using draws generated with the following procedure:

1. Take a draw ε_{ij}^d from its distribution truncated to $\varepsilon_{ij} \leq \xi$.
2. Take a draw ν_{ij}^d from its respective distribution truncated so that $\tilde{w}_{ij}(\varepsilon_{ij}^d) = u_j^e + \nu_{ij} + \varepsilon_{ij}^d \in b$ holds.
3. Calculate \tilde{w}_{ij}^d using draws ν_{ij}^d and ε_{ij}^d , and compute inner probability $p(\tilde{w}_{ij}^d)$.

Based on draws generated by this procedure, the expression can be calculated as the weighted average

$$\mathbb{P}(\varepsilon_{ij} \leq \xi) \sum_d \mathbb{P}(\tilde{w}_{ij}(\varepsilon_{ij}^d) \in b) p(\tilde{w}_{ij}^d) . \quad (25)$$

Finally, $\mathbb{P}(\tilde{W}_{ij} \in b \cap \varepsilon_{ij} > \xi) \mathbb{E}[p(\tilde{W}_{ij}) | \tilde{W}_{ij} \in b \cap \varepsilon_{ij} > \xi]$ can be calculated using the same steps.

B.2 Estimating Consumers' Adjusted beliefs

Given the assumptions on consumers' beliefs, they expect to discover alternatives with mean pre-search utilities given by equation (5). When they adjust beliefs to the new rankings, these beliefs will be true such that they can be recovered from the data after reordering hotels. Specifically, I first compute u_{ij}^e for all consumers and alternatives in the sample using the preference estimates. Then, I recover beliefs by estimating the following linear regression:

$$u_{ij}^e = \gamma_0 + \gamma_1 \log(1 + pos_{ij}) + \varepsilon_{ij} , \quad (26)$$

where pos_{ij} is the position of alternative j in the new ranking for consumer i . This yields an estimate for the new beliefs through $\hat{\rho} = \log(-\hat{\gamma}_1)$. $\hat{\mu}_u(1)$ then can be recovered by using $\hat{\rho}$ to adjust the previous $\mu_u(1)$ accordingly.

Table 7 reports the estimates for the beliefs. Standard errors are small such that beliefs are estimated precisely. Moreover, the reported estimates for ρ are in line with the rankings. Specifically, the estimates suggest that consumers expect alternatives to get worse at a substantially faster rate under the UR than under the R1R or BUR.

TABLE 7 – Estimates of Adjusted Beliefs

	ER	UR	R1R	BUR
$\hat{\rho}$	-3.07 (0.00)	-1.82 (0.00)	-2.13 (0.00)	-2.26 (0.00)
$\hat{\Xi}$	20.16 (0.00)	20.48 (0.00)	20.36 (0.00)	20.32 (0.00)

Notes: Standard errors in parentheses.

B.3 Monte Carlo Simulation Results

TABLE 8 – Monte Carlo Simulation

	Simulation 1 ($\sigma_\varepsilon = 1$)			Simulation 2 ($\sigma_\varepsilon = 2$)		
	True	Estimate	Std. Error	True	Estimate	Std. Error
Price (in 100\$)	-0.30	-0.31	(0.00)	-0.20	-0.19	(0.00)
Star rating	0.10	0.10	(0.01)	0.20	0.20	(0.01)
Review score	0.10	0.10	(0.01)	0.05	0.05	(0.01)
No reviews	0.30	0.31	(0.04)	0.20	0.20	(0.04)
Location score	0.05	0.05	(0.00)	-0.10	-0.10	(0.00)
Chain	0.10	0.10	(0.01)	0.20	0.21	(0.01)
Promotion	0.10	0.10	(0.01)	0.10	0.10	(0.01)
Outside option	2.50	2.46	(0.03)	3.50	3.52	(0.03)
Ξ	1.50	1.49	(0.01)	2.50	2.50	(0.02)
ξ	3.00	2.98	(0.03)	4.00	4.02	(0.03)
ρ	-3.50	-3.48	(0.04)	-2.50	-2.49	(0.02)
c_d	0.02	0.02		0.02	0.02	
c_s	0.03	0.03		0.10	0.10	
Log likelihood	-118,210.52			-103,119.63		
N consumers	11,467			11,467		

Notes: Each estimation is performed with 100 simulation draws. Observable characteristics are the same as in the estimation sample. Asymptotic standard errors are calculated from the inverse of the Hessian matrix. Discovery costs are calculated using 100,000 draws of effective values.

B.4 Additional Model Fit Measures

Table 9 reports additional model fit measures based on the same simulation procedure as used in Figure 4. The results reveal that the model predicts moments that are close to those observed in the estimation sample. Notably, the model closely matches the average number of clicks and the booking probability, as well as the positions at which these clicks and bookings occur on average. Moreover, the predicted averages of the attributes of hotels consumers search and eventually book mostly come close to those in the data, highlighting that the model also reasonably captures which alternatives consumers search and eventually choose. Nonetheless, the model fits the average attributes of clicks better than those of purchases, which I attribute to there being many more clicks than bookings in the data. Future work may further improve the model fit by additionally introducing preference or search cost heterogeneity.

TABLE 9 – Model Fit Measures

	Data	Predicted
Clicks		
N (per consumer)	1.13	1.14
Mean position where the consumer clicked	14.30	14.36
Highest position where the consumer clicked	13.86	13.43
Lowest position where the consumer clicked	14.69	14.74
Price	162.21	162.88
Star rating	3.51	3.51
Review score	3.92	3.92
No reviews	0.02	0.02
Location score	3.61	3.62
Chain	0.64	0.64
Promotion	0.36	0.36
Bookings		
N (per consumer)	0.06	0.06
Mean position	14.47	14.37
Price	145.17	162.75
Star rating	3.50	3.52
Review score	3.97	3.92
No reviews	0.01	0.02
Location score	3.79	3.62
Chain	0.67	0.64
Promotion	0.41	0.36

Notes: This table compares moments in the estimation sample with those predicted by the model. The moments are the average for the number of clicks and the booking probability per consumer; the average, highest, and lowest position at which consumers clicked; and the averages for the different attributes of hotels that consumers searched and eventually chose. The simulated search paths were generated with 20,000 draws for each consumer, conditional on searching at least one alternative.

C Comparison of Specifications

This appendix evaluates the impact of using alternative specifications for the model. First, I evaluate the impact of using different values for σ_ε and the upper bound in the distribution of η_i . To this end, I estimate each of these specifications using the same sample as in the main analysis, simulate how many and where clicks and bookings occur, and predict the revenue and the consumer welfare effects of implementing either the utility-based or the bottom-up ranking over a randomized ranking. To compute the consumer welfare effects, I use the method from Appendix D.2.

The results of this comparison are presented in Table 10. They reveal that most parameter estimates are insensitive to the choice of σ_ε . The exception are the estimates for β_0 , Ξ , ξ , and c_s in dollar terms, which all increase as σ_ε increases. However, the differences $\Xi - \beta_0$ and $\xi - \beta_0$ remain virtually unchanged. Moreover, differences in the log-likelihood and model fit become minimal once σ_ε is set large enough, highlighting the difficulty in identifying σ_ε from the data.

Because the estimate for the search costs increases in σ_ε , consumer welfare effects also increase in σ_ε if they are expressed in dollar terms. If they instead are expressed in percentage terms, they are quite similar across the different specifications if $\sigma_\varepsilon \geq 5$. Similarly, revenue effects of the different rankings are also comparable if $\sigma_\varepsilon \geq 5$. Notably, the pattern that the bottom-up ranking affects consumers only to a limited extent holds independent of σ_ε , highlighting that the choice of σ_ε does not influence the main conclusions.

Given these results, I choose $\sigma_\varepsilon = 10$ for the main specification and conclude that the results are not very sensitive to the choice of σ_ε . The last column of Table 10 compares another specification where $\eta_i \sim \text{Uniform}(0, 5)$, which yields very similar results to the main specification. Hence, I also conclude that the results are not very sensitive to increasing the upper bound of the distribution of the outside option.

To evaluate the impact of the functional form for beliefs, specified in (5), I further estimate the model with the following linear specification:

$$\mu_u(h) = \mu_u(1) - \exp(\rho)h . \quad (27)$$

Figure 7 compares the number of bookings (top panel) and clicks (bottom panel) and shows that with the linear specification, the model does not capture that clicks and bookings decrease at a decreasing rate across positions. Instead, it rationalizes the data through a large drop in clicks and bookings on the first position, which all consumers discover, following which clicks and bookings decrease linearly.

To evaluate the impact of the assumptions that consumers discover the first alternative for free and that they discover alternatives one by one, I also estimate two specifications that relax these assumptions. The results in Figures 8 and 9 show that the model does

not fit the position effects observed in the data in both cases.

TABLE 10 – Comparison of Specifications

	$\sigma_\varepsilon = 0.5$	$\sigma_\varepsilon = 1$	$\sigma_\varepsilon = 5$	Main	$\sigma_\varepsilon = 20$	$b = 5$
Parameter estimates						
Price (in 100\$)	-0.24	-0.24	-0.24	-0.24	-0.24	-0.24
Star rating	0.21	0.21	0.21	0.21	0.22	0.21
Review score	0.03	0.03	0.03	0.03	0.03	0.03
No reviews	0.11	0.10	0.10	0.10	0.10	0.10
Location score	0.08	0.07	0.07	0.07	0.07	0.07
Chain	-0.02	-0.02	-0.02	-0.02	-0.02	-0.02
Promotion	0.09	0.09	0.09	0.09	0.09	0.09
Outside option	4.32	5.06	11.60	19.88	36.12	19.88
Ξ	1.35	2.08	8.63	16.91	33.14	16.91
ξ	4.70	5.43	11.98	20.26	36.50	20.29
ρ	-2.49	-2.49	-2.48	-2.48	-2.48	-2.41
$\Xi - \beta_0$	0.37	0.38	0.38	0.38	0.38	0.41
$\xi - \beta_0$	-2.98	-2.98	-2.97	-2.97	-2.98	-2.97
Discovery costs (\$)	0.07	0.07	0.07	0.07	0.08	0.07
Click costs (\$)	0.23	2.82	35.59	77.51	167.77	77.63
Log likelihood	-48,975.57	-48,949.36	-48,927.10	-48,924.64	-48,924.78	-48,922.94
Fit: clicks						
N, model (cond. on click)	13,283.40	13,293.50	13,308.37	13,309.47	13,326.26	13,306.54
N, data	13,005.00	13,005.00	13,005.00	13,005.00	13,005.00	13,005.00
Mean position, model	14.17	14.22	14.29	14.30	14.30	14.28
Mean position, data	14.30	14.30	14.30	14.30	14.30	14.30
Fit: bookings						
N, model	696.00	675.28	655.41	651.63	673.98	650.48
N, data	634.00	634.00	634.00	634.00	634.00	634.00
Mean position, model	14.37	14.32	14.31	14.31	14.30	
Mean position, data	14.47	14.47	14.47	14.47	14.47	14.47
Effects of UR						
Δ total revenues (%)	11.65	10.66	9.87	9.66	9.79	9.79
Δ consumer welfare (\$)	22.02	24.19	43.48	68.14	117.94	71.36
Δ consumer welfare (%)	1.43	1.35	1.07	0.98	0.94	1.02
Effects of BUR						
Δ total revenues (%)	19.34	17.45	15.06	14.93	14.98	15.02
Δ consumer welfare (\$)	21.40	22.89	40.51	64.07	114.38	68.38
Δ consumer welfare (%)	1.39	1.27	0.99	0.92	0.91	0.98

Notes: The main specification uses $\sigma_\varepsilon = 1$ and $\eta_i \sim Uniform(0, 1)$. The other specifications are the same, except for either σ_ε or the distribution of $\eta_i \sim Uniform(0, b)$. The fit measures are averages across 20,000 draws per consumer, conditional on at least one click occurring. The effects of the utility-based ranking are relative to a randomized ranking, obtained by averaging across 100 randomizations.




FIGURE 7 – Model Fit under the Linear Belief Specification

Notes: Clicks and bookings averaged across 10,000 draws per consumer, conditional on consumers searching at least one hotel. The shaded area indicates the 95th percentile of the minimum and maximum number of clicks or bookings across draws and consumers.




FIGURE 8 – Model Fit When Consumers Initially Discover 3 Alternatives

Notes: Clicks and bookings averaged across 10,000 draws per consumer, conditional on consumers searching at least one hotel. The shaded area indicates the 95% percentile of the minimum and maximum number of clicks or bookings across draws and consumers.




FIGURE 9 – Model Fit When Consumers Discover 3 Alternatives at a Time
Notes: Clicks and bookings averaged across 10,000 draws per consumer, conditional on consumers searching at least one hotel. The shaded area indicates the 95% percentile of the minimum and maximum number of clicks or bookings across draws and consumers.

D Additional Derivations

D.1 Average Difference in Clicks

This appendix shows that the average difference in clicks under the randomized ranking is given by (14). Given two alternatives, A in h and B in $h + 1$, we can write

$$\begin{aligned}\Delta \text{no. clicks}(h) &= s_A(h) - s_B(h + 1) \\ &= \Delta s_A(h) + \Delta s_B(h) + s_A(h + 1) - s_B(h) .\end{aligned}\tag{28}$$

The random ranking then implies that when integrating over hotels in the same position, we have $\mathbb{E}[s_A(h)] = \mathbb{E}[s_B(h)]$. Hence, the average difference in clicks on position h can be written as

$$\mathbb{E}[\Delta \text{no. clicks}(h)] = \mathbb{E}[\Delta s_A(h)] .\tag{29}$$

Using Lemma 1 and applying the assumption that η_i follows a standard uniform distribution then yields (14).

D.2 Calculating Consumer Welfare

This appendix provides an expression for the expected consumer welfare that simplifies the proof of Proposition 4. Moreover, the expression provides a way to compute expected consumer welfare that circumvents the need to simulate search paths. The derivation of the expression builds on the eventual purchase theorem and follows almost the same steps as the derivations in EC.1.2. in the online appendix of Greminger (2022). The main adjustment is that the discovery value depends on the position and that welfare is calculated conditional on observable hotel attributes.

Define $\bar{w}_{ih} \equiv \max\{\tilde{w}_{i0}, \dots, \tilde{w}_{ih}\}$ as the maximum of values discovered up to position h , with $\tilde{w}_{ij} = x'_j\beta + \nu_{ij} + \min\{\xi, \varepsilon_{ij}\}$ being the effective value defined in Section 5.2. Moreover, let $\bar{w}_{i0} = \max_{j \in A_0} \tilde{w}_{ij}$ denote the maximum value in the initial awareness set, \bar{h} the maximum position to discover, and A_h the set of alternatives that are discovered up to position h . To simplify notation, let $y_j = x'_j\beta + \nu_{ij}$ denote the pre-search part of utility and $1(\cdot)$ the indicator function.

The consumer continues discovering whenever $\bar{w}_{ih} < z^d(h)$. Hence, given realizations ν_{ij} and ε_{ij} for all hotels, the discovery costs that the consumer pays are given by

$$\sum_{h=0}^{\bar{h}} 1(\bar{w}_{ih} < z^d(h)) c_d .\tag{30}$$

The consumer also stops discovering whenever $\bar{w}_{ih} > z^d(h)$, conditional on which the consumer searches any alternative that is discovered and satisfies $z_{ij}^s > \bar{w}_{ih}$. Hence,

consumer welfare without discovery costs is given by

$$\sum_{h=0}^{\bar{h}} 1(\bar{w}_{i,h-1} < z^d(h-1))1(\bar{w}_{ih} > z^d(h)) \times \left(\sum_{j \in A_h} 1(\tilde{w}_{ij} \geq \bar{w}_{ih})(y_j + \varepsilon_{ij}) - 1(y_j + \xi \geq \bar{w}_{ih})c_s \right) . \quad (31)$$

Using that $c_j = \mathbb{E}[1(\varepsilon_{ij} \geq \xi)1(\varepsilon_{ij} - \xi)]$ and taking expectations over the whole expression yields

$$\sum_{h=0}^{\bar{h}} \mathbb{E} \left[1(\bar{W}_{i,h-1} < z^d(h-1))1(\bar{W}_{ih} > z^d(h)) \times \left(\sum_{j \in A_h} 1(\tilde{W}_{ij} \geq \bar{W}_{ih})(Y_j + \varepsilon_{ij}) - 1(Y_j + \xi \geq \bar{W}_{ih})1(\varepsilon_{ij} \geq \xi)(\varepsilon_{ij} - \xi) \right) \right] . \quad (32)$$

As $1(y_j + \xi \geq \bar{w}_{ih})1(\varepsilon_{ij} \geq \xi)$ implies $1(\tilde{w}_{ij} \geq \bar{w}_{ih})$, the second part simplifies to $1(\tilde{w}_{ij} \geq \bar{w}_{ih})(y_j + \min\{\varepsilon_{ij}, \xi\}) = 1(\tilde{w}_{ij} \geq \bar{w}_{ih})\tilde{w}_{ij}$. Combining this with (30) then yields that expected consumer welfare is given by

$$\mathbb{E} \left[1(\bar{W}_{i,h-1} < z^d(h-1))1(\bar{W}_{ih} > z^d(h)) \times \sum_{j \in A_h} 1(\tilde{W}_{ij} \geq \bar{W}_{ih})\tilde{W}_{ij} \right] - \mathbb{E} \left[\sum_{h=0}^{\bar{h}} 1(\bar{W}_{ih} < z^d(h))c_d \right] . \quad (33)$$

D.3 Backing Out Discovery Costs

The definition of the discovery value given in (7) implies:

$$c_d = \int_{z^d(h)}^{\infty} [1 - G_h(t)] dt \quad (34)$$

This is a unique mapping from G_h and c_d to $z^d(h)$. Given c_d and G_h , (34) can be solved for $z^d(h)$, and given $z^d(h)$ and G_h , it can be solved for c_d . However, $G_h(t) = \mathbb{P}_h(\tilde{W}_{ij} \leq t)$ is based on consumers' beliefs over the effective value $\tilde{w}_{ij} = -\alpha p_j + x'_j \beta + \nu_{ij} + \min\{\xi, \varepsilon_{ij}\}$ revealed on position h .

To fully solve (34) for c_d , I utilize the following three assumptions I imposed on consumers' beliefs about the alternatives they will discover:

1. Consumers know the distributions of ν_{ij} and ε_{ij} .
2. The variance of U_{ij}^e does not depend on the position.
3. Consumers have correct beliefs about U_{ij}^e discovered in position \tilde{h} . In this application, I assume that \tilde{h} is the position at the mean rank, such that beliefs are correct in expectation across all positions.

These assumptions imply that it is possible to directly obtain consumers' beliefs on alternatives in position \tilde{h} by sampling from the joint distribution of attributes observed in the data. Hence, using that (34) is equivalent to

$$c_d = \mathbb{E}_{\tilde{h}} \left[\max\{0, \tilde{W}_{ij} - z^d(\tilde{h})\} \right] , \quad (35)$$

c_d can be computed by first obtaining $z^d(\tilde{h})$ from (5) and the estimate of $z^d(1)$, and then calculating the expectation on the right-hand-side using Monte Carlo integration, i.e., by sampling from the empirical joint distribution of hotel attributes.

In principle, it would be possible to do this inversion during estimation, i.e., it would be possible to estimate c_d directly, using the inversion (35) during estimation to obtain $z^d(h) \forall h$, which then enter the likelihood. However, solving (35) requires finding a root that does not admit an analytical solution and, hence, is computationally costly. Moreover, the Monte Carlo integration required to take expectations requires many draws to be accurate, which further adds to the computational cost. Using that (34) is a unique mapping and directly estimating $z^d(1)$ instead of c_d then allows me to circumvent this step during estimation while yielding numerically equivalent results.

D.4 Calculating the Product-Specific Demand

The probability of consumer i of eventually choosing q (i.e., booking hotel q or choosing the outside option if $q = 0$) given parameters θ is given by

$$D_{iq}(\theta) = \int_{-\infty}^{\infty} \mathbb{P}(U_{i0} \leq \tilde{w}_{iq}) \mathbb{P}\left(\max_{j \in A_i(\tilde{w}_{iq})} \tilde{W}_{ij} \leq \tilde{w}_{iq}\right) dH_q(\tilde{w}_{iq}) . \quad (36)$$

This integral can be calculated with a similar procedure for partitioning the probability space. The only difference that the inner probability now depends on

$$\tilde{p}(\tilde{w}_{iq}^r) = \prod_{j \in A_i(\tilde{w}_{iq}^r)} \mathbb{P}(\tilde{W}_{ij} \leq \tilde{w}_{iq}^r) = \prod_{j \in A_i(\tilde{w}_{iq}^r)} \mathbb{P}(Z_{ij}^s \leq \tilde{w}_{iq}^r \cup U_{ij} \leq \tilde{w}_{iq}^r) \quad (37)$$

and $\mathbb{P}(U_{i0} \leq \tilde{w}_{iq}^r)$. Whereas calculating $\mathbb{P}(U_{i0} \leq \tilde{w}_{iq}^r)$ is trivial, calculating $\tilde{p}(l)$ requires calculating a probability of the form $\mathbb{P}(Z_{ij}^s \leq l \cup U_{ij} \leq l)$ where l is some constant. This probability can be written as

$$\mathbb{P}(Z_{ij}^s \leq l \cup U_{ij} \leq l) = \mathbb{P}(Z_{ij}^s \leq l) + \mathbb{P}(Z_{ij}^s \geq l) \mathbb{P}(U_{ij} \leq l \cap Z_{ij}^s \geq l) . \quad (38)$$

$\mathbb{P}(Z_{ij}^s \leq l)$ then can be computed as it is the CDF of ν_{ij} . The second part is the same as (18) in Appendix A.3 and can be computed accordingly.

E Data

The original dataset from Kaggle.com contains 9,917,530 observations on a hotel-consumer level. Following Ursu (2018), I exclude sessions with at least one observation satisfying any of the following criteria:

1. The implied tax paid per night either exceeds 30% of the listed hotel price (in \$), or is less than 1\$.
2. The listed hotel price is below 10\$ or above 1,000\$.
3. There are less than 50 consumers looking for hotels at the same destination throughout the sample period.
4. The consumer observed a hotel in positions 5, 11, 17, or 23, i.e., the consumer did not have opaque offers (Ursu (2018) provides a detailed description of this feature in the data).

The final dataset contains 4,503,128 observations. This number differs from the one in Ursu (2018) by 85 observations. This difference stems from three sessions (IDs 79921, 94604, 373518). For these sessions, the criteria evaluation above yields different result due to differences in the numerical precision. Specifically, I evaluate the criteria with double precision calculations, whereas Ursu (2018) uses the Stata default, single precision.

Completing information on the dataset, Table 12 shows summary statistics for consumers who observed the Expedia ranking, and Table 11 provides a detailed description of each variable.

TABLE 11 – Description Variables

Hotel-level	
Price (in \$)	Gross price in USD
Star rating	Number of hotel stars
Review score	User review score, mean over sample period
No reviews	Dummy whether hotels has zero reviews (not missing)
Chain	Dummy whether hotel is part of a chain
Location score	Expedia’s score for desirability of hotel’s location
On promotion	Dummy whether hotel on promotion
Consumer-level	
Number of items	How many hotels in list for consumer, capped at first page
Number of clicks	Number of clicks by consumer
Made booking	Dummy whether consumer made a booking
Trip length (in days)	Length of stay consumer entered
Booking window (in days)	Number of days in future that trip starts
Number of adults	Number of adults on trip
Number of children	Number of children on trip
Number of rooms	Number of rooms in hotel

TABLE 12 – Summary statistics (Expedia ranking)

	N	Mean	Median	Std. Dev	Min.	Max.
Hotel-level						
Price (in \$)	3,146,022	154.54	129.00	96.54	10.00	1000.00
Star rating	3,084,716	3.31	3	0.87	1	5
Review score	3,143,741	3.92	4.00	0.80	0.00	5.00
No reviews	3,143,741	0.02	0	0.13	0	1
Chain	3,146,022	0.68	1.00	0.47	0.00	1.00
Location score	3,146,022	3.13	3	1.50	0	7
On promotion	3,146,022	0.26	0	0.44	0	1
Session-level						
Number of items	114,529	27.47	31	7.91	5	38
Number of clicks	114,529	1.11	1	0.59	1	24
Made booking	114,529	0.92	1	0.28	0	1
Trip length (in days)	114,529	2.13	2	1.67	1	38
Booking window (in days)	114,529	32.78	14	48.16	0	482
Number of adults	114,529	1.96	2	0.87	1	9
Number of children	114,529	0.37	0	0.77	0	9
Number of rooms	114,529	1.11	1	0.42	1	8

Notes: Summary statistics as in Table 1 for sessions under Expedia ranking.

F Additional Results and Robustness Checks

F.1 Comparing Heuristics for Revenue-Maximization

This appendix compares the different heuristics with the revenue-maximizing ranking when consumers search following the estimated SD model. To compute the revenue-maximizing ranking, I use a brute-force algorithm that iterates over all possible ranking. To make this feasible, I reduce the number of alternatives for each consumer to at most seven and focus on the same (randomly drawn) subsample used in the counterfactual analysis.

Table 13 presents the results. It shows that the bottom-up heuristic (BUR) gets reasonably close to the revenue-maximizing ranking, even as the number of alternatives increases; the decrease in revenues relative to the revenue-maximizing ranking is only 0.37%. This happens despite the BUR leading to a decrease in expected revenues for more than half of consumers, highlighting that when the BUR reduces revenues, the reduction is very small. The utility-maximizing and the R1R heuristic reduce revenues more strongly, with the R1R performing somewhat better and reducing revenues by at most 4.4% percent from the theoretical maximum.

TABLE 13 – Heuristics Relative to Revenue-Maximization

	UR	BUR	R1R
5 alternatives			
Change in total revenues (%)	-6.35	-0.21	-5.06
% consumers with revenue decrease	92.80	32.90	70.80
6 alternatives			
Change in total revenues (%)	-6.31	-0.28	-5.21
% consumers with revenue decrease	97.00	47.60	79.50
7 alternatives			
Change in total revenues (%)	-6.20	-0.37	-4.38
% consumers with revenue decrease	99.40	64.20	84.10

Notes: Predicted changes relative to the revenue-maximizing ranking.

F.2 Effects of Rankings in Randomized Ranking Sample

This appendix presents the comparison of rankings in the randomized ranking sample. It reproduces Table 5, with the difference that no result for Expedia’s ranking is presented. Throughout, the results are in line with the analysis in the main text.

TABLE 14 – Short-Term Ranking Effects (Random Ranking Sample)

	UR	R1R	BUR	PR	-UR
Expedia					
Total revenues	13.27	18.27	19.09	5.24	-11.27
Number of transactions	15.96	11.79	10.56	-4.34	-13.69
Avg. price of booking	-2.32	5.80	7.71	10.01	2.80
Consumers					
Consumer welfare	0.96	0.82	0.94	-0.69	-1.30
Discovery costs	-9.40	-7.17	-7.05	3.79	9.70

Notes: Percentage changes relative to a randomized ranking obtained by averaging across 100 randomizations.

F.3 Robust Position Effects

This appendix presents results for heterogeneous position effects under alternative specifications. Throughout, the results show that the main findings are robust to these alternative specifications. First, I replicate the analysis underlying Figures 1 and 2 for a Probit model and a linear probability model that uses a cubic specification for how position effects change across positions. The results are shown in Figures 10 to 13.

Table 15 presents coefficient estimates for a flexible specification where the position effect is specific to the first three positions and then follows a linear specification for the remaining hotels. This specification is given by

$$\mathbb{P}(Y_{ij} = 1|z_{ij}) = x'_j\beta_1 + w'_i\beta_2 + \sum_{q=2}^3 1(pos_{ij} \geq q)(\gamma_q + x'_j\theta_q) + 1(pos_{ij} \geq 4)(pos_{ij} - 3)(\gamma_4 + x'_j\theta_4) + \tau_d. \quad (39)$$

In this specification, (γ_2, θ_2) capture the position effect on the second position, (γ_3, θ_3) on the third, and (γ_4, θ_4) the on the remaining positions. This is because the position effect on position three is calculated as

$$(\gamma_2 + \gamma_3) + x'_j(\theta_3 + \theta_2) - \gamma_2 - x'_j\theta_2 = \gamma_3 + x'_j\theta_3, \quad (40)$$

and similarly for the other position effects.

Finally, I also estimate the following specification, which allows position effects to be fully flexible across all positions:

$$\mathbb{P}(Y_{ij} = 1|z_{ij}) = x'_j\beta_1 + w'_i\beta_2 + \sum_{q=2}^{37} 1(pos_{ij} = q)(\gamma_q + x'_j\theta_q) + \tau_d. \quad (41)$$

This specification requires estimating many parameters, and showing all results is infeasible. Instead, I present estimates for the relevant parameters θ_q for positions $q \leq 15$ in Figures 14 and 15. For clicks, the results are consistent with the parsimonious specification from the main text: price mutes position effects, while location score, a desirable attribute that also has a strong effect in the parsimonious specification, amplifies position effects. For other variables, the effects are not statistically significant, likely due to there being much less variation in these other attributes.

Given the small booking probabilities, differences in position-specific position effects across different hotels are difficult to identify, as evidenced by the coefficients γ_q not being statistically significant. Nonetheless, even with this extremely flexible specification, price continues to mute position effects for various positions, confirming that cheaper hotels tend to have stronger position effects and that revenue-based rankings indeed face a demand effect.




FIGURE 10 – Heterogeneous Position Effects: Probit

Notes: This figure replicates Figure 1 with estimates from a Probit model. The specification is the same as in columns 2 and 5 in Table 2 without scaling the estimates.




FIGURE 11 – Heterogeneous Position Effects: Probit

Notes: This figure replicates Figure 2 with estimates from a Probit model. The specification is the same as in columns 2 and 5 in Table 2 without scaling the estimates.




FIGURE 12 – Heterogeneous Position Effects: Cubic

Notes: This figure replicates Figure 1 with estimates from a linear probability model where pos_i^2 , $pos_i^2 x_j$, pos_i^3 and $pos_i^3 x_j$ are added to the specification shown in columns 2 and 5 in Table 2.




FIGURE 13 – Heterogeneous Position Effects: Cubic

Notes: This figure replicates Figure 1 with estimates from a linear probability model where pos_i^2 , $pos_i^2 x_j$, pos_i^3 and $pos_i^3 x_j$ are added to the specification shown in columns 2 and 5 in Table 2.

TABLE 15 – Coefficient Estimates (LPM, random ranking)

	Clicks			Bookings		
	(1)	(2)	(3)	(4)	(5)	(6)
1(Position ≥ 2)	-2.4100*** (0.2033)	-5.3510*** (1.3222)	-5.3327*** (1.3047)	0.0053 (0.0506)	-0.2022 (0.2953)	-0.2112 (0.2956)
1(Position ≥ 3)	-2.9828*** (0.1413)	-3.2634*** (0.9013)	-2.9026*** (0.8955)	-0.2108*** (0.0372)	-0.0042 (0.2136)	0.0556 (0.2121)
1(Position ≥ 4) \times (Position - 3)	-0.1412*** (0.0020)	-0.0696*** (0.0123)	-0.0744*** (0.0127)	-0.0094*** (0.0005)	-0.0014 (0.0029)	-0.0022 (0.0030)
Price	-0.0125*** (0.0002)	-0.0253*** (0.0013)	-0.0265*** (0.0013)	-0.0011*** (0.0000)	-0.0021*** (0.0003)	-0.0021*** (0.0003)
On promotion	1.1446*** (0.0497)	1.7599*** (0.3634)	1.8042*** (0.3655)	0.1255*** (0.0130)	0.1395 (0.0884)	0.1497* (0.0900)
Star rating	1.6161*** (0.0317)	2.3110*** (0.2174)		0.1049*** (0.0079)	0.1473*** (0.0498)	
Review score	0.0910*** (0.0350)	-0.5672** (0.2834)		0.0371*** (0.0082)	0.0821 (0.0633)	
No reviews	-0.2126 (0.1618)	-3.1401** (1.3427)		0.0890*** (0.0345)	0.0960 (0.2785)	
Chain	0.2317*** (0.0458)	-0.4027 (0.3213)		0.0252** (0.0113)	0.0814 (0.0760)	
Location score	0.4414*** (0.0168)	0.8734*** (0.1056)		0.0530*** (0.0036)	0.0462** (0.0211)	
1(Position ≥ 2) = 1 \times Price		0.0077*** (0.0018)	0.0074*** (0.0018)		0.0004 (0.0004)	0.0003 (0.0004)
1(Position ≥ 3) = 1 \times Price		0.0026** (0.0013)	0.0024* (0.0013)		0.0002 (0.0003)	0.0003 (0.0003)
1(Position ≥ 4) \times (Position - 3) \times Price		0.0002*** (0.0000)	0.0002*** (0.0000)		0.0000*** (0.0000)	0.0000*** (0.0000)
1(Position ≥ 2) = 1 \times Star rating		-0.0795 (0.2939)			-0.0084 (0.0706)	
1(Position ≥ 3) = 1 \times Star rating		-0.2559 (0.2060)			-0.0289 (0.0522)	
1(Position ≥ 4) \times (Position - 3) \times Star rating		-0.0274*** (0.0029)	-0.0231*** (0.0030)		-0.0006 (0.0007)	-0.0002 (0.0007)
1(Position ≥ 2) = 1 \times Review score		0.4816 (0.3772)			0.0250 (0.0882)	
1(Position ≥ 3) = 1 \times Review score		0.2925 (0.2578)			-0.0387 (0.0639)	
1(Position ≥ 4) \times (Position - 3) \times Review score		-0.0054 (0.0035)	-0.0032 (0.0036)		-0.0023*** (0.0008)	-0.0021** (0.0009)
1(Position ≥ 2) = 1 \times No reviews		2.0626 (1.7817)			0.1972 (0.3907)	
1(Position ≥ 3) = 1 \times No reviews		1.0307 (1.2202)			-0.1711 (0.2836)	
1(Position ≥ 4) \times (Position - 3) \times No reviews		-0.0013 (0.0166)	0.0065 (0.0170)		-0.0027 (0.0035)	-0.0012 (0.0036)
1(Position ≥ 2) = 1 \times Chain		0.3287 (0.4313)			0.0519 (0.1077)	
1(Position ≥ 3) = 1 \times Chain		0.5984** (0.3008)			-0.0883 (0.0794)	
1(Position ≥ 4) \times (Position - 3) \times Chain		-0.0167*** (0.0042)	-0.0141*** (0.0043)		-0.0017 (0.0011)	-0.0009 (0.0011)
1(Position ≥ 2) = 1 \times Location score		-0.1056 (0.1403)			-0.0090 (0.0309)	
1(Position ≥ 3) = 1 \times Location score		-0.3038*** (0.0970)			0.0227 (0.0234)	
1(Position ≥ 4) \times (Position - 3) \times Location score		-0.0036*** (0.0014)	-0.0049*** (0.0014)		-0.0004 (0.0003)	-0.0006* (0.0003)
1(Position ≥ 2) = 1 \times On promotion		-0.0540 (0.4936)	-0.0381 (0.4921)		0.1680 (0.1293)	0.1684 (0.1297)
1(Position ≥ 3) = 1 \times On promotion		-0.4305 (0.3492)	-0.4610 (0.3495)		-0.1963** (0.0979)	-0.2067** (0.0990)
1(Position ≥ 4) \times (Position - 3) \times On promotion		-0.0124** (0.0050)	-0.0130** (0.0051)		0.0004 (0.0013)	0.0005 (0.0013)
FE Hotel	no	no	yes	no	no	yes
N	1,220,917	1,220,917	1,219,253	1,220,917	1,220,917	1,219,253
R2 (adj.)	0.0172	0.0178	0.0291	0.0026	0.0027	-0.0018

Notes: A larger position means being displayed lower on the product list. Coefficient estimates are scaled to represent changes in terms of percentage points. Estimates for query characteristics and interaction of the squared position with other covariates are omitted. Standard errors are shown in parenthesis and are clustered at the query level. Star ratings are adjusted so that the position effect from the first row is for a hotel with 1 star and other characteristics equal to the minimum observed value.




FIGURE 14 – Flexible Heterogeneous Position Effects for Clicks

Notes: This figure shows parameter estimates θ_q in specification (41) estimated on clicks. An increase in position means moving down the list, such that a positive estimate implies that the attribute mutes position effects.




FIGURE 15 – Flexible Heterogeneous Position Effects for Bookings

Notes: This figure shows parameter estimates θ_q in specification (41) for bookings. An increase in position means moving down the list, such that a positive estimate implies that the attribute mutes position effects.