

Pricing Catastrophe Bonds — A Probabilistic Machine Learning Approach*

Xiaowei Chen[†] Hong Li[‡] Yufan Lu[§] Rui Zhou[¶]

Abstract

This paper proposes a probabilistic machine learning method to price catastrophe (CAT) bonds in the primary market. The proposed method combines machine-learning-based predictive models with Conformal Prediction, an innovative algorithm that generates distribution-free probabilistic forecasts for CAT bond prices. Using primary market CAT bond transaction records between January 1999 and March 2021, the proposed method is found to be more robust and yields more accurate predictions of the bond spreads than traditional regression-based methods. Furthermore, the proposed method generates more informative prediction intervals than linear regression and identifies important nonlinear relationships between various risk factors and bond spreads, suggesting that linear regressions could misestimate the bond spreads. Overall, this paper demonstrates the potential of machine learning methods in improving the pricing of CAT bonds.

Keywords and phrases: Catastrophe Bond, Machine Learning, Conformal Prediction, Probabilistic Forecasting, Nonlinear Pricing

JEL Classifications: C22, C51, G11

*We extend our gratitude for the valuable feedback received during various academic events, including the 2023 China International Conference on Insurance and Risk Management, the Actuarial Research Conference 2023, the 2023 INFORMS Annual Meeting, as well as from the engaging seminars held at the University of Connecticut, University of Waterloo, University of Science and Technology of China, and Nankai University. The usual disclaimer applies.

[†]School of Finance, Nankai University, Tianjin 300350, China. Email: chenx@nankai.edu.cn

[‡]Department of Economics and Finance, Gordon S. Lang School of Business and Economics, University of Guelph, Guelph, Canada. Email: lihong@uoguelph.ca

[§]School of Finance, Nankai University, Tianjin 300350, China. Email: yufanlu0121@gmail.com

[¶]Department of Economics, The University of Melbourne, Melbourne, VIC 3010, Australia. Email: rui.zhou@unimelb.edu.au

1 Introduction

Catastrophe (CAT) bonds have become increasingly vital in managing and transferring catastrophic risk. These bonds offer a source of capital to cover losses arising from natural disasters, allowing investors to diversify their portfolios while helping issuers mitigate potentially devastating financial consequences. Understanding the pricing dynamics of CAT bonds is essential, both for investors seeking informed decisions and for issuers optimizing their risk management strategies. This paper introduces a probabilistic machine-learning-based predictive framework for the pricing of CAT bonds, aiming to enhance empirical pricing accuracy and discover previously undetected nonlinear dependence between the key risk factors and CAT bond spreads.

Early research by [Lane \(2000\)](#) laid the groundwork for CAT bond pricing literature, proposing a log-linear regression model employing conditional expected loss and probability of first loss as predictors. Subsequent studies expanded on this linear framework, incorporating additional predictors and examining pricing under diverse conditions. [Gürtler et al. \(2016\)](#) incorporated bond characteristics like trigger type and bond rating, while [Braun \(2016\)](#) integrated market condition indices, such as the Lane Synthetic Rate on Line index and the BB corporate bond spread. [Götze and Gürtler \(2020a\)](#) explored sponsor-related pricing inefficiencies across different market conditions, and [Morana and Sbrana \(2019\)](#) focused on the impact of climate change on CAT bond returns. Further extending the research scope, [Zhao and Yu \(2020\)](#) utilized actual catastrophe data to forecast CAT bond prices using market-based methods, [Braun et al. \(2022\)](#) developed factor pricing models for cross-sectional CAT bond returns, and [Herrmann and Hibbeln \(2023\)](#) investigated liquidity premiums in the secondary market. [Chatoro et al. \(2023\)](#) explored issuer effects in the primary market. However, relying on linear models may lead to oversimplifications, disregarding nonlinear relationships and predictor interactions, potentially limiting predictive accuracy.

To overcome this limitation, recent literature has ventured into more flexible predictive methods. One line of research has focused on the development of structural models for CAT bond pricing. For example, [Lee and Yu \(2002\)](#) studied the pricing of default-risky CAT bonds in the presence of moral hazard and basis risk; [Zhu \(2011, 2017\)](#) proposed pricing formulas by allowing agents to act in a robust control framework against model misspecification; [Lee and Yu \(2007\)](#) proposed a contingent-claim framework for valuing catastrophe reinsurance contracts and catastrophe bonds.

More recently, machine learning models have been introduced to CAT bond pricing, aiming to better

capture the nonlinear dynamics and interactions between predictors. [Makariou et al. \(2021\)](#) introduced the Random Forest method to predict CAT bond spreads which produced superior predictive performance compared to traditional linear models. In addition, [Götze and Görtler \(2020b\)](#) and [Götze et al. \(2023\)](#) applied Random Forest and Neural Network techniques to improve the forecasting accuracy of CAT bond prices.

Machine learning methods often focus on point forecasts. However, considering that predictions often deviate from the actual prices due to market complexity and dynamism, exploring both points forecasts and prediction intervals is equally crucial. Generating prediction intervals for asset prices is standard practice in financial markets. When issuing a CAT bond, the process typically involves an initial offering where the issuer provides a range of spreads to potential investors. Probabilistic forecasts can help the issuer gauge how likely the final spread will fall within a specific range. Repricing can also happen during the issuing process based on investor feedback and market conditions, thereby highlighting the inadequacy of relying solely on point forecasts for informed decision-making and effective risk management. Bond issuers, who seek to transfer risks, should consider not just a single estimate but a credible range of potential costs, including bond spreads in unfavorable scenarios, to realistically appraise the cost of risk transfer. For investors, understanding the possible range where the actual price could fall within is also vital in making informed investment decisions.

While linear regression models readily facilitate the generation of prediction intervals with underlying distributional assumptions, machine learning techniques like Random Forest and Neural Network, while providing more precise price estimates, typically do not yield prediction intervals. This paper aims to combine the accuracy of machine learning predictions with the benefit of probabilistic forecasts in CAT bond pricing.

Our first methodological contribution introduces the use of Extreme Gradient Boosting (XGBoost) ([Chen and Guestrin, 2016](#)) for predicting CAT bond spreads. XGBoost, a robust machine learning tool, employs sequential boosting of weak learners (typically decision trees) to create a strong predictive model. While well-established in other domains, XGBoost has not been applied to CAT bond pricing. Our research explores its potential by comparing its prediction accuracy with that of the widely used linear regression pricing models and Random Forest. We also employ various interpretation tools, including feature importance and accumulated local effects plots, to understand the nonlinear relationships and complex interactions between different risk factors and bond spreads.

The second major contribution of our study applies Conformal Prediction for constructing prediction intervals around point forecasts from machine learning models. Conformal Prediction intervals, studied by [Shafer and Vovk \(2008\)](#), [Angelopoulos and Bates \(2021\)](#), and [Fontana et al. \(2023\)](#), are constructed from the residuals of the trained machine learning model and offer guaranteed coverage of the true response values with user-specified probability. Conformal Prediction is distribution-free and highly flexible, applicable to any prediction model, including Random Forest, Gradient Boosting algorithms, and various Neural Networks. It can even be applied to linear regression models, although this offers little value since producing prediction intervals is straightforward for linear regression models.

Empirically, our study analyzes primary CAT bond market transaction records from January 1999 to March 2021, utilizing data from reputable sources including trade notes provided by Lane Financial LLC, the Artemis Deal Directory, reports from rating agencies, and market research conducted by prominent industry participants such as Swiss Re, Munich Re, Aon Benfield, and Guy Carpenter. Similar data sets with smaller sample sizes were used in existing studies, such as [Braun \(2016\)](#). Our results highlight several advantages of the XGBoost model over traditional linear regression models. Firstly, XGBoost consistently achieves higher out-of-sample forecasting accuracy and generates more informative prediction intervals through Conformal Prediction. These prediction intervals are, on average, 8% narrower than those from linear models, yet they maintain comparable coverage rates. Furthermore, XGBoost effectively handles predictors with high correlations, such as expected loss and probability of first loss, while linear regression models often yield unstable estimates and interpretational challenges due to highly correlated predictors. In linear regression, the usual practice involves removing one of the correlated predictors, but this approach could inadvertently eliminate valuable information inherent in the excluded variable, leading to a less optimal model. XGBoost preserves the information they carry and enhances the model performance by allowing for highly correlated variables. Lastly, our approach reveals the nonlinear effects of several important predictors on CAT bond spreads, including expected loss, probability of first loss, issue size, and reinsurance market cycles. We also observe significant interactions between these predictors. For example, we find that the spread of bonds with higher expected loss values is more sensitive to reinsurance market conditions. In addition, the impact of issue size is negatively correlated with expected loss for bonds with high expected loss values. These nonlinear relationships and complex interactions are naturally captured by the XGBoost model. In summary, this paper extends the existing literature on CAT bond pricing by introducing a probabilistic machine learning approach that improves forecasting

accuracy, and provides probabilistic forecasts as well as insights on the nonlinear effects of various risk factors on CAT bond spread.

The structure of this paper is as follows: Section 2 outlines the methodologies employed in our study, including linear regression, ensemble learning techniques (Random Forest and XGBoost), and the Conformal Prediction approach. Section 3 provides an overview of the CAT bond transaction data and an exploratory analysis. Section 4 presents empirical analysis results and their interpretations. Section 5 constructs Conformal Prediction intervals and conducts the probabilistic analysis of CAT bond spreads. Finally, Section 6 concludes.

2 Methodology

This section introduces the predictive methods used in our analysis. Section 2.1 formulates the bond-yield prediction problem, while Sections 2.2 and 2.3 introduce the linear model and ensemble machine learning methods, respectively. Finally, Section 2.4 outlines the Conformal Prediction approach.

2.1 Problem Formulation

Let us denote the spread of a CAT bond at issuance as Y , and let $\mathbf{X} = (X_1, X_2, \dots, X_p)$ represent p distinct predictors. This predictor vector $\mathbf{X}$ encompasses variables that convey information about bond characteristics, market conditions, and economic indicators. We assume there exists a relationship between Y and $\mathbf{X}$, expressed as:

$$Y = f(\mathbf{X}) + \epsilon.$$

In this equation, f is a fixed but unknown function of $X_1, \dots, X_p$, and ϵ represents a random error term, independent of $\mathbf{X}$, with a mean value of zero. The function f incorporates the systematic information provided by $\mathbf{X}$ regarding Y .

Assume that we have observed a collection of n distinct data points from primary CAT bond market transactions. We use x_{ij} to represent the value of the j th predictor from the i th observation, where $i = 1, 2, \dots, n$ and $j = 1, 2, \dots, p$. Correspondingly, y_i denotes the value of the response variable from the i th observation. We can represent the observed dataset as $D = \{(\mathbf{x}_1, y_1), (\mathbf{x}_2, y_2), \dots, (\mathbf{x}_n, y_n)\}$, where $\mathbf{x}_i = (x_{i1}, x_{i2}, \dots, x_{ip})^T$.

The estimation of f involves exploring the hypothesis space H , which is the set of all feasible functions,

to find a function, denoted as $\hat{f}$, that can predict the response for a new input as accurately as possible. This process, commonly referred to as learning, is guided by minimizing a loss function that quantifies the difference between the true output $(y_1, y_2, \dots, y_n)$ from the observed data and the predicted outputs $(\hat{f}(\mathbf{x}_1), \hat{f}(\mathbf{x}_2), \dots, \hat{f}(\mathbf{x}_n))$.

2.2 Linear Regression

In the existing literature, linear regression is a popular choice for modeling (the transform of) CAT bond spreads. This method assumes a linear structure for f :

$$f(\mathbf{X}) = \beta_0 + \beta_1 X_1 + \beta_2 X_2 + \dots + \beta_p X_p.$$

One advantage of linear regression is its simplicity and ease of interpretation. However, this assumed linear relationship may not always accurately represent the true underlying relationship, which could lead to substantial errors in the predictions.

Typically, a linear regression model is estimated using ordinary least squares, where the estimates of the $p + 1$ coefficients, $\beta_0, \beta_1, \dots, \beta_p$, minimize the sum of the squares of the residuals. Model estimation for linear regression does not require a specific distribution assumption for the error term ϵ . However, for inference, which includes conducting statistical tests and calculating confidence and prediction intervals, a normal distribution assumption is commonly adopted.

2.3 Ensemble Learning

This subsection introduces two ensemble learning methods used in our analysis: Random Forest and XGBoost. An overview of ensemble methods is provided in Section 2.3.1, while Sections 2.3.2 and 2.3.3 explore the specifics of the two ensemble methods.

2.3.1 Overview

Ensemble learning is a widely adopted machine learning technique that leverages the power of multiple models (base learners) to collectively address a problem, resulting in improved accuracy and robustness compared to individual models. Instead of relying on a single function f for estimation, ensemble learning

combines the outputs of multiple functions that approximate f . In this study, we employ two well-established ensemble learning methods: Random Forest and XGBoost.

Ensemble learning uses base learners, often capable of capturing nonlinearity, such as decision trees, to model complex relationships between predictors and the response variable. Consequently, ensemble learning frequently outperforms linear regression in prediction accuracy. However, the amalgamation of multiple models can make the output less interpretable. To better understand the model’s behavior, various strategies, including partial dependence plots and feature importance measures, have been developed to illustrate the significance of individual predictors in model predictions. Nevertheless, the interpretability of an ensemble model remains less straightforward compared to that of a single decision tree or linear regression model.

2.3.2 Random Forest

The Random Forest algorithm, introduced by Breiman (Breiman, 2001), is a potent machine learning technique that combines two strategies: bagging (Breiman, 1996) and random feature selection (Amit and Geman, 1997; Ho, 1995, 1998). The construction of a Random Forest model comprises three steps. First, it generates K bootstrapped samples from the original dataset D . Next, it constructs a decision tree for each bootstrapped sample, using recursive binary splitting with random feature selection. This results in K estimators of the function f , denoted as $\hat{f}_1, \hat{f}_2, \dots, \hat{f}_K$. Finally, to create the Random Forest estimator, these individual estimators are averaged, yielding $\hat{f}(\mathbf{X}) = \frac{1}{K} \sum_{k=1}^K \hat{f}_k(\mathbf{X})$.

Random Forest typically employs fully grown and unpruned decision trees. Averaging results from multiple trees mitigates overfitting, which is a common issue with fully grown trees. Including more trees in a Random Forest model provides a more diverse set of predictions. This, in turn, reduces variance, resulting in a more robust and accurate model. However, the improvement in performance plateaus after a certain number of trees, where additional computation does not lead to substantial gains in model performance. Thus, the number of trees should be carefully chosen to balance computational efficiency and model performance. To increase the difference among trees and thus mitigate overfitting, Random Forest employs column sub-sampling, meaning that it selects only a subset of predictors for each tree.

2.3.3 XGBoost

XGBoost is a variation of the Gradient Boosting Machine (GBM), which was proposed by Friedman (Friedman, 2001, 2002). GBM is an ensemble learning method that has gained popularity for its superior predictive performance and versatility in handling various variable types and loss functions. GBM builds an ensemble of weak models, typically decision trees, iteratively. In each iteration, GBM fits a new model to the residuals of the cumulative prediction of all previous models. This approach focuses more on data points that are challenging to predict accurately, improving overall performance. After training, these weak models are combined to form a strong learner capable of accurate predictions. The GBM estimator is represented as $\hat{f}(\mathbf{X}) = \sum_{b=1}^B \eta \hat{f}_b(\mathbf{X})$, where $\hat{f}_b$ denotes the estimated model from the b th iteration, and η is the learning rate that scales the contribution of each tree, aiming for controlling overfitting. A detailed description of the GBM algorithm is provided in Appendix A, and for more detailed discussions on GBM, readers are referred to Natekin and Knoll (2013).

XGBoost (Chen and Guestrin, 2016) extends GBM in several aspects. Firstly, similar to Random Forest, XGBoost employs column sub-sampling, which reduces overfitting and enhances computational speed. Secondly, while standard GBM implementations stop splitting a node upon encountering negative loss, XGBoost grows the tree to its maximum depth and then prunes it backward to ensure optimal splits are not missed. Furthermore, XGBoost supports monotone and interaction constraints, which could improve model interpretability. Monotone constraints dictate that an increase in a particular feature should consistently lead to an increase (or decrease) in the predicted value of the response variable. This is particularly useful when prior knowledge suggests a monotonic relationship between a predictor and the response variable. For instance, all else being equal, a higher expected loss should lead to a higher bond spread. Interaction constraints specify which variables can interact with each other in the trees, making interactions more controllable and limiting model complexity.

2.4 Conformal Prediction

In this section, we introduce the Conformal Prediction algorithm, which we will use to generate prediction intervals for our ensemble methods. Section 2.4.1 defines the prediction interval, a concept fundamental to Conformal Prediction. Section 2.4.2 provides an overview of Conformal Prediction, while Section 2.4.3 introduces the *Jackknife+* method, a popular choice of Conformal Prediction that we will

employ in our analysis.

2.4.1 Prediction Interval

Ensemble methods like Random Forest and XGBoost only offer point predictions. Asset pricing and risk management problems typically require probabilistic predictions of the outcome. For instance, we are often interested in the prediction uncertainty, such as the 95% prediction region, which is an interval or set that contains the true value of the response variable with at least 95% probability. Formally, consider a set of independent and identically distributed (i.i.d.) training data $\{(\mathbf{x}_1, y_1), \dots, (\mathbf{x}_n, y_n)\}$ and a new observation $(\mathbf{x}_{n+1}, y_{n+1})$ drawn independently from the same distribution. After fitting a model to the training data and obtaining the fitted model $\hat{f}$, we aim to construct a prediction interval around $\hat{f}(\mathbf{x}_{n+1})$ that contains the true test response value with at least $100(1 - \alpha)\%$ probability. This prediction interval, denoted as $C_\alpha(\mathbf{x}_{n+1})$, is defined such that:

$$P(y_{n+1} \in C_\alpha(\mathbf{x}_{n+1})) \geq 1 - \alpha. \quad (2.1)$$

2.4.2 Overview of Conformal Prediction

Conformal prediction is a versatile approach applicable to any pre-trained model for constructing prediction intervals that guarantee coverage of the true response value with a predefined probability (Angelopoulos and Bates, 2021; Fontana et al., 2023; Shafer and Vovk, 2008). Conformal Prediction is distribution-free, meaning that it could generate prediction intervals without any distributional assumptions of the error term. While Conformal Prediction is applicable to both classification and regression problems, we will illustrate how to construct a prediction interval with a regression problem since it is the focus of this paper.

The fundamental idea behind Conformal Prediction is related to a result for sample quantiles. To illustrate the idea, let us first consider a set of generic i.i.d. observations $u_1, \dots, u_n$ from a scalar random variable. For a target coverage level $1 - \alpha$, with $\alpha \in (0, 1)$, and a new observation u_{n+1} drawn independently from the same distribution of $u_1, \dots, u_n$, we have:

$$P(u_{n+1} \leq \hat{q}_{1-\alpha}\{u_1, \dots, u_n\}) \geq 1 - \alpha,$$

where $\hat{q}_{1-\alpha}\{u_1, \dots, u_n\}$ represents the $(1 - \alpha)$ sample quantile of $u_1, \dots, u_n$. The sample quantile is calculated as:

$$\hat{q}_{1-\alpha}\{u_1, \dots, u_n\} = \begin{cases} u_{(\lceil (n+1)(1-\alpha) \rceil)} & \text{if } \lceil (n+1)(1-\alpha) \rceil \leq n \\ \infty & \text{otherwise,} \end{cases}$$

where $u_{(1)} \leq \dots \leq u_{(n)}$ denote the order statistics of $u_1, \dots, u_n$, and $\lceil (n+1)(1-\alpha) \rceil$ is the smallest integer larger or equal to $(n+1)(1-\alpha)$.

Based on this result, a naive way of constructing prediction intervals is to use residuals from the training data to estimate the typical prediction error for the new test data point. Returning to the training data $\{(\mathbf{x}_1, y_1), \dots, (\mathbf{x}_n, y_n)\}$ and a new observation $(\mathbf{x}_{n+1}, y_{n+1})$. Denoting the absolute residual for the i th data point as $r_i = |y_i - \hat{f}(\mathbf{x}_i)|$, the “naive” prediction interval can be constructed by adding and subtracting the $(1 - \alpha)$ sample quantile of the absolute residuals from the point forecasts of y_{n+1} , $\hat{f}(\mathbf{x}_{n+1})$:

$$C_\alpha(\mathbf{x}_{n+1}) = \left[\hat{f}(\mathbf{x}_{n+1}) - \hat{q}_{1-\alpha}\{r_1, \dots, r_n\}, \hat{f}(\mathbf{x}_{n+1}) + \hat{q}_{1-\alpha}\{r_1, \dots, r_n\} \right]. \quad (2.2)$$

Although being rather straightforward, the interval in Equation (2.2) may offer significantly lower coverage than the desired $1 - \alpha$ level due to overfitting, as fitted residuals tend to be smaller than residuals on unseen test points. A number of methods have been proposed to address the underestimation issue of the naive prediction region. The subsection below will introduce a few of these methods, including the *split-set*, the *Jackknife*, and eventually the *Jackknife+* method, which will be used in our analysis.

2.4.3 Jackknife+ Conformal Prediction Interval

One way to avoid the overfitting issue of the naive method is to construct prediction intervals based on residuals from observations not seen during training. Papadopoulos et al. (2002) and Vovk et al. (2005) introduced the *split-set* Conformal Prediction, which divides the training data into two subsets, $\mathcal{S}_1$ and $\mathcal{S}_2$. The model $\hat{f}$ is trained using $\mathcal{S}_1$, while absolute residuals are computed for $\mathcal{S}_2$ to inform the width of the prediction interval.

While splitting the training set reduces overfitting, it introduces extra randomness, as different splits can lead to different Conformal Prediction intervals. To mitigate this randomness, inferences from multiple splits can be combined to obtain a more stable interval. Here, we introduce the procedure of constructing a *Jackknife* Conformal Prediction interval (Barber et al., 2021), which leverages sample quantiles of

leave-one-out residuals for interval definition:

1. Train the model using all observations in the training set, excluding the i th observation: $(\mathbf{x}_1, y_1), \dots, (\mathbf{x}_{i-1}, y_{i-1}), (\mathbf{x}_{i+1}, y_{i+1}), \dots, (\mathbf{x}_n, y_n)$, and denote it as $\hat{f}^{(-i)}$.
2. Calculate the absolute residual for the i th observation, $r_i = |y_i - \hat{f}^{(-i)}(\mathbf{x}_i)|$, using $\hat{f}^{(-i)}$ and the predictor vector $\mathbf{x}_i$.
3. Repeat Steps 1 and 2 for all $i = 1, \dots, n$.
4. Determine the $(1 - \alpha)$ sample quantile of the absolute residuals, $\hat{q}_{1-\alpha}\{r_1, \dots, r_n\}$.
5. Train the model using the entire training set $\{(\mathbf{x}_i, y_i), i = 1 \dots, n\}$ and obtain the trained model $\hat{f}$.
6. The *Jackknife* Conformal Prediction interval for a new observation $(\mathbf{x}_{n+1}, y_{n+1})$ is defined as:

$$C_\alpha(\mathbf{x}_{n+1}) = \left[\hat{f}(\mathbf{x}_{n+1}) - \hat{q}_{1-\alpha}\{r_1, \dots, r_n\}, \hat{f}(\mathbf{x}_{n+1}) + \hat{q}_{1-\alpha}\{r_1, \dots, r_n\} \right].$$

While the *Jackknife* method often empirically achieves $1 - \alpha$ coverage, it does not guarantee finite sample coverage validity. Asymptotic validity is only ensured when non-trivial conditions are satisfied by the trained model (Steinberger and Leeb, 2016). The *Jackknife* prediction interval may exhibit poor coverage when the trained model $\hat{f}$ is unstable due to its lack of finite sample coverage validity.

To address this issue, Barber et al. (2021) introduced the *Jackknife+* method, which copes better with small data sets. It modifies the *Jackknife* procedure by computing $\hat{f}^{(-i)}(\mathbf{x}_{n+1})$ for $i = 1, \dots, n$ and defines the *Jackknife+* Conformal Prediction interval as the interval between the α sample quantile of $\{\hat{f}^{(-i)}(\mathbf{x}_{n+1}) - r_i\}$, $i = 1, \dots, n$, and the $(1 - \alpha)$ quantile of $\{\hat{f}^{(-i)}(\mathbf{x}_{n+1}) + r_i\}$, $i = 1, \dots, n$:

$$C_\alpha(\mathbf{x}_{n+1}) = \left[\hat{q}_\alpha \left\{ \hat{f}^{(-i)}(\mathbf{x}_{n+1}) - r_i, i = 1, \dots, n \right\}, \hat{q}_{1-\alpha} \left\{ \hat{f}^{(-i)}(\mathbf{x}_{n+1}) + r_i, i = 1, \dots, n \right\} \right].$$

The *Jackknife+* method is guaranteed to provide at least $1 - 2\alpha$ coverage and often empirically achieves $1 - \alpha$ coverage, even for small datasets. In the subsequent empirical analysis, we will use the *Jackknife+* method to generate prediction intervals of the ensemble learning methods.

3 Catastrophe Bond Data

Our empirical study focuses on the primary market transactions of CAT bonds. A significant challenge in empirical research on CAT bond pricing is the limited availability of transaction data. To tackle this issue, we adopted the strategy outlined by [Braun \(2016\)](#), which involves aggregating and verifying information from diverse sources. The dataset of CAT bonds used in this study encompasses a total of 765 bond tranches issued between January 1999 and March 2021. This dataset includes various critical bond characteristics, such as expected loss, probability of first loss, covered perils and territories, the trigger mechanism, sponsor information, and credit rating. The data was compiled from trade notes sourced from Lane Financial LLC¹, the Artemis Deal Directory², reports from credit rating agencies, and market research conducted by Swiss Re, Munich Re, Aon Benfield, and Guy Carpenter.

We begin with an exploratory analysis of the dataset. Figures [3.1a](#) and [3.1b](#) depict scatter plots of bond spread in relation to expected loss and the probability of first loss. We can see a strong positive correlation between bond spread and both expected loss and probability of first loss in the sample. While the majority of bonds exhibit expected loss values below 5% and probabilities of first loss below 10%, there are some bonds with relatively high values of these factors. Furthermore, a handful of bonds demonstrate exceptionally large spreads relative to their expected loss or probability of first loss. This observation reveals that factors beyond expected loss and probability of first loss may affect the bond spread.

Figure [3.2a](#) offers an overview of the volume and number of new transactions per year in the primary CAT bond market. We observe a sharp drop in CAT bond volume in 2008 during the financial crisis. This decline can be attributed to the flight-to-quality phenomenon, where investors tend to avoid risky assets during periods of market stress ([Caballero and Krishnamurthy, 2008](#)). However, investor confidence gradually rebounded, leading to a resurgence in CAT bond issuance in 2009 and 2010, with peak activity occurring in 2020. The surge in CAT bond issuance in 2020 was largely influenced by the COVID-19 pandemic, which motivated new issuers to enter the CAT bond market ([Chatoro et al., 2023](#)). Figure [3.2b](#) presents the total issuance volume and the number of new transactions per calendar month. This chart demonstrates that the primary CAT bond market experiences heightened activity during the first, second, and fourth quarters of the year, while activity tends to be quieter in the third quarter. As argued by [Braun \(2016\)](#), the upsurge in issuance volumes towards the end of the calendar year may be linked to

¹Source: <http://lanefinancialllc.com/>.

²Source: <https://www.artemis.bm/deal-directory/>.




Figure 3.1: Scatter plots of bond spread against expected loss (left) and probability of first loss (right) using the 765 bonds in the data set. The horizontal axes are percentage points.

sponsors using securitization to rebalance their firm-wide risk positions before preparing their financial statements. It is interesting to note that our findings differ from those of [Braun \(2016\)](#), which suggested relative inactivity in the first quarter. This discrepancy may arise from the inclusion of more recent transaction data in our study, which extends up to 2021, compared to the data used in [Braun \(2016\)](#)'s analysis, which covers up to December 2012. Over the past decade, the frequency and severity of natural disasters have increased, potentially contributing to greater demand for coverage in the first quarter. The expansion of the insurance-linked securities market is another potential contributor to the increased activity in the first quarter.

In addition to bond-specific data, we consider several market-level indices to proxy the reinsurance market and interest rate cycles. We employ the Lane Financial LLC Synthetic Rate on Line Index (ROLX), published quarterly by Thomson Reuters ILS Community, to represent the global reinsurance cycle. ROLX integrates data from the catastrophe bond, insurance-linked security (ILS), and industry-loss warranty (ILW) markets, thereby reflecting the average premiums paid for ILS and CAT bond-backed reinsurance or retrocession. In addition, we utilize the Guy Carpenter (GC) Global Property Catastrophe Rate on Line indices, covering different regions—Global, US, Asia Pacific, Europe, and UK—as indicators of the premium levels for reinsurance specific to catastrophe risk. These GC indices, published annually, monitor property catastrophe reinsurance rate-on-line movements in major global catastrophe reinsurance






Figure 3.2: The number of CAT bonds issued and the issue volume per year (left) and per calendar month (right).

markets. They are based on reinsurance costs and reflect the expenses incurred in protecting property against catastrophic losses. The GC indices were previously employed by [Gürtler et al. \(2016\)](#) as predictors of CAT bond spreads. A larger value of these reinsurance market indices suggests an upswing in the reinsurance market cycle (i.e., a hard market), when premiums increase, coverage terms are restricted, and capacity for most types of reinsurance decreases. Furthermore, we incorporate the Bank of America Merrill Lynch US High Yield BB Option-Adjusted Spread (BB spread), which is published daily, to capture the influence of the corporate bond markets. This index is calculated as the difference between a yield index for the BB rating category and the Treasury spot curve.

Figure 3.3 depicts the historical trends of ROLX and BB spread from January 1999 to March 2021. We can see that both indices peaked in 2009 due to the financial crisis. In addition, we observe a rising trend in ROLX since 2015, which suggests that global reinsurance demand has been growing faster than the reinsurance capacity, and reinsurance premiums have been increasing over this period. Figure 3.4 illustrates the Guy Carpenter index for the Global, European, US, and Asia Pacific markets. The GC index for UK closely mirrors the European index and is thus omitted from the visualization. While these indices share similar overall trends, they also display distinct patterns. For instance, the global index initially peaked in 2003, experienced a slight decrease, and then surged to a higher peak around 2007. The European index reached its peak in 2005 before gradually declining. The US index spiked in 2008, during the financial crisis. The Asia-Pacific market exhibited two peaks, in 2004 and 2014, respectively.



(a) Synthetic rate on line index




(b) US High Yield BB Option-Adjusted Spread


Figure 3.3: Lane Financial LLC Synthetic Rate on Line Index (left) and the US High Yield BB Option-Adjusted Spread (right) between January 1999 and March 2021.

Tables 3.1 and 3.2 present a range of descriptive statistics for our sample of 765 CAT bonds. Table 3.1 displays the mean, median, standard deviation, maximum, and minimum values for some key variables in the sample. The mean spread across all bonds is 771.38 bps, and the mean expected loss is 244.01 bps. The average risk premium per bond is 527.36 bps, calculated as the difference between spread and expected loss. The spread exhibits considerable variability with values ranging from 66 bps to 4,988 bps. The highest spread is reported by Successor Hurricane Industry Ltd. (Series 3), which was identified as an outlier in Braun (2016). However, since our analysis focuses on machine learning methods that are more robust to outliers than linear regression models, we choose to retain this record in our sample. Similarly, expected losses vary widely, spanning from 1 bps to 1,484 bps. The sample includes CAT bond tranches with sizes ranging from USD \$1.80 million to USD \$1.5 billion, with a median size of USD \$100 million. The CAT bond tranche with an exceptionally large size of \$1.5 billion is from Everglades Re 2014-1 A which covers Florida hurricanes. Terms for CAT bonds in the sample vary from 5 months to 73 months, with a median maturity period of 37 months.


Table 3.2 provides additional descriptive statistics for different categories of CAT bonds in the sample. An analysis of geographic classifications reveals that the majority of the sample consists of US bonds, making up 59.35% of the total. The second-largest category comprises bonds covering multi-territory, accounting for 26.54% of the sample. The frequency of bonds referencing a single territory other than




(a) Guy Carpenter Global RoL Index



(b) Guy Carpenter European RoL Index



(c) Guy Carpenter US RoL Index



(d) Guy Carpenter Asia Pacific RoL Index

Figure 3.4: The Guy Carpenter Rate on Line Index for the Global, European, US, and Asia Pacific markets, respectively, between January 1999 and March 2021.

the United States is relatively low, with Japan, Europe, and *Other* territories representing 6.41%, 6.67%, and 1.05% of the sample, respectively. Japanese peril bonds exhibit the highest average spreads, expected losses, and risk premiums, while bonds referencing *Other* territory generally offer the lowest, likely due to their rarity and valuable diversification characteristics. The risk-return trade-off, measured by multiples of spread to expected loss, varies significantly across different territories. Multiterritory bonds offer the highest multiples at 7.21, while bonds categorized under *Other* territories present the lowest multiples, at 2.65. Furthermore, Japanese bonds and bonds referencing *Other* territory have the smallest and largest average sizes, respectively.

Table 3.1: Descriptive statistics for the 765 CAT bonds in the sample.

	Mean	S.D.	Min	Median	Max
Spread (bps)	771.38	514.64	66.00	634.00	4988.00
Expected Loss (bps)	244.01	233.12	1.00	160.00	1484.00
Risk Premium (bps)	527.36	368.88	65.00	449.00	4363.00
Multiple	6.24	19.08	1.19	3.71	456.00
Size (USD mn)	134.48	114.42	1.80	100.00	1500.00
Term (months)	37.36	12.13	5.00	37.00	73.00

Table 3.2: Descriptive statistics for different categories of CAT bonds in the sample.

	No.	Percent	S ^{CAT} (bps)	EL (bps)	RP (bps)	Multi (bps)	Size (USD mn)	Term (months)
Territory								
Multiterritory	203	26.54	788.12	276.38	511.74	7.21	113.93	39.49
US	454	59.35	753.31	215.88	537.43	6.31	149.50	36.85
Europe	51	6.67	513.67	193.47	320.20	4.86	126.25	38.69
Japan	49	6.41	1199.55	427.61	771.94	3.58	77.90	32.57
Other	8	1.05	392.00	217.12	174.88	2.65	202.50	32.88
Total	765	100						
Peril								
Multiperil	464	60.65	834.12	276.05	558.07	6.82	118.09	39.22
Wind	165	21.57	806.00	220.58	585.42	4.97	143.21	32.65
Earthquake	121	15.82	447.97	139.76	308.21	5.78	181.72	35.89
Other	15	1.96	1058.40	351.67	706.73	6.18	164.31	43.33
Total	765	100						
Trigger								
Indemnity	327	42.75	677.62	219.06	458.55	7.63	158.55	38.94
Other	438	57.25	841.37	262.64	578.73	5.20	116.50	36.17
Total	765	100						
Sponsor								
Other	512	66.93	723.96	227.12	496.84	6.04	152.74	40.34
Swiss Re	253	33.07	867.34	278.21	589.13	6.65	97.52	31.32
Total	765	100						

Peril-specific figures show that wind, earthquake, and multiperil bonds account for 21.57%, 15.82%, and 60.65% of the sample, respectively. Earthquake bonds demonstrate by far the lowest average spreads, expected losses, and risk premiums among all categories while bonds covering *Other* peril have the highest. Among all peril categories, earthquake bonds have the largest average issue and *Other* peril bonds exhibit the longest average term. Regarding trigger types, bonds with an indemnity trigger account for about 42.75% of the sample. CAT bonds with indemnity triggers offer lower average spreads and risk premiums than those with other triggers, despite compensating investors for the moral hazard associated with the insured. This is due to indemnity-trigger bonds having on average lower expected losses. The risk-return trade-off appears attractive for indemnity trigger transactions, as they offer higher average multiples of spread to expected loss than transactions with other triggers by a significant margin. Finally, sponsors are distinguished between Swiss Re and all other institutions. Swiss Re accounts for nearly a third (33.07%) of the tranches in our sample. Swiss Re deals feature higher average spreads and expected losses than other bonds, with their average multiples also being greater.

4 Empirical Analysis

In this section, we provide empirical analyses of CAT bond pricing. Sections 4.1 and 4.2 present results obtained using the linear regression model and two ensemble learning methods, respectively.

4.1 Linear Regression Models

Our analysis begins with constructing an extensive linear regression model, incorporating a range of predictors considered in existing studies (Beer and Braun, 2022; Braun, 2016; Gürtler et al., 2016). The list of predictors and their descriptions are provided in Table B.1. The linear regression model takes the following form:

$$\begin{aligned}
S_i^{\text{CAT}} = & \alpha + \beta_{\text{EL}}\text{EL}_i + \beta_{\text{PFL}}\text{PFL}_i + \beta_{\text{SIZE}}\text{SIZE}_i + \beta_{\text{TERM}}\text{TERM}_i + \beta_{\text{INDEM}}\text{INDEM}_i \\
& + \beta_{\text{WIND}}\text{WIND}_i + \beta_{\text{EQ}}\text{EQ}_i + \beta_{\text{US}}\text{US}_i + \beta_{\text{EU}}\text{EU}_i + \beta_{\text{JP}}\text{JP}_i + \beta_{\text{SR}}\text{SR}_i \\
& + \beta_{\text{IG}}\text{IG}_i + \beta_{\text{ROLX}}\text{ROLX}_i + \beta_{\text{BBSPR}}\text{BBSPR}_i + \beta_{\text{GC.GLOB}}\text{GC.GLOB}_i + \beta_{\text{GC.US}}\text{GC.US}_i \quad (4.1) \\
& + \beta_{\text{GC.AP}}\text{GC.AP}_i + \beta_{\text{GC.EU}}\text{GC.EU}_i + \beta_{\text{GC.UK}}\text{GC.UK}_i \\
& + \beta_{\text{UU}}\text{US}_i \times \text{GC.US}_i + \beta_{\text{JA}}\text{JP}_i \times \text{GC.AP}_i + \beta_{\text{EE}}\text{EU}_i \times \text{GC.EU}_i + \epsilon_i.
\end{aligned}$$

Here, S_i^{CAT} denotes the spread in basis points for the i th bond. The model includes an intercept term, α , 19 predictors, and 3 interaction terms. EL_i , PFL_i , SIZE_i , TERM_i , and INDEM_i represent expected loss (in percentage points), probability of first loss (in percentage points), issue volume (in USD million), term (in months), and trigger type (indemnity trigger or not) for CAT bond i , respectively.

Our model incorporates various dummy variables, each of which takes a value of 1 when a specific condition is met, and 0 otherwise. The dummy variable INDEM_i is set to 1 when CAT bond i uses an indemnity trigger. Similarly, WIND_i and EQ_i are assigned a value of 1 for bonds referencing windstorms (e.g., hurricanes or tornadoes) and earthquakes, respectively. When both WIND_i and EQ_i are assigned a value of 0, it indicates that the bond covers either a different peril or multiple perils. Thus, we combine multiperil and other perils into a single category, which we then use as the reference level. The dummy variables for covered territories include US_i , EU_i , and JP_i , where the value of 1 indicates the connection of a bond to a specific territory (e.g., US or Japan). If none of these variables is set to 1, the bond is tied to a different territory (e.g., Mexico) or multiple territories. Furthermore, SR_i indicates whether CAT bond i is sponsored by Swiss Re, the largest CAT bond sponsor so far, and IG_i is set to one for investment-grade bonds.

The model also includes seven variables to capture market-wide cyclical spread drivers. ROLX_i represents the Lane Financial LLC Synthetic RoL Index, and BBSPR_i denotes the yield spread of BB-rated bonds. The five variables, GC.GLOB_i , GC.US_i , GC.AP_i , GC.EU_i , and GC.UK_i , correspond to the Guy Carpenter Global Property Catastrophe RoL index for the global, US, Asia Pacific, Europe, and UK regions, respectively. For the BB spread, the average value for the quarter before bond issuance is used, while for the remaining indices, the value from the previous year (or quarter) of bond issuance is used. Interaction terms are considered for the most common combinations of territory and Guy Carpenter RoL indices, including $\text{US} \times \text{GC.US}$, $\text{JP} \times \text{GC.AP}$, and $\text{EU} \times \text{GC.EU}$.

To address the potential overfitting problem, we employ variable selection techniques, including LASSO and forward/backward stepwise selection. Table 4.1 presents the estimation results for the full model (4.1), LASSO regression, and the optimal model (with the smallest AIC value) resulting from the stepwise selection. All models are applied to the full sample of 765 bonds. In the full model, the p -value of the coefficient for EL is close to zero, indicating its significance in predicting CAT bond spreads. The coefficient of EL is 179, indicating that a 1% increase in EL would lead to a 1.79% increment of the bond spread, all else equal. The identified strong correlation between EL and bond spread is consistent

with findings in the literature. Nevertheless, approximately one-third of the parameters are statistically insignificant, indicating the need for variable selection. We also find that the coefficient estimate for PFL is negative and not statistically significant, which seems counter-intuitive. A positive correlation between PFL and CAT bond spreads is well-documented within the literature, as evidenced by [Lane \(2000\)](#), [Wills and Sherris \(2010\)](#), and [Beer and Braun \(2022\)](#). Our finding can be attributed to a high degree of collinearity between PFL and EL, as indicated by Figures [3.1a](#) and [3.1b](#). Such collinearity can lead to coefficient estimates that are unstable and also result in inflated standard errors. While collinearity may not compromise the overall predictive capacity, it poses challenges to the interpretability of the regression coefficients within the model. For the same reason, coefficients for the Guy Carpenter indices and their p -values should be interpreted with caution due to the multi-collinearity among them.

The model derived from LASSO regression removes six variables, PFL, WIND, US, EU, GC.UK, and JP×GC.AP, from the full model, resulting in slightly lower R^2 and adjusted R^2 compared to the full model. The optimal model from step-wise variable selection excludes PFL, SIZE, INDEM, WIND, US, EU, and JP, six of which were found to be insignificant in the full model. By excluding these non-significant variables, the optimal step-wise model achieves the highest adjusted R^2 among the three models assessed. Moreover, all variables included in the optimal model are statistically significant.

The coefficients in the selected model exhibit the expected signs. For example, bonds covering earthquakes have on average lower spreads, as do bonds issued by Swiss Re or those with an investment-grade rating. It is worth noting that the negative coefficient associated with SR does not contradict the descriptive statistics in [Table 3.2](#), where bonds issued by Swiss Re are shown to have higher spreads on average. This discrepancy arises because bonds issued by Swiss Re typically have a higher average EL, leading to higher spreads. However, when all else is equal, the linear regression model predicts that having Swiss Re as the issuer tends to lower bond spreads.

Table 4.1: Estimation results of the linear regression model, including the full model (4.1), LASSO, and the optimal model selected using step-wise backward and forward variable selection, respectively. Significance levels: ‘***’ < 0.001, ‘**’ < 0.01, ‘*’ < 0.05, ‘.’ < 0.1.

	Full Model				LASSO		Step-wise Selection		
	Coeff.	Std.	p-Val.	Sig.	Coeff.	Std.	p-Val.	Sig.	
(Intercept)	-149.58	120.39	0.21		-177.64	104.46	0.10		
EL	179.05	17.22	<2e-16	***	165.41	165.68	<2e-16	***	
PFL	-9.03	12.40	0.47		.				
SIZE	0.11	0.09	0.21		0.05				
TERM	-3.34	0.93	0.00	***	-3.30	0.88	0.00	***	
INDEM	14.62	23.15	0.53		1.19				
WIND	-1.64	28.51	0.95		.				
EQ	-182.26	31.86	0.00	***	-171.87	28.16	0.00	***	
US	-61.24	90.76	0.50		.				
EU	20.64	198.08	0.92		.				
JP	-516.14	270.93	0.06	.	-42.72				
SR	-65.96	23.34	0.00	**	-58.17	22.91	0.00	**	
IG	-200.22	53.18	0.00	***	-187.51	52.81	0.00	***	
ROLX	3.22	0.83	0.00	***	3.34	0.82	0.00	***	
BBSPR	0.32	0.08	0.00	***	0.26	0.08	0.00	***	
GC.GLOB	2.41	0.68	0.00	***	2.37	0.67	0.00	***	
GC.US	-2.14	0.50	0.00	***	-2.15	0.42	0.00	***	
GC.AP	-2.78	0.59	0.00	***	-1.76	0.58	0.00	***	
GC.EU	7.84	2.76	0.00	**	2.86	2.72	0.00	**	
GC.UK	-7.08	4.10	0.08	.	.	4.06	0.07	.	
JP×GC.AP	2.70	1.52	0.08	.	.	1.51	0.07	.	
US×GC.US	0.83	0.50	0.10	.	0.46	0.12	0.00	***	
EU×GC.EU	-1.73	1.50	0.25		-1.51	0.30	0.00	***	
<i>R</i> -squared	0.775				0.772		0.7741		
<i>R</i> -squared Adj	0.7684				0.7635		0.7693		

4.2 Machine Learning Methods

We now proceed to the application of Random Forest and XGBoost models to CAT bond pricing. In these models, we incorporate all the variables in Equation (4.1), except interaction terms. The exclusion of interaction terms is deliberate, as machine learning models inherently capture interactions between variables. We keep both PFL and EL in the fitting of Random Forest and XGBoost models since tree-based methods are less sensitive to collinearity. However, high collinearity can still affect the interpretation of tree-based models, particularly when it comes to understanding the importance or impact of individual predictor variables. We will discuss this further in Section 4.3.2. To avoid overfitting and improve model performance, machine learning methods often require careful tuning of hyperparameters. This tuning process employs an exhaustive grid search of a predefined set of hyper-parameters to identify the combination that optimizes cross-validation prediction accuracy. Key hyperparameters for both models and their optimal values obtained through grid search are presented in Table B.2.

To evaluate the predictive accuracy of the machine learning and linear regression models, we perform a validation process involving 1,000 random data splits. For each split, 80% of the observations are randomly selected as the training set for tuning and training the models, while the remaining 20% forms the test set for assessing predictive performance. The out-of-sample mean squared errors (MSE) are calculated for each model and split on the test set. The resulting average test MSEs across the 1,000 splits for the XGBoost, Random Forest, as well as the linear regression models selected by the step-wise procedure and LASSO, are presented in Table 4.2. We can see that the two linear regression models produce similar forecasting results, and the two machine learning models generate more accurate forecasts than their linear counterparts. XGBoost produces the lowest average test MSE across all models. Therefore, we select XGBoost as the preferred machine learning model for the subsequent analysis.

Table 4.2: Average test MSE using 1,000 random training/test splits.

Model	Average test MSE
XGBoost	0.0004580
Random Forest	0.0005287
Linear regression (step-wise selection)	0.0006487
Linear regression with Lasso regularization	0.0006439

4.3 Interpreting the Trained XGBoost Model

We now proceed to interpret the results of the XGBoost model fitted with the hyperparameter values presented in Table B.2 to the full sample. To achieve this, we employ feature importance and accumulated local effects (ALE) plots, both widely used tools for interpreting machine-learning-based models.

4.3.1 Feature Importance Plots

Figure 4.1 presents the relative importance of each feature in the trained XGBoost model, measured by its contribution to improving the goodness of fit of the model. The plot shows that expected loss is the most important variable for explaining CAT bond spreads, in line with the findings in existing studies and the linear regression models. In contrast to the linear regression models, it is interesting to note that PFL is also important in improving the predictive power of the XGBoost model even after including EL. This suggests that despite the high correlation between EL and PFL, the latter still contributes additional useful information in predicting CAT bond spreads. The linear regression model likely excludes PFL due to its nonlinear contribution to the spreads, a characteristic that XGBoost can capture.

Besides EL and PFL, it is also worth considering the roles of other variables in the model. The Lane Financial LLC Synthetic RoL Index, ROLX, ranks as the second most important variable in the XGBoost model. Besides, the Guy Carpenter indices, GC.EU and GC.GLOB, designed to track the changes in reinsurance pricing for property catastrophe coverage in the European and global markets respectively, rank as the fifth and sixth most important. These observations are consistent with the fact that CAT bond investors expect a return that is commensurate with the risk they are taking, and this return is often benchmarked against the cost of traditional reinsurance. If reinsurance rates rise, investors demand higher yields from CAT bonds too. The pricing of reinsurance also reflects the market perception of risk, particularly for catastrophic events. Changes in reinsurance prices may signal a change in the perceived risk of catastrophic events, which affects CAT bond pricing as investors and issuers reassess the risk-return profile. The importance of the three indices—ROLX, GC.EU, and GC.GLOB—is also observed in the linear regression model.

SIZE ranks as the fourth most important variable in the XGBoost model, while this variable was excluded from the linear regression model selected with the step-wise procedure (c.f. Table 4.1). The exclusion of SIZE from the linear regression model could arise from the nonlinear relationship between




Figure 4.1: Feature importance plot for the XGBoost model.

SIZE and the bond spread and potential collinearity with other variables, which complicates the isolation of its unique contribution in a linear framework. XGBoost model can capture nonlinear relationships and interactions and is more robust to collinearity since it selects features based on their contribution to improving predictions across multiple decision trees. As a result, the XGBoost model recognizes the importance of SIZE even in the presence of correlated predictors. Finally, variables considered important in the linear regression model, such as IG and GC.US, contribute minimally to the goodness of fit in the XGBoost model.

4.3.2 Accumulated Local Effect Plots

The feature importance plot provides an initial overview of the relative contribution of each predictor to the model. However, this plot alone does not reveal how each predictor affects the CAT bond spreads. To address this, we further explore the impact of the six most important predictors on CAT bond spreads

by examining their accumulated local effect (ALE) plots, as shown in Figure 4.2. All ALE plots are centered to obtain an average of zero for enhanced interpretability. ALE plots are similar to the widely used partial dependence plots (PDP) but address the bias that arises in PDP when predictors are highly correlated (Apley and Zhu, 2020). For instance, as EL and PFL are highly correlated, it is unlikely that a CAT bond would have a very high EL and very low PFL simultaneously, or vice versa. PDPs are not able to cope with such situations as they rely on marginal distributions of the predictors. Consequently, when evaluating the impact of EL on bond spreads, PDPs treat EL independently with all other predictors, and would consider unrealistic cases, for example, in which EL is high and PFL is very low. ALE plots rely on conditional distributions, and thus account for the correlation among predictors, leading to more accurate interpretations of the estimated model. Hence, the ALE plot is a more appropriate choice for our analysis considering the potential high correlations among predictors.

From Figure 4.2, nonlinearity is observed in the ALE plots. Expected loss shows the strongest impact on bond spreads. When EL is close to zero, the bond spread is approximately 350 bps lower than the average bond spread. As EL increases to 15%, the bond spread rises to approximately 1,250 bps higher than the average bond spread. For EL values below 5%, there is an almost linear relationship, where bond spreads increase with the expected loss. Beyond the 5% threshold, the relationship becomes less straightforward. A sharp increase in bond spread is observed as EL increases from 5% to 6.25%. Nevertheless, as EL progresses from 6.25% to 10%, the increase in bond spread is minimal. For EL values beyond 10%, the bond spread experiences a modest increase with EL. Caution should be taken in interpreting the section with large EL values exceeding 10%, due to the limited number of observations in this range.

The ALE plot for PFL indicates that higher probabilities of first loss are associated with increased bond spreads. This observation aligns with existing literature (Beer and Braun, 2022) that identifies a positive correlation between PFL and bond spread. However, our interpretation differs significantly. In Beer and Braun (2022), where only PFL is used as a predictor, the effect of EL is indirectly captured by PFL due to their high correlation. Consequently, the impact attributed to PFL in their model is a combined effect of both PFL and EL. In contrast, our XGBoost model incorporates both PFL and EL as predictors, with EL being identified as the most significant factor. Given their strong correlation, much of the information represented by PFL is also encompassed within EL. As a result, PFL contributes to the XGBoost model with information that is not already accounted for by EL. Therefore, the XGBoost




Figure 4.2: Accumulated local effects plots for the six most important predictors in the XGBoost model.

model effectively utilizes all the information contained in EL and PFL. The impact of this additional information in PFL is captured in the ALE plot.

The impact of PFL on the bond spread is most significant at lower levels of PFL and diminishes to almost zero as PFL exceeds 5%. This indicates that at lower PFL values, investors are sensitive to changes in PFL and demand a higher spread for an increased PFL. However, as PFL reaches higher levels, further increases in PFL appear to only have a moderate impact on bond spread. A likely explanation for this observation is that when PFL is high, EL tends to be high as well due to their correlation. In such cases, investors may become less sensitive to small increases in PFL, shifting their focus more towards EL as the more influential factor in their decision-making process.

The impacts of ROLX and GC.EU on bond spreads also exhibit clear non-linear patterns. The impact

of GC.GLOB on the bond spread is similar to but less significant than that of ROLX and GC.EU. Both ROLX and GC.EU have a modest influence on bond spread when their values are below 120 which signifies a relatively soft reinsurance market. In a soft market, there is generally an abundance of capital and a competitive environment. Investors might also perceive lower risk in this environment, resulting in a lower impact of changes in reinsurance market conditions on CAT bond spreads. In addition, CAT bonds can be viewed as alternatives to traditional reinsurance products. Reinsurance is still the dominant risk transfer mechanism for catastrophe risks and the risk transfer choice reflects the trade-off between the benefits and costs of reinsurance relative to CAT bond (Subramanian and Wang, 2018). In a soft reinsurance market, where reinsurance capacity is ample and premiums are low, entities with hedging needs are more inclined to opt for reinsurance products rather than issuing CAT bonds. Small increases in reinsurance premiums are unlikely to divert these entities towards the CAT bond market, as the increased premiums remain affordable. Therefore, CAT bond spreads remain low and insensitive to reinsurance market conditions when the market is soft.

As the reinsurance market hardens, reflected by increased ROLX and the GC indices, there is tighter capital, higher demand for coverage, and increased perception of risk. Investors seek higher returns for assuming the same risks. The impact of ROLX and GC.EU on bond spread becomes more pronounced which is indicated by a steep increase in their corresponding ALE plots. Due to the limited capacity and high premiums in the reinsurance market, more entities with hedging demands turn to CAT bonds to transfer their risks. If reinsurance premiums continue to rise, more entities may shift towards the CAT bond market and thus drive up CAT bond spreads. This explains why CAT bond spreads are more sensitive to the reinsurance market conditions when the market is hard.

Our analysis also indicates that CAT bond spreads tend to increase with the issue size, particularly for issues smaller than 500 million US dollars. This observation is in contrast to the findings of Braun (2016), who reported a negative impact of issue size on spreads. This difference results from the incorporation of GC indices in our model, which exhibit a moderate negative correlation (Pearson correlation of -0.27 for GC.EU and -0.21 for GC.GLOB) with the issue size. The negative correlation suggests that in a hardening market, characterized by tighter capital and higher perceived risks, CAT bond issue sizes tend to decrease. Therefore, issue size may serve as a weak indicator of market cycle conditions. In the absence of Guy Carpenter indices as predictors, as in the analysis by Braun (2016), the observed negative impact of issue size on spreads could primarily reflect the effect of a hardening market. By incorporating GC

indices as predictors in our model, we can distinguish the specific impact of issue size on bond spreads from the effects captured by the GC indices. The ALE plot suggests that in a hard market, where the issue size is often small, an increase in issue size is associated with an increase in bond spread.


Overall, the ALE plots highlight the presence of significant nonlinear relationships between key risk factors and CAT bond spreads. Failing to account for these nonlinear patterns could potentially lead to inaccurate estimations of bond spreads.

4.3.3 Second-Order Accumulated Local Effects Plots


Machine learning models like Random Forest and XGBoost naturally account for interaction effects between predictors, an advantage over linear regression where interactions must be explicitly defined. To visualize these interactions within the estimated XGBoost model, we utilize second-order ALE plots. While first-order ALE plots illustrate the “main” effect of individual predictors, second-order ALE plots reveal the *additional* joint impact of predictor pairs on the response variable.

As an illustration, Figure 4.3 displays second-order ALE plots for four predictor pairs: EL & ROLX, EL & SIZE, EL & GC.EU, and EL & GC.GLOB. The contour values on these plots indicate the strength of the joint impact. All four plots demonstrate clear interaction effects between the respective predictor pairs since the contour values vary significantly in each plot. The magnitude of these values is smaller compared to the ALE values depicted in Figure 4.2, suggesting that while these second-order effects are significant, they are generally smaller than the main effects of the individual predictors.


We first examine Figure 4.3a, which displays the interaction between EL and ROLX. At an EL value of 2%, an increase in ROLX from 120 to 140 does not change the spread. In contrast, at an EL of 8%, the same increase in ROLX results in an 80 bps decrease in the spread, thereby suggesting a negative interaction between EL and ROLX. It is important to note that the second-order ALE effect is exclusive of the main effect. To fully understand the impact of ROLX on the spread given the EL value, one must also consider the main effect of an increase in ROLX which is positive for ROLX within the range of 120–140. Specifically, an increase in ROLX from 120 to 140 results in approximately a 140 bps increase in the spread of a bond with a 2% EL, as illustrated in Figure 4.2. However, this increase translates to only a 60 bps (140 bps – 80 bps) spread increase when EL is 8%. Therefore, for bonds with a higher EL, the impact of ROLX on the spread is still positive but weakened after combining the main and second-order effects.




(a) EL (x-axis) and ROLX (y-axis)



(b) EL (x-axis) and SIZE (y-axis)



(c) EL (x-axis) and GC.EU (y-axis)



(d) EL (x-axis) and GC.GLOB (y-axis)

Figure 4.3: Second-order ALE plots of four selected predictor pairs.

Analysis of Figure 4.3b indicates that at an EL value of 2%, the increase in SIZE from 150 to 250 has a minimal effect on the spread. Nevertheless, the same increase in SIZE results in approximately 45 bps decrease in the spread when EL is 10%, suggesting a negative interaction between EL and SIZE. We have observed a positive main effect of SIZE on bond spread in Figure 4.2. The negative interaction between EL and SIZE suggests that an increase in issue size leads to a less pronounced rise, or even decrease, in the spread for bonds with a higher EL. Considering that the main effect of SIZE on the spread is relatively modest, as depicted in Figure 4.2, it is conceivable that the combined main and interaction effects of certain increases in SIZE could result in a negative impact on the spread for bonds with a high EL.

Figures 4.3c and 4.3d depict the interactions between EL and the Guy Carpenter indices, GC.EU and GC.GLOB, respectively. These interactions exhibit a complex pattern, neither consistently positive nor negative. For instance, at an EL value of 2%, increasing GC.EU from 140 to 160 does not affect the spread. At an EL of 4%, this same increase in GC.EU is associated with an increase in the spread. Interestingly, at an EL of 8%, an identical change in GC.EU results in a decrease in spread. The XGBoost model, with its tree-based structure, can capture these complex interactions, and thus offer more flexibility and higher prediction accuracy over models that assume linear relationships.

5 Probabilistic Analysis

In this section, we examine the probabilistic predictions produced by the linear regression model with normally distributed error terms and XGBoost employing the *Jackknife+* prediction intervals introduced in Section 2.4.3. Section 5.1 presents the mean forecasts and prediction intervals generated by these two approaches. Section 5.2 further studies the conditional impact of expected loss and its interacting effects with a number of other factors.

5.1 Prediction Intervals

We first investigate the prediction intervals produced by the linear regression and the *Jackknife+* Conformal Prediction with the XGBoost model. To this end, we randomly divide the full sample into a training set consisting of 80% of the data, and a test set with the remaining 20%. Both models are trained and tuned on the training set. Figure 5.1 presents the point forecasts (solid lines) and the corresponding 95% prediction intervals (shaded areas) produced by both models on the test data. The observed bond

spreads (grey circles) are also depicted for reference and arranged in the order of their EL values. We observe that both models produce prediction intervals with a coverage close to the 95% target, while the coverage produced by XGBoost is slightly higher. Nevertheless, the average length of the prediction interval produced by XGBoost is approximately 13% smaller than that generated by the linear regression model. This suggests that the combination of Conformal Prediction with XGBoost yields more informative and precise prediction intervals.




Figure 5.1: Mean forecasts and the 95% prediction intervals for the test data generated by the linear regression and XGBoost with *Jackknife+*.

The results in Figure 5.1 are based on one random split, and thus could be subject to randomness in data splitting. To evaluate the robustness of this result, we calculate the average coverage and length of the 95% prediction intervals generated by the linear regression and XGBoost with *Jackknife+* based on the 1,000 random splits of the full sample that are used in Table 4.2. The results are presented in Table 5.1. We can see that, similar to the results in Figure 5.1, the XGBoost with *Jackknife+* model generates prediction intervals with average coverage closer to the desired 95% level and average length 8% smaller than the linear regression models.

Table 5.1: Average coverage and length of the 95% prediction intervals generated by the linear regression and XGBoost with *Jackknife+* using 1,000 random training/test splits.

Model	Average Coverage	Average Length
Linear Regression	0.9568	958.85
XGBoost + Conformal Prediction	0.9499	886.43

5.2 Conditional Predictions

We further explore the conditional impact of several key risk factors using both linear regression and XGBoost models. Conditional impact refers to the effect of a single predictor on the predicted outcome, while keeping all other variables constant. To compute these conditional impacts, we initially calculate conditional predictions by varying the value of the risk factor under examination while holding all other factors at their median values for continuous variables or at the most common category for categorical variables. This process enables us to isolate and assess the impact of the specific risk factor. Furthermore, prediction intervals can be computed for these pseudo-observations, offering insights into the variation in conditional predictions.

Figure 5.2 depicts the conditional predictions of bond spreads across various EL values generated by both the linear regression model (red line) and XGBoost (blue line), and their corresponding 95% prediction intervals (shaded areas). Firstly, while the linear regression model predicts a linear impact of EL on CAT bond spreads, the XGBoost model exhibits nonlinear effects. Specifically, while increasing EL will in general lead to larger spreads, this effect is more pronounced for smaller EL values, and levels off when it exceeds 7%. Secondly, the linear regression model consistently yields higher spreads compared to XGBoost for all EL values. This observation suggests that the linear regression model tends to overestimate bond spreads, particularly for larger EL values. Importantly, the mean forecast produced by the linear regression model lies outside the 95% prediction interval generated by Conformal Prediction for the majority of EL values considered. This observation indicates that the overestimation by the linear model could be substantial.

Figure 5.2 examines the conditional impact of EL on bond spread while all other risk factors are set at the median value or the most common category. We now further investigate the impact of EL under different reinsurance market conditions which are represented by ROLX values. Figure 5.3 displays the conditional impact of EL in three reinsurance market conditions. The blue line represents a hard reinsurance market, where the ROLX value is set as the average of the top 10% values, which is 144. The




Figure 5.2: The conditional impact of expected loss on CAT bond spreads. All other risk factors are set to their median values (for continuous variables) or the most common type (for categorical variables).

yellow line depicts a soft reinsurance market, where ROLX averages the bottom 10% value, 88. Finally, the red line corresponds to a normal market, with ROLX set at the median value, 116. Figures 5.3a and 5.3b present the predictions generated by the XGBoost and linear regression models, respectively, along with 95% prediction intervals for each conditional prediction.

Figure 5.3a demonstrates that using the XGBoost model, the shape of conditional prediction curves remains largely consistent across varying market conditions for different EL values, indicating a persistent nonlinear relationship between EL and spread. Nevertheless, the shifts of the conditional predictions across market conditions are not parallel. First, shifts from soft to normal market conditions result in only modest changes in conditional predictions for EL values below 7%, as evidenced by the close alignment of the red and yellow lines over this interval. This observation suggests that transitions from soft to normal market conditions have minor effects on the spreads of CAT bonds with lower EL values. However, a transition from normal to hard market conditions leads to a significant increase in conditional predictions for the same EL values. This indicates a lower investor sensitivity to the reinsurance market cycle in softer conditions, whereas in hard markets, characterized by constrained capacity and rising premiums, investors seek higher returns to offset the risks associated with CAT bonds, even those with lower EL values. Second, the upward shifts of bond spreads have comparable sizes for higher EL values when the reinsurance market transitions from soft to normal, and from normal to hard. This suggests that CAT

bonds with higher EL values are sensitive to the tightening of reinsurance market conditions, even when the market is soft. These non-parallel changes of conditional impact curves across market conditions suggest an interaction between reinsurance market conditions and expected loss. In contrast, in Figure 5.3b where the linear regression model is applied, the conditional prediction curve shifts in parallel with changes in market conditions. The equal magnitude of shift, when market condition changes, reflects that the linear regression model only captures the linear effects of ROLX.




Figure 5.3: Conditional impact of expected loss on CAT bond spreads under different reinsurance market conditions implied by XGBoost (left) and the linear regression model (right).

Figure 5.4 illustrates the conditional impact of EL for bonds with different issue sizes. The blue line represents a high issuance volume, where the SIZE value is set as the average of the top 10% values, amounting to \$374.5 million. The yellow line depicts a low issuance volume, averaging the bottom 10% value, which is \$14.96 million. The red line corresponds to a median SIZE value of \$100 million. Two observations consistent with Figures 4.2 and 4.3b can be drawn. First, for small EL values, bonds with low issuance volumes generally have lower spreads compared to those with high or medium issuance volumes. This indicates that SIZE has a positive impact on bond spreads. However, this impact appears to be relatively minor. Second, when EL is large, SIZE exhibits a negative impact on spread. This is attributed to the negative interaction between SIZE and EL, the impact of which is stronger for high EL values, as discussed in Section 4.3.3.




Figure 5.4: Conditional impact of expected loss on CAT bond spreads with different sizes.

6 Conclusion

In this study, we employ probabilistic machine learning techniques to analyze CAT bond pricing. Specifically, we use the XGBoost ensemble learning method to generate point forecasts of bond spreads, accompanied by Conformal Prediction to construct prediction intervals. This machine learning method has demonstrated improved prediction accuracy and more reliable prediction intervals compared to widely used linear regression models. It also provides insights into the complex relationships between various risk factors and CAT bond spreads and interaction effects among risk factors.

Our analysis utilizes a comprehensive dataset of primary market CAT bond transactions from January 1999 to March 2021. We begin with extensive linear regression models, and then proceed to feature selection through Lasso Regression and a stepwise approach. This process identifies expected loss (EL) as a primary predictor of CAT bond spreads, while another important risk factor, the probability of first loss (PFL), is excluded due to its strong correlation with EL. When employing the XGBoost model, interestingly, PFL is identified as the third most important factor. This indicates that, even with its correlation to EL, PFL offers valuable predictive information not captured by EL alone. Nonlinear impact on bond spread has been observed from factors such as EL, PFL, issue size, and market-wide indices representing reinsurance market conditions. Additionally, we uncover nontrivial interacting effects among these factors. Furthermore, we find that the XGBoost model, combined with the Conformal Prediction

method, consistently produces not only more accurate point forecasts but also prediction intervals that are closer to the desired coverage level and exhibit smaller lengths.

This study advances our understanding of CAT bond pricing dynamics through machine learning techniques. These advancements offer tangible benefits to stakeholders in the CAT bond market, including investors, issuers, and policymakers. The improved understanding of risk factors and market sensitivities we provide is crucial for effective risk management and strategic decision-making. Future research could explore the nonlinear relationships revealed in this study, incorporate additional risk factors, and expand our dataset to further improve prediction accuracy. In addition, experimenting with alternative machine learning algorithms may offer new insights into the evolving landscape of CAT bond pricing. Finally, investigating the pricing dynamics of CAT bonds in the secondary market presents an intriguing avenue for future exploration.

Acknowledgement Hong Li is supported in part by funding from the Social Sciences and Humanities Research Council [430-2022-00401].

References

- Amit, Y. and Geman, D. (1997). Shape quantization and recognition with randomized trees. *Neural computation*, 9(7):1545–1588.
- Angelopoulos, A. N. and Bates, S. (2021). A gentle introduction to conformal prediction and distribution-free uncertainty quantification. *ArXiv*, 2107(07511).
- Apley, D. W. and Zhu, J. (2020). Visualizing the effects of predictor variables in black box supervised learning models. *Journal of the Royal Statistical Society Series B: Statistical Methodology*, 82(4):1059–1086.
- Barber, R. F., Candès, E. J., Ramdas, A., and Tibshirani, R. J. (2021). Predictive inference with the jackknife+. *The Annals of Statistics*, 49(1):486 – 507.
- Beer, S. and Braun, A. (2022). Market-consistent valuation of natural catastrophe risk. *Journal of Banking & Finance*, 134:106350.

- Braun, A. (2016). Pricing in the primary market for cat bonds: new empirical evidence. *Journal of Risk and Insurance*, 83(4):811–847.
- Braun, A., Herrmann, M., and Hibbeln, M. T. (2022). Common risk factors in the cross section of catastrophe bond returns. *Available at SSRN 3901695*.
- Breiman, L. (1996). Bagging predictors. *Machine learning*, 24:123–140.
- Breiman, L. (2001). Random forests. *Machine learning*, 45:5–32.
- Caballero, R. J. and Krishnamurthy, A. (2008). Collective risk management in a flight to quality episode. *The Journal of Finance*, 63(5):2195–2230.
- Chatoro, M., Mitra, S., Pantelous, A. A., and Shao, J. (2023). Catastrophe bond pricing in the primary market: The issuer effect and pricing factors. *International Review of Financial Analysis*, 85:102431.
- Chen, T. and Guestrin, C. (2016). Xgboost: A scalable tree boosting system. In *Proceedings of the 22nd ACM SIGKDD International Conference on Knowledge Discovery and Data Mining*, KDD ’16, page 785–794, New York, NY, USA. Association for Computing Machinery.
- Fontana, M., Zeni, G., and Vantini, S. (2023). Conformal prediction: a unified review of theory and new challenges. *Bernoulli*, 29(1):1–23.
- Friedman, J. H. (2001). Greedy function approximation: A gradient boosting machine. *The Annals of Statistics*, 29(5):1189–1232.
- Friedman, J. H. (2002). Stochastic gradient boosting. *Computational Statistics & Data Analysis*, 38(4):367–378. Nonlinear Methods and Data Mining.
- Götze, T. and Gürtler, M. (2020a). Hard markets, hard times: On the inefficiency of the cat bond market. *Journal of Corporate Finance*, 62:101553.
- Götze, T. and Gürtler, M. (2020b). Risk transfer and moral hazard: An examination on the market for insurance-linked securities. *Journal of Economic Behavior & Organization*, 180:758–777.
- Götze, T., Gürtler, M., and Witowski, E. (2023). Forecasting accuracy of machine learning and linear regression: evidence from the secondary cat bond market. *Journal of Business Economics*, pages 1–32.

- Gürtler, M., Hibbeln, M., and Winkelvos, C. (2016). The impact of the financial crisis and natural catastrophes on cat bonds. *Journal of Risk and Insurance*, 83(3):579–612.
- Herrmann, M. and Hibbeln, M. (2023). Trading and liquidity in the catastrophe bond market. *Journal of Risk and Insurance*, 90(2):283–328.
- Ho, T. K. (1995). Random decision forests. In *Proceedings of 3rd international conference on document analysis and recognition*, volume 1, pages 278–282. IEEE.
- Ho, T. K. (1998). The random subspace method for constructing decision forests. *IEEE transactions on pattern analysis and machine intelligence*, 20(8):832–844.
- Lane, M. N. (2000). Pricing risk transfer transactions. *ASTIN Bulletin: The Journal of the IAA*, 30(2):259–293.
- Lee, J.-P. and Yu, M.-T. (2002). Pricing default-risky cat bonds with moral hazard and basis risk. *Journal of Risk and Insurance*, pages 25–44.
- Lee, J.-P. and Yu, M.-T. (2007). Valuation of catastrophe reinsurance with catastrophe bonds. *Insurance: Mathematics and Economics*, 41(2):264–278.
- Makariou, D., Barrieu, P., and Chen, Y. (2021). A random forest based approach for predicting spreads in the primary catastrophe bond market. *Insurance: Mathematics and Economics*, 101:140–162.
- Morana, C. and Sbrana, G. (2019). Climate change implications for the catastrophe bonds market: An empirical analysis. *Economic Modelling*, 81:274–294.
- Natekin, A. and Knoll, A. (2013). Gradient boosting machines, a tutorial. *Frontiers in neurorobotics*, 7:21.
- Papadopoulos, H., Proedrou, K., Vovk, V., and Gammerman, A. (2002). Inductive confidence machines for regression. In *Machine Learning: ECML 2002: 13th European Conference on Machine Learning Helsinki, Finland, August 19–23, 2002 Proceedings 13*, pages 345–356. Springer.
- Shafer, G. and Vovk, V. (2008). A tutorial on conformal prediction. *Journal of Machine Learning Research*, 9(3).

- Steinberger, L. and Leeb, H. (2016). Leave-one-out prediction intervals in linear regression models with many variables. *ArXiv*, /abs/1602.05801.
- Subramanian, A. and Wang, J. (2018). Reinsurance versus securitization of catastrophe risk. *Insurance: Mathematics and Economics*, 82:55–72.
- Vovk, V., Gammerman, A., and Shafer, G. (2005). *Algorithmic learning in a random world*, volume 29. Springer.
- Wills, S. and Sherris, M. (2010). Securitization, structuring and pricing of longevity risk. *Insurance: Mathematics and Economics*, 46(1):173–185.
- Zhao, Y. and Yu, M.-T. (2020). Predicting catastrophe risk: Evidence from catastrophe bond markets. *Journal of Banking & Finance*, 121:105982.
- Zhu, W. (2011). Ambiguity aversion and an intertemporal equilibrium model of catastrophe-linked securities pricing. *Insurance: Mathematics and Economics*, 49(1):38–46.
- Zhu, W. (2017). Wanting robustness in insurance: A model of catastrophe risk pricing and its empirical test. *Insurance: Mathematics and Economics*, 77:14–23.

Appendix A GBM Algorithm

A detailed GBM algorithm is provided below.

1. **Initialization:** Set $\hat{f}(\mathbf{x}_i) = c$ for all i in the training set, where c is a constant, typically chosen as the mean of the target variable in a regression setting.
2. **Residual Calculation:** Compute the residuals $r_i = y_i - \hat{f}(\mathbf{x}_i)$, which represent the differences between the observed and predicted values of the target variable.
3. **Fit Model to Residuals:** Fit a new weak model $\hat{f}_b$ to these residuals, indexed by the iteration number b . This objective is to predict and correct the errors made by the existing ensemble of models.
4. **Update Predictions:** Modify the prediction function $\hat{f}(\mathbf{x}_i)$ using the formula $\hat{f}(\mathbf{x}_i) \leftarrow \hat{f}(\mathbf{x}_i) + \eta \hat{f}_b(\mathbf{x}_i)$. Here, the predictions from the new weak model $\hat{f}_b$ are scaled by a learning rate η to mitigate overfitting, and then added to the previous predictions to form updated predictions.
5. **Update Residuals:** Adjust the residuals using $r_i \leftarrow r_i - \eta \hat{f}_b(\mathbf{x}_i)$. This update directs the algorithm to focus on the areas where the model is performing poorly in the current iteration.
6. **Iterate:** Repeat steps 2 to 5 for a specified number of iterations B . Each iteration refines the model by fitting a new weak learner to the updated residuals, progressively enhancing the prediction accuracy.
7. **Output Final Model:** The ultimate model is formulated as $\hat{f}(\mathbf{X}) = \sum_{b=1}^B \eta \hat{f}_b(\mathbf{X})$, which represents an ensemble of scaled predictions from weak learners.

Appendix B Glossary of Predictors and Optimal Hyperparameters

Table B.1 reports the predictors used in the empirical analysis, and Table B.2 reports the hyperparameter values of the Random Forest and XGBoost models tuned from the full sample of 765 bonds.

Table B.1: Glossary of predictors.

Variable	Description	Type
EL	Annual expected loss (in percentage points)	Continuous
PFL	Probability of first loss (in percentage points)	Continuous
SIZE	Issue volume (in US million)	Continuous
TERM	CAT bond term (in months)	Continuous
INDEM	Dummy variable indicating whether the trigger type is indemnity or not)	Binary
WIND	Dummy variable indicating whether the CAT bond only covers losses from windstorms (e.g., hurricanes or tornadoes)	Binary
EQ	Dummy variable indicating whether the CAT bond only covers losses from earthquakes	Binary
US	Dummy variable indicating whether the covered territory is in US only	Binary
EU	Dummy variable indicating whether the covered territory is in Europe only	Binary
JP	Dummy variable indicating whether the covered territory is in Japan only	Binary
SR	Dummy variable indicating whether the CAT bond is sponsored by Swiss Re	Binary
IG	Dummy variable indicating whether the bond is rated investment grade	Binary
ROLX	Quarterly values of Lane Financial LLC Synthetic Rate on Line Index	Continuous
BBSPR	Yield spread of BB-rated bonds over risk-free securities such as US treasuries bonds	Continuous
GC.GLOB	Guy Carpenter Global Property Catastrophe RoL index for the global property catastrophe insurance market	Continuous
GC.US	Guy Carpenter Global Property Catastrophe RoL index for the US property catastrophe insurance market	Continuous
GC.AP	Guy Carpenter Global Property Catastrophe RoL index for the Asia-Pacific property catastrophe insurance market	Continuous
GC.EU	Guy Carpenter Global Property Catastrophe RoL index for the European property catastrophe insurance market	Continuous
GC.UK	Guy Carpenter Global Property Catastrophe RoL index for the global property catastrophe insurance the UK property catastrophe insurance market	Continuous

Table B.2: Optimal hyperparameters of the Random Forest and XGBoost models.

Random Forest		
Hyperparameter	Description	Optimal Value
ntree	Number of trees to grow	2500
mtry	Number of variables randomly sampled as candidates at each split	5
XGBoost		
Hyperparameter	Description	Optimal Value
learning_rate	Learning rate that shrinks the contribution of each tree	0.01
max_depth	Maximum depth of each tree	4
min_reduction	Minimum loss reduction required to make a further partition on a leaf node of the tree	0.00004
min_child_weight	Minimum sum of instance weight needed in a leaf node	5
subsample	The ratio of subsample that XGBoost randomly collects to grow trees	0.9
lambda	$L2$ regularization term on weights	400
nrounds	Number of decision trees	800