

ASYMPTOTICS OF LOWER DIMENSIONAL ZERO-DENSITY REGIONS

BY HENGRUI LUO¹, STEVE N. MACEachern^{1,*} AND MARIO PERUGIA^{1,†*}

¹*Department of Statistics, The Ohio State University, luo.619@osu.edu; * snm@stat.osu.edu;*

† peruggia@stat.osu.edu

Abstract Topological data analysis (TDA) allows us to explore the topological features of a dataset. Among topological features, lower dimensional ones have recently drawn the attention of practitioners in mathematics and statistics due to their potential to aid the discovery of low dimensional structure in a data set. However, lower dimensional features are usually challenging to detect from a probabilistic perspective.

In this paper, lower dimensional topological features occurring as zero-density regions of density functions are introduced and thoroughly investigated. Specifically, we consider sequences of coverings for the support of a density function in which the coverings are comprised of balls with shrinking radii. We show that, when these coverings satisfy certain sufficient conditions as the sample size goes to infinity, we can detect lower dimensional, zero-density regions with increasingly higher probability while guarding against false detection. We supplement the theoretical developments with the discussion of simulated experiments that elucidate the behavior of the methodology for different choices of the tuning parameters that govern the construction of the covering sequences and characterize the asymptotic results.

1. Introduction. Topological data analysis (TDA) has been developed in the past several decades to explore and understand the topological structure of the space where the data arise (for example, the support of a probability distribution) using a finite amount of observed data. We refer readers who are interested in a detailed treatment of these data analysis techniques to the introductory texts by Carlsson [5] and Edelsbrunner and Harer [9].

TDA operates on a data set, usually a set of n points in \mathbb{R}^d or a more general metric space. The data and the metric determine simplices leading to simplicial complexes, and the filtration of the complexes constructed at different scales is analyzed to reveal topological features. TDA makes use of the arrangement of the points in \mathbb{R}^d and extracts all features for every dimension simultaneously, but does not take the data generating mechanism into consideration. Our goal is to investigate how knowledge of the distributional properties of the data can help detection of lower dimensional features that are typically difficult to identify based on the data arrangement alone.

Having the data in hand, it is quite natural to consider them as a random sample from some probability distribution. Interest then focuses on the limiting behavior of geometric complexes based on a point set of growing size. In this regard, Kahle [12] and Kahle and Meckes [13] have developed results about the limiting behavior of Betti

*This material is based upon work supported by the National Science Foundation under Grants No. DMS-1613110 and No. SES-1921523.

MSC 2010 subject classifications: Primary 62G20; secondary 62H12

Keywords and phrases: Topological Data Analysis, covering, zero-density regions

numbers of complexes, based on the probabilistic results for random geometric graphs given by Penrose [19]. Subsequent work in this direction characterizes other types of topological features [8, 2, 14]. These results provide a picture of how the probability mechanism informs us about the underlying topology. Bobrowski and Kahle [3] provide a comprehensive review of results along this line. This body of literature suggests that asymptotic regimes provide a convenient framework for analyzing the topology of data.

In this paper, we first discuss situations where independent and identically distributed (i.i.d.) data points are drawn from a distribution having continuous density function f (with respect to Lebesgue measure on \mathbb{R}^d) on its support $\text{supp}(f) = M \subset \mathbb{R}^d$. Our results are first formally stated for $\text{supp}(f) = M = [0, 1]^d$, $d \in \mathbb{N}$, and then extended to more general situations. We work with a well-behaved version of the density f for which the notion of a zero-density region $S_0 \subset M$ (to be formally defined later) is meaningful. If S_0 is of dimension lower than d , $\text{supp}(f) = \text{supp}(f) \cup S_0$ by definition, and the support has no topological features of interest. Such a zero-density region S_0 is difficult to identify with traditional constructions of simplices or density estimators.

EXAMPLE. Let $S_0 = \{\frac{1}{2}\} \times [0.25, 0.75]$ and define $d(\mathbf{x}, S_0) = \inf_{\mathbf{y} \in S_0} d(\mathbf{x}, \mathbf{y})$, where d denotes the L^2 metric. Consider the density $f(\mathbf{x}) \propto d(\mathbf{x}, S_0)^4 \circ \mathbf{1}_{[0,1]^2}$ shown in Figure 1.1, for which S_0 is a zero density region of lower dimension. S_0 does not contain any probability mass and, being a segment, is a “lower dimensional object” (a concept to be made more precise later).

The volume of S_0 as a subset of the support of the density, $[0, 1]^2$, is zero and the density assigns positive probability to any neighborhood of any point in S_0 . Hence, given a single sample of points drawn from this density, no matter how large, it will be impossible to identify the topological structure of S_0 with accuracy. The intuition is that identification of S_0 can only be attained by evaluating the rate at which points accumulate in its vicinity as the sample size grows. The situation would be different if the density were zero on a region of positive volume, such as a disk, and nonzero elsewhere. The disk could then be identified with a large enough sample as a “hole” not containing any points.

Our upcoming results allow us to detect the lower dimensional object S_0 with probability one as the sample size n goes to infinity, and help us to avoid detection of false holes.

Our approach to detecting zero-density regions is to conduct an analysis as we vary the radius of a collection of covering balls of $\text{supp}(f)$. By choosing the shared radius of the covering balls appropriately relative to the increasing sample size n , we wish that S_0 be covered only by balls having no observations inside. For each point in the non-zero density region we wish for the point to eventually be covered by a ball with at least one observation inside. If our wishes come true, then we can simply collect the empty covering balls and recover an approximation to the region S_0 . In Theorem 10 we present a set of sufficient conditions for our detection method to work asymptotically.

This notion of varying the radius of the covering balls can be related to the construction of complexes in TDA. For the Čech complex, balls are centered at the observed points. Balls of a fixed radius r lead to a Čech complex $C(\mathcal{X}, r)$. Varying the radius r , the Čech filtration, a collection of Čech complexes, is produced. For a small radius r , the balls will not overlap and no holes will be discovered. For a large radius r , lower dimensional zero-density regions will be covered and these holes will not be found.

The rest of the paper is organized as follows. We first illustrate our observations above with a simple example in Section 2. Then, in Section 3, we discuss our approach for the




FIGURE 1.1. A lower dimensional region $S_0 = \{\frac{1}{2}\} \times [0.25, 0.75]$ (red segment) for the density function $f(\mathbf{x}) \propto d(\mathbf{x}, S_0)^4 \circ \mathbf{1}_{[0,1]^2}(\mathbf{x})$, where $d(\mathbf{x}, S_0) = \inf_{\mathbf{y} \in S_0} d(\mathbf{x}, \mathbf{y})$ and d denotes Euclidean distance. The density f evaluates to 0 over S_0 , but nowhere else over $[0, 1]^2$.

construction of coverings of a compact support along with a set of sufficient conditions that ensure asymptotic consistency of the procedure for the detection of zero-density regions. Generalizations of the results to the case of a non-compact support are provided in Section 4. We present some experimental results and connections to other areas in Section 5 and end with a brief discussion of our findings in Section 6.

2. An Illustrative Example. The central problem we investigate in this paper is the detection of a lower dimensional zero-density region. Before formally addressing the problem, we present an illustrative example to show how dimensionality plays an important role.

We consider three different densities on the interval $M = [-1, 1]$, $\dim M = 1$, and the problem of detecting interesting topological features by partitioning M into the union of disjoint, equally sized bins. The density $g(x) = \frac{2}{3} (\mathbf{1}_{[-1, -1/4]}(x) + \mathbf{1}_{[1/4, 1]}(x))$ has a genuine hole, $(-1/4, 1/4)$, consisting of an interval of dimension one. This hole is apparent, as there will never be any observations in it. As the sample size n goes to infinity, one need only consider bins whose width decrease at a rate no faster than $n^{-1+\varepsilon}$, $\varepsilon > 0$, to ensure that the bins away from the hole are eventually filled. When $S_0 = \emptyset$, as is the case for the density $h(x) = \frac{3}{8} \mathbf{1}_{[-1, 1]}(x) \cdot (x^2 + 1)$, and the width of the bins decreases at a rate no faster than $n^{-1+\varepsilon}$, we cannot detect any hole as all bins will eventually be filled.

The interesting case has $S_0 \neq \emptyset$ and $\dim S_0 < \dim M = 1$, as is the case for $f(x) = \frac{3}{2} x^2 \mathbf{1}_{[-1, 1]}(x)$. Here, $S_0 = \{0\}$, and the question is whether we can detect this topological feature of dimension zero with positive probability. The hole is difficult to detect because samples will accumulate around $S_0 = \{0\}$. If the bins are too large, they will be filled as n goes to infinity and the binary heatmaps of f , constructed by drawing a vertical segment at the center of every bin in which there is at least one observation, will look more and more like the ones for h .

In the Figure 2.1, the binary heatmaps show the denseness of the non-empty bins. The first column represents histograms and heatmaps for the density f with a zero-dimensional hole $\{0\}$. The second column represents histograms and heatmaps for the density g with a one-dimensional hole $(-1/4, 1/4)$. The third column represents histograms and heatmaps for the density h with no holes.




FIGURE 2.1. *Binned histogram and binary heatmaps based on random samples of size $n = 100$ and $n = 10,000$ from three distributions with densities f, g , and h . All graphical summaries are constructed using 100 equal-width bins over the interval $[-1, 1] \subset \mathbb{R}$.*

The figure suggests that, as the sample size n goes to infinity, we should be able to distinguish between f and h by using binary heatmaps with an appropriate scaling scheme. This is perhaps surprising, because f and h have the same support. Formally, our Theorem 10 shows that, if we shrink the common width of the bins (which corresponds to the radius of the covering balls in higher dimensions) at appropriate rates as a function of sample size n , the lower dimensional holes will be characterized in terms of empty bins with probability tending to one. This result can be extended to more general situations.

The objective of this article is to show that, without appropriate scaling, authentic topological holes of strictly lower dimension cannot be detected, while, with appropriate scaling, they can. The sufficient conditions that we will impose on the scaling schemes to attain these results depend on the dimension of the zero-density region S_0 and also on the local smoothness of the density that generates the data.

3. Statement of the Main Result. Consider a random vector X having density f with respect to Lebesgue measure on \mathbb{R}^d . For any Borel set $A \in \mathbb{R}^d$, let $P(X \in A) = \int_A f(x) dx$.

DEFINITION 1. (Support) The *support* of X is defined to be

$$(3.1) \quad \text{supp}(X) := \bigcap_{\{R_X \text{ closed in } \mathbb{R}^d | P(X \in R_X) = 1\}} R_X.$$

With an abuse of notation, we write $\text{supp}(f)$ to represent the support of X .

In most applications where TDA is employed, a compact support M can be reasonably assumed. For technical convenience, we will also assume the existence of a continuous version of the density f on its support M . The latter is a mild condition satisfied

for most theoretical questions and applied scenarios. In the following discussion, as will be stated in [Assumption 1](#) on page 8, we consider the case of $M = [0, 1]^d \subset \mathbb{R}^d$, $d > 0$. With this particular M in mind, we turn to a special region called the zero-density region lying in its interior.

DEFINITION 2. (Zero-density region) For the continuous version of a density f on M , we call the inverse image of $\{0\}$, i.e. $f^{-1}(\{0\})$, the *zero-density region* of f and denote it by S_0 .

S_0 may consist of more than one connected component. Our main results are easy to extend to the case of a finite number of connected components. Topological restrictions on S_0 are summarized in [Assumption 2](#) on page 8.

The local behavior of the density f around the zero-density region $S_0 \subset M$ is a crucial aspect of our investigation. The following concepts will help us to describe the behavior of f near S_0 . We consider the L^2 metric and the associated norm, $\|\cdot\|$, in the following discussion, but remark that our methods can be generalized to other metrics and norms.

A *ball* of radius r centered at \mathbf{x} in \mathbb{R}^d is the open set

$$B_r(\mathbf{x}) := \left\{ \mathbf{y} \in \mathbb{R}^d \mid \|\mathbf{x} - \mathbf{y}\| < r \right\}.$$

An ϵ -neighborhood ($\epsilon > 0$) of S_0 is the open set

$$B_\epsilon(S_0) := \left\{ \mathbf{x} \in \mathbb{R}^d \mid \inf_{\mathbf{y} \in S_0} \|\mathbf{x} - \mathbf{y}\| < \epsilon \right\}.$$

(Note that the definition of an ϵ -neighborhood makes sense for an arbitrary set, not just a zero-density region. In particular, the ϵ -neighborhood of a point \mathbf{y} , $B_\epsilon(\mathbf{y})$, is just the open ball of radius ϵ centered at \mathbf{y} .)

DEFINITION 3. (Upper and lower ϵ -order of smoothness) We consider densities f for which the following quantities, called the *upper* and *lower ϵ -order of smoothness*, respectively, exist and are well-defined for every $0 < \epsilon < 1$:

$$\overline{K}_f(\epsilon) := \inf \left\{ \alpha > 0 \mid 0 < \inf_{\mathbf{x} \in B_\epsilon(S_0) \setminus S_0} \frac{f(\mathbf{x})}{d(\mathbf{x}, S_0)^\alpha} \right\},$$

and

$$\underline{K}_f(\epsilon) := \sup \left\{ \alpha > 0 \mid \infty > \sup_{\mathbf{x} \in B_\epsilon(S_0) \setminus S_0} \frac{f(\mathbf{x})}{d(\mathbf{x}, S_0)^\alpha} \right\}.$$

Because our result concerns the limiting case as ϵ goes to zero, we give the following definition.

DEFINITION 4. (Upper and lower order of smoothness) The *upper* and *lower order of smoothness* of the density f w.r.t. S_0 , are

$$\overline{K}_f = \lim_{\epsilon \rightarrow 0^+} \overline{K}_f(\epsilon) \quad \text{and} \quad \underline{K}_f = \lim_{\epsilon \rightarrow 0^+} \underline{K}_f(\epsilon),$$

respectively, provided they exist.




FIGURE 3.1. Lower dimensional region $S_0 = \{\frac{1}{2}\} \times [0.25, 0.75]$ of a density function $f(\mathbf{x})$ with $\overline{K_f} \neq \underline{K_f}$. The density f evaluates to 0 over S_0 but nowhere else over $[0, 1]^2$.

It can be shown that $\overline{K_f}$ and $\underline{K_f}$ will exist if $\overline{K_f}(\epsilon)$ and $\underline{K_f}(\epsilon)$ exist for some ϵ and that there are densities for which $\overline{K_f}(\epsilon)$ and $\underline{K_f}(\epsilon)$ are undefined for all ϵ . The limits $\overline{K_f}$ and $\underline{K_f} > 0$, if they exist, need not coincide. If they do exist and coincide, we will use the notation $K_f = \overline{K_f} = \underline{K_f}$.

The following example, depicted in Figure 3.1, shows that the upper and lower orders of smoothness $\overline{K_f}$ and $\underline{K_f}$ need not coincide.

EXAMPLE. For $\mathbf{x} = (x, y) \in \mathbb{R}^2$, define $h(\mathbf{x})$ as

$$h(\mathbf{x}) = \begin{cases} d(\mathbf{x}, S_0)^4, & \mathbf{x} \in [0.5, 1] \times [0.25, 0.75], \\ d(\mathbf{x}, S_0)^2, & \mathbf{x} \in [0, 0.5] \times [0.25, 0.75], \\ d(\mathbf{x}, S_0)^{4 - \frac{2}{\pi}\theta_1}, & \mathbf{x} \in [0, 1] \times (0.75, 1], \\ d(\mathbf{x}, S_0)^{4 + \frac{2}{\pi}\theta_2}, & \mathbf{x} \in [0, 1] \times [0, 0.25), \end{cases}$$

where d is the L^2 metric, $\theta_1 = \arctan\{(y - 0.75)/(x - 0.5)\}$, and $\theta_2 = \arctan\{(y - 0.25)(x - 0.5)\}$. Consider the density function f satisfying the relationship $f(\mathbf{x}) \propto g(\mathbf{x}) \times \mathbf{1}_{[0, 1]^2}(\mathbf{x})$. For $\mathbf{x} \in M$ with $d(\mathbf{x}, S_0) = \delta$, $\delta > 0$, $\sup_{\mathbf{x}} f(\mathbf{x}) = \delta^2$ and $\inf_{\mathbf{x}} f(\mathbf{x}) = \delta^4$. Thus $\overline{K_f}(\epsilon) = 4$ and $\underline{K_f}(\epsilon) = 2$.

3.1. *Covering balls and dimension of S_0 .* We cover the support M of the density f with a collection of balls of equal radius and, letting the radius shrink to zero at an appropriate rate, we attempt to detect the zero-density region S_0 with a certain limiting probability guarantee. In what follows we will make use of the following piece of notation.

Notation. (Covering) Let E be a given subset of \mathbb{R}^d . We denote by $\mathcal{B}_r^d(E)$ a collection of d -dimensional balls of radius r whose union contains E . Note that a covering $\mathcal{B}_r^d(E)$ may also depend on the sample size n through the radius $r = r(n)$ in subsequent developments. We also use $|\mathcal{B}_r^d(E)|$ to denote the cardinality of $\mathcal{B}_r^d(E)$ and write $\mathcal{B}_r^d(E) = \mathcal{B}$ when the meaning is unambiguous.

We distinguish between three types of covering balls based on how far they are from the zero-density region S_0 .




FIGURE 3.2. Illustration of the types of balls with the density in Figure 1.1. The blue region is an epsilon neighborhood surrounding the zero-density region S_0 . The red ball is an ϵ -inside ball, the orange balls are ϵ -neighboring balls and the green balls are ϵ -outside balls.

DEFINITION 5. (Types of covering balls) Consider a density f with respect to Lebesgue measure on \mathbb{R}^d that is continuous on M and zero on $\mathbb{R}^d \setminus M$. Let S_0 be a zero-density region for f . Denote by \mathcal{B} a covering of M with balls of radius r and let $B_r(\mathbf{x}) \in \mathcal{B}$. We classify $B_r(\mathbf{x})$ into one of these three types:

1. an ϵ -outside ball: a ball $B_r(\mathbf{x})$ such that $\mathbf{x} \notin B_\epsilon(S_0)$;
2. an ϵ -neighboring ball: a ball $B_r(\mathbf{x})$ such that $\mathbf{x} \in B_\epsilon(S_0)$ and $B_r(\mathbf{x}) \cap S_0 = \emptyset$;
3. an ϵ -inside ball: a ball $B_r(\mathbf{x})$ such that $\mathbf{x} \in B_\epsilon(S_0)$ and $B_r(\mathbf{x}) \cap S_0 \neq \emptyset$.

The main result will rely on the condition $r \leq \epsilon/2$ to ensure that every ϵ -inside ball is contained in $B_\epsilon(S_0)$. The various types of covering balls are illustrated in Figure 3.2.

DEFINITION 6. (Big O notation [4]) Given two positive real sequences $f(n)$ and $g(n)$, we write $f \sim O(g)$ and say that f is big O of g if there exist constants L_1 and $L_2 \in (0, \infty)$ and an $n_0 \in \mathbb{N}$, such that

$$L_1 \cdot g(n) \leq f(n) \leq L_2 \cdot g(n), \text{ for all } n > n_0.$$

This condition means that the asymptotic behaviors of f and g are comparable.

Next, we introduce the notion of Minkowski dimension which we will later use to characterize the dimension of S_0 .

DEFINITION 7. (Minkowski dimension, or box-counting dimension. Definition 3.1 in 10) The *upper and lower Minkowski dimensions* of a bounded subset $E \subset M$ of \mathbb{R}^d , are defined respectively as

$$\overline{\dim}_M(E) := \limsup_{\Delta \rightarrow 0} \frac{\log \mathcal{N}_\Delta(E)}{-\log \Delta},$$

$$\underline{\dim}_M(E) := \liminf_{\Delta \rightarrow 0} \frac{\log \mathcal{N}_\Delta(E)}{-\log \Delta},$$

where $\mathcal{N}_\Delta(E)$ is the Δ -covering number of $E \subset \mathbb{R}^d$

$$\mathcal{N}_\Delta(E) := \min \left\{ k \in \mathbb{N} \mid E \subset \bigcup_{i=1}^k B_\Delta(x_i) \text{ for some } x_i \in \mathbb{R}^d \right\},$$

i.e., the smallest number of balls of radius $\Delta > 0$ needed to cover E . We call this covering of minimal cardinality a *minimal Δ -covering* for E . When $\overline{\dim}_M(E) = \underline{\dim}_M(E) = d_M$, we define the *Minkowski dimension* (or box-counting dimension) $\dim_M(E)$ of E to be d_M .

By Proposition 3.4 in Falconer [10], in the case of $M = [0, 1]^d$, we always have $\dim_M(M) = d$, matching the usual definition of dimension.

We now state the formal assumptions **A.1-A.6** which we will use to prove our main results.

A.1. (Compact support) The support of f is $\text{supp}(f) = M = [0, 1]^d$, $d > 0$ and we consider the version of the density f that is zero on $\mathbb{R}^d \setminus M$ and continuous on M .

A.2. (Single component) The zero-density region S_0 is contained in the interior of M and has one connected component.

A.3. (Order of smoothness) There exists an $\epsilon_0 > 0$ such that both quantities $\overline{K}_f(\epsilon_0) > 0$ and $\underline{K}_f(\epsilon_0) > 0$ exist. As remarked on page 6, the existence of $\epsilon_0 > 0$ implies that the limiting values $\overline{K}_f > 0$ and $\underline{K}_f > 0$ also exist.

A.4. Let $\epsilon_0 > 0$ be as described in A.3. There exist two positive constants L_f and U_f such that, for all ϵ with $0 < \epsilon < \min(1, \epsilon_0)$, $L_f \cdot d(\mathbf{x}, S_0)^{\overline{K}_f(\epsilon)} \leq f(\mathbf{x}) \leq U_f \cdot d(\mathbf{x}, S_0)^{\underline{K}_f(\epsilon)}$ for all $\mathbf{x} \in B_\epsilon(S_0) \cap M$.

A.5. (Regular covering) There is an $\eta > 0$ such that the elements of the sequence of coverings $\mathcal{B}_{r(n)}^d(M)$ are comprised of balls whose centers lie in M and whose radii satisfy $r(n) \sim O(n^{-\eta})$. The sequence of coverings is *regular*, i.e., the cardinalities $|\mathcal{B}_{r(n)}^d(M)|$ of the coverings in the sequence satisfy the condition $|\mathcal{B}_{r(n)}^d(M)| \sim O(n^{d\eta})$.

A.6. (Restriction of covering to S_0) Let $\mathcal{B}_{r(n)}^d(M)$ be the covering considered in A.5. If d_0 is the Minkowski dimension of S_0 and $d_0 < d$, then the number of balls in $\mathcal{B}_{r(n)}^d(M)$ intersecting S_0 is bounded from above by $H_\epsilon(n) \sim O(n^{d_0\eta(1+\epsilon)})$, for each $\epsilon > 0$. $H_\epsilon(n)$ is a function of sample size n that depends on the parameter ϵ .

This set of assumptions can be roughly categorized into three groups. [Assumptions A.1 and A.2](#) can be regarded as restrictions on the topological properties of the support of the density function and we will see later that both assumptions can be relaxed under suitable conditions. [Assumptions A.3 and A.4](#) describe the local behavior of f in the vicinity of S_0 .

[Assumptions A.5 and A.6](#), however, are tied intrinsically to the Minkowski dimension of S_0 and the covering scheme we devise for detection of S_0 .

Next we prove that under [Assumptions A.1 and A.2](#) there exists one covering that satisfies [Assumptions A.5 and A.6](#) for S_0 of Minkowski dimension d_0 .

LEMMA 8. *Suppose that A.1 and A.2 hold and that S_0 is a lower dimensional zero-density region of Minkowski dimension $d_0 < d$. Then there exists a sequence of coverings $\mathcal{B}_{r(n)}^d(M)$ that satisfies A.5 and A.6.*

PROOF. Step 1. We prove first that A.6 can be satisfied. Let $r(n) = cn^{-\eta}$, $c > 0$, and let $\mathcal{B}_{r(n)}^d(S_0)$ be a minimal $r(n)$ covering of S_0 of cardinality $|\mathcal{B}_{r(n)}^d(S_0)|$. Since we assume that $\dim_M(S_0) = d_0$,

$$(3.2) \quad \lim_{r(n) \rightarrow 0} \frac{\log \mathcal{N}_{r(n)}(S_0)}{-\log r(n)} = \lim_{n \rightarrow \infty} \frac{\log \mathcal{N}_{r(n)}(S_0)}{\log 1/r(n)} = d_0 \Rightarrow \lim_{n \rightarrow \infty} \frac{\log \mathcal{N}_{r(n)}(S_0)}{\log (1/r(n))^{d_0}} = 1.$$

Thus, for each $\varepsilon > 0$, there exists an $N_*(\varepsilon)$ such that, for all $n > N_*(\varepsilon)$

$$(3.3) \quad \frac{\log \mathcal{N}_{r(n)}(S_0)}{\log (1/r(n))^{d_0}} \leq 1 + \varepsilon, \quad \log \mathcal{N}_{r(n)}(S_0) \leq (1 + \varepsilon) \cdot \log (1/r(n))^{d_0},$$

$$\mathcal{N}_{r(n)}(S_0) \leq \left(\frac{1}{r(n)^{d_0}} \right)^{1+\varepsilon} = c^{-d_0(1+\varepsilon)} n^{d_0\eta(1+\varepsilon)} = H_\varepsilon(n).$$

This establishes that each term in the tail of the sequence $\{|\mathcal{B}_{r(n)}^d(S_0)|\}$ is bounded by $H_\varepsilon(n)$ as in A.6, provided $\mathcal{B}_{r(n)}^d(S_0) \cap \mathcal{B}_{r(n)}^d(M) = \mathcal{B}_{r(n)}^d(S_0)$, where $\mathcal{B}_{r(n)}^d(M)$ is as in A.5.

Step 2. Now we turn to the proof of A.5.

First, we take n sufficiently large so that there exists a hyper cube $C(n)$ of dimension d and side length $r(n)$ such that $B_{3r(n)}(C(n)) \subset \text{int } M \setminus B_{5r(n)}(S_0)$. For such a fixed n and the $r(n)$ -covering $\mathcal{B}_{r(n)}^d(S_0)$ we derived above, we now construct such a covering $\mathcal{B}_{r(n)}^{d,i}(M)$ where the centers of covering balls in $\mathcal{B}_{r(n)}^{d,i}(M)$ are on the grid set

$$G(n) := M \cap \{ \mathbf{x} = (x_1, \dots, x_d) \in \mathbb{R}^d \mid x_i \in \mathbb{N} \cdot \frac{r(n)}{d}, \forall i = 0, \dots, d \}.$$

For this grid, the maximal distance from an arbitrary point in M to a point in $G(n)$ is at most $\sqrt{d \cdot \left(\frac{r(n)}{d}\right)^2} = \frac{r(n)}{\sqrt{d}} \leq r(n)$ for $d \geq 1$. This maximal distance is attained by a pair of points with coordinates in the form $(x_1, \dots, x_d), (x_1 + \frac{r(n)}{d}, \dots, x_d + \frac{r(n)}{d}) \in G(n)$. So an arbitrary point in M is contained in some ball of radius $r(n)$ with its center in $G(n)$. The cardinality of this covering is the same as the cardinality of the set $G(n)$ of centers, which is of order $O\left(\left(1/\frac{r(n)}{d}\right)^d\right) \sim O(n^{\eta d})$.

Second, we delete all covering balls in $\mathcal{B}_{r(n)}^{d,i}(M)$ that intersect S_0 . That is, we obtain another covering $\mathcal{B}_{r(n)}^{d,ii}(M) = \{B \in \mathcal{B}_{r(n)}^{d,i}(M) \mid B \cap S_0 = \emptyset\}$, which ensures that there are no additional covering balls intersecting S_0 and A.6 is still guaranteed by the covering $\mathcal{B}_{r(n)}^d(S_0)$ we choose in Step 1 because no additional covering balls are touching S_0 . This operation only deletes those covering balls that are completely contained in $\mathcal{B}_{3r(n)}^d(S_0)$, so no covering ball intersecting $C(n)$ will be deleted. As argued in the first step, $\mathcal{B}_{r(n)}^{d,ii}(M)$ is also a covering of $C(n)$ of Minkowski dimension d so it must contain covering balls of cardinality $O(n^{\eta d})$.

Third, we recognize that after deletion and obtaining the covering $\mathcal{B}_{r(n)}^{d,ii}(M)$, the union $\cup_{B \in \mathcal{B}_{r(n)}^{d,ii}(M) \cup \mathcal{B}_{r(n)}^d(S_0)} B$ may not cover all points of M . In the previous deletion operation, we delete every covering ball such that its center p satisfies $d(p, S_0) \leq r(n)$. Therefore any point q in $M \setminus \left(\cup_{B \in \mathcal{B}_{r(n)}^{d,ii}(M) \cup \mathcal{B}_{r(n)}^d(S_0)} B \right)$ will satisfy $d(q, S_0) \leq 2r(n)$. Now we add *finitely many* translated copies of $\mathcal{B}_{r(n)}^d(S_0)$ to $\mathcal{B}_{r(n)}^{d,ii}(M) \cup \mathcal{B}_{r(n)}^d(S_0)$ to obtain our final covering. Denote by $\mathcal{B}_{r(n)}^d(S_0) + \mathbf{v}$ the covering obtained by translating each




FIGURE 3.3. Illustration of the construction in Proposition 9 with the density in Figure 1.1. With $r = 0.1$, the grid centers in $G(n)$ are displayed. The range of $G_0(n)$ is displayed in red; the ranges of $G_1(n)$ and $G_2(n)$ are displayed in green and blue, respectively.

covering ball in $\mathcal{B}_{r(n)}^d(S_0)$ by vector \mathbf{v} . We let the translation vector \mathbf{v} vary in following set of vectors

$$G_1(n) := \left\{ \mathbf{v} = (v_1, \dots, v_d) \in \mathbb{R}^d \mid v_i \in \kappa \cdot \frac{r(n)}{d}, \kappa = 0, \pm 1, \dots, \pm 4d, \forall i = 0, \dots, d \right\}$$

which is a set consisting of $(4d \times 2 + 1)^d = (8d + 1)^d$ vectors. This construction forms a (irregular) grid $G_1(n)$ by translating the centers of balls in $\mathcal{B}_{r(n)}^d(S_0)$. This grid covers all points in $B_{2r(n)}(S_0)$ since it translates $4r(n)$ in each coordinate direction. The maximal distance from an arbitrary point in $B_{2r(n)}(S_0)$ to a point in $G_1(n)$ is no more than $\sqrt{d \cdot \left(\frac{r(n)}{d}\right)^2} = \frac{r(n)}{\sqrt{d}} \leq r(n)$ for $d \geq 1$. Therefore

$$\mathcal{B}_{r(n)}^{d,iii} := \{B \in \mathcal{B}_{r(n)}^d(S_0) + \mathbf{v} \mid \mathbf{v} \in G_1(n)\}$$

will cover the area $B_{2r(n)}(S_0)$. This will add at most $(8d + 1)^d \cdot \left| \mathcal{B}_{r(n)}^d(S_0) \right| \sim O\left(\left| \mathcal{B}_{r(n)}^d(S_0) \right|\right)$ additional covering balls that intersect S_0 . This addition will not affect the order of magnitude of the cardinality of $\mathcal{B}_{r(n)}^{d,ii}(M) \cup \mathcal{B}_{r(n)}^d(S_0)$ satisfying A.5. We simply add finitely many $(8d + 1)^d$ translated copies of $\mathcal{B}_{r(n)}^d(S_0)$ to cover the ‘‘gaps’’ created by deletion in the previous step.

The covering $\mathcal{B}_{r(n)}^{d,\dagger} := \mathcal{B}_{r(n)}^{d,ii}(M) \cup \mathcal{B}_{r(n)}^d(S_0) \cup \mathcal{B}_{r(n)}^{d,iii}$ satisfies both A.5 and A.6 by construction as we saw above. \square

The constructive proof of the previous lemma makes explicit use of minimal coverings of S_0 . There are many situations in which sequences of coverings satisfying A.5 and A.6 can be produced without resorting to the use of a minimal covering of S_0 . The following proposition gives an explicit example of such a situation.

PROPOSITION 9. *For the example in Figure 1.1, for a fixed $\eta > 0$, there exists a sequence of coverings $\mathcal{B}_{r(n)}^2(M)$ satisfying A.5 and A.6.*

PROOF. We consider the covering where the centers of the balls in $\mathcal{B}_{r(n)}^2(M)$ are exactly the grid set

$$(3.4) \quad G(n) = M \cap \{\mathbf{y} = (y_1, y_2) \in \mathbb{R}^2 \mid y_1, y_2 \in \mathbb{N} \cdot \frac{r(n)}{2}\}.$$

(See Figure 3.3 for an illustration.) The cardinality of this covering is the same as the cardinality of the grid set $G(n)$. As n increases, we have a sequence of coverings whose cardinalities are of order $O\left(\frac{1}{r(n)/2}\right)^2 \sim O(n^{2\eta})$ as required in A.5.

Next, we prove that the covering balls of $\mathcal{B}_{r(n)}^2(M)$ intersecting S_0 also have cardinalities that satisfy A.6. Let n be large enough that $r(n) < 1/10$ and the $r(n)$ -neighborhood of S_0 , $B_{r(n)}(S_0) \subset \text{int } M$. Consider the set of grids $G_0(n) := \{\mathbf{y} = (y_1, y_2) \in G(n) \mid 0 \leq d(\mathbf{y}, S_0) < r(n)\}$. A covering ball in $\mathcal{B}_{r(n)}^2(M)$ intersects S_0 if and only if its center is in $G_0(n)$. We construct the rectangular grids defined below to bound the cardinality of $G_0(n)$.

$$G_1(n) := \{\mathbf{y} = (y_1, y_2) \in G(n) \mid \frac{1}{2} - 2r(n) \leq y_1 \leq \frac{1}{2} + 2r(n), \frac{1}{4} - 2r(n) \leq y_2 \leq \frac{3}{4} + 2r(n)\},$$

$$G_2(n) := \{\mathbf{y} = (y_1, y_2) \in G(n) \mid \frac{1}{2} - \frac{r(n)}{2} \leq y_1 \leq \frac{1}{2} + \frac{r(n)}{2}, \frac{1}{4} + \frac{r(n)}{2} \leq y_2 \leq \frac{3}{4} - \frac{r(n)}{2}\}.$$

It is clear from their definitions that $G_2(n) \subset G_0(n) \subset G_1(n)$.

In the grid set $G_2(n)$, there are at least $\frac{r(n)}{r(n)/2} = 2$ grid points with the same value of y_2 ; and at least $\left\lfloor \frac{1/2-r(n)}{r(n)/2} \right\rfloor = \left\lfloor \frac{1}{r(n)} - 2 \right\rfloor$ points with the same value of y_1 . Thus there are at least $2 \cdot \left\lfloor \frac{1}{r(n)} - 2 \right\rfloor$ grid points in $G_2(n)$. Similarly, in the grid set $G_1(n)$ there are at most $\frac{4r(n)}{r(n)/2} + 1 = 9$ grid points with the same value of y_2 ; and at most $\left\lceil \frac{1/2+4r(n)}{r(n)/2} + 1 \right\rceil = \left\lceil \frac{1}{r(n)} + 9 \right\rceil$ points with the same value of y_1 . Thus there are at most $9 \cdot \left\lceil \frac{1}{r(n)} + 9 \right\rceil$ grid points in $G_1(n)$.

Since $G_2(n) \subset G_0(n) \subset G_1(n)$, the number of balls intersecting S_0 has cardinality $|G_0(n)|$ bounded by the inequality

$$(3.5) \quad 2 \cdot \left\lfloor \frac{1}{r(n)} - 2 \right\rfloor \leq |G_2(n)| \leq |G_0(n)| \leq |G_1(n)| \leq 9 \cdot \left\lceil \frac{1}{r(n)} + 9 \right\rceil.$$

Both sides of (3.5) have order of magnitude $O\left(\frac{1}{r(n)}\right) \sim O(n^\eta)$ and this verifies A.6. \square

Although we have shown by example that our Assumption A.1-A.6 can be verified for many densities, we point out that in general it might not be easy to verify these assumption when S_0 or M possesses a complicated topological structure.

3.2. Main result.

THEOREM 10. Suppose we have a set of i.i.d. data X_1, \dots, X_n drawn from a continuous density $f(\mathbf{x})$ w.r.t. the d -dimensional Lebesgue measure ν^d defined on a compact subset $M = [0, 1]^d$ of \mathbb{R}^d and assume that Assumptions A.1-A.6 hold. Assume also that the radius r and the separation distance ϵ satisfy the following growth rates:

$$\begin{aligned} r(n) &\sim O(n^{-\eta}), \quad 0 < \eta < \frac{1}{d}, \\ \epsilon(n) &\sim O(n^{-\psi}), \quad 0 < \psi \leq \eta, \\ 2r(n) &\leq \epsilon(n) < 1. \end{aligned}$$

Finally, assume the validity of the following bounding condition for the density f outside the ϵ -neighborhood of S_0 :

$$m(f, n) := \min_{\mathbf{w} \in M \setminus B_\epsilon(S_0)} f(\mathbf{w}) \in (0, \infty) \sim O(n^{-\xi}), \quad 0 < \xi < \frac{1 - 2\eta d}{2}.$$

Then:

(A) If η and ψ satisfy

$$1 - 2\eta d - 2\overline{K_f}\psi > 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{no empty } \epsilon(n)\text{-outside balls}) = 1$.

(B) If η and ψ satisfy

$$1 + d_0\eta - \underline{K_f}\eta - d\eta < 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{all } \epsilon(n)\text{-inside balls are empty}) = 1$.

PROOF. See Appendix. □

Similarly, we have a result dealing with the situation where S_0 has more than one (but a finite number) connected component.

COROLLARY 11. *Under the same assumptions as in Theorem 10, suppose that the zero-density region can be decomposed into K disjoint connected components, $S_0 = \sqcup_{k=1}^K S_{0k}$. For n large enough (so that ϵ is small enough), an ϵ -neighborhood of S_0 will also be comprised of K disjoint connected components, the ϵ -neighborhoods of each component S_{0k} .*

Assume that the following bounding conditions for the density f outside the ϵ -neighborhood of each component S_{0k} hold:

$$m_k(f, n) := \min_{\mathbf{w} \in M \setminus B_{\epsilon(n)}(S_{0k})} f(\mathbf{w}) \in (0, \infty) \sim O(n^{-\xi}), \quad 0 < \xi < \frac{1 - 2\eta d}{2}.$$

Assume also that the orders of smoothness of f w.r.t. S_{0k} are $\overline{K_{f,k}}$ and $\underline{K_{f,k}} > 0$ and that, for S_{0k} of dimension d_{0k} , the cardinality of the set of covering balls intersecting S_{0k} is of order $O(n^{nd_{0k}})$.

Then:

(A) *If η and ψ satisfy*

$$\min_{k=1, \dots, K} 1 - 2\eta d - 2\overline{K_{f,k}}\psi > 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{no empty } \epsilon(n)\text{-outside balls}) = 1$ for all k .

(B) *If η and ψ satisfy*

$$\max_{k=1, \dots, K} 1 + d_{0k}\eta - \underline{K_{f,k}}\eta - d\eta < 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{all } \epsilon(n)\text{-inside balls are empty}) = 1$ for all k .

4. Non-compact support. The main result of the previous section relies on the assumption of a compact support for the density f . However, in practice, many distributions have unbounded supports. In this section we consider the case of a density function f with a non-compact support contained in \mathbb{R}^d and, assuming that the tails of the density decay at certain rates, we derive results similar to those of the previous section.

Our strategy restricts our consideration to a region within the support that contains most of the probability mass of the density f . The original motivation for these ideas comes from the concentration inequalities that describe the fact that observations usually “concentrate” around the “center” of a probability density with high probability (for example, Talagrand [23]).

Suppose that the support of the probability density function f is a non-compact set $M' \subset \mathbb{R}^d$. We consider a truncation of the non-compact support M' to a compact subset that contains most of the probability mass of f and whose interior contains (all components of) S_0 . This allows us to examine the topological features of M' over a compact truncated region that contains the bulk of the data and to establish our results using arguments similar to those used to prove Theorem 10. For ease of exposition, we focus parts of our discussion on the situation where $M' = \mathbb{R}^d$, although most of our results can be extended to more general situations. We will state the restrictions on the tail behavior of the density functions in Proposition 18.

DEFINITION 12. (($1 - \delta$)-support containing S_0) A ($1 - \delta$)-*support* containing S_0 for some $0 < \delta < 1$, denoted by $S_f^{1-\delta} \subset \mathbb{R}^d$, is a subset of the form $S_f^{1-\delta} := [-B, B]^d \subset \mathbb{R}^d$ for some $B \in (0, \infty)$, such that $S_0 \subset \text{int } S_f^{1-\delta} = (-B, B)^d$ and $P\{X \in S_f^{1-\delta}\} = 1 - \delta$.

The hypercube $[-B, B]^d$ containing $1 - \delta$ of the probability expands as δ shrinks. If S_0 is compact then $S_f^{1-\delta}$ exists for a small enough $\delta \in (0, 1)$; if S_0 is non-compact, then it is unbounded and $S_f^{1-\delta}$ does not exist for any $\delta \in (0, 1)$. For our subsequent results, we assume that the ($1 - \delta$)-support is completely contained in the interior of the support M' .

Passing from M' to $S_f^{1-\delta}$ allows us to work with a compact cubical subset and removes the technical difficulties associated with densities whose tails decay to zero. We replicate the results of Section 3 with modifications to Assumptions A.1-A.6. The modifications stem from replacing the compact support $[0, 1]^d$ with a compact set $S_f^{1-\delta}$ that covers S_0 and contains $1 - \delta$ mass of the probability measure.

We first consider the case where $\delta > 0$ and $S_f^{1-\delta}$ are both fixed and state Assumptions A.1'-A.6' for the non-compact support case.

A.1'. (Non-compact support) The support of f is $\text{supp}(f) = M' \subset \mathbb{R}^d$, $d > 0$ and we consider the version of the density f that is zero on $\mathbb{R}^d \setminus M'$ and continuous on M' .

A.2'. (Single component) The zero-density region S_0 is contained in the interior of M' and has one connected component.

A.3'. (Order of smoothness) There exists an $\epsilon_0 > 0$ such that both quantities $\overline{K}_f(\epsilon_0) > 0$ and $K_f(\epsilon_0) > 0$ exist.

A.4'. Let $\epsilon_0 > 0$ be as described in A.3'. There exist two positive constants L_f and U_f such that, for all ϵ with $0 < \epsilon < \min(1, \epsilon_0)$, $L_f \cdot d(\mathbf{x}, S_0)^{\overline{K}_f(\epsilon)} \leq f(\mathbf{x}) \leq U_f \cdot d(\mathbf{x}, S_0)^{K_f(\epsilon)}$ for all $\mathbf{x} \in B_\epsilon(S_0) \cap S_f^{1-\delta}$.

A.5'. (Regular covering) There is an $\eta > 0$ such that the elements of the sequence of coverings $\mathcal{B}_{r(n)}^d(S_f^{1-\delta})$ are comprised of balls whose centers lie in $\text{int } S_f^{1-\delta}$ and whose radii satisfy $r(n) \sim O(n^{-\eta})$. The sequence of coverings is *regular*, i.e., the cardinalities $|\mathcal{B}_{r(n)}^d(S_f^{1-\delta})|$ of the coverings in the sequence satisfy the condition $|\mathcal{B}_{r(n)}^d(S_f^{1-\delta})| \sim O(n^{d\eta})$.

A.6'. (Restriction of covering to S_0) Let $\mathcal{B}_{r(n)}^d(S_f^{1-\delta})$ be the covering considered in A.5'. If d_0 is the Minkowski dimension of S_0 and $d_0 < d$, then the number of balls in $\mathcal{B}_{r(n)}^d(S_f^{1-\delta})$ intersecting S_0 is bounded from above by $H_\epsilon(n) \sim O(n^{d_0\eta(1+\epsilon)})$, for each $\epsilon > 0$.

As for the compact case on page 8, these assumptions can be divided into three groups. A.1' and A.2' are restrictions on the topology on the support; A.3' and A.4' are descriptions of the local behavior of the density function; and A.5' and A.6' stipulate the existence of a sequence of coverings with good properties.

THEOREM 13. Consider a sequence of i.i.d. data $X_1, X_2 \dots$ drawn from a distribution having a continuous density $f(\mathbf{x})$ w.r.t. the d -dimensional Lebesgue measure ν^d on \mathbb{R}^d . Assume that A.1'-A.6' hold and that $S_f^{1-\delta} \subset \text{int } M'$. Assume also that the radius r and the separation distance ϵ satisfy the following growth rates:

$$\begin{aligned} r(n) &\sim O(n^{-\eta}), \quad 0 < \eta < \frac{1}{d}, \\ \epsilon(n) &\sim O(n^{-\psi}), \quad 0 < \psi \leq \eta, \\ 2r(n) &\leq \epsilon(n) < 1. \end{aligned}$$

Finally, assume that the density f outside the ϵ -neighborhood of S_0 satisfies:

$$m(f, n) := \min_{\mathbf{w} \in S_f^{1-\delta} \setminus B_\epsilon(S_0)} f(\mathbf{w}) \in (0, \infty) \sim O(n^{-\xi}), \quad 0 < \xi < \frac{1-2\eta d}{2}.$$

Then:

(A) If η and ψ satisfy

$$1 - 2\eta d - 2\overline{K}_f \psi > 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{no empty } \epsilon(n)\text{-outside balls}) = 1$.

(B) If η and ψ satisfy

$$1 + d_0 \eta - \underline{K}_f \eta - d\eta < 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{all } \epsilon(n)\text{-inside balls are empty}) = 1$.

PROOF. The idea of the proof is that the number of samples falling inside $S_f^{1-\delta}$ is close to the total number of samples, n , by the definition of $(1-\delta)$ -support and the law of large numbers. By assumption, we know that $S_f^{1-\delta}$ is the hyper-cube $[-B, B]^d$ contained in $\text{int } M'$ and that A.1'-A.6' hold. The number n_δ of observations that fall in $S_f^{1-\delta}$ has a $\text{Binom}(n, 1-\delta)$ distribution. Using the two-sided Hoeffding inequality, (A.6) of the appendix, with $\gamma = \frac{\delta}{2}, p = 1-\delta$, we have:

$$\begin{aligned} P(n_\delta \geq n(1 - \delta - \frac{\delta}{2})) &= P(n_\delta \geq n(1 - \frac{3\delta}{2})) \\ &\geq P((1 - \frac{3\delta}{2})n \leq n_\delta \leq (1 - \frac{\delta}{2})n) \\ &\geq 1 - 2 \exp\left(-\frac{\delta^2}{2} n\right). \end{aligned}$$

Conditioning on the event that that $n_\delta \geq n(1 - \frac{3\delta}{2})$ merely adds a nonzero multiplicative factor to the probabilities of the events appearing in cases (A) and (B) of the statement of the theorem. With this adjustment the proof of this theorem parallels that of Theorem 10. The conditional probabilities of the events in (A) and (B) tend to 1 as $n \rightarrow \infty$. We also know that, as $n \rightarrow \infty$, the probability of the conditioning event tends to 1, completing the proof. \square

The result above is stated for a fixed $(1 - \delta)$ -support $S_f^{1-\delta}$. As the sample size n tends to infinity, we do not want to constrain ourselves to a fixed $S_f^{1-\delta}$, since this will prevent us from exploring the entire support of f . Consider a sequence of regions $S_f^{1-\delta(n)}$ with a decreasing sequence of $\delta = \delta(n)$, expanding the region under consideration as the sample accumulates. To retain the conclusions of the theorem, we must take care to expand the region slowly enough to control the decay of the density near the edges of $S_f^{1-\delta(n)}$.

In what follows, we denote by $\mathcal{B}_{r(n)}^d$ a covering of $S_f^{1-\delta(n)}$ and assume that A.5' and A.6' hold for this sequence of coverings. (Note that, here, $\mathcal{B}_{r(n)}^d$ denotes a covering of the $(1 - \delta)$ support, not of \mathbb{R}^d , and that we dropped the explicit dependence on $S_f^{1-\delta(n)}$ that appears in A.5' and A.6' to simplify notation.)

THEOREM 14. Under the assumptions of Theorem 13, consider a positive decreasing sequence $\delta(n)$ satisfying $\lim_{n \rightarrow \infty} \delta(n) = 0$ and the associated sequence of $(1 - \delta)$ -supports $S_f^{1-\delta(n)}$. For each $(1 - \delta)$ -support $S_f^{1-\delta(n)}$ we consider its corresponding covering $\mathcal{B}_{r(n)}^d$ consisting of open balls of radius $r(n)$.

Assume that

$$M(f) := \sup_{\mathbf{w} \in \mathbb{R}^d} f(\mathbf{w}) \in (0, \infty),$$

$$m(f, n) := \min_{\mathbf{w} \in S_f^{1-\delta(n)} \setminus B_{\epsilon(n)}(S_0)} f(\mathbf{w}) \in (0, \infty) \sim O(n^{-\xi}), \quad 0 < \xi < \frac{1 - 2\eta d}{2},$$

and that the cardinality $|\mathcal{B}_{r(n)}^d| \sim o(n^\Omega)$, $\Omega \geq \eta > 0$.

Then, if η and ψ satisfy

$$1 - 2\eta d - 2\overline{K}_f \cdot \psi > 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{no empty } \epsilon(n)\text{-outside balls}) = 1$.

PROOF. We denote the number of total samples by n and the number of samples falling inside $S_f^{1-\delta(n)}$ by $\mathcal{N}_{\delta(n)}$. To start, let us consider a sufficiently large $n \geq \mathbf{N}_1$ such that the decreasing sequence satisfies $\delta(n) \leq 0.1$ so that $1 - \delta(n) \geq 0.9$. Then, let us decompose the event $C_n = \{\text{no empty } \epsilon(n)\text{-outside balls}\}$ using the event $D_n = \{0.95n \leq \mathcal{N}_{\delta(n)} \leq n\}$ and its complement. The the law of total probability yields:

$$\begin{aligned} P(C_n) &= P(C_n | D_n) \cdot P(D_n) + P(C_n | D_n^c) \cdot P(D_n^c) \\ (4.1) \quad &\geq P(C_n | D_n) \cdot P(D_n). \end{aligned}$$

The event D_n involves a binomial random variable $\mathcal{N}_{\delta(n)}$, therefore $P(D_n)$ can be bounded by the Hoeffding inequality, (A.6) of the appendix. Since $1 - \delta(n) \geq 0.9$,

$$(4.2) \quad P(D_n) = P(0.95n \leq \mathcal{N}_{\delta(n)} \leq n) \geq 1 - 2 \exp\left(-\frac{0.1^2}{2} n\right).$$

The other term, $P(C_n | D_n)$, can also be bounded by the following argument. (Note that $r(n)$ and $\epsilon(n)$ only depend on the total sample size n , not on $\mathcal{N}_{\delta(n)}$.)

$$\begin{aligned} P(C_n | D_n) &= 1 - P(C_n^c | D_n) \\ &\geq 1 - \sum_{B \in \{\epsilon(n)\text{-outside balls}\}} P(B \text{ empty} | D_n) \end{aligned}$$

$$(4.3) \quad \geq 1 - |\mathcal{B}_{r(n)}^d| \cdot \left(1 - \inf_{B \in \{\epsilon(n)\text{-outside balls}\}} P(B \text{ not empty} \mid D_n) \right).$$

By the bound in (A.8) in the proof of Theorem 10 in the appendix and the assumption that $|\mathcal{B}_{r(n)}^d| \sim o(n^\Omega)$ we have

$$|\mathcal{B}_{r(n)}^d| \cdot \left(1 - \inf_{B \in \{\epsilon(n)\text{-outside balls}\}} P(B \text{ not empty} \mid D_n) \right) \sim o(n^\Omega) \cdot O \left(\exp \left(-n^{\min(1-2\eta d - 2\overline{K}_f \cdot \psi, 1-2\eta d - 2\xi)} \right) \right),$$

which is of order $o(n^\Omega) \cdot O \left(\exp \left(-n^{1-2\eta d - 2\overline{K}_f \cdot \psi} \right) \right)$, since $0 < \xi < \frac{1-2\eta d}{2}$. Using the definition of big/small O notation, we can find a constant $L \in (0, \infty)$ such that

$$(4.4) \quad P(C_n \mid D_n) \geq 1 - L \cdot n^\Omega \cdot \exp \left(-n^{1-2\eta d - 2\overline{K}_f \cdot \psi} \right) \text{ for sufficiently large } n.$$

The bounds (4.2) and (4.4) can be substituted back into (4.1) to obtain

$$(4.5) \quad \begin{aligned} P(C_n) &\geq P(C_n \mid D_n) \cdot P(D_n) \\ &\geq \left(1 - L \cdot n^\Omega \cdot \exp \left(-n^{1-2\eta d - 2\overline{K}_f \cdot \psi} \right) \right) \left(1 - 2 \exp \left(-\frac{0.1^2}{2} n \right) \right). \end{aligned}$$

As long as $1 - 2\eta d - 2\overline{K}_f \cdot \psi > 0$, this lower bound tends to 1 as n goes to infinity. \square

It is important to notice that it is the decay rates of $m(f, n)$ and $|\mathcal{B}_{r(n)}^d| \sim o(n^\Omega)$ that determine the sufficient conditions of Theorem 14, not the rate at which the volume of $S_f^{1-\delta(n)}$ increases.

The following theorem deals with the $\epsilon(n)$ -inside balls.

THEOREM 15. Under the assumptions of Theorem 13, consider a positive decreasing sequence $\delta(n)$ satisfying $\lim_{n \rightarrow \infty} \delta(n) = 0$ and the associated sequence of $(1 - \delta)$ -supports $S_f^{1-\delta(n)}$. For each $(1 - \delta)$ -support $S_f^{1-\delta(n)}$ we consider its corresponding covering $\mathcal{B}_{r(n)}^d$ consisting of open balls of radius $r(n)$.

Assume that

$$m(f, n) := \min_{\mathbf{w} \in S_f^{1-\delta(n)} \setminus B_{\epsilon(n)}(S_0)} f(\mathbf{w}) \in (0, \infty) \sim O(n^{-\xi}), \quad 0 < \xi < \frac{1 - 2\eta d}{2}.$$

Then, if η and ψ satisfy

$$1 + d_0\eta - \underline{K}_f\eta - d\eta < 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{all } \epsilon(n)\text{-inside balls are empty}) = 1$.

PROOF. This result can be established by following exactly the same proof as that for case (B) in Theorem 13. Since $S_0 \subset \text{int } M'$ we can choose \mathbf{N}_1 sufficiently large so that $B_{\epsilon(n)}(S_0) \subset \text{int } S_f^{1-\delta(n)}$, for $n \geq \mathbf{N}_1$. The probability of the event that an individual $\epsilon(n)$ -inside ball is empty does not depend on the varying sequence of regions $S_f^{1-\delta(n)}$. For an appropriate \mathbf{N}_2 and every $n \geq \mathbf{N}_2$, our assumption A.6' restricts the number of ϵ -inside balls and this cardinality does not depend on the varying $(1 - \delta(n))$ -supports. The rest of the proof parallels that of Theorem 13 (B), considering $n \geq \max(\mathbf{N}_1, \mathbf{N}_2) + 1$. \square




FIGURE 4.1. Density functions with polynomial tails (blue) and exponential tails (orange).

The existence of a sequence of $\delta(n)$ values satisfying the above conditions can be verified for densities exhibiting specific tail behaviors on their supports. Two examples of such densities are given in the two examples following Definitions 16 and 17 and are depicted in Figure 4.1.

DEFINITION 16. (Polynomial tail) We say that a continuous density f supported on \mathbb{R}^d has a *polynomial tail* if it has the form

$$(4.6) \quad f(\mathbf{x}) = \begin{cases} f_1(d(\mathbf{x}, S_0)) = C_1 \cdot d(\mathbf{x}, S_0)^\gamma, & d(\mathbf{x}, S_0) < \epsilon_0, \\ f_2(d(\mathbf{x}, S_0)) = C_2 \cdot d(\mathbf{x}, S_0)^\chi, & d(\mathbf{x}, S_0) \geq \epsilon_0, \end{cases}$$

for some $C_1, C_2 \in (0, \infty)$, $\gamma > 0$, and $\chi < -d$. Note that the continuity assumption on the density f requires $C_1 \cdot \epsilon_0^\gamma = C_2 \cdot \epsilon_0^\chi$.

EXAMPLE. Consider a continuous density f of the form (4.6) with $d = 1$, $S_0 = \{0\}$, $\epsilon_0 = 1$, $\gamma = \frac{1}{3}$, and $\chi = -2$, leading to the density $f(x) = \begin{cases} \frac{2}{7} \cdot |x|^{1/3}, & |x| < 1, \\ \frac{2}{7} \cdot |x|^{-2}, & |x| \geq 1, \end{cases}$. This density yields $\frac{2}{7} \int_{-1}^1 |x|^{1/3} dx = \frac{3}{7}$. We can take n sufficiently large so that $\delta(n) < \frac{4}{7}$. From the definition of $(1 - \delta(n))$ -support we have $B(n) > \epsilon_0 = 1$ for $\delta(n) < \frac{4}{7}$. The defining equation of $B(n)$ is $\int_{-\infty}^{-B(n)} f(x) dx + \int_{B(n)}^{\infty} f(x) dx = 2 \int_{B(n)}^{\infty} f(x) dx = \delta(n)$. Therefore $B(n) = \frac{1}{\frac{2}{7}\delta(n)} \sim O(\delta(n)^{-1})$.

The maximum of this density function is attained at $x = \pm 1$ and equals $M(f) = \frac{2}{7}$. Let ξ and ψ be as defined in Theorem 13. Then, if we choose sequences $\delta(n) \sim O(n^{\xi/\chi}) \sim O(n^{-\xi/2})$ and $\epsilon(n) \sim O(n^{-\psi}) \sim O(n^{-\xi/\gamma}) \sim O(n^{-3\xi})$, we will ensure that the minimal value $m(f, n) := \min_{\mathbf{w} \in S_f^{1-\delta(n)} \setminus B_{\epsilon(n)}(S_0)} f(\mathbf{w}) = \min(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot B(n)^\chi) = \min\left(\frac{2}{7}\epsilon(n)^{1/3}, \frac{2}{7}B(n)^{-2}\right)$. We have $\frac{2}{7}\epsilon(n)^{1/3} \sim O(n^{-\xi})$ and $\frac{2}{7}B(n)^{-2} \sim O(n^{-\xi})$, so that $m(f, n) \sim O(n^{-\xi})$. Furthermore, $\delta(n) \sim O(n^{-\xi/2}) \rightarrow 0$. The assumptions on the density function in Theorem 13 are therefore satisfied.

DEFINITION 17. (Exponential tail) We say that a continuous density f supported on \mathbb{R}^d has an *exponential tail* if it has the form

$$(4.7) \quad f(\mathbf{x}) = \begin{cases} f_1(d(\mathbf{x}, S_0)) = C_1 \cdot d(\mathbf{x}, S_0)^\gamma, & d(\mathbf{x}, S_0) < \epsilon_0, \\ f_2(d(\mathbf{x}, S_0)) = C_2 \cdot \exp(\beta d(\mathbf{x}, S_0)), & d(\mathbf{x}, S_0) \geq \epsilon_0, \end{cases}$$

for some $C_1, C_2 \in (0, \infty)$, $0 < \gamma$ and $\beta < 0$. Note that the continuity assumption on the density f requires $C_1 \cdot \epsilon_0^\gamma = C_2 \cdot \exp(-\beta\epsilon_0)$.

EXAMPLE. Consider a continuous density f of the form (4.7) with $d = 1$, $S_0 = \{0\}$, $\epsilon_0 = 1$, $\gamma = \frac{1}{3}$, and $\beta = -2$, leading to the density $f(x) = \begin{cases} \frac{2}{5} \cdot |x|^{1/3}, & |x| < 1, \\ \frac{2}{5} \cdot e^2 \cdot e^{-2|x|}, & |x| \geq 1. \end{cases}$ This density yields $\int_{-1}^1 \frac{2}{5} \cdot |x|^{1/3} dx = \frac{3}{5}$. We can take n sufficiently large so that $\delta(n) < \frac{2}{5}$. From the definition of $(1 - \delta(n))$ -support we have $B(n) > \epsilon_0 = 1$ for $\delta(n) < \frac{2}{5}$. The defining equation of $B(n)$ is $\int_{-B(n)}^{-\infty} f(x) dx + \int_{B(n)}^{\infty} f(x) dx = 2 \int_{B(n)}^{\infty} f(x) dx = \delta(n)$. Therefore $B(n) = 1 - \frac{1}{2} \log(1 + \frac{5}{2} \delta(n)) \sim O(-\log \delta(n))$.

The maximum of this density function is attained at $x = \pm 1$ and equals $M(f) = \frac{2}{5}$. Let ξ and ψ be as defined in Theorem 13. Then if we choose sequences $\delta(n) \sim O(n^{\xi/\beta}) \sim O(n^{-\xi/2})$ and $\epsilon(n) \sim O(n^{-\psi}) \sim O(n^{-\xi/\gamma}) \sim O(n^{-3\xi})$, we will ensure that the minimal value $m(f, n) := \min_{\mathbf{w} \in S_f^{1-\delta(n)} \setminus B_{\epsilon(n)}(S_0)} f(\mathbf{w}) = \min(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot \exp(\beta B(n))) = \min\left(\frac{2}{5} \epsilon(n)^{1/3}, \frac{2}{5} e^2 \cdot \exp(-2B(n))\right)$. We have $\frac{2}{5} \epsilon(n)^{1/3} \sim O(n^{-\xi})$ and $\frac{2}{5} e^2 \cdot \exp(-2B(n)) \sim O(n^{-\xi})$, so that $m(f, n) \sim O(n^{-\xi})$. Furthermore, $\delta(n) \sim O(n^{-\xi/2}) \rightarrow 0$. The assumptions on the density function in Theorem 13 are therefore satisfied.

The essence of the examples above is embodied in the following general result whose proof follows along the path suggested by the examples.

PROPOSITION 18. Assume that a continuous density supported on \mathbb{R}^d is of the form (4.6) or (4.7) with a compact zero-density region S_0 . For fixed $0 < \eta < \frac{1}{d}$, $0 < \xi < \frac{1-2\eta d}{2}$, we can find a sequence $\epsilon(n) \sim O(n^{-\psi})$, $0 < \psi \leq \eta$, and a decreasing sequence of $\delta(n)$, with $\lim_{n \rightarrow \infty} \delta(n) = 0$, such that

$$M(f) := \sup_{\mathbf{w} \in \mathbb{R}^d} f(\mathbf{w}) \in (0, \infty),$$

$$m(f, n) := \min_{\mathbf{w} \in S_f^{1-\delta(n)} \setminus B_{\epsilon(n)}(S_0)} f(\mathbf{w}) \in (0, \infty) \sim O(n^{-\xi}), \quad 0 < \xi < \frac{1-2\eta d}{2}.$$

PROOF. That $M(f) := \sup_{\mathbf{w} \in \mathbb{R}^d} f(\mathbf{w}) \in (0, \infty)$ is a direct consequence of the assumptions about the form of (4.6) or (4.7).

We want to show that we can construct a decreasing sequence $\delta(n)$, with $\lim_{n \rightarrow \infty} \delta(n) = 0$, such that the corresponding $1 - \delta(n)$ supports $S_f^{1-\delta(n)} := [-B(n), B(n)]^d$ have minimal values $m(f, n) \sim O(n^{-\xi})$. First, we choose the sequences $B(n)$ and $\epsilon(n)$, which jointly determine the desired decay rate of $m(f, n)$. Then, if $B(n)$ is an increasing sequence, by the definition of $S_f^{1-\delta(n)}$ as a cube, $\delta(n)$ is automatically a decreasing sequence.

To determine $B(n)$, we use a sandwich argument on the minimal value $m(f, n)$ attained on $S_f^{1-\delta(n)}$. We will consider two sequences of balls, one where each ball is contained in $S_f^{1-\delta(n)}$, called the sequence of *inner tangential balls* $\mathcal{B}_*(n)$, and the other where each ball contains $S_f^{1-\delta(n)}$, called the sequence of *outer inclusive balls* $\mathcal{B}^*(n)$:

$$(4.8) \quad \mathcal{B}_*(n) := B_{B(n)}(\mathbf{0}) \equiv \{\mathbf{x} \in \mathbb{R}^d \mid d(\mathbf{x}, \mathbf{0}) < B(n)\},$$

$$(4.9) \quad \mathcal{B}^*(n) := B_{4\sqrt{d}B(n)}(\mathbf{0}) \equiv \{\mathbf{x} \in \mathbb{R}^d \mid d(\mathbf{x}, \mathbf{0}) < 4\sqrt{d}B(n)\}.$$

Consider the following minimal values of f on $\mathcal{B}_*(n) \setminus B_{\epsilon(n)}(S_0)$ and $\mathcal{B}^*(n) \setminus B_{\epsilon(n)}(S_0)$,

$$\begin{aligned} m_*(f, n) &= \inf_{\mathbf{w} \in \mathcal{B}_*(n) \setminus B_{\epsilon(n)}(S_0)} f(\mathbf{w}), \\ m^*(f, n) &= \inf_{\mathbf{w} \in \mathcal{B}^*(n) \setminus B_{\epsilon(n)}(S_0)} f(\mathbf{w}). \end{aligned}$$

Since $\mathcal{B}_*(n) \subset S_f^{1-\delta(n)} \subset \mathcal{B}^*(n)$ by the above construction, we have $m_*(f, n) \geq m(f, n) \geq m^*(f, n)$. When f is of the form (4.6) or (4.7), we can choose the sequence $\epsilon(n) = \left(\frac{1}{C_1} \cdot n^{-\xi}\right)^{1/\gamma_1}$ where $\gamma_1 \geq \gamma > 0$ such that $0 < \frac{\xi}{\gamma_1} \leq \eta$. We use this choice of $\epsilon(n)$ to ensure that $\epsilon(n) \sim O(n^{-\psi}) \sim O(n^{-\frac{\xi}{\gamma_1}})$, and $0 < \psi \leq \eta$ hold. Note that $\epsilon(n)$ is a decreasing sequence by definition.

(Polynomial tail) When f is of the form (4.6), we use the $\epsilon(n)$ above and choose another sequence $B(n) = \left(\frac{1}{C_2} \cdot n^\xi\right)^{-1/\chi}$ and take n sufficiently large so that $\epsilon(n) < \frac{1}{4}B(n)$ and $\epsilon_0 < B(n)$. Then the minimal values for $\mathcal{B}_*(n)$ satisfy

$$\begin{aligned} m_*(f, n) &\leq \min(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot (B(n) - \epsilon(n))^\chi) \\ &\sim O(\min(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot B(n)^\chi)) \\ &\sim O\left(\min\left(C_1 \cdot n^{-\frac{\gamma}{\gamma_1}\xi}, n^{-\xi}\right)\right). \end{aligned}$$

Since $\gamma/\gamma_1 \leq 1$ for $n > 1$ large enough, we have that this asymptotic order of magnitude is determined by the behavior of the second term and $m_*(f, n) \sim O(n^{-\xi})$. Similarly, the minimal values for $\mathcal{B}^*(n)$ satisfy

$$\begin{aligned} m^*(f, n) &\geq \min\left(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot (4\sqrt{d}B(n) + \epsilon(n))^\chi\right) \\ &\sim O(\min(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot B(n)^\chi)) \\ &\sim O(n^{-\xi}). \end{aligned}$$

(Exponential tail) When f is of the form (4.7), we use the $\epsilon(n)$ above and choose another sequence $B(n) = \frac{1}{\beta} \log\left(\frac{1}{C_2} \cdot n^{-\xi}\right)$ and take n sufficiently large so that $\epsilon(n) < \frac{1}{4}B(n)$ and $\epsilon_0 < B(n)$. Then the minimal values for $\mathcal{B}_*(n)$ satisfy

$$\begin{aligned} m_*(f, n) &\leq \min(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot \exp(\beta(B(n) - \epsilon(n)))) \\ &\sim O(\min(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot \exp(\beta B(n)))) \\ &\sim O\left(\min\left(C_1 \cdot n^{-\frac{\gamma}{\gamma_1}\xi}, n^{-\xi}\right)\right). \end{aligned}$$

Since $\gamma/\gamma_1 \leq 1$ for $n > 1$ large enough, we have that this asymptotic order of magnitude is determined by the behavior of the second term and $m_*(f, n) \sim O(n^{-\xi})$. Similarly, the minimal values for $\mathcal{B}^*(n)$ satisfy

$$\begin{aligned} m^*(f, n) &\geq \min\left(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot \exp(\beta(4\sqrt{d}B(n) + \epsilon(n)))\right) \\ &\sim O(\min(C_1 \cdot \epsilon(n)^\gamma, C_2 \cdot \exp(\beta B(n)))) \\ &\sim O(n^{-\xi}). \end{aligned}$$

By a sandwich argument with $\mathcal{B}_*(n) \subset S_f^{1-\delta(n)} \subset \mathcal{B}^*(n)$ and $m_*(f, n) \geq m(f, n) \geq m^*(f, n)$, we know that we can find some $\frac{1}{4\sqrt{d}} \cdot \left(\frac{1}{C_2} \cdot n^\xi\right)^{-1/\chi} \leq B(n) \leq \left(\frac{1}{C_2} \cdot n^\xi\right)^{-1/\chi}$ for

a density of the form (4.6) or some $\frac{1}{4\sqrt{d}} \cdot \frac{1}{\beta} \log\left(\frac{1}{C_2} \cdot n^{-\xi}\right) \leq B(n) \leq \frac{1}{\beta} \log\left(\frac{1}{C_2} \cdot n^{-\xi}\right)$ for a density of the form (4.7). This choice of an increasing sequence of $B(n)$ proves our claim that we can find a sequence of $\delta(n)$, with $\lim_{n \rightarrow \infty} \delta(n) = 0$, such that $M(f) \in (0, \infty)$ and $m(f, n) \sim O(n^{-\xi})$. \square

COROLLARY 19. *Consider a continuous density supported on \mathbb{R}^d of the form (4.6) or (4.7). We can find a sequence $\epsilon(n) \sim O(n^{-\psi})$, $0 < \psi \leq \eta$, and a decreasing sequence of $\delta(n)$ values, with $\lim_{n \rightarrow \infty} \delta(n) = 0$, such that the associated sequence of $(1 - \delta(n))$ -supports $S_f^{1-\delta(n)}$ have corresponding coverings $\mathcal{B}_{r(n)}^d$ satisfying A.5' and A.6'. Then*

(A) *If η and ψ satisfy*

$$1 - 2\eta d - 2\overline{K}_f \cdot \psi > 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{no empty } \epsilon(n)\text{-outside balls}) = 1$.

(B) *If η and ψ satisfy*

$$1 + d_0\eta - \underline{K}_f\eta - d\eta < 0,$$

we have $\lim_{n \rightarrow \infty} P(\text{all } \epsilon(n)\text{-inside balls are empty}) = 1$.

PROOF. By the result in Proposition 18, it suffices to consider the grid construction in Lemma 8. The cardinality of the resulting coverings $\mathcal{B}_{r(n)}^d$ of $S_f^{1-\delta(n)}$ can be guaranteed to be $O\left(\frac{B(n)^d}{r(n)^d}\right)$. So, for case (4.6) we can have $|\mathcal{B}_{r(n)}^d| \sim O\left(\left(\frac{1}{C_2} \cdot n^{-\xi}\right)^{d/\chi} \cdot n^{\eta d}\right)$ and for case (4.7) we can have $|\mathcal{B}_{r(n)}^d| \sim O\left(\frac{1}{\beta^d} \log^d\left(\frac{1}{C_2} \cdot n^{-\xi}\right) \cdot n^{\eta d}\right)$. In either case, $|\mathcal{B}_{r(n)}^d|$ is obviously $o(n^\Omega)$ for some sufficiently large $\Omega > 0$. Therefore all assumptions in Theorems 14 and 15 are met. \square

5. Simulations and Connections to Other Areas.

5.1. *Simulation Studies for the choice of r, ϵ .* Our theoretical results establish the rate of decay for the radius $r(n)$ and the neighborhood width $\epsilon(n)$. That is, for any positive constants M_r and M_ϵ ,

$$r(n) = M_r \cdot O(n^{-\eta}),$$

$$\epsilon(n) = M_\epsilon \cdot O(n^{-\psi}).$$

(with η and ψ following the same notation used in Theorem 10) the asymptotic guarantees of filled and empty balls hold. These guarantees allow one to identify lower dimensional zero-density regions in the limit. However, for a fixed sample size, the actual values of $r(n)$ and $\epsilon(n)$ matter. This subsection reports simulations investigating choice of the constants M_r and M_ϵ .

We consider the density $f(\mathbf{x}) \propto d(\mathbf{x}, S_0)^4 \circ \mathbf{1}_{[0,1]^2}$.

The zero-density region $S_0 = \{\frac{1}{2}\} \times [0.25, 0.75]$ is of strictly lower dimension. For this example, $m(f, n)$ decays as a polynomial with $\xi = 4 \cdot \psi$ and $M(f) < 2$. The conditions of Theorem 10, parts (A) and (B), hold with, for example, $\eta = 0.21$ and $\psi = 0.01$ (therefore $0 < \xi \leq \frac{1-4\eta}{2}$).

In the simulation, random samples of various sizes are generated from the density. A grid of balls with centers on a lattice is used to cover the unit square. The centers of the balls depend on M_r and n and follow the rule we described in Proposition 9. We




FIGURE 5.1. The percentage of various types of non-empty covering balls under different multipliers M_r and M_ϵ for ball radius $r(n)$ of the covering and neighborhood width of S_0 , $\epsilon(n)$, for various sample sizes n .

note that the fraction of filled balls of a particular kind serves as an empirical estimate of the mean probability that a particular kind of ball is non-empty.

Figure 5.1 presents the results of the simulation. The color scheme is the same as in Figure 3.2. Proceeding down a column, the sample size changes from 100 to 10,000. Tracking the red lines, we see that the percentage of filled ϵ -inside balls tends to 0 as n increases. The orange lines represent the ϵ -neighboring balls. The percentage of these that are filled does not always tend to 0. The green lines represent the ϵ -outside balls. Here, the fraction filled increases toward the eventual limit of 1.

As we step across rows of the figure, the value of M_ϵ increases from 0.05 to 0.40. Within a plot, the value of M_r increases from 0.05 to 0.40. As $r(n)$ increases, the balls are larger and a greater fraction are filled, as evidenced by the lines within each plot. As M_ϵ increases, balls in the covering are moved from ϵ -outside to ϵ -neighboring to ϵ -inside. The changing values of $\epsilon(n)$ and $r(n)$ shuffle the group membership of the balls and change the resulting fractions. In general, the larger values of M_r that we have investigated lead to greater separation of the red and green lines—hence greater differentiation between ϵ -inside and ϵ -outside balls. Larger values of M_ϵ have a similar, though weaker effect.

The simulation also provides a caution. The plots toward the bottom of the figure show much greater separation between the red and green lines. This separation (near 0, near 1) is needed in order to reliably detect a zero-density region. For this density, the larger sample sizes prove much more effective than do the smaller sample sizes.

The simulation results suggest an interesting possibility—the use of multiple coverings with balls of different sizes. Doing so could allow one to examine the set of M_r, M_ϵ pairs that suggest the presence of a zero-density region. In practice, when n is finite, the choice of multipliers M_r and M_ϵ impacts the results.

5.2. *Connections to Existing Research.* Our object of interest in this paper is the inverse image of $\{0\}$ under the continuous density function f . In the existing literature, Cuevas [6] and Rigollet and Vert [21] study the related concept of the λ -level set for density f . That is, the set $S_\lambda := \{\mathbf{x} \in \mathbb{R}^d \mid f(\mathbf{x}) > \lambda\}, \lambda > 0$. The special case where $\lambda = 0$ is studied in Devroye and Wise [7]. The difference between the regions is that S_λ is the inverse image of an open set that contains positive mass if non-empty while $S_0 := \{\mathbf{x} \in \mathbb{R}^d \mid f(\mathbf{x}) = 0\}$ is the inverse image of a closed set and contains no mass. To the best of our knowledge, regions like S_0 have not previously been studied.

In the level set estimation literature, there are two major approaches to the problem of estimating level sets. Suppose we are interested in estimating the level sets of density f (corresponding to a probability measure F). One approach is to construct plug-in estimators $\hat{S}_\lambda := \{\mathbf{x} \in \mathbb{R}^d \mid \hat{f}(\mathbf{x}) > \lambda\}$ for a level set, based on a kernel density estimator \hat{f} computed from the data and appropriate choices of the bandwidth parameters for the kernel [21, 17, 22].

The other approach is based on the empirical excess-mass functional. The (empirical) excess-mass functional $E(\lambda) := F(S_\lambda) - \lambda \text{Leb}(S_\lambda)$ measures how the “excess probability mass” of the probability measure F distributes over the region S_λ when compared to Lebesgue measure [11]. If we substitute the set S_λ with a set estimator \hat{S}_λ for the λ -level set S_λ , we can similarly consider the functional $H(\lambda) := F(\hat{S}_\lambda) - \lambda \text{Leb}(\hat{S}_\lambda)$, which can be used to evaluate the estimator \hat{S}_λ . The functional H is maximized over a class of sets to obtain the level set estimator \hat{S}_λ [20, 24], to obtain level set estimators \hat{S}_λ . The consistency and asymptotic behavior of both approaches has been derived under regularity assumptions.

In this paper, we study the lower dimensional object that arises as the inverse image of density function f of a single point set. When we restrict our concern to the manifold $\text{supp}(f)$ and the inverse of the density function f^{-1} is sufficiently smooth, $f^{-1}(\{a\}), f^{-1}(\{b\})$ encode the boundary of the manifold defined by the inverse image $f^{-1}((a, b))$, as a sub-manifold of $\text{supp}(f)$. When $a = \lambda$ and $b = \infty$, this inverse image defines λ -level sets. The object $S_0 = f^{-1}(\{0\})$ is the boundary of such a particular example where $a = 0$ and $b = \infty$.

Our method detects this specific kind of lower dimensional topological feature that could arise as a manifold boundary. We construct a sequence of covering families to detect S_0 and we derive a set of sufficient conditions that ensure consistent detection. As is to be expected, when more sample points are available, our covering scheme locates the zero-density region S_0 more accurately. In applied scenarios where the boundaries arise as zero-density regions of certain density functions, our method could help in detection [15].

The main results in this paper also exhibit the relation between topological features that arise as S_0 , and its dimensionality. In Adler, Bobrowski and Weinberger [1] and Owada and Adler [18], the authors observe that higher dimensional topological features are generally smaller in scale. As shown by the sufficient conditions in Theorem 10 and 13, when the dimension d_0 of S_0 is higher, we need to specify a faster decay rate for radii $r(n)$ of the covering sequence in order to meet the sufficient conditions. This interplay between the dimension of the support, the dimension of the zero-density region S_0 and the sufficient growth rates supports Adler, Bobrowski and Weinberger [1]’s observation from a different angle.

6. Conclusions. In this paper, we consider the question of detection of $S_0 = f^{-1}(\{0\})$ lying in the support M of a continuous density f when S_0 has Minkowski dimension strictly lower than the dimension of the data, d . This type of topological feature is difficult to identify and has not been studied before. The main contribution in this paper is to provide a novel approach, based on a sequence of coverings tied to growing sample sizes, to study a specific kind of lower dimensional object S_0 in the support of a density function. This approach works under both compact and non-compact support and its construction has geometric intuition. Being of lower dimension, S_0 is a delicate object. It is in the closure of $M \setminus S_0$ and, in a sense, disappears when one looks at it at too coarse a resolution.

Our strategy is to construct a sequence of covering balls (e.g., Lemma 8) and shrink their radius as the sample size n goes to infinity. We derive a set of sufficient conditions, using the local behavior of f , captured by \overline{K}_f and \underline{K}_f , that ensure that a particular covering scheme leads to probability one consistency results in Theorem 10 (compact support) and Theorem 13 (non-compact support). This set of theorems in Section 3 and 4 can be generalized to the case where S_0 has multiple disconnected components. As the sample size n tends to ∞ , a shrinking ϵ -neighborhood of S_0 can be identified by empty covering balls asymptotically with probability one while the rest of M will be covered by non-empty balls.

Our result provides a range of asymptotic schemes for the radius of covering balls under which the lower dimensional topological feature can be detected. We provide experimental evidence to support our claim in Section 5. Our approach supports the insight that different dimensional topological features occur at different scales. The novelty of our result is the role of the ambient dimension of the data in addition to the local behavior of f near S_0 .

Our approach and results focus on the connection between i.i.d. samples and the near-topological features of the support of the density from which they are drawn. As future work, it is of great interest to generalize the results to dependent draws from the density, with the eventual goal of understanding how probabilistic dependence in the sample can be useful in the construction of complexes based on sub-samples (e.g. witness complexes) used in TDA [16].

APPENDIX A: PROOF OF MAIN THEOREM

The Theorem 10 is established by providing a bound on the probability mass of a covering ball $B_r(\mathbf{x})$, counting the number of each type of covering ball under consideration and taking a limit as the sample size $n \rightarrow \infty$. A sequence of upper bounds is needed for ϵ -inside balls and a sequence of lower bounds is needed for ϵ -outside balls.

In the statement of the theorem, we assume that the sequence

$$\begin{aligned} r(n) &\sim O(n^{-\eta}), \quad 0 < \eta < \frac{1}{d}, \\ \epsilon(n) &\sim O(n^{-\psi}), \quad \psi \leq \eta, \\ &\text{and } 2r(n) \leq \epsilon(n) < 1. \end{aligned}$$

To establish the bounds on the probability on the probability mass $P(B_r(\mathbf{x})) = \int_{B_r(\mathbf{x})} f(\mathbf{w}) d\mathbf{w}$ of a ball $B_r(\mathbf{x})$, it suffices to consider the volume of the ball and a bound on the density function over the ball. The volume for a d -dimensional ball of radius r is

$$(A.1) \quad V_d(r) = \frac{\pi^{\frac{d}{2}}}{\Gamma\left(\frac{d}{2} + 1\right)} r^d,$$

which for our sequence of radii $r(n)$ is $V_d(r(n)) \sim O(n^{-d\eta})$. Recall from the definitions of ϵ -inside and ϵ -outside covering balls:

ϵ -inside balls are those balls $B_r(\mathbf{x})$ such that $\mathbf{x} \in B_\epsilon(S_0)$ and $B_r(\mathbf{x}) \cap S_0 \neq \emptyset$.

ϵ -outside balls are those balls $B_r(\mathbf{x})$ such that $\mathbf{x} \notin B_\epsilon(S_0)$.

Outside $B_{\epsilon(n)}(S_0)$ the density is bounded below by $m(f, n) \sim O(n^{-\xi})$. Inside $B_{\epsilon(n)}(S_0)$ the density is bounded below by the inequality in the [Assumption A.4](#):

$$(A.2) \quad L_f \cdot d(\mathbf{x}, S_0)^{\overline{K}_f(\epsilon(n))} \leq f(\mathbf{x}) \leq U_f \cdot d(\mathbf{x}, S_0)^{\underline{K}_f(\epsilon(n))}.$$

- *Upper bound for an $\epsilon(n)$ -inside covering ball.*

Since the $\epsilon(n)$ -inside ball intersects S_0 , i.e. $B_{r(n)}(\mathbf{x}) \cap S_0 \neq \emptyset$, we know that any point $\mathbf{y} \in B_{r(n)}(\mathbf{x})$ will be at most $2r(n) \leq \epsilon(n)$ away from the zero-density region S_0 . The probability mass contained in an $\epsilon(n)$ -inside covering ball $B_{r(n)}(\mathbf{x})$ is bounded from above by

$$(A.3) \quad P(B_{r(n)}(\mathbf{x})) \leq U_f \cdot V_d(r(n)) \cdot (2r(n))^{\underline{K}_f(\epsilon(n))}$$

There are two types of $\epsilon(n)$ -outside balls: those that are entirely contained in $M = [0, 1]^d$ and those that are only partially contained in M . Probability mass $P(B_{r(n)}(\mathbf{x})) = \int_{B_{r(n)}(\mathbf{x})} f(\mathbf{w}) d\mathbf{w}$ is bounded from below by volume of the ball times the minimum of the density $f(\mathbf{x})$ in the ball.

- *Lower bound for an $\epsilon(n)$ -outside covering ball that lies within M .*

From the assumption on density f ,

$$m(f, n) := \min_{\mathbf{w} \in M \setminus B_\epsilon(S_0)} f(\mathbf{w}) \in (0, \infty) \sim O(n^{-\xi}), \quad 0 < \xi < \frac{1 - 2\eta d}{2}.$$

The probability mass contained in the $\epsilon(n)$ -outside covering ball is bounded from below by

$$(A.4) \quad P(B_{r(n)}(\mathbf{x})) \geq V_d(r(n)) \cdot \min \left[L_f \cdot (\epsilon(n) - r(n))^{\overline{K}_f(\epsilon(n))}, m(f, n) \right].$$

- *Lower bound for an $\epsilon(n)$ -outside covering ball that does not lie entirely within M .*

[Assumption A.5](#) states that the center of the covering ball $B_{r(n)}(\mathbf{x})$ is in M . We know that the volume of such an $\epsilon(n)$ -outside ball $B_{r(n)}(\mathbf{x})$ will be at least $(\frac{1}{2})^d$ times the volume $V_d(r(n))$ of a full d -dimensional ball. With the same $m(f, n) > 0$ we have

$$(A.5) \quad P(B_{r(n)}(\mathbf{x})) \geq \left(\frac{1}{2}\right)^d V_d(r(n)) \cdot \min \left[L_f \cdot (\epsilon(n) - r(n))^{\overline{K}_f(\epsilon(n))}, m(f, n) \right]$$

This lower bound also holds for $\epsilon(n)$ -outside balls that are entirely contained in M .

In the following discussion, we use the notation $p_{B_{r(n)}(\mathbf{x})} := P(B_{r(n)}(\mathbf{x}))$ to emphasize that we use it as a parameter.

Part (A) (Outside balls). Consider regular families of covering balls $\mathcal{B}_{r(n)}^d$ of $\text{supp}(f)$ and a sequence of $\epsilon(n)$ -neighborhoods of the zero-density region S_0 where $\dim S_0 < d$. The Hoeffding concentration inequality for $X \sim \text{Binom}(n, p)$ can be written for arbitrary $\gamma > 0$,

$$(A.6) \quad P\{(p - \gamma)n \leq X \leq (p + \gamma)n\} \geq 1 - 2 \exp(-2\gamma^2 n).$$

The inequality ensures that the number of observations falling into a single ball $B_{r(n)}(\mathbf{x})$ will be close to its expectation. In a single ball, the number $N_{B_{r(n)}(\mathbf{x})}$ of observations

falling in the d -dimensional ball of radius $r(n)$, is distributed as a binomial distribution $\text{Binom}(n, p_{B_{r(n)}(\mathbf{x})})$. Also,

$$P(B_{r(n)}(\mathbf{x}) \text{ not empty}) = P\left(N_{B_{r(n)}(\mathbf{x})} \geq 1\right).$$

By assumption on the range of η , the lower bounds (A.4), (A.5) under the different situations are determined by the factor $r(n)^d$. But note that $r(n)^d \sim O(n^{-d\eta})$ with $-d\eta > -1$ as assumed. We can choose $\mathbf{N}(\mathbf{x}) \in \mathbb{N}$ large enough such that $\mathbf{N}(\mathbf{x}) \cdot p_{B_{r(n)}(\mathbf{x})} \geq 1$, ensuring $n \cdot p_{B_{r(n)}(\mathbf{x})} \geq 1$ when $n \geq \mathbf{N}(\mathbf{x})$. We take $\mathbf{N}(\mathbf{x}) = \frac{1}{p_{B_{r(n)}(\mathbf{x})}}$ and observe that $\mathbf{N}(\mathbf{x}) \sim O(n^{d\eta})$ with $d\eta < 1$, rendering such a choice of $n \geq \mathbf{N}(\mathbf{x})$ possible. Assume in the arguments below that $n \geq \mathbf{N}(\mathbf{x})$.

For an $\epsilon(n)$ -outside ball $B_{r(n)}(\mathbf{x})$, we can rewrite the probability using (A.6) with $X = N_{B_{r(n)}(\mathbf{x})}$, $p = p_{B_{r(n)}(\mathbf{x})}$ and $\gamma = \frac{p_{B_{r(n)}(\mathbf{x})}}{2}$,

$$\begin{aligned} P(B_{r(n)}(\mathbf{x}) \text{ not empty}) &\geq P\left(\left|N_{B_{r(n)}(\mathbf{x})} - np_{B_{r(n)}(\mathbf{x})}\right| < n \cdot \frac{p_{B_{r(n)}(\mathbf{x})}}{2}\right) \\ (A.7) \qquad \qquad \qquad &\geq \left[1 - 2 \exp\left(-\frac{1}{2} p_{B_{r(n)}(\mathbf{x})}^2 \cdot n\right)\right]. \end{aligned}$$

From the discussion of the probability mass contained in each type of covering ball above, if $B_{r(n)}(\mathbf{x})$ is an $\epsilon(n)$ -outside covering ball, then from formulas (A.4) and (A.5) we have

$$(A.8) \qquad P(B_{r(n)}(\mathbf{x}) \text{ not empty}) \geq \left[1 - 2 \exp\left(-\frac{1}{2} \left[V_d(r(n)) \cdot \min\left[L_f \cdot (\epsilon(n) - r(n))^{\overline{K}_f(\epsilon(n))}, m(f, n)\right]\right]^2 \cdot n\right)\right]$$

If $\min\left[L_f \cdot (\epsilon(n) - r(n))^{\overline{K}_f(\epsilon(n))}, m(f, n)\right] = m(f, n)$ then

$$P(B_{r(n)}(\mathbf{x}) \text{ not empty}) \geq \left[1 - 2 \exp\left(-\frac{1}{2} [V_d(r(n)) \cdot m(f, n)]^2 \cdot n\right)\right]$$

If $\min\left[L_f \cdot (\epsilon(n) - r(n))^{\overline{K}_f(\epsilon(n))}, m(f, n)\right] = L_f \cdot (\epsilon(n) - r(n))^{\overline{K}_f(\epsilon(n))}$ then

$$P(B_{r(n)}(\mathbf{x}) \text{ not empty}) \geq \left[1 - 2 \exp\left(-\frac{1}{2} [V_d(r(n)) \cdot L_f \cdot (\epsilon(n) - r(n))^{\overline{K}_f(\epsilon(n))}]^2 \cdot n\right)\right]$$

Consider the right hand side of (A.8), taking $n \rightarrow \infty$. If it holds that

$$(A.9) \qquad 1 - 2\eta d - 2\xi > 0 \text{ and } 1 - 2\eta d - 2\overline{K}_f \cdot \psi > 0$$

then the limit $\lim_{n \rightarrow \infty} P(B_{r(n)}(\mathbf{x}) \text{ not empty})$ is 1. For the first inequality, it is simply $\xi < \frac{1-2\eta d}{2} \leq \frac{1}{2}$ (the second equality holds iff $d = 0$) as we assumed in the statement of the theorem so it suffices to consider the second inequality.

We want to let $n > \frac{1}{p_{B_{r(n)}(\mathbf{x})}}$ for all $\mathbf{x} \in M \setminus B_\epsilon(S_0)$. But $\frac{1}{p_{B_{r(n)}(\mathbf{x})}}$ reaches its maximum when $p_{B_{r(n)}(\mathbf{x})}$ attains its minimum $m(n, f) := \min_{\mathbf{w} \in M \setminus B_\epsilon(S_0)} f(\mathbf{w})$, i.e. $\frac{1}{p_{B_{r(n)}(\mathbf{x})}} \leq \frac{1}{\sqrt{d}(r(n)) \cdot m(n, f)} \sim O(n^{\eta d + \xi})$. As long as $\eta d + \xi < 1$, which is guaranteed by (A.9), we can ensure that n is greater than the maximum value $\max_{\mathbf{w} \in M \setminus B_\epsilon(n)(S_0)} \frac{1}{p_{B_{r(n)}(\mathbf{w})}}$. Therefore, such an n is greater than all such quantities $\frac{1}{p_{B_{r(n)}(\mathbf{x})}}, \forall \mathbf{x} \in M \setminus B_\epsilon(n)(S_0)$ and so

$n \cdot p_{B_{r(n)}(\mathbf{x})} \geq 1$ holds simultaneously for all $\mathbf{x} \in M \setminus B_{\epsilon(n)}(S_0)$.

$$\begin{aligned}
P(\text{no empty } \epsilon(n)\text{-outside balls}) &= P(\cap_{B \in \{\epsilon(n)\text{-outside balls}\}} \{B \text{ not empty}\}) \\
&= 1 - P(\cup_{B \in \{\epsilon(n)\text{-outside balls}\}} \{B \text{ empty}\}) \\
&\geq 1 - \sum_{B \in \{\epsilon(n)\text{-outside balls}\}} P(B \text{ empty}) \\
\text{(A.10)} \quad &\geq 1 - \left| \mathcal{B}_{r(n)}^d \right| \cdot \sup_{B \in \{\epsilon(n)\text{-outside balls}\}} P(B \text{ empty})
\end{aligned}$$

By the equation (A.7) and the subsequent bound (A.8) we obtain that

$$\begin{aligned}
P(\text{no empty } \epsilon(n)\text{-outside balls}) &\geq 1 - \left| \mathcal{B}_{r(n)}^d \right| \cdot \left(1 - \inf_{B \in \{\epsilon(n)\text{-outside balls}\}} P(B \text{ not empty}) \right) \\
\text{(A.11)} \quad &\geq 1 - (L_1 \cdot n^{dn}) \cdot \left(L_2 \cdot \exp\left(-n^{1-2\eta d - 2\overline{K}_f \cdot \psi}\right) \right)
\end{aligned}$$

for sufficiently large n . The constants $L_1, L_2 \in (0, \infty)$ exist by the definition of the big O notation for sufficiently large n . The last expression follows from $|\mathcal{B}_{r(n)}^d| \sim O(n^{dn})$ and (A.8). It is dominated by the second term in the product. Therefore, if $1 - 2\eta d - 2\overline{K}_f \cdot \psi > 0$ then

$$\lim_{n \rightarrow \infty} P(\text{no empty } \epsilon(n)\text{-outside balls}) = 1.$$

Part (B) (Inside balls). We observe that the event “all $B_{\epsilon(n)}(S_0)$ -inside balls are empty” can be regarded as all observations falling into the other two types of covering balls. Note that, as stated in the theorem, we only ensure that $\epsilon(n)$ -inside covering balls are empty but not every $\epsilon(n)$ -outside ball contains at least one observations under the assumptions in part (B). We investigate the upper bound on the probability mass in each of these covering balls.

Since the observations are i.i.d. we have, using the notation that $p_{\cup_{B \in \{\epsilon(n)\text{-inside balls}\}} B} := P(\cup_{B \in \{\epsilon(n)\text{-inside balls}\}} B)$,

$$\begin{aligned}
P(\text{all } \epsilon(n)\text{-inside balls are empty}) &= \left(1 - p_{\cup_{B \in \{\epsilon(n)\text{-inside balls}\}} B} \right)^n \\
&\quad \text{since covering balls may overlap,} \\
\text{(A.12)} \quad &\geq \left(1 - \sum_{B \in \{\epsilon(n)\text{-inside balls}\}} p_B \right)^n
\end{aligned}$$

from the upper bound above.

Assumption 3 asserts that the limit $\underline{K}_f = \lim_{\epsilon \rightarrow 0^+} \underline{K}_f(\epsilon)$ exists and that we can choose a bound $K_U \geq \lim_{\epsilon \rightarrow 0^+} \underline{K}_f(\epsilon)$ uniformly. By the bounds (A.2) for $\epsilon(n)$ -inside covering balls, there is a positive constant $D_{f,d} := U_f \cdot \frac{\pi^{\frac{d}{2}}}{\Gamma(\frac{d}{2}+1)} \cdot 2^{K_U} \geq U_f \cdot \frac{\pi^{\frac{d}{2}}}{\Gamma(\frac{d}{2}+1)} \cdot 2^{\underline{K}_f(\epsilon(n))}$ depending only on density f and the dimension d . The factor $\frac{\pi^{\frac{d}{2}}}{\Gamma(\frac{d}{2}+1)}$ comes from the multiplier of the volume of a d -dimensional ball (A.1). We denote by $\mathcal{B}_{r(n)}^{d_0}$ the sub-collection of covering balls from $\mathcal{B}_{r(n)}^d$ that intersect S_0 .

$$\begin{aligned}
P(\text{all } \epsilon(n)\text{-inside balls are empty}) &\geq \left(1 - \left| \mathcal{B}_{r(n)}^{d_0} \right| \cdot \left[U_f \cdot V_d(r(n)) \cdot (2r(n))^{\underline{K}_f(\epsilon(n))} \right] \right)^n \\
\text{(A.13)} \quad &\geq \left(1 - H_\epsilon(n) \cdot \left[D_{f,d} \cdot (r(n))^{\underline{K}_f(\epsilon(n))+d} \right] \right)^n
\end{aligned}$$

Due to the [Assumption A.6](#), the collection of covering balls $\mathcal{B}_{r(n)}^{d_0}$ that intersect S_0 satisfy $|\mathcal{B}_{r(n)}^{d_0}| \leq H_\varepsilon(n) \sim O(n^{d_0\eta(1+\varepsilon)})$ for any $\varepsilon > 0$. On one hand, by the assumption for part (B), we have

$$(A.14) \quad 1 + d_0\eta - \underline{K}_f\eta - d\eta < 0$$

and so we can find $1 > \varepsilon > 0$ small enough such that,

$$(A.15) \quad 1 + d_0\eta(1 + \varepsilon) - \underline{K}_f\eta - d\eta < 0$$

We need a simple but nontrivial lemma known as the Bernoulli inequality to proceed.

LEMMA. (*Bernoulli inequality*) *If $1 + x > 0$, then $(1 + x)^n \geq 1 + nx$ for $\forall n \in \mathbb{N}$.*

PROOF. Let us prove the lemma by induction. For $n = 0, 1$ this trivially holds as an equality. Assume that the inequality $(1 + x)^n \geq 1 + nx$ holds for every $n \leq k \in \mathbb{N}$ and proceed by induction for $n = k + 1$.

$$(1 + x)^n = (1 + x) \cdot (1 + x)^{n-1} = (1 + x) \cdot (1 + x)^k$$

since $n - 1 = k \leq k$ by the inductive hypothesis,

$$\geq (1 + x) \cdot (1 + kx)$$

due to the fact that $(1 + x) > 0$ does not flip the inequality,

$$= 1 + kx + x + kx^2 = 1 + (k + 1) \cdot x + kx^2$$

$$\geq 1 + (k + 1) \cdot x,$$

since $kx^2 \geq 0$, which completes the induction. \square

Let $x = H_\varepsilon(n) \cdot \left[D_{f,d} \cdot (r(n))^{\underline{K}_f(\varepsilon(n))+d} \right] \sim O(n^{d_0\eta(1+\varepsilon)}) \cdot \left[D_{f,d} \cdot (r(n))^{\underline{K}_f(\varepsilon(n))+d} \right]$, which is of order $O(n^{d_0\eta(1+\varepsilon) - \underline{K}_f\eta - d\eta})$ as $n \rightarrow \infty$. We emphasize again that $\varepsilon > 0$ is an auxiliary quantity which we first define in [Assumption 5](#). The $\varepsilon = \varepsilon(n)$ is the quantity in [Theorem 10](#) that defines the neighborhood size of S_0 . These two are different quantities. Under the assumption

$$(A.16) \quad 1 + d_0\eta(1 + \varepsilon) - \underline{K}_f\eta - d\eta < 0 \Leftrightarrow d_0\eta(1 + \varepsilon) - \underline{K}_f\eta - d\eta < -1,$$

we can take n sufficiently large, say $n \geq \mathbf{N}_1$, to ensure $d_0\eta(1 + \varepsilon) - \underline{K}_f\eta - d\eta < -1$ and therefore $1 + x > 0$. Then we can apply the Bernoulli inequality to the right hand side of [\(A.13\)](#) and we have the following lines, with $H_\varepsilon(n) \sim O(n^{d_0\eta(1+\varepsilon)})$ and [\(A.13\)](#), as $n \rightarrow \infty$:

$$(A.17) \quad \begin{aligned} P(\text{all } \varepsilon(n)\text{-inside balls are empty}) &\geq \left(1 - (L_3 \cdot n^{d_0\eta(1+\varepsilon)}) \cdot \left[D_{f,d} \cdot (r(n))^{\underline{K}_f+d} \right]^n \right) \\ &\geq \left(1 - n \cdot (L_3 \cdot n^{d_0\eta(1+\varepsilon)}) \cdot \left[D_{f,d} \cdot (r(n))^{\underline{K}_f+d} \right] \right) \\ &\geq \left(1 - L_{f,d} \cdot (n^{1+d_0\eta(1+\varepsilon) - \underline{K}_f\eta - d\eta}) \right) \end{aligned}$$

for sufficiently large n . The constant $L_3 \in (0, \infty)$ exists by the definition of the big O notation for sufficiently large n . If we take the limit $n \geq \mathbf{N}_1, n \rightarrow \infty$ on both sides of the inequality we know that the quantity $\left(1 - L_{f,d} \cdot (n^{1+d_0\eta(1+\varepsilon) - \underline{K}_f\eta - d\eta}) \right)$ converges to 1 from [\(A.15\)](#). therefore if $1 + d_0\eta - \underline{K}_f\eta - d\eta < 0$ then

$$\lim_{n \rightarrow \infty} P(\text{all } \varepsilon(n)\text{-inside balls are empty}) = 1.$$

Acknowledgements. This material is based upon work supported by the National Science Foundation under Grants No. DMS-1613110 and No. SES-1921523.

REFERENCES

- [1] ADLER, R. J., BOBROWSKI, O. and WEINBERGER, S. (2013). Crackle: The persistent homology of noise. *arXiv:1301.1466* 1-25.
- [2] BAUER, U. and PAUSINGER, F. (2018). Persistent Betti numbers of random Čech complexes. *arXiv:1801.08376* 1-11.
- [3] BOBROWSKI, O. and KAHLE, M. (2017). Topology of random geometric complexes: a survey. *arXiv:1409.4734* 1-42.
- [4] BÜRGISSER, P. and CUCKER, F. (2013). *Condition: The Geometry of Numerical Algorithms*. Berlin: Springer.
- [5] CARLSSON, G. (2009). Topology and data. *Bulletin of the American Mathematical Society* **46.2** 255-308.
- [6] CUEVAS, A. (2009). Set estimation: Another bridge between statistics and geometry. *Boletín de Estadística e Investigación Operativa (BEIO)* **25.2** 71-85.
- [7] DEVROYE, L. and WISE, G. L. (1980). Detection of abnormal behavior via nonparametric estimation of the support. *SIAM Journal on Applied Mathematics* **38.3** 480-488.
- [8] DUY, T. K., HIRAOKA, Y. and SHIRAI, T. (2016). Limit theorems for persistence diagrams. *arXiv:1612.08371* 1-41.
- [9] EDELSBRUNNER, H. and HARER, J. (2010). *Computational Topology: an Introduction*. American Mathematical Society.
- [10] FALCONER, K. (2004). *Fractal Geometry: Mathematical Foundations and Applications*. New York: John Wiley & Sons.
- [11] HARTIGAN, J. A. (1987). Estimation of a convex density contour in two dimensions. *Journal of the American Statistical Association* **82.397** 267-270.
- [12] KAHLE, M. (2009). Topology of random clique complexes. *Discrete Mathematics* **309.6** 1658-1671.
- [13] KAHLE, M. and MECKES, E. (2013). Limit theorems for Betti numbers of random simplicial complexes. *Homology, Homotopy and Applications* **15.1** 343-374.
- [14] KALISNIK, S., LEHN, C. and LIMIC, V. (2019). Geometric and probabilistic limit theorems in topological data analysis. *arXiv:1903.00470* 1-30.
- [15] LUO, H. and STRAIT, J. (2019). Combining geometric and topological information in image segmentation. *arXiv:1910.04778* 1-27.
- [16] LUO, H., PATANIA, A., KIM, J. and VEJDEMO-JOHANSSON, M. (2020+). Generalized penalty for circular coordinate representation. *Submitted*.
- [17] MASON, D. M. and POLONIK, W. (2009). Asymptotic normality of plug-in level set estimates. *The Annals of Applied Probability* **19.3** 1108-1142.
- [18] OWADA, T. and ADLER, R. J. (2017). Limit theorems for point processes under geometric constraints (and topological crackle). *The Annals of Probability* **45.3** 2004-2055.
- [19] PENROSE, M. (2003). *Random Geometric Graphs*. Oxford: Oxford University Press.
- [20] POLONIK, W. (1995). Measuring mass concentrations and estimating density contour clusters – an excess mass approach. *The Annals of Statistics* 855-881.
- [21] RIGOLLET, P. and VERT, R. (2009). Optimal rates for plug-in estimators of density level sets. *Bernoulli* **15.4** 1154-1178.
- [22] RINALDO, A. and WASSERMAN, L. (2010). Generalized density clustering. *The Annals of Statistics* **38.5** 2678-2722.
- [23] TALAGRAND, M. (2014). *Upper and Lower Bounds for Stochastic Processes: Modern Methods and Classical Problems*. Heidelberg: Springer.
- [24] WALTHER, G. (1997). Granulometric smoothing. *The Annals of Statistics* **25.6** 2273-2299.