

Inverting Cryptographic Hash Functions via Cube-and-Conquer

Oleg Zaikin

ISDCT, Irkutsk, Russia

ZAIKIN.ICC@GMAIL.COM

Abstract

MD4 and MD5 are seminal cryptographic hash functions proposed in early 1990s. MD4 consists of 48 steps and produces a 128-bit hash given a message of arbitrary finite size. MD5 is a more secure 64-step extension of MD4. Both MD4 and MD5 are vulnerable to practical collision attacks, yet it is still not realistic to invert them, i.e. to find a message given a hash. In 2007, the 39-step version of MD4 was inverted via reducing to SAT and applying a CDCL solver along with the so-called Dobbertin’s constraints. As for MD5, in 2012 its 28-step version was inverted via a CDCL solver for one specified hash without adding any additional constraints. In this study, Cube-and-Conquer (a combination of CDCL and lookahead) is applied to invert step-reduced versions of MD4 and MD5. For this purpose, two algorithms are proposed. The first one generates inversion problems for MD4 by gradually modifying the Dobbertin’s constraints. The second algorithm tries the cubing phase of Cube-and-Conquer with different cutoff thresholds to find the one with minimal runtime estimation of the conquer phase. This algorithm operates in two modes: (i) estimating the hardness of an arbitrary given formula; (ii) incomplete SAT-solving of a given satisfiable formula. While the first algorithm is focused on inverting step-reduced MD4, the second one is not area-specific and so is applicable to a variety of classes of hard SAT instances. In this study, for the first time in history, 40-, 41-, 42-, and 43-step MD4 are inverted via the first algorithm and the estimating mode of the second algorithm. 28-step MD5 is inverted for four hashes via the incomplete SAT-solving mode of the second algorithm. For three hashes out of them this is done for the first time.

1. Introduction

A cryptographic hash function maps a message of arbitrary finite size to a hash of a fixed size (Menezes, van Oorschot, & Vanstone, 1996). Such a computation must be very easy, but at the same time it should be computationally infeasible to invert it, i.e. to find a message given its hash. Cryptographic hash functions are really pervasive in the modern digital world. Examples of their applications include verification of data integrity, passwords, and signatures.

A relevant cryptographic hash function must be resistant. It is well known that such a resistance can be practically analyzed by reducing to the Boolean satisfiability problem (SAT) (Biere, Heule, van Maaren, & Walsh, 2021b) and applying SAT solvers. SAT in its decision form is to determine whether a given Boolean formula is satisfiable or not. This is one of the most well-studied NP-complete problems (Cook, 1971; Garey & Johnson, 1979). Over the last 25 years, numerous crucial scientific and industrial problems have been successfully solved by SAT. In almost all these cases, CDCL solvers, i.e. ones which are based on the Conflict-Driven Clause Learning (Marques-Silva & Sakallah, 1999) algorithm, were used.

Cube-and-Conquer is an approach for solving extremely hard SAT problems (Heule, Kullmann, Wieringa, & Biere, 2011), for which CDCL solvers alone are not enough. According to this approach a given problem is split into subproblems on the cubing phase via a lookahead solver (Heule & van Maaren, 2009). Then on the conquer phase the subproblems are solved via a CDCL solver. Several hard mathematical problems from number theory and combinatorial geometry have been solved by Cube-and-Conquer recently, e.g., the Boolean Pythagorean Triples problem (Heule, Kullmann, & Marek, 2016). However, the authors of this study are not aware of any successful application of this approach to cryptanalysis problems. This study is aimed at filling this gap by analyzing the preimage resistance of the cryptographic hash functions MD4 and MD5 via Cube-and-Conquer.

MD4 was proposed back in 1990 (Rivest, 1990). It consists of 48 steps and produces a 128-bit hash given a message of arbitrary finite size. Since 1995, MD4 is not collision resistant (Dobbertin, 1996), i.e. it is computationally feasible (moreover, it is very easy) to find a pair of different messages with the same MD4-hash. Despite this vulnerability, MD4 is still used to compute password-derived hashes in some operating systems of the Windows family. One of the reason is that it still remains preimage resistant, i.e. inversion of MD4 (finding a message given its hash) is still a computationally infeasible task. That is why step-reduced MD4 have been studied recently. In 1998, the Dobbertin’s constraints on intermediate states of MD4 registers were proposed, which reduce the number of preimages, but at the same time significantly simplify the inversion (Dobbertin, 1998). This breakthrough approach made it possible to easily invert 32-step MD4. Hereinafter, the first steps are meant in all cases. In 2007, SAT encodings of slightly modified Dobbertin’s constraints were constructed, and as a result 39-step MD4 was inverted via a CDCL solver (De, Kumarasubramanian, & Venkatesan, 2007) for one very regular hash (128 1s). Note, that it is a common practice to invert very regular hashes such as all 1s or all 0s. Since 2007, several unsuccessful attempts have been made to invert 40-step MD4.

The second studied cryptographic hash function, MD5, is a more secure yet slower 64-step version of MD4, proposed in 1992 (Rivest, 1992). MD5 is still widely used to verify the integrity of files and messages. Since 2005, MD5 is not collision-resistant (Wang & Yu, 2005). Because of a more secure design, the Dobbertin’s constraints are not efficient for MD5. 26-step MD5 was inverted in 2007 (De et al., 2007), while for 27- and 28-step MD5 it was done for the first time in 2012 (Legendre, Dequen, & Krajecki, 2012b). In both papers CDCL solvers were applied, at the same time no additional constraints were added. In (Legendre et al., 2012b), 28-step MD5 was inverted for only one hash `0x01234567 0x89abcdef 0xfedcba98 0x76543210`. This hash is a regular binary sequence (it is symmetric, and the numbers of 0s and 1s are equal), but at the same time it is less regular than 128 1s mentioned above. The same result was presented in later two papers of the same authors (Legendre, Dequen, & Krajecki, 2012a, 2013). Unfortunately, none of these three papers explained the non-existence of results for 128 1s and 128 0s. Apparently, the authors just could not do that because the corresponding SAT instances were too hard for CDCL solvers. Since 2012 no further progress in inverting step-reduced MD5 has been made.

This paper proposes Dobbertin-like constraints, a generalization of Dobbertin’s constraints. Two algorithms are proposed. The first one generates Dobbertin-like constraints until a preimage of a step-reduced MD4 is found. The second algorithm does sampling to

find a cutoff threshold for the cubing phase of Cube-and-Conquer with minimal runtime estimation of the conquer phase. This algorithm operates in two modes: (i) estimating the hardness of an arbitrary given formula; (ii) incomplete SAT-solving of a given satisfiable formula. The first algorithm is MD4-specific, but the same approach can be potentially applied to other cryptographic hash functions. The second algorithm in its estimating mode is general, so it can be applied to any SAT instance (including unsatisfiable ones). Yet the incomplete SAT-solving mode is oriented only on satisfiable SAT instances, preferably with many solutions.

With the help of the first algorithm and the estimating mode of the second algorithm, 40-, 41-, 42-, and 43-step MD4 are inverted for four hashes: 128 1s, 128 0s, the one from (Legendre et al., 2012b), and a random hash. 28-step MD5 is inverted for the same four hashes via the incomplete SAT-solving mode of the second algorithm. All the experiments are held on a personal computer.

In summary, the contributions of this paper are:

- Dobbertin-like constraints, a generalization of Dobbertin’s constraints.
- An algorithm that generates Dobbertin-like constraints and the corresponding inversion problems to find preimages of a step-reduced MD4.
- A general algorithm with two modes (estimating and incomplete SAT-solving) for finding a cutoff threshold with the minimal runtime estimation of the conquer phase of Cube-and-Conquer.
- For the first time in history, 40-, 41-, 42-, and 43-step MD4 are inverted.
- A runtime estimation and recommendations for inverting 44-step MD4 are given.
- For the first time in history, 28-step MD5 is inverted for two most regular hashes (128 1s and 128 0s), and a random non-regular hash.

The paper is organized as follows. Preliminaries on SAT and cryptographic hash functions are given in Section 2. Section 3 proposes Dobbertin-like constraints and the algorithm aimed at inverting step-reduced MD4. The Cube-and-Conquer-based algorithm is proposed in Section 4. The considered inversion problems for step-reduced MD4 and MD5, as well as their SAT encodings, are described in Section 5. Experimental results on inverting step-reduced MD4 and MD5 are presented in sections 6, 7, and 8. Section 9 outlines related work. Finally, conclusions are drawn.

This paper builds on an earlier work (Zaikin, 2022), but extends it significantly in several directions. First, the algorithm for generating Dobbertin-like constraints for MD4 is improved by cutting off impossible values of the last bits in the modified constraint. As a result, in most cases the considered step-reduced versions of MD4 are inverted about 2 times faster than in (Zaikin, 2022). Second, the incomplete SAT-solving mode of the Cube-and-Conquer-based algorithm is proposed. Third, all considered step-reduced versions of MD4 are inverted for four hashes compared to two hashes in (Zaikin, 2022). Fourth, a runtime estimation for inverting 44-step MD4 is calculated, while in (Zaikin, 2022) this extremely hard problem was not considered. Finally, 28-step MD5 is inverted, while in (Zaikin, 2022) only step-reduced MD4 was studied.

2. Preliminaries

This section gives preliminaries on SAT and cryptographic hash functions.

2.1 Boolean Satisfiability

Problems from various areas (verification, cryptanalysis, combinatorics, bioinformatics, etc.) can be efficiently reduced to the *Boolean satisfiability problem* (SAT) (Biere et al., 2021b). In its decision form SAT is to determine whether a given Boolean formula satisfiable or not. Usually SAT is considered as the problem of search for solutions of a Boolean equation in the form $CNF = 1$, where CNF stands for *Conjunctive Normal Form*. CNF is a conjunction of clauses, where a *clause* is a disjunction of literals. A *literal* is a Boolean variable or its negation. All known SAT solving algorithms are exponential in the worst case since SAT itself is NP-hard. Moreover, SAT is historically the first NP-complete problem (Cook, 1971). Nevertheless, modern SAT solvers successfully cope with huge SAT instances based on the problems from the areas mentioned above.

When a cryptanalysis problem is reduced to SAT and solved using SAT solvers, this is called *SAT-based cryptanalysis* (Cook & Mitchell, 1996; Massacci & Marraro, 2000). It is in fact a special type of the algebraic cryptanalysis (Bard, 2009). In the last two decades, SAT-based cryptanalysis have been successfully applied to stream ciphers, block ciphers, and cryptographic hash functions.

The *Davis–Putnam–Logemann–Loveland* (DPLL) algorithm is a complete backtracking SAT-solving algorithm (Davis, Logemann, & Loveland, 1962). It forms a binary search tree, where each internal node corresponds to a decision variable, while edges correspond to variables’ values. The *Unit Propagation* (UP (Dowling & Gallier, 1984)) is used to reduce the tree after assigning a decision variable. UP iteratively applies the *Unit clause rule*: if there is only one remaining unassigned literal in a clause, and all other literals are assigned to False, then this literal is assigned to True. If an unsatisfied clause is encountered, a *conflict* is declared, and the chronological backtracking is performed.

In opposite to DPLL, in *Conflict-Driven Clause Learning* (CDCL) when a conflict happens, the reason is found and the *non-chronological backtracking* is performed (Marques-Silva & Sakallah, 1999). To forbid the conflict, a *conflict clause* is formed based on the reason and added to the CNF. As a result, the algorithm learns from conflicts. This complete algorithm is much more efficient than DPLL, so most modern complete SAT solvers are based on CDCL.

Lookahead is another complete SAT-solving algorithm (Heule & van Maaren, 2009). It improves DPLL by the following heuristic. When a decision variable should be chosen, each variable is assigned to True followed by UP, the reduction is measured, then the same is done for False assignment. *Failed literal* denotes a literal for which a conflict is found during UP. If for a variable both literals are not failed, the reduction measure for this variable is calculated as a combination of literal-measures. A variable with the largest reduction measure is picked as a decision variable. There are two special cases. First, if both literals of a variable are failed, then the unsatisfiability of the CNF is proven. Second, if there is only one failed literal l for some variable, then l is forced to be assigned to False. This rule is known as *failed literals elimination*. Thus lookahead allows one to choose better decision variables and in addition simplifies a CNF by the described reasoning. In a binary

search tree, produced by lookahead, internal nodes correspond to decision variables. There are two types of leaves in such a tree: satisfying assignments and *refuted leaves*. The latter correspond to failed literals.

2.2 Cube-and-Conquer

While SAT instances are usually quite hard, it makes sense to solve them in parallel. If only complete algorithms are considered, then there are two main approaches to parallel SAT solving: *Portfolio* and *Divide-and-Conquer* (Balyo & Sinz, 2018). According to the Portfolio approach, many different sequential SAT solvers (or maybe different configurations of the same solver) solve the same problem simultaneously. In the Divide-and-Conquer approach, the problem is decomposed into a family of simpler subproblems that are solved by sequential solvers.

Cube-and-conquer (Heule et al., 2011; Heule, Kullmann, & Biere, 2018) is a Divide-and-Conquer SAT solving approach that combines lookahead with CDCL. On the *cubing phase* of Cube-and-Conquer, a lookahead solver splits a given CNF into *cubes*. For each cube by joining it with the CNF a subproblem is formed. If the original CNF is unsatisfiable, then all the subproblems are unsatisfiable. Otherwise, at least one subproblem is satisfiable. On the *conquer phase*, the subproblems are solved via a CDCL solver. Since cubes can be processed independently, the conquer phase can be easily parallelized. Note, that further a CDCL solver is used on the conquer phase in just its default configuration. On the other hand, lookahead is adjusted by optimising one of its most important parameters.

As it was mentioned in the previous subsection, lookahead is a complete algorithm. When used in the cubing phase of Cube-and-Conquer, a lookahead solver is forced to cut off some branches thus producing cubes. Therefore, such a solver produces a binary search tree, where leaves are either refuted ones (with no possible solutions), or cubes. There are two main cutoff heuristics that decide when a branch becomes a cube. In the first one, a branch is cut off after a given number of decisions (Hyvärinen, Junttila, & Niemelä, 2010). According to the second one, it happens when the number of variables in the corresponding subproblem drops below a given threshold (Heule et al., 2011). In the present study the second cutoff heuristic is used since it usually shows better results on hard instances.

2.3 Cryptographic Hash Functions

Hereinafter only unkeyed cryptographic hash functions are considered, see (Menezes et al., 1996). Inputs of cryptographic hash functions are usually called *messages*, while outputs are called *hash values* or just *hashes*.

A cryptographic hash function h ideally must have the following five properties.

1. *Compression*: h maps a message x of arbitrary finite size to a hash $h(x)$ of fixed size.
2. *Ease of computation*: for any given message x , $h(x)$ is easy to compute.
3. *Collision resistance*: it is computationally infeasible to find any two messages x and x' such that $x \neq x', h(x) = h(x')$.
4. *Preimage resistance*: for any given hash y , it is computationally infeasible to find any of its preimages, i.e. any such message x' that $h(x') = y$.

5. *Second-preimage resistance*: for any given message x , it is computationally infeasible to find x' such that $x' \neq x, h(x) = h(x')$.

The first two properties are obligatory, while the remaining three are potential and can be compromised. Usually at the time of publishing a cryptographic hash function all the five properties are valid. However, the subsequent publications may propose methods for abolishing one (or even all) of the three potential properties. These methods are called *collision attacks*, *preimage attacks*, and *second preimage attacks*, respectively. If an attack is computationally feasible, then it is called *practical*. Usually it is much easier to propose a practical collision attack than attacks of two other types. It is clear that collision resistance implies second-preimage resistance, while second-preimage attack implies a collision attack. This study is focused on practical preimage attacks on the cryptographic hash functions MD4 and MD5. In the rest of the paper, a practical inversion of a cryptographic hash function implies a practical preimage attack and vice versa.

2.4 MD4

The Message Digest 4 (MD4) cryptographic hash function was proposed by Ronald Rivest in 1990 (Rivest, 1990). Given a message of arbitrary finite size, *padding* is applied to obtain a message that can be divided into 512-bit blocks. Then a 128-bit hash is produced by iteratively applying the MD4 compression function to the blocks.

Consider the compression function in more detail. Given a 512-bit input, it produces a 128-bit output. The function consists of three rounds, sixteen steps each, and operates by transforming data in four 32-bit registers A, B, C, D . If a message block is the first one, then the registers are initialized with the constants specified in the standard. Otherwise, registers are initialized with an output produced by the compression function on the previous message block. The message block is divided into sixteen 32-bit words. In each step, one register's value is updated by mixing one word with values of all four registers and an additive constant. In this transformation a nonlinear function takes part, which is specific for each round. Additive constants are also round-specific. As a result, in each round all sixteen words take part in such updates. Finally, registers are incremented by the values they had after the current block initialization, and the hash is produced as a concatenation of A, B, C, D .

In 1995, a practical collision attack on MD4 was proposed (Dobbertin, 1996). In 2005, it was theoretically shown that on a very small fraction of messages MD4 is not resistant to the second preimage attack (Wang, Lai, Feng, Chen, & Yu, 2005). In 2008, a theoretical preimage attack on MD4 was proposed (Leurent, 2008). Despite the found vulnerabilities, MD4 is still used to compute password-derived hashes in some operating systems of the Windows family, including the modern ones. The reason is that MD4 still remains preimage-resistant in practice, i.e. it is still computationally infeasible to invert a hash produced by MD4. That is why step-reduced versions of MD4 have been actively studied recently. In 1998, Hans Dobbertin showed that by adding additional constraints (further they are called *Dobbertin's constraints*) 32-step MD4 can be easily inverted (Dobbertin, 1998). In 2007, a SAT-based implementation of slightly modified Dobbertin's constraints made it possible to invert 39-step MD4 (De et al., 2007). Since 2007, several unsuccessful attempts have been

made to invert 40-step MD4, see, e.g. (Legendre et al., 2012b). The present study is aimed at inverting 40-, 41-, 42-, and 43-step MD4.

2.5 MD5

MD5 was proposed in 1992 by Ronald Rivest as a slightly slower, but at the same time much more secure extension of MD4 (Rivest, 1992).

The main changes in MD5 compared to MD4 are as follows:

1. addition of the fourth round of 16 steps with its own round function, so MD5 consists of 64 steps;
2. replacement of the second round’s nonlinear function by a new function;
3. usage of unique additive constants in each of the 64 steps;
4. addition of output from the previous step in each of the 64 steps.

For the first time a practical collision attack on MD5 was presented in 2005 (Wang & Yu, 2005), so it took 13 years to find the first collision compared to 5 years for MD4. In 2009, a theoretical preimage attack was proposed (Sasaki & Aoki, 2009). Because of a more secure design compared to MD4, the Dobbertin’s constraints are not efficient for MD5. In 2007, 26-step MD5 was inverted in (De et al., 2007). In 2012, it was done for 27-, and 28-step MD5 (Legendre et al., 2012b). In both papers SAT-based cryptanalysis via CDCL solvers was applied, yet no additional constraints were added to the corresponding CNFs.

MD5 is still widely used in practice as a checksum to verify data integrity. Another application is the storage of passwords’ hashes in operating systems. Thanks to elegant yet efficient designs, both MD4 and MD5 have become one of the most influential cryptographic functions with several notable successors, such as RIPEMD and SHA-1.

3. Dobbertin-like Constraints for Inverting Step-reduced MD4

As it was mentioned in Subsection 2.4, the progress in inverting step-reduced MD4 was mainly due to the Dobbertin’s constraints. This section describes these constraints and proposes their generalization — Dobbertin-like constraints. Finally an algorithm for inverting MD4 via Dobbertin-like constraints is proposed.

Hereinafter if a step-reduced version of MD4 is mentioned, at least 32 (first) steps are assumed. The *Dobbertin’s constraints* for step-reduced MD4 are as follows: the registers A , D , and C are equal to a constant 32-bit word K in steps 12, 16, 20, 24, steps 13, 17, 21, 25, and steps 14, 18, 22, 26, respectively (numbering from 0) (Dobbertin, 1998). As a result, for any given hash and a randomly chosen K the number of preimages (messages) is significantly reduced, maybe even to 0. On the other hand, if at least one preimage exists, then it is usually much simpler to find it. According to (Dobbertin, 1998), K can be chosen randomly until a consistent system is formed and a preimage is found.

3.1 Dobbertin-like Constraints

Suppose that given a constant word K , the Dobbertin’s constraints are applied as usual only in 11 out of 12 steps, while in the remaining step only $b, 0 \leq b \leq 32$ bits of the register

are equal to the corresponding b bits of K , at the same time the remaining $32 - b$ bits in the register take values, opposite to those in K . Denote these constraints as *Dobbertin-like constraints*. It is clear that the Dobbertin's constraints is a special case of Dobbertin-like constraints when $b = 32$.

Denote an inversion problem for step-reduced MD4 with applied Dobbertin-like constraints as $\text{MD4inversion}(y, s, K, p, L)$, where:

- y is a given 128-bit hash;
- s is the number of first MD4 steps;
- K is a 32-bit constant word used in the Dobbertin's constraints;
- $p \in \{12, 13, 14, 16, 17, 18, 20, 21, 22, 24, 25, 26\}$ is the specially constrained step;
- L is a 32-bit word such that if $L_i = 0, 0 \leq i \leq 31$, then i -th bit of the register value modified in step p is equal to K_i . Otherwise, if $L_i = 1$, it is equal to $\sim K_i$.

In other words, the 32-bit word L serves as a bit mask and controls how similar the specially constrained register is to the constant word K . To make this definition more clear, three examples are given below. Hereinafter *ohash* and *ihash* mean 16 words $0x00000000$ and $0xffffffff$, respectively.

Example 3.1 ($\text{MD4inversion}(\text{ohash}, 32, 0x62c7Ec0c, 20, 0x00000000)$). The problem is to invert *ohash* produced by 32-step MD4. Since $L = 0x00000000$, then the specially constrained register (in step 20) has value K , so all 12 Dobbertin's constraints are applied as usual with $K = 0x62c7Ec0c$. A similar inversion problem (up to choice of K) in fact was solved in (Dobbertin, 1998).

Example 3.2 ($\text{MD4inversion}(\text{ihash}, 39, 0xffff0000, 12, 0xffffffff)$). The problem is to invert *ihash* produced by 39-step MD4. Since $L = 0xffffffff$, the specially constrained register (in step 12) has value $\sim K = 0x000fffff$. In the remaining 11 Dobbertin's steps the registers have value $K = 0xffff0000$.

Example 3.3 ($\text{MD4inversion}(\text{ihash}, 40, 0xffffffff, 12, 0x00000003)$). The problem is to invert *ihash* produced by 40-step MD4. Since $L = 0x00000003$, the first 30 bits of the specially constrained register (in step 12) are equal to those in K , while the last two bits have values $\sim K_{30}$ and $\sim K_{31}$, respectively. It means that this register has value $0xfffffff$ **c**, while in the remaining 11 Dobbertin's steps the registers have value $K = 0xfffffff$.

3.2 Inversion Algorithm

Dobbertin-like constraints can be used for finding preimages of a step-reduced MD4 according to the following idea. For a given hash and a random K , an inversion problem is formed with $L = 0x00000000$. Thus all 12 Dobbertin's constraints are applied. The inversion problem is solved and, if a preimage is found, nothing else should be done. Otherwise, if it is proven that no preimages exist in the current inversion problem, then a new one is formed with $L = 0x00000001$. In this case the specially constrained register's value is just 1 bit shy of being K . This inversion problem is solved as well. If still no preimage exists, then

L is further modified: $0x00000002, 0x00000003$, and so on. The intuition here is that the Dobbertin’s constraints lead to a system of equations that is either consistent (with very few solutions) or quite “close” to a consistent one. In the latter case trying different values of L helps to form a consistent system and find its solution.

Algorithm 1 follows the described idea. In the pseudocode a complete algorithm \mathcal{A} is used, which for a formed inversion problem returns all the preimages if they exist.

Algorithm 1 Algorithm for inverting step-reduced MD4 via Dobbertin-like constraints.

Input: Hash y ; the number of MD4 steps s ; constant K ; step p with specially constrained register; a complete algorithm \mathcal{A} .

Output: Preimages for hash y .

```

1:  $preimages \leftarrow \{\}$ 
2:  $i \leftarrow 0$ 
3: while  $i < 2^{32}$  do
4:    $L \leftarrow \text{DECIMALTOBINARY}(i)$ 
5:    $preimages \leftarrow \mathcal{A}(\text{MD4inversion}(y, s, K, p, L))$ 
6:   if  $preimages$  is not empty then
7:     break
8:    $i \leftarrow i + 1$ 
9: return  $preimages$ 

```

Note that it is not guaranteed that Algorithm 1 finds any preimage for a given hash. If the algorithm terminates with no found preimages, then another value of p can be tried in a similar way and so on. However, as it will be shown in sections 6 and 7, in practice Algorithm 1 is able to find preimages for step-reduced MD4. Moreover, it usually does it in just few iterations (from 1 to 3).

Complete algorithms of various types can be used to solve inversion problems formed in Algorithm 1. In particular, wide spectrum of constraint programming (Rossi, van Beek, & Walsh, 2006) solvers are potential candidates. In preliminary experiments, state-of-the-art sequential and parallel CDCL SAT solvers were tried to invert 40-step MD4, but even on the first iterations (where all 12 Dobbertin’s constraints are added) CNFs turned out to be way too hard for them. That is why it was decided to use Cube-and-Conquer SAT solvers, which are more suitable for extremely hard SAT instances. The next section describes how a given problem can be properly split into simpler subproblems on the cubing phase of Cube-and-Conquer.

4. Finding Cutoff Thresholds for Cube-and-Conquer

This section proposes an algorithm aimed at finding a cutoff threshold with minimal estimated runtime of the conquer phase of Cube-and-Conquer.

Recall (see Subsection 2.2) that in Cube-and-Conquer the following cutoff threshold n is meant in the cubing phase: the number of variables in a subproblem, formed by adding the cube to the original CNF and applying UP. It is crucial to properly choose this threshold. If it is too high, then the cubing phase is performed in no time, but very few extremely

hard (for a CDCL solver) cubes might be produced; if it is too low, then the cubing phase will be extremely time consuming, and also there will be too huge number of cubes.

To find a threshold with minimal estimated runtime of the conquer phase, first it is needed to preselect promising values of n . On the one hand, the number of refuted leaves should be quite significant since it might indicate that at least some subformulas have become really simpler compared to the original CNF. On the other hand, the total number of cubes should not be too large due to the reasons mentioned above. Algorithm 2 follows this idea.

Algorithm 2 Preselect promising thresholds for the cubing phase of Cube-and-Conquer.

Input: CNF \mathcal{F} ; lookahead solver ls ; starting threshold n_{start} ; threshold decreasing step $nstep$; maximal number of cubes $maxc$; minimal number of refuted leaves $minr$.

Output: Stack of promising thresholds and corresponding cubes.

```

1: function PRESELECTTHRESHOLDS( $\mathcal{F}, ls, n_{start}, nstep, maxc, minr$ )
2:    $stack \leftarrow \{\}$ 
3:    $n \leftarrow n_{start}$ 
4:   while  $n > 0$  do
5:      $\langle c, r \rangle \leftarrow \text{LOOKAHEADWITHCUT}(ls, \mathcal{F}, n)$     ▷ Get cubes and number of refuted
6:     if  $\text{SIZE}(c) > maxc$  then
7:       break                                          ▷ Break if too many cubes
8:     if  $r \geq minr$  then
9:        $stack.\text{push}(\langle n, c \rangle)$                         ▷ Add threshold and cubes
10:     $n \leftarrow n - nstep$                             ▷ Decrease threshold
11:  return  $stack$ 

```

When promising values of the threshold are preselected, it is needed to estimate the hardness of the corresponding conquer phases. It can be done by choosing a fixed number of cubes among those produced in the cubing phase by simple random sampling (Starnes, Yates, & Moore, 2010). If all cubes from the sample are solved by a CDCL solver in a reasonable time, then an estimated total solving time for all cubes can be easily calculated.

This idea is implemented as Algorithm 3. On the first stage, promising thresholds are preselected by Algorithm 2, while on the second stage the one with minimal runtime estimation of the conquer phase is chosen among them. This algorithm operates in two possible modes. In the *estimating* mode, the algorithm terminates upon reaching a time limit by a CDCL solver on some subproblem in random samples, while any amount of satisfying assignment is allowed for finding. In the *incomplete SAT-solving* (Kautz, Sabharwal, & Selman, 2021) mode, vice versa — the algorithm terminates upon finding a satisfying assignment, while the CDCL solver is allowed to interrupt unlimited number of times.

The proposed algorithm has the following features.

1. A stack is used to preselect promising thresholds on the first stage in order to start the second stage with solving the simplest subproblems (with lowest n). In practice it allows obtaining some estimation quickly and then improve it.
2. The runtime of the cubing phase is not estimated because it is assumed that this is negligible compared to the conquer phase. In all further experiments it is really so.

Algorithm 3 Finding a cutoff threshold with minimal estimated runtime of the conquer phase.

Input: CNF \mathcal{F} ; lookahead solver ls ; threshold decreasing step $nstep$; maximal number of cubes $maxc$; minimal number of refuted leaves $minr$; sample size N ; CDCL solver cs ; CDCL solver time limit $maxcst$; the number of CPU cores $cores$; operating mode $mode$.

Output: A threshold n_{best} with runtime estimation e_{best} and cubes c_{best} ; whether a satisfying assignment is found $isSAT$.

```

1:  $isSAT \leftarrow \text{Unknown}$ 
2:  $n_{start} \leftarrow \text{VARNUM}(\mathcal{F}) - nstep$ 
3:  $\langle n_{best}, e_{best}, c_{best} \rangle \leftarrow \langle n_{start}, +\infty, \{\} \rangle$ 
4:  $stack \leftarrow \text{PRESELECTTHRESHOLDS}(\mathcal{F}, ls, n_{start}, nstep, maxc, minr)$  ▷ First stage
5: while  $stack$  is not empty do ▷ Second stage: estimate thresholds
6:    $\langle n, c \rangle \leftarrow stack.pop()$  ▷ Get a threshold and cubes
7:    $sample \leftarrow \text{SIMPLERANDOMSAMPLE}(c, N)$  ▷ Select  $N$  random cubes
8:    $runtimes \leftarrow \{\}$ 
9:   for each  $cube$  from  $sample$  do
10:     $\langle t, st \rangle \leftarrow \text{SOLVECUBE}(cs, \mathcal{F}, cube, maxcst)$  ▷ Add cube and solve
11:    if  $t > maxcst$  and  $mode = \text{estimating}$  then ▷ If CDCL was interrupted,
12:      break ▷ stop processing sample.
13:    else
14:       $runtimes.add(t)$  ▷ Add proper runtime
15:      if  $st = \text{True}$  then ▷ If SAT,
16:         $isSAT \leftarrow \text{True}$ 
17:        if  $mode = \text{solving}$  then ▷ and if SAT solving mode,
18:          return  $\langle n_{best}, e_{best}, c_{best}, isSAT \rangle$  ▷ return SAT immediately.
19:      if  $\text{SIZE}(runtimes) < N$  then ▷ If at least one interrupted in sample,
20:        break ▷ stop main loop.
21:       $e \leftarrow \text{MEAN}(runtimes) \cdot \text{SIZE}(c)/cores$  ▷ Calculate runtime estimation
22:      if  $e < e_{best}$  then
23:         $\langle n_{best}, e_{best}, c_{best} \rangle \leftarrow \langle n, e, c \rangle$  ▷ Update best threshold
24: return  $\langle n_{best}, e_{best}, c_{best}, isSAT \rangle$ 

```

3. In the *estimating* mode, if on the second stage a CDCL solver fails solving some subproblem within time limit, the algorithm terminates. This is done because in this case it is impossible to calculate a meaningful estimation for the threshold. Another reason is that subproblems from the next thresholds (with higher n) will likely be even harder.
4. It is possible that satisfying assignments are found when solving subproblems from random samples. Indeed, if a given CNF is satisfiable, then cubes which imply satisfying assignments might be chosen to samples.
5. In the *estimating* mode it is a general algorithm that is able to estimate the hardness of an arbitrary CNF.

6. The *incomplete SAT-solving* mode can be applied to an arbitrary satisfiable CNF (preferably with many solutions).
7. In fact, the runtime estimation is a stochastic costly black-box objective function (see, e.g., (Zaikin & Kochemazov, 2021)) that takes an integer value n as input. The algorithm minimizes this objective function.

If the estimating mode has been chosen, cubes produced by Algorithm 3 (if any) are processed on the conquer phase. First, subproblems are created by adding cubes to the original CNF in the form of unit clauses. Second, the subproblems are solved by the same CDCL solver that was used to find the threshold for the cubing phase. In the present study the goal is to find all solutions of a considered problem. That is why, given a subproblem, the CDCL solver finds all the satisfying assignments. In opposite to the cubing phase, here the runtime of the CDCL solver is not limited.

5. Considered Inversion Problems and Their SAT Encodings

This section describes the considered inversion problems for step-reduced MD4 and MD5, as well as their SAT encodings.

5.1 Considered hashes

The following four hashes are chosen for inversion:

1. 0x00000000 0x00000000 0x00000000 0x00000000;
2. 0xffffffff 0xffffffff 0xffffffff 0xffffffff;
3. 0x01234567 0x89abcdef 0xfedcba98 0x76543210;
4. 0x62c7Ec0c 0x751e497c 0xd49a54c1 0x2b76cff8.

Recall that *ohash* and *ihash* mean the first and the second hash from the list, respectively. These two hashes are chosen for inversion because it is a common practice in the cryptographic community. The reason is that inverting some hash, that looks just like a random word, is suspicious. Indeed, one can take a random message, produce its hash and declare that this very hash is inverted. On the other hand, if a hash has a regular structure, this approach does not work. All 0s and all 1s are just two hashes with the most regular structure, that is why they are usually chosen. For the first time 32-step MD4 was inverted for *ohash* (Dobbertin, 1998), while in 39-step case it was done for *ihash* (De et al., 2007), and later for *ohash* (Legendre et al., 2012b). As for the cryptographic hash functions SHA-0 and SHA-1, their 23-step (out of 80) versions for the first time were inverted for *ohash* (Legendre et al., 2012a).

The third hash from the list was used to invert 28-step MD5 (Legendre et al., 2012b). Hereinafter this hash is called *symmhash*. It is symmetrical — the last 64 bits are the first 64 bits in reverse order, but at the same time it is less regular than *ihash* or *ohash*. The same result for 28-step MD5 was described in later two papers of the same authors (Legendre et al., 2012a, 2013). Unfortunately, none of these three papers explained the non-existence

of the results for *1hash* and *0hash*. Apparently, the authors just could not do that because the corresponding SAT instances were too hard for CDCL solvers.

The fourth hash from the list is chosen randomly. The goal is to show that the proposed approach is applicable not only to hashes with a regular structure. This hash is further called *randhash*.

5.2 Step-reduced MD4

While in (De et al., 2007) only $K = 0x00000000$ was used as a constant in the Dobbertin’s constraints, in the present study both $K = 0x00000000$ and $K = 0xffffffff$ are tried in Dobbertin-like constraints. The constraint in step 12 is chosen for the modification (so $p = 12$, see Subsection 3.1) since in (De et al., 2007) the constraint for this very step was entirely omitted. Eight step-reduced versions of MD4, from 40 to 47 steps, as well as the full MD4 are studied. Hence there are $9 \times 4 \times 2 = 72$ MD4-related inversion problems in total.

Consider 40-step MD4. Since K has two values and y has four values, Algorithm 1 should be run on eight inputs. As a result, according to the notation from Subsection 3.1, the following eight inversion problems are formed in the corresponding first iterations of Algorithm 1:

1. `MD4inversion(0hash, 40, 0x00000000, 12, 0x00000000);`
2. `MD4inversion(0hash, 40, 0xffffffff, 12, 0x00000000);`
3. `MD4inversion(1hash, 40, 0x00000000, 12, 0x00000000);`
4. `MD4inversion(1hash, 40, 0xffffffff, 12, 0x00000000).`
5. `MD4inversion(symmhash, 40, 0x00000000, 12, 0x00000000);`
6. `MD4inversion(symmhash, 40, 0xffffffff, 12, 0x00000000);`
7. `MD4inversion(randhash, 40, 0x00000000, 12, 0x00000000);`
8. `MD4inversion(randhash, 40, 0xffffffff, 12, 0x00000000).`

For illustrative purpose, consider the first case: invert *0hash* produced by 40-step MD4 with Dobbertin’s constraints formed with $K = 0x00000000$. If no preimage exists for this inversion problem, then on the second iteration of Algorithm 1 L is increased by 1, so the inversion problem `MD4inversion(0hash, 40, 0x00000000, 12, 0x00000001)` is formed and so on.

Following all earlier attempts to invert step-reduced MD4 via SAT (see, e.g. (De et al., 2007; Legendre et al., 2012b; Lafitte, Jr., & Heule, 2014)), the goal in fact is to invert a step-reduced compression function of MD4, therefore the padding is omitted (see Subsection 2.4). The final incrementing is also omitted since it should be done only after 48-th step. Finally, the problem is as follows: given a 128-bit output produced by the compression function of a step-reduced MD4, find a 512-bit preimage. Note that none of the described 72 inversion problems have been solved so far.

5.3 Step-reduced MD5

Inversion of only 28-step MD5 compression function is considered in this study for the four hashes presented above. Recall that compared to MD4, no additional constraints that reduce the number of preimages are added. Note that for all hashes but *symmhash* the inversion problems have not been solved earlier.

5.4 SAT Encodings

For sake of simplicity, further MD4 means the MD4 compression function, the same for MD5. It is possible to construct CNFs that encode MD4 and MD5 via the following tools: CBMC (Clarke, Kroening, & Lerda, 2004); SAW (Carter, Foltzer, Hendrix, Huffman, & Tomb, 2013); TRANSALG (Otpuschennikov, Semenov, Gribanova, Zaikin, & Kochemazov, 2016); CRYPTOSAT (Lafitte, 2018). In the present paper, the CNFs are taken from (Semenov, Otpuschennikov, Gribanova, Zaikin, & Kochemazov, 2020), where they were constructed via TRANSALG.

In the CNF that encodes MD4, the first 512 variables correspond to a message, the last 128 variables correspond to a hash, while the remaining auxiliary variables are needed to encode how the hash is produced given the message. The first 512 variables are further called *message variables*, while the last 128 ones — *hash variables*. The Tseitin transformations are used in TRANSALG to introduce auxiliary variables (Tseitin, 1970).

Characteristics of the constructed CNFs are given in Table 1.

Table 1: Characteristics of CNFs that encode the considered step-reduced MD4 and MD5.

| Function | Variables | Clauses | Size |
|----------|-----------|---------|------|
| MD4-40 | 7 025 | 70 809 | 1.8M |
| MD4-41 | 7 211 | 73 158 | 1.9M |
| MD4-42 | 7 397 | 75 507 | 1.9M |
| MD4-43 | 7 583 | 77 856 | 2.0M |
| MD4-44 | 7 769 | 80 205 | 2.1M |
| MD4-45 | 7 955 | 82 554 | 2.2M |
| MD4-46 | 8 141 | 84 903 | 2.2M |
| MD4-47 | 8 327 | 87 252 | 2.3M |
| MD4-48 | 8 513 | 89 601 | 2.4M |
| MD5-28 | 7 471 | 54 672 | 1.3M |

The CNF that encodes 40-step MD4 has 7 025 variables and 70 809 clauses. Then every step adds 186 variables and 2 349 clauses, so as a result a CNF that encodes the full (48-step) MD4 has 8 513 variables and 89 601 clauses. Note that these CNFs encode the functions themselves, so all message and hash variables are unassigned. To obtain a CNF that encodes an inversion problem for a given 128-bit hash, 128 corresponding one-literal clauses are to be added, so all hash variables become assigned. The problem is to find values of the message variables. The Dobbertin’s constraints are added as another 384 one-literal clauses (32 clauses for each constraint). As a result a CNF that encodes the inversion of 40-step MD4 with all 12 Dobbertin’s constraints has 7 025 variables and 71 321 clauses,

while that for the 48-step version consists of 8 513 variables and 90 113 clauses. Note that any Dobbertin-like constraints (see Subsection 3.1) are also added as 384 one-literal clauses — the only difference is in values of the corresponding 32 variables that encode the specially constrained register.

The CNF that encodes 28-step MD5 has 7 471 variables and 54 672 clauses. 128 one-literal clauses for hash variables are added, so each of four CNFs that encode the inversion problems has 7 471 variables and 54 800 clauses.

6. Inverting 40-step MD4 via Dobbertin-like Constraints

This section describes the experimental setup and results for 40-step MD4.

To invert several given hashes for a step-reduced MD4, Algorithm 1 and the estimating mode of Algorithm 3 can be used in the following combinations:

1. The estimating mode of Algorithm 3 is run on a CNF that encodes the inversion problem for one (arbitrary) hash among given ones, yet the Dobbertin’s constraints are fully applied, i.e. $L = 0x00000000$. When the best cutoff threshold is found, Algorithm 1 is iteratively run using a Cube-and-Conquer solver with the found threshold as algorithm \mathcal{A} on all given hashes. It means that the threshold found for one hash and $L = 0x00000000$ is used for all other hashes and values of L .
2. For each hash, its own best threshold is found for $L = 0x00000000$ and is used for all other values of L . In Algorithm 1, \mathcal{A} is again a Cube-and-Conquer solver with the found threshold.
3. For each hash and each value of L own threshold is found. Therefore \mathcal{A} is the estimating mode of Algorithm 3 followed by a Cube-and-Conquer solver.

In this study, the second combination is used since for any value of L the same amount of one-literal clauses is added to a CNF.

6.1 Experimental Setup

Algorithm 1, Algorithm 3, and the conquer phase of Cube-and-Conquer were implemented in C++ and Python. The implementations, as well as all the constructed CNFs are available online¹. All experiments in this paper were held on a personal computer equipped with the 12-core CPU AMD 3900X and 48 Gb of RAM. The implementations are multithreaded, so all 12 CPU cores were employed in all runs. In case of Algorithm 3, values of n and then subproblems from samples are processed in parallel. In case of the conquer phase, subproblems are processed in parallel.

The input parameters’ values of Algorithm 1 in case of 40-step MD4 were discussed in Section 5. As for Algorithm 3, the following input parameters’ values were used:

- The MARCH_CU lookahead solver (Heule et al., 2011) since it has been recently successfully applied to several hard problems (Heule et al., 2016; Heule, 2018).

1. <https://github.com/olegzaikin/EnCnC>

- $nstep = 5$. It was chosen in preliminary experiments. If this parameter is equal to 1, then a better threshold usually can be found, but at the same time Algorithm 3 becomes quite time-consuming. On the other hand, if $nstep$ is quite large, e.g., 50, then as a rule almost all most promising thresholds are just skipped.
- $maxc = 2\,000\,000$. On the considered CNFs, MARCH_CU reaches 2 000 000 cubes in about 30 minutes, so that value of $maxc$ looks reasonable. Higher values were also tried, but it did not give any improvement.
- $minr = 1\,000$. If it is less than 1 000, then subproblems are too hard because they are not simplified enough by lookahead. At the same time, higher value of this parameter did not allow collecting enough amount of promising thresholds.
- $N = 1\,000$. First $N = 100$ was tried, but it led to too optimistic estimations which were several times lower than real solving time. On the other hand, $N = 10\,000$ is too time-consuming and gives just modest improvement in accuracy compared to $N = 1\,000$. The accuracy of obtained estimations is discussed later in Subsection 7.1.
- The KISSAT CDCL solver of version sc2021 (Biere, Fleury, & Heisinger, 2021a). The reason is that KISSAT and its modifications won SAT Competitions 2020 and 2021.
- $maxst = 5\,000$ seconds. It is a standard time limit in SAT Competitions (see, e.g., (Balyo, Froleys, Heule, Iser, Järvisalo, & Suda, 2021)), so modern CDCL solvers are designed to show all their power within this time.
- $cores = 12$.
- $mode = estimating$. Here the goal is not just to find one preimage, but rather find all preimages for a given inversion problem (up to the added Dobbertin-like constraints).

It should be noted that in both Algorithm 3 and the conquer phase of Cube-and-Conquer subproblems were solved by KISSAT in the non-incremental mode, i.e. it solved them independently from each other.

6.2 Simplification

In case of 40-step MD4, two parameters were varied for each of four considered hashes (see Section 5.1). The first one is the value of the Dobbertin’s constant K (see Section 3): `0x00000000` and `0xffffffff`. The second one is a simplification type applied to CNF. A motivation behind varying the second parameter is as follows. First, it is crucial to simplify a CNF before giving it to a lookahead solver. Second, in preliminary experiments it was found out that the simplification type might significantly alter the effectiveness of Cube-and-Conquer on the considered problems.

The CDCL solver CADICAL of version 1.5.0 (Froleys & Biere, 2021) was used to simplify the CNFs. It allows one to run a quick preprocessing — in fact, UP (see Subsection 2.1) on a given CNF. By default this solver uses inprocessing, i.e. a given CNF is simplified during the CDCL search (Biere, 2011). Roughly speaking, the more conflicts have been generated by a CDCL solver so far, the more simplified the CNF have been

made. A natural simplification measure in this case is the number of generated conflicts. In the experiments related to 40-step MD4, 5 simplification types were tried. The first one is UP, the remaining are inprocessing with the following limits on the number of generated conflicts: 10 thousand, 100 thousand, 1 million, 10 million. In Table 2, the characteristics of the CNFs that encode the problem `MD4inversion(1hash, 40, 0xffffffff, 12, 0x00000000)` are given. The original (unsimplified) CNF is described by the number of variables, clauses, and the size in megabytes. For those simplified by CADICAL also the runtime on 1 CPU core is given.

Table 2: CNFs that encode `MD4inversion(1hash, 40, 0xffffffff, 12, 0x00000000)`. The best values are marked with bold.

| Simplif. type | Variables | Clauses | Size | Simplif. runtime |
|-------------------|--------------|---------------|---------------|------------------|
| no (original CNF) | 7 025 | 71 321 | 1.8 MB | - |
| UP | 3 741 | 33 371 | 804 KB | 0.02 sec |
| 10 thousand | 2 968 | 27 355 | 671 KB | 0.31 sec |
| 100 thousand | 2 803 | 23 121 | 543 KB | 4.29 sec |
| 1 million | 2 756 | 22 391 | 521 KB | 1 min 19 sec |
| 10 million | 2 054 | 24 729 | 627 KB | 33 min |

It is clear, that first the number of variables, clauses, and size decrease, but then 10 million conflicts provides lower number of variables yet the number of clauses and size are higher than on 1 million conflicts. For other hashes and values of L the picture is similar.

In preliminary experiments also the limits of 1 thousand and 100 million conflicts were tried. However, it turned out that the first variant is usually similar to UP in number of variables and clauses. The second variant in all cases was similar to 10 million conflicts in number of variables, though the number of clauses was a bit lower. Yet generating 100 million conflicts is quite time consuming — it takes about 1 day on average. On the other hand, 10 million conflicts are generated in about a half an hour. That is why these two simplification types, 1 thousand and 100 million conflicts, were omitted.

6.3 Experiments

Of course, more parameters can be varied for each hash in addition to K and simplification type mentioned in the previous subsection. One of the most natural is the CDCL solver used in Cube-and-Conquer. For example, a cryptanalysis-oriented solver can be chosen (Soos, Nohl, & Castelluccia, 2009; Nejati & Ganesh, 2019; Kochemazov, 2021). Moreover, internal parameters of the chosen CDCL solver can be varied as well.

Recall that there are 4 hashes, 5 simplification types, while K has 2 values. Therefore in total $4 \times 5 \times 2 = 40$ CNFs were constructed with fully applied Dobbertin’s constraints ($L = 0x00000000$) for MD4-40. On each of them the first iteration of Algorithm 1 was run. It turned out, that Algorithm 3 could not find any estimations for all 20 CNFs with $K = 0x00000000$. The reason is because in all these cases KISSAT was interrupted due to the time limit even for the simplest (lowest) values of the cutoff threshold n . On the other hand, for $K = 0xffffffff$ much more positive results were achieved. For *0hash*, *symmhash*, and *randhash*, estimations for all simplification types were successfully calculated, and the

best one was UP in all these cases. On the other hand, for *lhash* no estimations were found for UP and 10 thousand conflicts, while the best estimation was gained for 1 million conflicts.

The results are presented in Table 3. For each pair (simplification type, hash) the best estimation for 12 CPU cores, the corresponding cutoff threshold, and the number of cubes are given. Here “-” means that no estimation was obtained because KISSAT was interrupted on the simplest threshold. Runtimes of Algorithm 3 are not presented there, but on average it took about 2 hours for $K = 0x00000000$ and about 3 hours for $K = 0xffffffff$.

Table 3: Runtime estimations for 40-step MD4. The best estimations are marked with bold.

| Hash | Simplif. type | e_{best} | n_{best} | $ c_{best} $ |
|-------------|------------------|--------------------|--------------|----------------|
| <i>o</i> | UP | 15 h 33 min | 3 290 | 303 494 |
| | 10 thousand | 21 h 43 min | 2 530 | 210 008 |
| | 100 thousand | 52 h 32 min | 2 485 | 107 657 |
| | 1 million | 22 h 19 min | 2 400 | 148 518 |
| | 10 million | 34 h 27 min | 1 895 | 69 605 |
| <i>l</i> | UP | - | - | - |
| | 10 thousand | - | - | - |
| | 100 thousand | 81 h 31 min | 2 535 | 362 429 |
| | 1 million | 42 h 43 min | 2 510 | 182 724 |
| | 10 million | 991 h 12 min | 1 890 | 1 671 849 |
| <i>symm</i> | UP | 19 h 16 min | 3 395 | 80 491 |
| | 10 thousand | 29 h 47 min | 2 725 | 181 267 |
| | 100 thousand | 22 h 44 min | 2 615 | 60 403 |
| | 1 million | 21 h 11 min | 2 530 | 151 567 |
| | 10 million | 59 h 28 min | 1 945 | 189 744 |
| <i>rand</i> | UP | 14 h 27 min | 3 400 | 75 823 |
| | 10 thousand | 227 h 54 min | 2 660 | 1 098 970 |
| | 100 thousand | 20 h 22 min | 2 540 | 159 942 |
| | 1 million | 17 h 33 min | 2 455 | 225 854 |
| | 10 million | 81 h 3 min | 1 915 | 242 700 |

Figure 1 depicts how the objective function was minimized on the inversion problem for *Ohash*. Here 10k stands for 10 thousand conflicts, 1m for 1 million conflicts and so on. The figures for the remaining three hashes can be found in Appendix A.

In Section 4 it was mentioned that in the estimating mode of Algorithm 3 it is possible to find satisfying assignments of a given satisfiable CNF. That is exactly what happened for *symmhash* — a satisfying assignments was found for the CNF minimized by 100 thousand conflicts. It means that a preimage for *symmhash* generated by 40-step MD4 was found just in few hours during the search for good thresholds for the cubing phase. However, the goal was to find all preimages of the considered inversion problems (up to chosen value of L). That is why using the cubes produced with the help of the best cutoff thresholds, the conquer phase was run on all four inversion problems: UP-based for *Ohash*, *symmhash*,




Figure 1: Minimization of the objective function on 40-step MD4, *ohash*. The intersection of two dotted lines shows the best estimation.

and *randhash*; 1-million-conflicts-based for *1hash*. As a result, all subproblems were solved successfully. The subproblems’ solving times in case of *ohash* are shown in Figure 2.




Figure 2: KISSAT runtimes on subproblems from the conquer phase applied to `MD4inversion(ohash, 40, 0xffffffff, 12, 0x00000000)`

For *ohash* and *1hash*, no satisfying assignments were found, therefore the corresponding inversion problems have no solutions. On the other hand, satisfying assignments were found for hashes *symmhash* and *randhash*. The found thresholds, estimations, and the real runtimes are presented in Table 4. In the header, `sol` stands for the number of solutions. Note that the best estimation e_{best} was calculated only for $L = 0x00000000$, so for other

values of L it is equal to “-”. The right three columns present subproblems’ statistics: mean solving time; maximum solving time; and standard deviation of times (when they are in seconds). The minimum solving time is not reported since it was equal to 0.007 seconds in all cases.

Table 4: Estimated and real runtimes (on 12 CPU cores) of the conquer phase for inversion problems related to 40-step MD4. The best estimations from Table 3 are presented.

| Hash | L | e_{best} | real time | sol | mean | max | sd |
|--------|------------|-------------|-------------|-----|-----------|--------|-------|
| 0 | 0x00000000 | 15 h 33 min | 20 h 9 min | 0 | 2.84 sec | 1 h | 13.68 |
| | 0x00000001 | - | 19 h 25 min | 0 | 2.61 sec | 29 min | 10.22 |
| | 0x00000002 | - | 34 h 27 min | 1 | 5.7 sec | 38 min | 20.62 |
| 1 | 0x00000000 | 42 h 43 min | 48 h 29 min | 0 | 11.5 sec | 26 min | 30.23 |
| | 0x00000001 | - | 59 h 7 min | 0 | 4.08 sec | 17 min | 11.4 |
| | 0x00000002 | - | 28 h 1 min | 1 | 7.7 sec | 17 min | 18.68 |
| $symm$ | 0x00000000 | 19 h 16 min | 20 h 45 min | 2 | 11.24 sec | 18 min | 21.1 |
| $rand$ | 0x00000000 | 14 h 27 min | 15 h 48 min | 1 | 9.08 sec | 38 min | 21.59 |

The next iteration of Algorithm 1 (with $L = 0x00000001$) was executed for $0hash$ and $1hash$. Note that the same simplification and cutoff threshold as for $L = 0x00000000$ were applied to the corresponding CNFs. The conquer phase again did not find any satisfying assignment. Finally, preimages for both hashes were found on the third iteration ($L = 0x00000002$), see Table 4. All found preimages are presented in Table 5.

Table 5: Found preimages for 40-step MD4.

| | |
|--------|---|
| 0 | 0xe57d8668 0xa57d8668 0xa57d8668 0xbc8c857b 0xa57d8668 0xa57d8668 0xa57d8668 0xcb0a1178 |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x307bc4e7 0xad02e703 0xe1516b23 0x981c2a75 0xc08ea9f7 |
| 1 | 0xe57d8668 0xa57d8668 0xa57d8668 0x1d236482 0xa57d8668 0xa57d8668 0xa57d8668 0x97a13204 |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x991ede3 0x301e2ac3 0x5bed2a3d 0xe167a833 0x890d22f0 |
| $symm$ | 0xa57d8668 0xa57d8668 0xa57d8668 0xc8cf2f7c 0xa57d8668 0xa57d8668 0xa57d8668 0x61915bc1 |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x2c017cc4 0xda6acfa2 0x55e9f993 0x50d83f7b 0x2d7d47a6 |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x154f3b86 0xa57d8668 0xa57d8668 0xa57d8668 0x95b7616d |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0xf3ca15df 0x7eb66f5e 0x446dc43f 0x7d8e2888 0xaf37a76 |
| $rand$ | 0xa57d8668 0xa57d8668 0xa57d8668 0xbb809ab0 0xa57d8668 0xa57d8668 0xa57d8668 0xab67285f |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x85517639 0xc3eab3d 0x6edfba39 0xa1512693 0xaa686ac9 |

7. Inverting 41-, 42-, and 43-step MD4 via Dobbertin-like Constraints

This section presents results on inverting 41-, 42-, and 43-step MD4. Finally, a runtime estimation for inverting 44-step MD4 is given.

Recall that in the previous section on inverting 40-step MD4, Algorithm 1 was run on 40 CNFs: for each of 4 hashes, 2 values of K and 5 simplification types were tried. Note that $K = 0x00000000$ did not allow solving any 40-step-related problem. As for

simplification types, for 3 hashes out of 4 the best estimations were obtained on UP, while for the remaining one 1 million conflicts was the best. Following these results, in this section only $K = 0\text{x}\text{ffffff}\text{ff}$ is used, as well as only two mentioned simplification types. Therefore only 8 CNFs were constructed for 41-step MD4, and the same for 42-, 43-, and 44-step MD4. Also it turned out that the best 40-step-related estimations were achieved when at most 303 494 cubes were produced, see Table 3. That is why in this section the value of $maxc$ is reduced from 2 000 000 to 500 000. The remaining input parameters of Algorithm 3 are the same.

The same approach was applied as in the previous section: for each pair (steps, hash) first the best cutoff threshold was found via Algorithm 3 for a CNF with added Dobbertin’s constraints ($L = 0\text{x}00000000$), and then Algorithm 1 used the found threshold to run Cube-and-Conquer as a complete algorithm on each iteration. For 44 steps, no estimations were obtained. The hardness of the corresponding problems is discussed further in this section. On the other hand, for 41, 42, and 43 steps estimations were successfully calculated and they turned out to be comparable with that for 40 steps. Moreover, Algorithm 3 found preimages for two problems: 41 step and *1hash*; 42 steps and *0hash*. In Section 4 it was discussed that such a situation is possible if a given CNF is satisfiable. The found estimations for 43-step MD4 are presented in Table 6. For all hashes, UP was the best. For 41 steps, UP was better on *0hash* and *1hash*, while on remaining two hashes 1-million-conflicts based simplification was the winner. On 42-step MD4, UP was the best for all hashes except *1hash*.

Table 6: Runtime estimations for 43-step MD4. The best estimations are marked with bold.

| Hash | Simplif. type | e_{best} | n_{best} | $ c_{best} $ |
|-------------|---------------|--------------------|--------------|----------------|
| <i>0</i> | UP | 15 h 26 min | 3 390 | 103 420 |
| | 1 million | - | - | - |
| <i>1</i> | UP | 39 h 10 min | 3 395 | 98 763 |
| | 1 million | 52 h 5 min | 2 575 | 121 969 |
| <i>symm</i> | UP | 37 h 51 min | 3 395 | 81 053 |
| | 1 million | 50 h 7 min | 2 555 | 253 489 |
| <i>rand</i> | UP | 49 h 13 min | 3 385 | 120 619 |
| | 1 million | 86 h 23 min | 2 565 | 246 972 |

Figure 3 depicts how the objective function was minimized on the inversion problem for *1hash* in case of 43 steps. Figures for the remaining three 43-steps-related inversion problems can be found in Appendix A.

Since the goal was to find all solutions, Algorithm 1 was anyway run on all inversion problems with $L = 0\text{x}00000000$, and, as a result, for 43 steps preimages were found for all four hashes. For 41 and 42 steps, preimages were found on the first or the second iteration of Algorithm 1. The results are presented in Table 7. Here values 0 and 1 of L stand for $0\text{x}00000000$ and $0\text{x}00000001$, respectively. It can be seen that at least some inversion problems turned out to be easier compared to that for 40-step MD4. This phenomenon is discussed in the next subsection.




Figure 3: Minimization of the objective function on the inversion problem $\text{MD4inversion}(1\text{hash}, 43, 0\text{xffffffff}, 12, 0\text{x00000000})$. The intersection of two dotted lines shows the best estimation among all simplification types.

Table 7: Estimated and real runtimes (on 12 CPU cores) of the conquer phase for inversion problems related to 41-, 42, and 43-step MD4.

| Steps | Hash | L | e_{best} | real time | sol | mean | max | sd |
|--------|--------|-------------|-------------|-------------|-----------|-----------|---------|--------|
| 41 | 0 | 0 | 8 h 40 min | 10 h 11 min | 0 | 6.4 sec | 17 min | 16.77 |
| | | 1 | - | 21 h 23 min | 1 | 12.41 sec | 863 min | 421.41 |
| | 1 | 0 | 37 h | 45 h 10 min | 3 | 9.78 sec | 52 min | 44.73 |
| | | 1 | - | 20 h 15 min | 4 | 11.57 sec | 17 min | 23.66 |
| | $symm$ | 0 | 19 h 54 min | 20 h 10 min | 0 | 12.08 sec | 17 min | 24.28 |
| | | 1 | - | 20 h 15 min | 4 | 11.57 sec | 17 min | 23.66 |
| $rand$ | 0 | 16 h 6 min | 17 h 25 min | 1 | 10.05 sec | 43 min | 31.07 | |
| 42 | 0 | 0 | 19 h 36 min | 22 h 32 min | 3 | 11.68 sec | 19 min | 25.51 |
| | | 1 | 25 h 15 min | 29 h 19 min | 0 | 10.91 sec | 74 min | 45.61 |
| | 1 | 0 | - | 39 h | 1 | 16.38 sec | 138 min | 86.32 |
| | | 1 | - | 39 h | 1 | 16.38 sec | 138 min | 86.32 |
| | $symm$ | 0 | 28 h 20 min | 29 h 35 min | 1 | 12.25 sec | 32 min | 19.98 |
| | | 1 | - | 20 h 35 min | 3 | 9.34 sec | 13 min | 16.71 |
| $rand$ | 0 | 21 h 16 min | 21 h 30 min | 0 | 10.22 sec | 15 min | 18.51 | |
| 43 | 0 | 0 | 15 h 26 min | 17 h 14 min | 2 | 7.23 sec | 16 min | 16.6 |
| | | 1 | 39 h 10 min | 42 h 16 min | 1 | 18.64 sec | 39 min | 29.88 |
| | 1 | 0 | 37 h 51 min | 41 h 55 min | 1 | 22.59 sec | 34 min | 46.44 |
| | | 1 | - | 51 h 21 min | 1 | 18.51 sec | 46 min | 30.41 |
| | $symm$ | 0 | 49 h 13 min | 51 h 21 min | 1 | 18.51 sec | 46 min | 30.41 |

The subproblems' solving times in case of 43 steps and 1hash are shown in Figure 4. In Table 8, the found preimages for 43-step MD4 are presented. The corresponding tables for 41 and 42 steps can be found in Appendix B.




Figure 4: KISSAT runtimes on subproblems from the conquer phase applied to $\text{MD4inversion}(1hash, 43, 0xffffffff, 12, 0x00000000)$.

Table 8: Found preimages for 43-step MD4.

| Hash | Preimages |
|-------------|---|
| <i>0</i> | 0xa57d8668 0xa57d8668 0xa57d8668 0xf48a97a3 0xa57d8668 0xa57d8668 0xa57d8668 0xd330e8ed |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x37c9ca21 0xe1df551f 0x7f49d66a 0x135a1c93 0x9e744bdb |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0xb289afa0 0xa57d8668 0xa57d8668 0xa57d8668 0xaf2c850e |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x19c5ce09 0xcae6b29e 0xb2595b20 0xab3a433d 0xf6cdee42 |
| <i>1</i> | 0xa57d8668 0xa57d8668 0xa57d8668 0x82ef987a 0xa57d8668 0xa57d8668 0xa57d8668 0xe18fbc3b |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x558f3513 0xbf09004d 0x8fb490dd 0x502eca9 0xbd0e1a80 |
| <i>symm</i> | 0xa57d8668 0xa57d8668 0xa57d8668 0xd1c33d35 0xa57d8668 0xa57d8668 0xa57d8668 0xc8519181 |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x8157aaf2 0xd7bdc37b 0xe52f3348 0xf17901d9 0x7e2de5a4 |
| <i>rand</i> | 0xa57d8668 0xa57d8668 0xa57d8668 0x24f0e099 0xa57d8668 0xa57d8668 0xa57d8668 0xe57e4c54 |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0x8fbbadcd 0xc0326ae6 0xe0e6a048 0x6217a3b9 0x15ee5a3b |

7.1 Discussion

The correctness of the found preimages was verified by the reference implementations from (Rivest, 1990, 1992). This verification might be easily reproduced since MD4 and MD5 are hard to invert, but the direct computation is extremely fast. First, the additional actions (padding, incrementing, see Section 5), as well as the corresponding amount of the last steps should be deleted. Then the found preimages should be given as inputs to a compression function.

According to the results, in most cases UP-based simplification gives CNFs for which the best estimations are calculated. On the other hand if only UP had been chosen, then the inversion problem for *1hash* produced by 40-step MD4 would have remained unsolved.

All in all, UP and CADICAL-based inprocessing complement each other on the considered problems.

The obtained estimations can be treated as accurate ones since they are close to the real solving time (see Tables 4 and 7). On average the real time on inversion problems with $L = 0x00000000$ is 11 % higher than the estimated time, while in the worst case for 40-step MD4 and *Ohash* the real time is 30 % higher. As for real time on inversion problems with $L = 0x00000001$ and $L = 0x00000002$, the picture is different. In some cases, the real time is still close to the estimated time for $L = 0x00000000$. However, for `MD4inversion(Ohash, 41, 0xffffffff, 12, 0x00000001)` the real time is 2.5 times higher, while the standard deviation is also very high. It can be concluded that the heavy-tail behavior occurs in this case (Gomes & Sabharwal, 2021). These results might indicate that it is better to find its own cutoff threshold for each value of L , that corresponds to the 3rd combination of Algorithm 1 and Algorithm 3 described at the beginning of Section 6. Note that for those problems where their own thresholds were used, i.e. when $L = 0x00000000$, the heavy-tail behavior does not occur.

It might seem counterintuitive that for 40-43 steps the hardness of the inversion problems in fact is more or less the similar. Denote by M a 512-bit message divided into 16 32-bit blocks $M[i], 0 \leq i \leq 31$. When Dobbertin-like constraints are applied, values of 9 blocks with indices 0, 1, 2, 4, 5, 6, 8, 9, 10 are derived automatically (in a CNF this is done by UP), so only 7 blocks remain unknown. It means that 224 message bits are unknown compared to 512 message bits when Dobbertin-like constraints are not added. On 40th step, the register value is updated via a nonlinear function that takes as input an unknown block $M[14]$ along with registers' values. That is why the 40th step gives a leap in hardness compared to 39 steps. On the next 8 steps, blocks with the following indices are used for updating: 1, 9, 5, 13, 3, 11, 7, 15. It means that on 41st, 42nd, and 43rd steps the nonlinear function operates with known (constant) $M[1]$, $M[9]$, and $M[5]$, respectively. Therefore steps 41-43 do not add hardness, but rather additional connections between registers' values. On the other hand, on all remaining steps 44-48, unknown blocks are used for updating, so each of these steps gives a new leap in hardness.

7.2 Runtime Estimation for Inverting 44-step MD4

As it was stated above, adding the 40th step of MD4 gives a leap in hardness of inversion problems, and the next such a leap happens when adding the 44th step. If these leaps have similar nature, than the inversion problems for 44-step MD4 are about 10 000 times harder than that for 40-43 steps, so about 50 years on a single computer are needed to solve one such problem via the same approach. On the other hand, this is reachable on a very powerful supercomputer in just few days. The first natural step is to try more meticulous and time consuming cubing phase. An extremely large value of the parameter *maxc* of Algorithm 3, say 1 000 000 000, can be tried, while *minr* also should be significantly increased. The estimation should be calculated on the supercomputer. If it is reasonable, then the inversion might be done as well. It also makes sense to try another branching strategies on the cubing phase, see (Kullmann, 2009).

8. Inverting Unconstrained 28-step MD5

Due to its more secure design, MD5 is resistant against the Dobbertin’s constraints. One of the reasons is that a unique additive constant is used in each of the 64 steps, while in MD4 only 3 such constants are used for each group of 16 steps, see Subsection 2.5. That is why in this study 28-step MD5 is inverted without adding any additional constraints, just like it was done in (Legendre et al., 2012b). Recall that in this case for an arbitrary hash there are about 2^{384} preimages, but it is not easy to find any of them even for 28 steps.

First a CNF that encodes 28-step MD5 was constructed based on the encoding from Subsection 5.3. The CNF has 7 471 variables and 54 672 clauses. The same four hashes were considered for inversion as for MD4: *ohash*, *1hash*, *symmhash*, *randhash*. Therefore, 4 CNFs were constructed by adding corresponding 128 one-literal clauses to the original CNF. All four CNFs were simplified by UP. The characteristics of the simplified CNFs are presented in Table 9. Size of each CNF is about 1.2 MB.

Table 9: Characteristics of UP-simplified CNFs that encode inversion problems for 28-step MD5.

| Hash | Variables | Clauses |
|-------------|-----------|---------|
| <i>0</i> | 6 732 | 50 572 |
| <i>1</i> | 6 793 | 50 749 |
| <i>symm</i> | 6 788 | 50 737 |
| <i>rand</i> | 6 788 | 50 741 |

ENCNC, an implementation of Algorithm 3, was run on these CNFs in the incomplete solving mode. The following input parameters’ values were used:

- MARCH_CU.
- *step* = 10.
- *minr* = 0.
- *N* = 1 000.
- KISSAT_SC2021.
- *maxst* = 5 000 seconds.
- *cores* = 12.
- *mode* = *solving*.

The key parameter here is *maxc*, for which the following values were tried: 2 000 000; 1 000 000; 500 000; 250 000; 125 000; 60 000. Note that the default value of *maxc* in ENCNC is 1 000 000. Recall that in the incomplete solving mode, ENCNC stops if a satisfying assignment is found; if a CDCL solver is interrupted due to a time limit on some subproblem, ENCNC continues working. The corresponding 6 versions of ENCNC with different values of *maxc* were run on the CNFs with the wall-clock time limit of 1 day. In

Table 10, the wall-clock solving times are presented. Also, the same data is presented in Figure 5.

Table 10: Wall clock time for 28-step MD5 on a 12-core CPU. Here “-” means that the solver was interrupted due to the time limit of 1 day. The best results are marked with bold.

| Solver | <i>0hash</i> | <i>1hash</i> | <i>symmhash</i> | <i>randhash</i> |
|-----------------|--------------|--------------|-----------------|-----------------|
| ENCnC-MAXC=2M | 1 h 47 min | 1 h 41 min | 39 min | 1 h 36 min |
| ENCnC-MAXC=1M | 42 min | 53 min | 13 min | 59 min |
| ENCnC-MAXC=500K | 48 min | 32 min | 22 min | 15 min |
| ENCnC-MAXC=250K | 38 min | 4 min | 41 min | 37 min |
| ENCnC-MAXC=125K | 16 min | 35 min | 6 min | 20 min |
| ENCnC-MAXC=60K | 4 min | 3 min | 14 min | 1 h 32 min |
| P-MCOMSPS | - | - | - | - |
| TREENGELING | - | - | - | - |




Figure 5: Runtimes of ENCnC in the incomplete solving mode on four MD5-28-related inversion problems.

Additionally, two complete parallel SAT solvers were tried. The first one, P-MCOMSPS, is the winner of the Parallel track in SAT Competition 2021 (Vallade, Frioux, Oanea, Baair, Sopena, Kordon, Nejati, & Ganesh, 2021). It is a portfolio solver built upon the widely-used PAINLESS framework (Frioux, Baair, Sopena, & Kordon, 2017). The second one, TREENGELING (Biere, 2016), is a Cube-and-Conquer solver. It was chosen to compare ENCnC with a competitor built upon a similar strategy. Besides this, TREENGELING won several prizes in SAT Competitions and SAT Races.

Let us discuss the results. Based on average runtime, the best version of ENCnC is ENCnC-MAXC=125K, while the worst is ENCnC-MAXC=2M. Nevertheless, all versions managed to find satisfying assignments for all 4 CNFs within the time limit. On 23 runs

Table 11: Preimages found by ENCNC-MAXC=2M for 28-step MD5.

| | |
|-------------|---|
| <i>0</i> | 0xd825e4fb 0xa73fcaa9 0x660cd53d 0xb9308515 0x4677d4e0 0xcadcee62 0x40722cb3 0xf41a4b12 0xac2fdec3 0x9c9cbcb4a3 0xffcca30f 0x9a0e2026 0x475763e5 0x30ce233b 0xbef0cd57 0x1a6b39d |
| <i>1</i> | 0xdf6fee6b 0xc4437a85 0x11af5182 0xe3b13f03 0x5103e1fc 0xea231da2 0xc3b513d1 0xb95fa9d7 0x7a2a331c 0x2ddf2607 0x699a2dae 0xc1827561 0xfe80aedd 0xcf45b09a 0x5b596c8f 0xd0265347 |
| <i>symm</i> | 0x54032182 0x2a1693f1 0x1053aef3 0x9f4d7c87 0x9f0d5ba1 0xb43a63f8 0x4310aa89 0x9df4e0d8 0xada73cbf 0x63fd55c2 0x49f1f4a0 0x5e05beff 0x6c149122 0x54a25f8e 0x12ef4bb0 0x78482fb4 |
| <i>rand</i> | 0x120686db 0xad5834c6 0x7d660963 0x71c408fe 0x17cf4511 0x75df78de 0x544ae232 0x13745ecc 0x9190f8a2 0x4878ab8d 0x43229cc7 0x5013f2de 0xd49b395a 0xa151b704 0x5f1dd4ec 0xc860dfb5 |

out of 24, versions of ENCNC did it during solving the first 12 subproblems from the first random sample (for the lowest values of the cutoff threshold). It means that KISSAT did not reach the time limit of 5 000 seconds in these cases. The only exception is ENCNC-MAXC=60K on *randhash*, where on all 12 first subproblems KISSAT was interrupted due to the time limit, and then a satisfying assignment was found in one of the next 12 subproblems from the same sample. As for competitors, they could not solve anything within the time limit. In Table 11, the preimages found by ENCNC-MAXC=2M are presented. It should be noted that preimages for *ohash*, *1hash*, and *randhash* have not been published so far.

9. Related Work

SAT-based cryptanalysis via CDCL solvers has been earlier applied to MD4 as follows. For the first time it was done in (Jovanovic & Janicic, 2005) to construct benchmarks with adjustable hardness. In (Mironov & Zhang, 2006), a practical collision attack on MD4 was performed. 39-step MD4 was inverted in (De et al., 2007; Legendre et al., 2012b; Lafitte et al., 2014; Gribanova, Zaikin, Kochemazov, Otpuschennikov, & Semenov, 2017; Gribanova & Semenov, 2018). In (Gladush, Gribanova, Kondratiev, Pavlenko, & Semenov, 2022), the hardness of practical preimage attacks on 43-, 45-, and 47-step MD4 was estimated. In (Gribanova & Semenov, 2020), an MD4-based function was constructed and the full (48-step) version of this function was inverted.

As for MD5, SAT-based cryptanalysis has been applied to it as follows. In (Mironov & Zhang, 2006) and later in (Gribanova et al., 2017), practical collision attacks on MD5 were performed. In (De et al., 2007), 26-step MD5 was inverted, while in (Legendre et al., 2012b) it was done for 27- and 28-step MD5.

CDCL solvers were also applied to analyze cryptographic hash functions of the SHA family. In particular, step-reduced versions of SHA-0, SHA-1, SHA-256, and SHA-3 were inverted in (Nossum, 2012; Legendre et al., 2012a; Homsirikamol, Morawiecki, Rogawski, & Srebrny, 2012; Nejati, Liang, Gebotys, Czarnecki, & Ganesh, 2017). In (Homsirikamol et al., 2012), it was also done for the BLAKE-256 and JH-256 cryptographic hash functions. An algebraic fault attack on SHA-1 and SHA-2 was performed in (Nejati, Horáček, Gebotys, & Ganesh, 2018), while that on SHA-256 was done in (Nakamura, Hori, & Hirose, 2021).

The following hard mathematical problems have been solved via Cube-and-Conquer: the Erdős discrepancy problem (Konev & Lisitsa, 2015); the Boolean Pythagorean Triples

problem (Heule et al., 2016); Schur number five (Heule, 2018); Lam’s problem (Bright, Cheung, Stevens, Kotsireas, & Ganesh, 2021). In (Weaver & Heule, 2020), new minimal perfect hash functions were found. Note that these hash functions are not cryptographic ones and find their application in lookup tables. In the present paper, for the first time significant cryptanalysis problems were solved via Cube-and-Conquer.


The hardness of SAT instances is usually estimated via approaches, which are not connected with Cube-and-Conquer. In (Ansótegui, Bonet, Levy, & Manyà, 2008), it was proposed to use the tree-like space complexity for this purpose. In (Hutter, Xu, Hoos, & Leyton-Brown, 2014), it was done via supervised machine learning that operates with characteristics of a given formula. In (Almagro-Blanco & Giráldez-Cru, 2022) the popularity–similarity model is used for this purpose. Finally, a backdoor, a small set of variables of a given formula, can be used to estimate the hardness. For the first time it was proposed in (Williams, Gomes, & Selman, 2003). Later, different types of backdoors were introduced and applied in (Semenov & Zaikin, 2015; Semenov, Chivilikhin, Pavlenko, Otpuschennikov, Ulyantsev, & Ignatiev, 2021b; Semenov, Zaikin, & Kochemazov, 2021a). A generalization of backdoors from (Williams et al., 2003) was proposed recently in (Semenov, Pavlenko, Chivilikhin, & Kochemazov, 2022). In all these papers, the search for a backdoor with a minimal hardness was reduced to minimization of a costly stochastic black-box function. In the present paper, a similar function is minimized to find a cutoff threshold of the cubing phase of Cube-and-Conquer rather than a backdoor.

10. Conclusion


This paper proposed two algorithms. Given a hash, the first algorithm gradually modifies one of twelve Dobbertin’s constraints for MD4 until a preimage for the hash is found. Potentially, this algorithm is applicable to some other cryptographic hash functions. The second algorithm can operate with a given CNF in two modes. In the estimating mode, values of the cutoff threshold of the cubing phase of Cube-and-Conquer are varied, and the CNF’s hardness for each value is estimated via sampling. The threshold with the best estimation can be naturally used to choose a proper computational platform and solve the instance in case if the estimation is reasonable. This mode is general, so it can be applied to estimate the hardness and solve hard SAT instances from various classes. In the incomplete SAT-solving mode, the second algorithm is a SAT solver, oriented on satisfiable CNFs with many satisfying assignments.

The preimage resistance of two seminal cryptographic hash functions, MD4 and MD5, was analyzed. In opposite to MD4, MD5 served as an example of a cryptographic hash function for which no problem-specific constraints are added. In case of MD4, a combination of the first algorithm and the estimating mode of the second algorithm was used. As a result, 40-, 41-, 42-, and 43-step MD4 were inverted for the first time in history. The hardness of inversion problems for 44-step MD4 was also estimated. As for MD5, its 28-step version was inverted for two most regular hashes (128 1s and 128 0s) for the first time via the incomplete SAT-solving mode of the second algorithm. In other words, the first practical SAT-based preimage attacks on the mentioned step-reduced MD4 and MD5 were proposed. In the future it is planned to apply the proposed approach to other cryptographic hash functions.


Appendix A. Figures for step-reduced MD4




(a) *MD4-40*, 1hash




(b) *MD4-43*, 0hash




(c) *MD4-40*, symmhash



(d) *MD4-43*, symmhash



(e) *MD4-40*, randhash



(f) *MD4-43*, randhash

Figure 6: Minimization of the objective function on 40- and 43-step MD4.

Appendix B. Found Preimages for Step-reduced MD4

Table 12: Found preimages for 41-step MD4.

| | |
|-------------|--|
| <i>0</i> | 0x257d8668 0xa57d8668 0xa57d8668 0xdafb914d 0xa57d8668 0xa57d8668 0xa57d8668 0x1edf9f78 0xa57d8668 0xa57d8668 0xa57d8668 0x12984195 0x97f0b6c 0xd9e5df17 0xab4e82c7 0x23d98522 |
| <i>1</i> | 0xa57d8668 0xa57d8668 0xa57d8668 0x5c31dc3 0xa57d8668 0xa57d8668 0xa57d8668 0x52f59fb2 0xa57d8668 0xa57d8668 0xa57d8668 0x1e8a7cbb 0x3982e99f 0x812d980d 0x27b8d0b5 0xb81a00d1 |
| <i>symm</i> | 0x257d8668 0xa57d8668 0xa57d8668 0xeaaf86e 0xa57d8668 0xa57d8668 0xa57d8668 0xc3b97274 0xa57d8668 0xa57d8668 0xa57d8668 0x21b8d189 0x15fc5540 0xd283c2c4 0x7d27396b 0x7bb74632 |
| | 0x257d8668 0xa57d8668 0xa57d8668 0x5e8d818a 0xa57d8668 0xa57d8668 0xa57d8668 0x8fc29cce 0xa57d8668 0xa57d8668 0xa57d8668 0x8c6b49cc 0xe31a2c8d 0x9a5e1c5d 0x2dd896f5 0x1ed72fab |
| | 0x257d8668 0xa57d8668 0xa57d8668 0x9278c8f 0xa57d8668 0xa57d8668 0xa57d8668 0x4e3194eb 0xa57d8668 0xa57d8668 0xa57d8668 0x22efb603 0xe2b4a054 0xd74ec43 0xf09b0821 0xe4ca9fca |
| | 0x257d8668 0xa57d8668 0xa57d8668 0x6172bd01 0xa57d8668 0xa57d8668 0xa57d8668 0x8e35540f 0xa57d8668 0xa57d8668 0xa57d8668 0x4b8210a9 0xd5c0fedb 0x45c28d93 0x1b542bb8 0x74c28676 |
| <i>rand</i> | 0xa57d8668 0xa57d8668 0xa57d8668 0x4b11d0ca 0xa57d8668 0xa57d8668 0xa57d8668 0x4c195670 0xa57d8668 0xa57d8668 0xa57d8668 0x76529071 0x68d3862d 0xdd3779df 0x768ce847 0x77e1b04e |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0xcfbf3444 0xa57d8668 0xa57d8668 0xa57d8668 0xaac69f2f 0xa57d8668 0xa57d8668 0xa57d8668 0xbdaf1de9 0xfb9496dc 0x537e7a8c 0xd083975f 0xf3a5fc76 |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0xbfbf37eb 0xa57d8668 0xa57d8668 0xa57d8668 0xf3252a5c 0xa57d8668 0xa57d8668 0xa57d8668 0x3f829fe3 0x28c0fe6 0x27eadfa1 0xc87af86e 0x48fcd23d |

Table 13: Found preimages for 42-step MD4.

| | |
|-------------|--|
| <i>0</i> | 0xa57d8668 0xa57d8668 0xa57d8668 0xecdab667 0xa57d8668 0xa57d8668 0xa57d8668 0xe3844a01 0xa57d8668 0xa57d8668 0xa57d8668 0xa3205929 0xfad1ea59 0xd2cae4d2 0x52149d55 0xc82cffbf |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0xae60af85 0xa57d8668 0xa57d8668 0xa57d8668 0x8bcd69e3 0xa57d8668 0xa57d8668 0xa57d8668 0x59b8bf6 0x7755a76 0xfbe0b515 0xf9a31765 0x14d516a6 |
| | 0xa57d8668 0xa57d8668 0xa57d8668 0xa9210d09 0xa57d8668 0xa57d8668 0xa57d8668 0xba9694ea 0xa57d8668 0xa57d8668 0xa57d8668 0x6a8157fe 0xd6566aae 0xbacb3d6c 0x1ec4854d 0x22357d65 |
| | 0x257d8668 0xa57d8668 0xa57d8668 0xd8f77148 0xa57d8668 0xa57d8668 0xa57d8668 0x88275d15 0xa57d8668 0xa57d8668 0xa57d8668 0xcf6b92d0 0x4a8e498d 0x3beb0878 0xb55e027 0x87b4d62c |
| <i>1</i> | 0x257d8668 0xa57d8668 0xa57d8668 0xd8f77148 0xa57d8668 0xa57d8668 0xa57d8668 0x88275d15 0xa57d8668 0xa57d8668 0xa57d8668 0xcf6b92d0 0x4a8e498d 0x3beb0878 0xb55e027 0x87b4d62c |
| <i>symm</i> | 0xa57d8668 0xa57d8668 0xa57d8668 0xd1dce7ea 0xa57d8668 0xa57d8668 0xa57d8668 0xcbc2a90 0xa57d8668 0xa57d8668 0xa57d8668 0xd9834f6d 0x5267d5d6 0x41a9cf18 0x71469663 0xbd507731 |
| <i>rand</i> | 0x257d8668 0xa57d8668 0xa57d8668 0xbd7389e6 0xa57d8668 0xa57d8668 0xa57d8668 0x3eb8ae3a 0xa57d8668 0xa57d8668 0xa57d8668 0x162c323e 0xa4056a04 0x9da74aac 0xfec2c77 0x8b25de8e |
| | 0x257d8668 0xa57d8668 0xa57d8668 0xc1748842 0xa57d8668 0xa57d8668 0xa57d8668 0xd7e32a57 0xa57d8668 0xa57d8668 0xa57d8668 0x21c5baab 0x552a7372 0xa21b2963 0x2fe88ffb 0xadfddb3 |
| | 0x257d8668 0xa57d8668 0xa57d8668 0xc455558f 0xa57d8668 0xa57d8668 0xa57d8668 0xff87976a 0xa57d8668 0xa57d8668 0xa57d8668 0x3e82e858 0x46ad9cde 0x76f3b1d0 0x31aad79 0x45cc1c91 |

References

- Almagro-Blanco, P., & Giráldez-Cru, J. (2022). Characterizing the temperature of SAT formulas. *Int. J. Comput. Intell. Syst.*, 15(1), 69.
- Ansótegui, C., Bonet, M. L., Levy, J., & Manyà, F. (2008). Measuring the hardness of SAT instances. In *AAAI*, pp. 222–228.
- Balyo, T., Froleyks, N., Heule, M., Iser, M., Järvisalo, M., & Suda, M. (Eds.). (2021). *Proceedings of SAT Competition 2021: Solver and Benchmark Descriptions*. Department of Computer Science Report Series B. Department of Computer Science, University of Helsinki.
- Balyo, T., & Sinz, C. (2018). Parallel satisfiability. In Hamadi, Y., & Sais, L. (Eds.), *Handbook of Parallel Constraint Reasoning*, pp. 3–29. Springer.
- Bard, G. V. (2009). *Algebraic Cryptanalysis* (1st edition). Springer Publishing Company, Incorporated.
- Biere, A. (2011). Preprocessing and inprocessing techniques in SAT. In *HVC 2011*.
- Biere, A. (2016). SplatZ, Lingeling, Plingeling, Treengeling, YalSAT Entering the SAT Competition 2016. In *Proc. of SAT Competition 2016 – Solver and Benchmark Descriptions*, Vol. B-2016-1, pp. 44–45. University of Helsinki.
- Biere, A., Fleury, M., & Heisinger, M. (2021a). CaDiCaL, Kissat, Paracooba entering the SAT Competition 2021. In *SAT Competition 2021 – Solver and Benchmark Descriptions*, pp. 10–13. University of Helsinki.
- Biere, A., Heule, M., van Maaren, H., & Walsh, T. (Eds.). (2021b). *Handbook of Satisfiability - Second Edition*, Vol. 336 of *Frontiers in Artificial Intelligence and Applications*. IOS Press.
- Bright, C., Cheung, K. K. H., Stevens, B., Kotsireas, I. S., & Ganesh, V. (2021). A SAT-based resolution of Lam’s problem. In *AAAI*, pp. 3669–3676.
- Carter, K., Foltzer, A., Hendrix, J., Huffman, B., & Tomb, A. (2013). SAW: the software analysis workbench. In *HILT*.
- Clarke, E., Kroening, D., & Lerda, F. (2004). A tool for checking ANSI-C programs. In *Tools and Algorithms for the Construction and Analysis of Systems (TACAS 2004)*.
- Cook, S. A. (1971). The complexity of theorem-proving procedures. In *STOC*, pp. 151–158. ACM.
- Cook, S. A., & Mitchell, D. G. (1996). Finding hard instances of the satisfiability problem: A survey. In *Satisfiability Problem: Theory and Applications*.
- Davis, M., Logemann, G., & Loveland, D. W. (1962). A machine program for theorem-proving. *Commun. ACM*, 5(7), 394–397.
- De, D., Kumarasubramanian, A., & Venkatesan, R. (2007). Inversion attacks on secure hash functions using SAT solvers. In *SAT*, pp. 377–382.
- Dobbertin, H. (1996). Cryptanalysis of MD4. In *FSE*, pp. 53–69.
- Dobbertin, H. (1998). The first two rounds of MD4 are not one-way. In *FSE*, pp. 284–292.

- Dowling, W. F., & Gallier, J. H. (1984). Linear-time algorithms for testing the satisfiability of propositional horn formulae. *J. Log. Program.*, 1(3), 267–284.
- Frioux, L. L., Baarir, S., Sopena, J., & Kordon, F. (2017). PaInleSS: A framework for parallel SAT solving. In *SAT 2017*, pp. 233–250.
- Froleyks, N., & Biere, A. (2021). Single clause assumption without activation literals to speed-up IC3. In *FMCAD*.
- Garey, M. R., & Johnson, D. S. (1979). *Computers and Intractability: A Guide to the Theory of NP-Completeness*. W. H. Freeman.
- Gladush, A., Gribanova, I., Kondratiev, V., Pavlenko, A., & Semenov, A. (2022). Measuring the effectiveness of SAT-based guess-and-determine attacks in algebraic cryptanalysis. In *Parallel Computational Technologies*, pp. 143–157.
- Gomes, C. P., & Sabharwal, A. (2021). Exploiting runtime variation in complete solvers. In *Handbook of Satisfiability - Second Edition*, Vol. 336 of *Frontiers in Artificial Intelligence and Applications*, pp. 463–480. IOS Press.
- Gribanova, I., & Semenov, A. A. (2018). Using automatic generation of relaxation constraints to improve the preimage attack on 39-step MD4. In *MIPRO*, pp. 1174–1179.
- Gribanova, I., & Semenov, A. A. (2020). Constructing a set of weak values for full-round MD4 hash function. In *MIPRO*, pp. 1212–1217.
- Gribanova, I., Zaikin, O., Kochemazov, S., Otpuschennikov, I., & Semenov, A. (2017). The study of inversion problems of cryptographic hash functions from MD family using algorithms for solving Boolean satisfiability problem. In *MIT*, pp. 98–113.
- Heule, M., Kullmann, O., Wieringa, S., & Biere, A. (2011). Cube and conquer: Guiding CDCL SAT solvers by lookaheads. In *HVC*, pp. 50–65.
- Heule, M., & van Maaren, H. (2009). Look-ahead based SAT solvers. In *Handbook of Satisfiability*, pp. 155–184. IOS Press.
- Heule, M. J. H. (2018). Schur number five. In *AAAI*, pp. 6598–6606.
- Heule, M. J. H., Kullmann, O., & Biere, A. (2018). Cube-and-conquer for satisfiability. In *Handbook of Parallel Constraint Reasoning*, pp. 31–59. Springer.
- Heule, M. J. H., Kullmann, O., & Marek, V. W. (2016). Solving and verifying the Boolean Pythagorean triples problem via Cube-and-Conquer. In *SAT*, pp. 228–245.
- Homsirikamol, E., Morawiecki, P., Rogawski, M., & Srebrny, M. (2012). Security margin evaluation of SHA-3 contest finalists through SAT-based attacks. In *CISIM*, pp. 56–67.
- Hutter, F., Xu, L., Hoos, H. H., & Leyton-Brown, K. (2014). Algorithm runtime prediction: Methods & evaluation. *Artificial Intelligence*, 206, 79–111.
- Hyvärinen, A. E. J., Junttila, T. A., & Niemelä, I. (2010). Partitioning SAT instances for distributed solving. In *LPAR*, pp. 372–386.
- Jovanovic, D., & Janicic, P. (2005). Logical analysis of hash functions. In *FroCoS*, pp. 200–215.

- Kautz, H. A., Sabharwal, A., & Selman, B. (2021). Incomplete algorithms. In *Handbook of Satisfiability - Second Edition*, Vol. 336 of *Frontiers in Artificial Intelligence and Applications*, pp. 213–232. IOS Press.
- Kochemazov, S. (2021). Exploring the limits of problem-specific adaptations of sat solvers in sat-based cryptanalysis. In *Parallel Computational Technologies*.
- Konev, B., & Lisitsa, A. (2015). Computer-aided proof of Erdős discrepancy properties. *Artif. Intell.*, *224*, 103–118.
- Kullmann, O. (2009). Fundamentals of branching heuristics. In *Handbook of Satisfiability*, pp. 205–244. IOS Press.
- Lafitte, F. (2018). Cryptosat: a tool for SAT-based cryptanalysis. *IET Information Security*, *12*(6), 463–474.
- Lafitte, F., Jr., J. N., & Heule, D. V. (2014). Applications of SAT solvers in cryptanalysis: Finding weak keys and preimages. *J. Satisf. Boolean Model. Comput.*, *9*(1), 1–25.
- Legendre, F., Dequen, G., & Krajecki, M. (2012a). Encoding hash functions as a SAT problem. In *ICTAI*, pp. 916–921.
- Legendre, F., Dequen, G., & Krajecki, M. (2012b). Inverting thanks to SAT solving - an application on reduced-step md*. In *SECRYPT 2012*, pp. 339–344. SciTePress.
- Legendre, F., Dequen, G., & Krajecki, M. (2013). From a logical approach to internal states of hash functions - how SAT problem can help to understand sha-* and md*. In *SECRYPT 2013*, pp. 435–443.
- Leurent, G. (2008). MD4 is not one-way. In *FSE*, pp. 412–428.
- Marques-Silva, J. P., & Sakallah, K. A. (1999). GRASP: A search algorithm for propositional satisfiability. *IEEE Trans. Computers*, *48*(5), 506–521.
- Massacci, F., & Marraro, L. (2000). Logical cryptanalysis as a SAT problem. *J. Autom. Reasoning*, *24*(1/2), 165–203.
- Menezes, A., van Oorschot, P. C., & Vanstone, S. A. (1996). *Handbook of Applied Cryptography*. CRC Press.
- Mironov, I., & Zhang, L. (2006). Applications of SAT solvers to cryptanalysis of hash functions. In *SAT*, pp. 102–115.
- Nakamura, K., Hori, K., & Hirose, S. (2021). Algebraic fault analysis of SHA-256 compression function and its application. *Inf.*, *12*(10), 433.
- Nejati, S., & Ganesh, V. (2019). Cdel(crypto) SAT solvers for cryptanalysis. In *CASCON*.
- Nejati, S., Horáček, J., Gebotys, C. H., & Ganesh, V. (2018). Algebraic fault attack on SHA hash functions using programmatic SAT solvers. In *CP*, pp. 737–754.
- Nejati, S., Liang, J. H., Gebotys, C. H., Czarnecki, K., & Ganesh, V. (2017). Adaptive restart and CEGAR-based solver for inverting cryptographic hash functions. In *VSTTE*.
- Nossum, V. (2012). SAT-based preimage attacks on SHA-1. Master’s thesis, University of Oslo, Department of Informatics.

- Otpuschennikov, I. V., Semenov, A. A., Griбанова, I., Zaikin, O., & Kochemazov, S. (2016). Encoding cryptographic functions to SAT using TRANSALG system. In *ECAI*.
- Rivest, R. L. (1990). The MD4 message digest algorithm. In *CRYPTO*, pp. 303–311.
- Rivest, R. L. (1992). The MD5 message-digest algorithm. *RFC*, 1321, 1–21.
- Rossi, F., van Beek, P., & Walsh, T. (Eds.). (2006). *Handbook of Constraint Programming*, Vol. 2 of *Foundations of Artificial Intelligence*. Elsevier.
- Sasaki, Y., & Aoki, K. (2009). Finding preimages in full MD5 faster than exhaustive search. In Joux, A. (Ed.), *EUROCRYPT*, pp. 134–152.
- Semenov, A., Zaikin, O., & Kochemazov, S. (2021a). Finding effective SAT partitionings via black-box optimization. In Pardalos, P. M., Rasskazova, V., & Vrahatis, M. N. (Eds.), *Black Box Optimization, Machine Learning, and No-Free Lunch Theorems*, pp. 319–355. Springer International Publishing, Cham.
- Semenov, A. A., Chivilikhin, D., Pavlenko, A., Otpuschennikov, I. V., Ulyantsev, V., & Ignatiev, A. (2021b). Evaluating the hardness of SAT instances using evolutionary optimization algorithms. In *CP*, pp. 47:1–47:18.
- Semenov, A. A., Otpuschennikov, I. V., Griбанова, I., Zaikin, O., & Kochemazov, S. (2020). Translation of algorithmic descriptions of discrete functions to SAT with applications to cryptanalysis problems. *Log. Methods Comput. Sci.*, 16(1).
- Semenov, A. A., Pavlenko, A., Chivilikhin, D., & Kochemazov, S. (2022). On probabilistic generalization of backdoors in Boolean satisfiability. In *AAAI*.
- Semenov, A. A., & Zaikin, O. (2015). Using Monte Carlo method for searching partitionings of hard variants of Boolean satisfiability problem. In *PaCT*.
- Soos, M., Nohl, K., & Castelluccia, C. (2009). Extending SAT solvers to cryptographic problems. In *12th International Conference on Theory and Applications of Satisfiability Testing*, pp. 244–257.
- Starnes, D., Yates, D., & Moore, D. (2010). *The Practice of Statistics*. W. H. Freeman.
- Tseitin, G. S. (1970). On the complexity of derivation in propositional calculus. In *Studies in constructive mathematics and mathematical logic, part II, Seminars in mathematics*, Vol. 8, pp. 115–125. V.A.Steklov Mathematical Institute, Leningrad.
- Vallade, V., Frioux, L. L., Oanea, R., Baarir, S., Sopena, J., Kordon, F., Nejati, S., & Ganesh, V. (2021). New concurrent and distributed Painless solvers: P-MCOMSPS, P-MCOMSPS-COM, P-MCOMSPS-MPI, and P-MCOMSPS-COM-MPI. In *SAT Competition 2021 – Solver and Benchmark Descriptions*, pp. 40–41. University of Helsinki.
- Wang, X., Lai, X., Feng, D., Chen, H., & Yu, X. (2005). Cryptanalysis of the hash functions MD4 and RIPEMD. In *EUROCRYPT*, pp. 1–18.
- Wang, X., & Yu, H. (2005). How to break MD5 and other hash functions. In Cramer, R. (Ed.), *EUROCRYPT*, pp. 19–35.
- Weaver, S. A., & Heule, M. (2020). Constructing minimal perfect hash functions using SAT technology. In *AAAI*.

- Williams, R., Gomes, C. P., & Selman, B. (2003). Backdoors to typical case complexity. In *IJCAI*, pp. 1173–1178.
- Zaikin, O. S., & Kochemazov, S. E. (2021). On black-box optimization in divide-and-conquer SAT solving. *Optimization Methods and Software*, *36*(4), 672–696.
- Zaikin, O. (2022). Inverting 43-step MD4 via Cube-and-Conquer. In *IJCAI-ECAI*, p. in press.